


100

30

32



IMPERIAL GAZETTEER

OF

INDIA.

VOLUME XII

Ratlám —Native State under the Western Malwá Agency of Central India. Area, 729 square miles. Population (1881) 87 314, namely, 45,779 males and 41,535 females occupying 18 040 houses, in 1 town and 162 villages. Persons per square mile, 120. Houses per square mile, 24 7. Persons per house, 4 8. Hindus number 154,034, Muhammadans 9913, Jains, 6038, Christians, 19, Parsis, 13, and non Hindu aborigines, 17,297. The aborigines include — Bhils, 16,810, Moghias, 417, Mhars, 48, and Minas, 22. The revenue from all sources is estimated at £130 000 of which more than half is alienated in *jágirs* and other grants. The Malwa branch of the Rájputana Malwa State Railway passes by Ratlám town.

The Rajá of Ratlám, who is descended from a younger branch of the Jodhpur family, ranks as the first Rajput chief in Western Málwa. One of his ancestors, Ratan Singh, having displayed conspicuous courage in Delhi, received a grant of territory in Málwá from the Emperor Sháh Jahán. The State is held as tributary to Sindhia, but in 1819 an arrangement was made by which the Rajá of Ratlám agreed to pay an annual tribute of Salám Sháh Rs 84 000 (or about £6600), while Sindhia engaged never to send any troops into the country or interfere with the internal administration. This tribute was assigned, by the treaty of 1844 between the British Government and Sindhia, in part payment for the Gwalior Contingent, and it is now paid to the British Government. The present Rajá, Jaswant Singh, a Rahtor Rajput, was born about 1860. He was placed on the *gadi* when only three years old. During his minority, the State has been managed by Mir Shíhamat Ali, C S I, as Superintendent. Education has much

advanced of late years; there were in 1882, 24 schools, including three for girls and a central college at Ratlám town. Jail; good roads. In 1883, 12,149 patients were treated at the Ratlám Dispensary. The Rájá of Ratlám has a personal salute of 13 guns. His military establishment consisted in 1882 of 5 field guns, 12 artillerymen, 136 cavalry, and 198 infantry. Police, 461 men.

Ratlám.—Chief town of Ratlám State, Málwá, Central India. Lat. $23^{\circ} 21' N.$, long. $75^{\circ} 7' E.$; 1577 feet above sea-level. Population (1881) 31,066, namely, 16,544 males and 14,522 females. Hindus numbered 18,676; Muhammadans, 7357; and 'others,' 5033. Ratlám city is a great centre for transactions in opium and grain, to which it owes much of its prosperity. Good *bizárs*. One of the principal seats of the opium trade of Málwá. In 1883-84, opium exports—to China, 1394½ chests, duty secured, £90,643; to Bombay, 80 chests (of which 26 chests were free), duty secured, £4480. Newly built palace; well-kept garden; dispensary; post-office; central college. A station on the Málwá branch of the Rájputána-Málwá State Railway.

Ratnágiri.—British District in the Konkan or Southern Division of the Bombay Presidency, lying between lat. $15^{\circ} 43'$ and $18^{\circ} 5' N.$, and between long. $73^{\circ} 3' 30''$ and $74^{\circ} 2' E.$ Area, 3922 square miles. Population (1881) 997,090. Bounded on the north by the Native State of Janjira and Kolába District; on the east by Sátára District and the Native State of Kolhápúr; on the south by the Sávantwári Native State and Portuguese possessions of Goa; and on the west by the Arabian Sea.

Physical Aspects.—The District may be described generally as rocky and rugged. Near the coast, it consists of bare elevated plateaux, intersected by numerous creeks and navigable rivers, flowing between steep and lofty hills. These rivers have along their banks the chief seaports, and almost all the fertile land of the District. Ten miles or so inland, the country becomes more open; but advancing a little farther, it is occupied by spurs of the Sahyádrí hills. This range itself forms the continuous eastern boundary, running parallel to the coast, at distances varying from 30 to 45 miles. It varies in height from 2000 to 3000 feet, though some of the peaks attain an altitude of 4000 feet. While the banks of the rivers produce fine crops of rice in the rains, and of pulse in the cold weather, and some of the inland valleys exhibit the utmost fertility, the soil is, as a rule, poor and barren, and supports with difficulty its dense population.

The seaboard, about 160 miles in length, from Bánkot or Fort Victoria to a point two miles south of Redi Fort, is almost uniformly rocky and dangerous. It consists of a series of small bays and coves shut in between jutting headlands, and edged with sand of dazzling whiteness. At places the hills recede a little, leaving at their base a

rich tract of rice fields, with generally a strip of cocoa nut gardens between them and the beach. At intervals of about 10 miles, a river or bay opens, sufficiently large to form a secure harbour for native craft, and the promontories at the river mouths are almost invariably crowned with the ruins of an old fort. At SUVARADRUG and MALWAN rocky islands stand out from the mainland still preserving the remains of strong Maráthá fortifications. The larger rivers and creeks have deep water for 20 or 30 miles from the coast, and many of the most important towns are situated at their farthest navigable point, for in so rough a country the rivers form the best highways of trade. The wells of the coast villages supply a brackish but not unwholesome water.

Forests—In the early days of British occupation, the region round Bankot creek was clothed with fine teak wood. Curved teak logs known as Bankot knees, were largely exported to Bombay, and from Bankot came most of the stout ribs and frameworks of the old Indian navy. The Maráthás had shipbuilding yards at Málnan and Vyazdrug, and showed a prudent regard to forest preservation. After the transfer of the District from the Maráthá Peshwa in 1818 cultivation greatly increased, and the larger part of the District was laid bare. In 1829 the forests were left to the people for unrestricted use, and in consequence enormous quantities of timber were felled unchecked, and despatched to the Bombay market. The effect of this treatment has left Ratnágiri denuded of forest to the present day and in 1879 only 4 per cent. of the area was returned as tree covered. The village groves along the coast are dense and well supplied with mango oil nut (*Calophyllum inophyllum*) and jack trees. The denudation so far has not affected the rainfall. Active measures of late years, have been adopted to preserve and extend the forest area. The area reserved on 31st March 1881 in Ratnágiri District was 20 square miles or 12,800 acres, and a further area of 146 square miles is now (1884) in process of reservation. The receipts in 1881 from the sale of teak and firewood in Ratnágiri District was £397.

The chief trees of the District are teak *ain* (*Terminalia tomentosa*) *kúgal* (*Terminalia paniculata*) catechu *shisham* (*Dalbergia latifolia*) *mana* (*Lagerstrœmia lanceolata*), *taman* (*Lagerstrœmia Reginæ*), and bamboos. *Casuarina* has been found to thrive in Dapoli Sub division, and it is supposed that the sandhills along the seaboard would make excellent sites for casuarina plantations.

From an economic point of view, the cocoa nut palm is the most important tree in the District. As a rule, cocoa nut palms owned by Bráhmans and Maráthas are cultivated for their fruit only, while those held or rented from Bráhmans by Bhandáris are tapped for their juice or toddy. Under Maratha rule, the owner paid a cess of about

2s. 6d. to Government for each tree tapped. Under the British system, the owner obtains a special licence at a fixed rate (from 2s. to 6s.) for each tree annually; under which the owner may sell the toddy at the foot of the tree, but may not distil it. An average tree yields about from 35 to 64 imperial gallons of juice each year. Number of toddy-yielding palms in the District (approximately), 800,000. A cocoa-nut tree does not bear fruit or yield juice until its eighth or tenth year. It lives for 70 or 80 years; and it bears fruit up to its sixtieth. If tapped, it ceases to be productive much earlier.

Wild Animals. — Game is scarce in Ratnágiri District. Tigers, *sámbar* deer, and bears are few, and have their haunts in the most inaccessible localities. Leopards are not uncommon: wild hog are plentiful, but owing to the nature of the ground hunting them on horse-back is impossible. Deer, antelope, hares, jackals, and foxes abound. Monkeys of the *langur* species are usually to be seen about all towns and villages. The flying-fox (or fruit bat) and musk-rat are common everywhere. The bears are the usual Indian black or sloth species; they inhabit the upper slopes of the Sahyádris, living mostly on their favourite food, the fruit of the wild fig-tree. Wolves are unknown, but packs of wild dogs have been met with.

Snakes are abundant, of both venomous and harmless kinds. The python is stated to measure 10 to 20 feet, but the species is only occasionally met. The Rock snake, *dhaman* (*Ptyas mucosus*), and the common brown tree snake are general. The cobra (*nág*) (*Naja tripudians*) is often killed in human habitations. Owing to its nocturnal habits, it is not often seen by daylight. The *fursa* (*Echis carinata*), identical with the *kapar* of Sind, is by far the most common of the venomous snakes found in the District. The *fursa* is most dangerous owing to its small length (12 to 18 inches).

As regards its game birds, Ratnágiri is an indifferent sporting country; partridges, grouse, and bustard are wanting, while quail is scarce. Duck, snipe, and plover are plentiful. Among birds of prey, the vulture, the falcon, the eagle, and the osprey are found. Owls are common, as also swallows, king-fishers, and parakeets. The Indian oriole or mango bird is rare.

Ratnágiri is well supplied with sea-water fish, and in a less degree with fresh-water fish. Sharks are numerous, and whales are sometimes seen off the seaboard. Sardines swarm on the coast at certain seasons in such abundance as to be used for manure. The fishermen often stay for days at sea, but the usual custom is to start in the afternoon about four, and to return next morning about ten. Women and old men carry fish to market, or hawk them from door to door. The fish are often bartered for grain and firewood; and are largely purchased by wholesale dealers for the purpose of being salted and cured. A con-

siderable quantity of cured fish is exported through the passes of the Sahyádrí range into the Deccan. Small fish are cured by being simply dried in the sun.

Geology—The rocks of Ratnagiri belong to five groups. These, arranged in their true or descending order, are —

I Post tertiary or recent	{ 7 Subaerial formations and soils
	{ 6 Alluvial deposits
II Upper tertiary	5 Konkan laterite
III Middle or lower tertiary	4 Ratnagiri plant beds
IV Upper secondary	3 Deccan trap and iron clay (laterite) series
	{ 2 Kaladgi quartzites and shales
V Azoic	{ 1 Gneissic (metamorphic) series with trap and granite intrusions

Hot springs are found in various parts of the District. The line of springs runs half way between the Sahyádrí Hills and the sea, and seems to stretch both north and south of the District. Three villages, two in Dápoli Sub division and one in Rajapur, have been named Unhala from their hot springs. There are similar springs near the towns of Khed and Sangameshwar, and at the villages of Arvali and Tural. The water of all these springs seems strongly impregnated with sulphur.

On the top of a hill, two miles from Rajapur, close above the Unhala hot spring, a curious phenomenon is from time to time observed. Certain springs, at irregular intervals, but almost always during the fair season, bubble up, and suddenly, without any warning, overflow the rocky soil, covering a considerable area of ground. This apparent freak of nature can only be accounted for on the hypothesis of an underground syphon forcing the water through a permeable stratum. The natives regard the water as a true stream of the sacred Ganges. According to local tradition, the springs were first observed about 300 years ago, and up to the year 1821 continued to flow regularly every year for six weeks in January–February. From that date to the present time, the phenomenon has been manifested only once in every two or three years. The area covered by the springs is about 3150 square yards.

History—The Chiplun and Kol caves show that between B.C. 200 and A.D. 50, North Ratnágiri had Buddhist settlements of some importance. The District passed under several Hindu dynasties, of whom the Chalukyas were the most powerful. In 1312, Ratnágiri was overrun by the Muhammadans who established themselves at Dabhol, but the rest of the country was practically unsubdued till 1470, when the Bahmani kings gained a complete ascendancy by the capture of Vishalgarh and Goa. About 1500, the whole of the Konkan south of the Savitri came under Bijápur rule, when war with the Portuguese wrought grievous loss

to Dábhól and other coast towns. The decline of the Portuguese power was accompanied by the rise of that of the Maráthás, who under Sivaji established themselves in Ratnágiri (1658–1680), defeating the Bijápur armies, repelling the Mughals, and overcoming the Sidis and Portuguese. For some years after this the Sidis held possession of part of the District.

The successes of the pirate Kanhoji Angria led to his being appointed admiral of the Maráthá fleet, and obtaining part of Ratnágiri as his principality. In 1745, Tulaji Angria, one of his illegitimate sons, succeeded to the lands between Bánkot and Sáwantwári, disavowed the Peshwá's authority, and seized and plundered all the ships he could master. The English, in conjunction with the Peshwá, in 1755 destroyed the piratical forts at Suvarndrug. The following year, after the destruction of the whole of Angria's fleet, Vijiadrug was taken. For these services, Bánkot with nine villages was ceded to the British. In 1765, Málwán and Redi were reduced. The former was restored to the Rájá of Kolhápúr, and Redi was given to the chief of Sáwantwári. The wars between Kolhápúr and Sáwantwári, carried on for 23 years with varying success, threw the country into great disorder, as each party in turn became supreme. They finally entered into agreements with the British Government, and ceded Málwán and Vengurla, and arrangements were made for the cession of the Peshwá's dominions in Ratnágiri. But war breaking out in 1817, the country was occupied by a military force, and the forts were speedily reduced.

Population.—The Census returns of 1872 disclosed a total population of 1,019,136 persons, and that of 1881, 997,090; so that a decrease of 22,046, or 2 per cent., occurred within the decade. This decrease is attributed—(1) to the enumeration in this District being placed in the hands of men picked up for the few days required for the Census, who had little interest in work which, however defective, would not be tested in any detail till long after they had been paid; (2) to emigration, due to the increased demand for labour in the mills and docks of Bombay city; and (3) to a movement from the District, indicated by a careful consideration of the returns of the Census, in which families as well as working men were included.

The population of 1881 was resident in 5 towns and 1292 villages with 177,844 houses; unoccupied houses numbered 16,910. Density of population, 254·2 persons per square mile; houses per square mile, 49·6; persons per village, 768; persons per house, 5·58. Classified according to sex, there were 473,053 males and 524,037 females; proportion of males, 47·4 per cent. Classified according to age, there were—under 15 years, boys 208,636, and girls 198,463; total children, 407,099, or 40·9 per cent. of the population: 15 years and upwards—males 264,417, and females 325,574; total adults, 589,991, or 59·1 per cent.

The fertile land is found along the banks of the rivers or salt water creeks in the neighbourhood of the sea, but the soil is generally poor, consisting in great measure of a stiff ferruginous clay, often mixed with gravel. Neither wheat nor cotton is grown. There are several coconut plantations in the District, and hemp is grown by the fishermen for net making. In 1876-77, rice occupied 143,636 acres, and in 1883-84, 166,904 acres. The better kinds of rice land produce also second crops of some description of pulse or vegetable. By far the greater proportion of the food crops consist of inferior grains, as *harid* (*Paspalum scrobiculatum*), 369,011 acres in 1883-84, *ragi* (*Eleusine coracina*), 292,464 acres, and *waru* (*Panicum miliaceum*). These coarse grains are grown on *warlas* soil in the uplands, light and poor. The *warlas* lands may be divided into the more level parts, *mal*, where the plough can be used, and the steeper slopes, *dongri*, admitting only of cultivation by manual labour. The best of the poorer soils bear crops for five or six successive years, and then require a fallow of from three to twelve years.

The land tenures of Ratnagiri differ from that of Bombay generally, in that there is a class of large landholders, called *khots*, in the position of middle men between Government and the actual cultivators. Nearly one half of the whole number of villages in the District are held on the *khots* tenure, under which the *khots* makes himself responsible for the payment of the assessment. Some of the *khots* grants date back to the time of the Bijapur kings, and were made to Muhammadans, Mirathas, and Hindus alike. In 1829 the *khots* were well off, and many of them were men of capital, who laid out money in bringing new land under tillage. On the other hand, the tenants were deep in the *khots* debt, and wholly at his mercy, and the first efforts of Government were directed to ascertain the extent of the relative rights of the *khots* and their tenants. In 1851 it was found that the tenants were extremely impoverished, having no motive to improve their lands for the benefit not of themselves, but of the *khots*, and that a labour tax was exacted from them. It was decided to take a survey which would record the rights of occupancy tenants, and would obtain information upon which legislation could be based. The terms of the settlement were embodied in the Survey Act of 1865. The District was settled under its provisions against the strenuous opposition of the *khots*, and as money rates had been substituted for payments in kind, the change was disliked by the people. In 1874 the discontent was so pronounced that a Commission was appointed to reinvestigate the subject, and to endeavour to effect a compromise. A settlement was carried out between 1877 and 1880, by personal inquiries before the whole of the assembled villagers. All extra cesses were abolished, and the relations between *khots* and tenant were placed upon a satisfactory footing. The

frugal, teachable middle classes, and to its sober, sturdy, and orderly lower classes, Bombay city owes many of its ablest officials and lawyers, its earliest and cleverest factory workers, its most useful soldiers and constables, and its cheapest and most trusty supply of unskilled labour. The Census of 1872 disclosed in Bombay city 70,947 persons born in Ratnágiri District, while that of 1881 showed that the number had increased to 126,190, or by nearly 78 per cent. About the year 1864, before Bombay offered so large a market for labour, numbers went from Ratnágiri to the Mauritius, but of late years this emigration has almost entirely ceased.

The Census of 1881 divided the male population into six main groups as regards occupation :—(1) Professional class, including State officials of every kind and members of the learned professions, 9147 ; (2) domestic servants, inn and lodging keepers, 3634 ; (3) commercial class, including bankers, merchants, and carriers, 9197 ; (4) agricultural and pastoral class, including gardeners, 203,334 ; (5) industrial class, including all manufacturers and artisans, 32,240 ; and (6) indefinite and non-productive class, comprising general labourers, male children, and persons of unspecified occupation, 215,501.

Of the 1297 towns and villages in Ratnágiri District in 1881, 138 contained less than two hundred inhabitants ; 454 from two to five hundred ; 436 from five hundred to one thousand ; 205 from one to two thousand ; 40 from two to three thousand ; 18 from three to five thousand ; 3 from five to ten thousand ; 2 from ten to fifteen thousand ; and 1 from fifteen to twenty thousand. The principal towns are—Málwán (15,565) ; Ratnágiri (12,616) ; Chiplun (12,065) ; Vengurla (8947) ; Rájápur (7448) ; and Dápoli (2652). The last five named towns are municipalities.

Agriculture.—In 1881, agriculture supported 689,837 persons, or 69·2 per cent. of the total population ; the number of ‘workers’ being 379,979, and of ‘dependants’ 309,858. In the same year, the total area of revenue-paying land was, approximately, 2439 square miles, out of a District area of 3922 square miles. On this 2439 square miles, the assessment, quit-rent, and local cess amounted to £94,150. The average incidence of State charge, including local cess, per acre of cultivated land, was 1s. 2½d. Average number of cultivable and cultivated land per agricultural ‘worker,’ 4·1 acres. As Ratnágiri District has not been entirely brought under the operations of the Survey, the exact area of Government cultivable land is not known. Up to the end of 1883–84, six out of the nine Sub-divisions of the District had been surveyed and settled. Of 1,078,821 acres under actual cultivation in 1883–84, of which 36,865 acres were twice cropped, grains occupied over 1,020,583 acres ; pulses, 41,773 ; oil-seeds, 25,222 ; fibres, 7723 ; garden produce, 11,827 ; sugar-cane, 6629 ; and miscellaneous crops, 3929 acres.

RATNAGIRI

The fertile land is found along the banks of creeks in the neighbourhood of the sea, consisting in great measure of a soft gravel. Neither wheat nor cotton is grown in nut plantations in the District, and hence it is for net making. In 1876-77, rice amounted to 1883-84, 166,904 acres. The better land produces second crops of some description of food crops (Paspalum scrobiculatum), 369,011 acres, and corocana, 292,464 acres, and coarse grains are grown on poorer lands. The *warkas* lands may be admitted only of cultivation by poorer soils bear crops for five or six years.

The land tenures of Ratnagiri are in that there is a class of large holders of middle men between Government and one half of the whole number of *khots* tenure, under which the *khots* pay to the time of the Bijapur king, and Marathas, and Hindus alike. In many of them were men of capital, and new land under tillage. On the *khots*' debt, and wholly at his expense were directed to ascertain the *khots* and their tenants. In 1851, *khots* extremely impoverished, having no benefit not of themselves, but of the rights of occupancy tenants, which legislation could be based embodied in the Survey Act of 1857, its provisions against the strenuous money rates had been substituted. In 1874, also disliked by the people. In 1874, a Commission was appointed to endeavour to effect a compromise between 1877 and 1880, by persons assembled villagers. All extra cesses between *khots* and tenant were placed

Khot Act I. of 1880 legalized the settlements. Considerable areas on the coast and along the banks of the larger creeks have been granted on reclamation leases.

In 1883-84, the prices current of produce per *maund* of 80 lbs. were—rice, forming the food of the better class, 9s. 4½d. to 5s. 8½d., according to quality; *harik*, food of the poorest class, 1s. 10¾d.; *nagli* or *ragi*, 5s.; *wari*, 4s. 1½d.; *dál* (split-peas), 7s.; salt, 5s. 10¾d.; *ghi*, £3, 3s. The average wages per day of skilled labour were 1s. 2½d.; of unskilled labour, 5¼d. The day's hire for a cart was 1s. 2d. The agricultural stock and implements were—cows, bullocks, and buffaloes, 363,847; horses, 295; donkeys, 2; sheep and goats, 38,230; ploughs, 88,743; carts—riding, 175, and carrying, 1277.

Natural Calamities.—Since the beginning of British rule there has been no year of distress so severe and general as to amount to famine. Of only two of the older famines, those of 1790 and 1802-03, does any information remain. Both of these seem to have been felt all over the District. In 1824, a very light rainfall was followed by a complete failure of crops in high grounds, and a partial failure in low rice lands. In 1876, an insufficient rainfall caused a serious loss of crops and local distress, but not actual famine. Public health was bad, and there was considerable distress. A total of £7736 was spent on relief works. An unusual demand for labour sprang up in and near Bombay city; and it was estimated that at least 150,000 (double the usual number) of the poor workers moved to Bombay for part of the fair season, and returned with savings enough to last them till the next harvest.

Trade, etc.—From beyond the line of the Sahyádris, grain, cotton, and sugar are brought down to the sea-coast for exportation, and the carts and bullocks thus engaged generally take back cocoa-nuts, salt, and dried fish. Steamers from Bombay call regularly at the ports in the fair season, bringing piece-goods and stores, and taking back cotton from Vengurla and Ratnágiri. The local shipping traffic has suffered through the competition of steamers; but a large traffic is still carried on by this means with the Malabar coast, Cutch, Káthiáwár, and Karáchi. In 1883-84, the number of vessels which entered and cleared the ports of the District was 33,328, of 959,737 tonnage; of these, 444 were steamers, of 579,194 tonnage.

The Ratnágiri seaboard contains 29 ports and harbours. They are of two classes—coast ports on sheltered bays and river mouths; and inland ports up tidal creeks, generally at the point where navigation ceases. Of the whole, nine, Bánkot, Harnai, Chiplun, Sangameshwar, Ratnágiri, Rájápur, Khárepátan, Málwán, and Vengurla, are places of some trade and consequence; the rest are insignificant. The ports are grouped for customs purposes into six divisions—Anjanwel, Málwán, Ratnágiri, Suvarndrug, Vengurla, and Vijiadrug. The total value of

the seaborne trade of the ports in the District amounted in 1876 to £2,410,611, of which £1,004,547 represented the exports, and £1,406,064 the imports, and in 1883-84 to £2,601,301—exports £1,467,390, and imports £1,133,911. The manufactures of the District are unimportant, but the School of Industry at Ratnágiri town possesses steam sawmills, and undertakes wood and iron work of all descriptions. In 1852, Captain (now Sir George) Wingate wrote 'There are not even bullock paths from many villages to the nearest market towns, and the whole of the produce sent there for sale is taken upon men's heads. Carts are unknown. Of late years, however, many improvements have been made. Three good cart roads now cross the Sahyadri Hills, and also a trunk road, with branches from one end of the District to the other. During the famine of 1876-77, nearly 90,000 tons of grain passed inland from the coast. There are at present 763 miles of road in the District.

Administration — In 1819, the South Konkan was formed into a separate District, with Bankot as its head quarters, which in the next year were removed to Ratnágiri, a more central and convenient place. In 1830, the three *talu's* north of Bankot were transferred to the North Konkan, and Ratnágiri reduced to the rank of a Sub collectorate. But in 1832 it was again made a District. The total revenue in 1883-84 under all heads, imperial, local and municipal, amounted to £135,088, the incidence of taxation per head being 2s 7½d. The land tax forms the principal source of income, yielding £91,429. The local funds, created since 1863 yielded a total of £5306. There are five municipalities, containing an aggregate population of 43,728 persons. The municipalities are Ratnágiri, Chiplun, Vengurla, Rajápur, and Dapoli. The native members of the committees numbered in all 72, and the European members 15. The receipts of the municipalities were returned at £8,431, and the incidence of taxation varied from 5½d (Dapoli) to 3s 5½d (Vengurla) per head of population. The form of taxation known as octroi, levied upon commodities brought within municipal limits, furnished an income of £2275. The District is administered by a Collector and 6 Assistants. It is provided with a District Judge's court, and 8 civil courts. The total strength of the regular police in 1883-84 consisted of 737 officers and men, giving 1 policeman to every 1354 of the population and to every 5 square miles of the area. The total cost was £10,514, equal to £2, 13s 7½d per square mile and 2½d per head of population. The District contains one jail, daily average number of prisoners in 1880, 312, of whom 16 were women. Education has widely spread of late years. In 1855-56 there were only 20 schools, attended by 2403 pupils. In 1876-77 there were 147 schools, with 8776 pupils. In 1883-84 the number of schools was 155, and the number of scholars 12,014, the average being 1

school to every 8 villages. The Census of 1881 returned 14,104 boys and 215 girls as under instruction, besides 29,889 males and 224 females able to read and write, but not under instruction. Four newspapers were published in 1876-77, and six in 1883-84.

Climate.—The climate of the District, though moist and relaxing, is on the whole healthy. The rainfall is abundant and comparatively regular. The annual rainfall during the five years ending 1876 averaged 105 inches; and for about twenty years ending 1881, 107·3 inches. Maximum heat at Ratnágiri in 1883, 99·9° F.; minimum, 58·6° F. The prevailing diseases are intermittent fevers and leprosy. There are 4 dispensaries in the District, and a hospital for lepers; in-door patients (1883), 799; out-door, 21,135. Registered birth-rate, 20 per thousand; registered death-rate, 16·7 per thousand. The deaths from cholera in 1883 numbered 91; from small-pox, 904; from fevers, 8235. Total number of persons vaccinated, 25,349.

Ratnágiri.—Sub-division of Ratnágiri District, Bombay Presidency. Situated in the centre of the District, bounded on the west by the sea. Area, 432 square miles. Population (1881) 126,227, namely, 59,311 males and 66,916 females, occupying 22,504 houses, in 1 town and 149 villages. Hindus numbered 111,056; Muhammadans, 14,939; and 'others,' 232. The coast-line is bold, and indented with numerous creeks. Climate moist and relaxing. Alluvial deposits on the banks and at the estuaries of the creeks. The plateaux and hills consist entirely of laterite. In 1877-78, 150,538 acres were under tillage. Grain crops occupied 146,285 acres; pulses, 1500 acres; fibres, 125 acres; oil-seeds, 1050 acres; and miscellaneous crops, 1578 acres. In 1883-84 the Sub-division contained 1 civil and 2 criminal courts; police circles (*thánás*), 5; regular police, 68 men. Land revenue, £10,578.

Ratnágiri.—Chief town of Ratnágiri District, Bombay Presidency; situated in lat. 16° 59' 37" N., and long. 73° 19' 50" E., 136 miles south by east of Bombay. Population (1872) 10,614; (1881) 12,616, namely, 6418 males and 6198 females. Hindus number 9343; Muhammadans, 3076; Christians, 192; and Jains, 5. The town is open, and faces the sea; the fort stands on a rock between two small bays, but these afford neither shelter nor good anchorage, as they are completely exposed and have a rocky bottom. With any breeze from the west, a heavy surf breaks on the bar, and boats can only enter at high tide. The water-supply is entirely derived from wells, which are for the most part never-failing. One object of interest connected with Ratnágiri is the *tárli* or sardine fishery, which usually takes place in the months of January and February, when fleets of canoes may be seen engaged in this occupation. A single net-caster will fill his canoe in the course of a morning. The fishing ground is just outside the breakers. The industry can be carried on only when the water is clear enough to

RATO DERO—RATSAR

admit of the fish being readily seen. The salt water creek to the south of the fort is only practicable for country craft of under 20 tons burden.

The chief ports in the Ratnágiri customs division are Jaigarh, Ratnágiri, and Purangarh. The average annual value of the trade of the Ratnágiri customs division for the five years ending 1883-84 is returned at £128,763, viz imports £91,029 and exports £37,734. In 1883-84 the value was £141,824—imports £97,358, and exports £44,466. The chief imports are salt, timber, catechu, and grain, the exports—fuel, fish, and bamboos.

Besides being the head quarters of the District Ratnágiri has a sub-judges court, civil and leper hospitals and four schools. In 1878 it was constituted a municipality. The income is chiefly derived from a house tax. The streets and the landing place are lighted, and a travellers' or string bungalow is kept up. From a perennial stream two and a half miles east of the town water has been conducted, and pipes have been laid through all the chief quarters. In 1883-84 the municipal committee was composed of 6 European and 22 native members. The income was £649. Incidence of municipal taxes, road per head. The lighthouse was erected in 1867. The elevation of the lantern above high water is 250 feet, and the height of the building from base to vane 22 feet. It exhibits a small red dioptric light of order 6 which is visible at 8 to 10 miles.

Rato Dero—*Taluk* of Larkhána Sub-division, Shikarpur District, Sind, Bombay Presidency. Area 228 square miles. Population (1872) 35,896, (1881) 41,588, namely 22,480 males and 19,107 females, occupying 6023 houses, in 1 town and 86 villages. Hindu 3,379, Muhammadans 34,517, Sikhs, 3604, and aboriginal tribes, 88. Gross revenue (1882-83) £14,388. Area assessed to land revenue 43,329 acres, area of actual cultivation, 41,328 acres. The Sub-division contained—criminal courts, 2, police circles (*thánás*), 4 regular police, 26 men.

Rato Dero—Chief town of Rato Dero *taluk*, in Larkhána Sub-division, Shikarpur District, Sind, Bombay Presidency, 18 miles north-east by north from Larkhána. Head quarters of a *mukhtiyárkár*, and *tappadar*, and contains the usual public buildings. Population (1881) 3170. Local trade in grain. Rato Dero was formerly the encampment of a chief of the Jalbani tribe called Rato. Municipal revenue in 1883-84, £370, incidence of taxation, 15 1/2d per head on population.

Ratsar (or *Ratsar Kalan*)—Village in Ballia *taluk*, Ballia District, North Western Provinces, situated in lat. 25° 54' 02" N, and long. 85° 07' E, on the Gwárá Sikandarpur road. Population (1881) 105. The principal village of the Ratsar *taluk* or estate, which

manently settled with Karcholiá Rájputs, and is still in the possession of the descendants of the original proprietors. The village contains two sugar factories, and a primary school. A large *bázár* is held twice a week.

Rattihalli.—Village in the Kod Sub-division of Dhárwár District, Bombay Presidency; situated about 10 miles south-east of Kod. Population (1881) 2332. Till 1864, Rattihalli was the head-quarters of the Sub-division. In 1764, in the war between Haidar Ali and the Maráthás, Rattihalli was the scene of a signal rout of Haidar's army. A temple in Jakhanáchárya style, built of sculptured slabs, and with three domes supported on 36 pillars. Seven inscriptions varying in date from 1174 to 1550 A.D. Weekly market on Friday. Ruined fort.

Rau Karna.—Town in Unao District, Oudh; situated 7 miles from Unao town, on the road to Sasipur. Population (1881) 2200, of whom 46 are Muhammadans. Small market, twice a week.

Rauk-thwa (or more correctly *Yauk-thwa*).—Stream which rises in the Paung-laung range in Taung-gú District, Tenasserim Division, Lower Burma.—See YAUK-THWA.

Ráver.—Town in the Savda Sub-division of Khándesh District, Bombay Presidency. Lat. $21^{\circ} 15' N.$, long. $76^{\circ} 4' 30'' E.$ Population (1881) 7482, namely, Hindus, 5698; Muhammadans, 1510; Jains, 189; and 'others,' 85. A good road, two miles long and carefully bridged, connects the town with Ráver station on the north-east line of the Great Indian Peninsula Railway, 297 miles north-east of Bombay. Ráver has a local reputation for its manufactures of gold thread and articles of native apparel. In the main street, leading from the market-place to the fort, the houses are nearly all three-storied, and tiled with richly-carved wooden fronts. Ráver was ceded by the Nizám to the Peshwá in 1763, and by the latter bestowed on Holkar's family. Post-office. Small rest-house at the railway station.

Ráver.—Village in Nimár District, Central Provinces; on the Narbada (Nerbudda) river, 40 miles from Khandwá. Contains the cenotaph of the Peshwá Báji Ráo, who died at Ráver in 1740, when about to invade Northern India for the second time. The monument is built of variegated sandstone, enclosed in a spacious *dharmśála* of strong masonry. A handsome *ghát*, opposite the platform in the centre of the river, where the funeral rites were performed, has been much injured by floods. Ráver lies a short distance from the Barwái or Dhangáon travellers' bungalow, and is also accessible from Barwái by boat.

Rávi.—River in the Punjab (Panjáb); one of the five great streams from which the Province derives its name. The *Hydraotes* of Arrian, and the *Iravati* of Sanskrit authors. It rises in the Kúlu Sub-division of Kángra District, and immediately passes into Chamba State,

after which it strikes upon British territory again on the borders of Gurdaspur District, opposite Basaoli in Jamu, and forms the boundary for 25 miles, with a general south westerly course. It leaves the hills on the southern bank at Shahpur, but still flows between high cliffs, while on the Jamu side the mountains descend to its very brink. At Madhupur, the head works of the BARI DOAB CANAL draw off a large portion of its waters. Thence forward the banks sink in height and the river assumes the usual character of the Punjab streams, flowing in the centre of an alluvial valley, with outer banks at some distance from the present bed. In 1810 it carried away the Tali Sahib shrine near Dera Nanak, a place of great sanctity with the Sikhs, and still threatens the town. The Ravi next passes between Sidkhot and Amritsar Districts, preserving the general south westerly direction which it has taken since March and April, swelling in June and September to 18 or 20 feet leaving the mountains. The depth is here not more than a foot in. Entering the District of Lahore, it runs within 1 mile of Lahore city, and throws out several branches, which soon, however, rejoin the parent stream. A bridge of boats conveys across the Lahore and Peshawar road. After entering Montgomery District it receives its chief tributary, the Degh, on its north western bank, and then passes into Multan (Mooltan) District. Finally, it falls into the Chenab (Chinab) in lat $30^{\circ} 31' N$, long $71^{\circ} 51' 20'' E$, after a total length of about 450 miles.

Throughout its course in the plains, the Ravi flows everywhere in a comparatively narrow valley, often only a couple of miles in width, with generally a very tortuous channel. In one part, however, the river runs a perfectly straight course for 12 miles from Kuchlumba to Sarai Sidhu in Multan District, between high wooded banks, forming a beautiful reach. Few islands are formed, but the bed shifts occasionally from place to place. The floods of the Ravi only fertilize a fringe of 1 or 2 miles on either side, and it is little employed for direct irrigation, although it supplies water both to the Bari Doab and Hasli Canals. Navigation is difficult, but grain is shipped from Lahore in considerable quantities. *Deodar* timber, floated down in rafts from the Chambra forests, only finds its way to Lahore in seasons of heavy flood. In former times the Ravi did not join the Chenab until a point below Multan city, and its ancient bed may still be traced. Even now, at times of high flood, the water finds its way to Multan by the old channel.

Rawal Pindi—Division or Commissionership under the jurisdiction of the Lieutenant Governor of the Punjab, lying between $31^{\circ} 32'$ and $4^{\circ} N$ lat, and between $71^{\circ} 37'$ and $74^{\circ} 31' E$ long. The Division, which includes an area of 15,435 square miles, comprises the four

Districts of RAWAL PINDI, JEHLAM (Jhelum), GUJRAT, and SHAHPUR, all of which see separately. Bounded on the north by Hazára and Pesháwar Districts; on the east by the Native State of Kashmír; on the south by Jhang, Gujránwála, and Siálkot Districts; and on the west by Kohát, Bannu, and Dera Ismáíl Khán Districts.

The population of Ráwal Pindi Division was returned by the Census of 1868 at 2,197,041. The last enumeration in 1881 disclosed a population of 2,520,508, showing an increase of 323,467 in thirteen years. The results of the Census of 1881 may be summarized as follows:—Area of the Division, 15,435 square miles, with 24 towns and 4570 villages; number of houses, 329,573; number of families, 541,822. Total population, 2,520,508, namely, males 1,346,573, and females 1,173,935; proportion of males, 53·4 per cent. Average density of population, 163 persons per square mile, varying from 349 per square mile in Gujrát to 90 per square mile in Sháhpur. Average number of persons per town or village, 549; inmates per house, 7·65. Classified according to sex and age, the Census shows—under 15 years of age, males 544,743, and females 475,962; total children, 1,020,705, or 40·5 per cent. of the population: 15 years and upwards, males 801,830, and females 697,973; total adults, 1,499,803, or 59·5 per cent.

Religion.—As regards religious distinctions, Muhammadans form the great majority of the population, numbering 2,193,558, or 87 per cent. Hindus are returned at 278,587, or 11·0 per cent.; Sikhs, 42,555, or 1·6 per cent.; Christians, 4522; Jains, 1100; and Pársís and ‘others,’ 186. Among the ethnical divisions, the Játs come first, numbering 352,914. Of these, only 7769, or 2·2 per cent., still retain the ancestral creed of their Hindu or Sikh forefathers; the remainder are the descendants of converts who embraced Islám during the earlier Muhammadan invasions. Rájputs number 303,131, of whom all except 2563 are returned as Muhammadans by religion. The Muhammadan population by race, as distinguished from descendants of converts, consists of—Sayyids, 60,138; Shaikhhs, 49,341; Patháns, 46,192; Mughals, 44,016; Kashmírís, 66,937; and Balúchís, 13,497. The chief Hindu castes who still retain their ancient faith, although representatives of Islám are found even among them, include—Bráhmans, 42,663; Khattris, 109,885; and Arorás, 83,507. The other principal castes and tribes, almost all Muhammadans by religion, with a sprinkling of Hindus and Sikhs, include—Awáns, 279,204; Gújars, 138,655; Chuhras, 113,601; Juláhas, 111,963; Mochís, 90,004; Tar-kháns, 69,372; Moniars, 53,115; Kumbhárs, 52,869; Arains, 44,432; Náís, 43,659; Lohárs, 40,214; Machhís, 32,347; Telís, 31,360; Mirásís, 30,077; Charhoás, 29,053; Dhobís, 25,735; Sonárs, 21,372 (including 18,143 Hindus); Ghakkars, 20,776; Jhinwárs, 17,363;

RAJAL PINDI

Khokhar, 12,841, Durzis, 10,244, and Khojas, 7658 The Christian population consists of Europeans, 4128, Eurasians, 214, and natives of India, 180

Town and Rural Population—Rawal Pindi Division contains six towns with a population exceeding ten thousand inhabitants, namely, RAWAL PINDI, 52,975, JEHLAM, 21,107, GUJRAT, 18,743, PIND DADAN KHAN, 16,724, BHERA, 15,165, and JALALPUR, 12,839 Besides the foregoing, there are 18 minor towns, with an aggregate of 102,910 inhabitants, bringing up the total urban population to 240,463, or 9.6 per cent of the population of the Division There are 20 municipalities, with an aggregate population of 213,403, total municipal income (1883-84) £28,414, or an average of 2s 8d per head Of the 4594 towns and villages in the Division, 1496 are returned as containing less than two hundred inhabitants, 1604 between two and five hundred, 922 from five hundred to a thousand, 423 from one to two thousand, 98 from two to three thousand, 33 from three to five thousand, 12 from five to ten thousand, and 6 upwards of ten thousand inhabitants As regards occupation, the male population over 15 years of age are thus returned—(1) Professional class, including civil and military, 39,293, (2) domestic class 25,423, (3) commercial class, including bankers, merchants, traders, and carriers, 28,437, (4) agricultural and pastoral class, including gardeners, 420,369, (5) industrial and manufacturing class, including gardeners, 184,705, (6) indefinite and non productive class, including general labourers, 67,195, and (7) unspecified class, 36,408

Agriculture—According to the Punjab Administration Report for 1883-84, out of a total assessed area of 15,308 square miles, or 9,796,992 acres, 3,518,493 acres were under cultivation in that year, 1,246,287 acres were returned as grazing land 2,011,847 acres were cultivable, but not under tillage, and 3,020,366 acres were uncultivable waste Of the cultivated area, 660,086 acres were artificially irrigated, namely, 62,407 acres from Government works, and 597,679 acres by private individuals from wells, etc The great crop of the Division is wheat, which is grown on 1,362,339 acres, followed by *barley*, 792,889 acres, *jowar*, 175,823 acres, *barley*, 136,617 acres, *gram*, 95,347 acres, Indian corn, 79,948 acres, and pulses, 190,331 acres Rice is grown on only 8309 acres Cotton occupies 82,045 acres, sugar cane, 9737 acres, and tobacco, 6474 acres

Administration—The administrative staff of the Rawal Pindi Division consists of a Commissioner of Division, who is directly responsible to the Lieutenant Governor of the Province, with an additional Judicial Commissioner, 4 Deputy Commissioners, each with a Judicial Assistant, a Cantonment Magistrate, and ordinarily 10 Assistant and extra Assistant Commissioners, 17 *tahsildars*, 12 *munisifs*, and

9 honorary magistrates, besides a staff of subordinate village officials, and the usual police, medical, and public works officials. The gross revenue of the Division in 1883-84 amounted to £329,160, of which £238,070 was derived from the land. Protection to person and property is afforded by 53 civil and revenue courts, and 41 criminal courts, with a regular police force of 2370 officers and men, stationed at 62 police circles, besides a village watch or rural police of 2682 *chaukidárs*. There are altogether 8 jails and Sub-divisional lock-ups, with an average daily prison population in 1883 of 1505, of whom 1395 were labouring convicts. Means of communication are afforded by 301 miles of the Punjab Northern State Railway, with its branches to Kushalgarh, and to the Salt Mines; by 224 miles of metalled and 3752 miles of unmetalled roads; and by 407 miles of navigable rivers.

There are 247 Government and aided schools in the Division, attended by 20,952 pupils in 1883-84. This is exclusive of uninspected indigenous village schools; and the Census of 1881 returned 22,853 boys and 875 girls as under instruction, besides 59,734 males and 1160 females able to read and write, but not under instruction.

Medical relief is furnished by 36 hospitals and dispensaries, attended in 1883-84 by 4540 in-door and 284,189 out-door patients. Total number of deaths registered in the Division in 1883-84, 64,701, showing a death-rate of 25·6 per thousand.

Ráwal Pindi.—District in the Lieutenant-Governorship of the Punjab, lying between 33° 3' and 34° 4' N. lat., and between 71° 46' and 73° 41' E. long.; with an area of 4861 square miles, and a population in 1881 of 820,512 souls. It forms the most northern of the four Districts of the Ráwal Pindi Division, and occupies the table-land between the Salt Range, the outer Himálayas, and the Indus. Bounded on the north by Hazára District; on the east by the river Jehlam (Jhelum); on the south by Jehlam (Jhelum) District; and on the west by the river Indus, which separates it from Pesháwar and Kohát Districts. Ráwal Pindi stands sixth in order of area, and seventh in order of population, among the 32 Districts of the Punjab, comprising 4·56 per cent. of the total area, and 4·36 per cent. of the total population of the Province. It is divided into seven *tahsils*, of which Pindi Gheb lies in the south-west; Attock in the north-west; Fatehjang in the south centre; Gújar Khán in the south-east; and Ráwal Pindi in the north-east; with Kahúta *tahsíl* in the extreme east, and the small *tahsíl* of Marri (Murree) in the extreme north-eastern corner. The administrative head-quarters of the District and Division are at the town of RAWAL PINDI.

Physical Aspects.—The District of Ráwal Pindi forms a portion of the rugged and broken Himálayan spur which projects irregularly into the northern angle of the Sind Sagar Doáb. Its surface is cut up in

every direction by mountain ranges entering it from either side, while the intermediate valleys are intersected by minor heights, whose confused and irregular masses crop out in picturesque diversity, to the despair of the systematic geographer. So far as these fantastic bosses can be reduced to any order, they naturally divide themselves into two characteristic regions, on the east and west of an imaginary central line. The eastern range, running along the side of the Jehlam (Jhelum) river, is known by the name of the Murree (Marri) Hills, from the sanitarium perched upon its northern extremity. It is composed of sandstone slopes, the direct outliers of the Himálays and is clothed with magnificent forest trees and a rich undergrowth of brushwood. Near the summer station of Murree (Marri) the spur attains a height of 8000 feet, and stretching thence into the District of Hazára loses itself at last in the snowy ranges of Kashmir. The view from the sanitarium embraces the white cloud like summits of the Kashmir Mountains, with a rich and varied foreground of mingled forest and cultivation clothing the hill sides angular, but gaining in picturesqueness what they lose in sublimity. Southward the hills decrease in height, growing more diversified and cottages appear on every jutting ledge half hidden amid the foliage, overtopped by a graceful mosque and threatened from above by some frowning fortress of Sikh or Ghakkar chieftain. At length, on the southern frontier the hills slowly subside into a comparatively level country, only divided from the valley of the Jehlam by a narrow barrier of sandstone.

The western half of the District presents a very different appearance. Its mountains belong to the trans Indus system, which is here severed by the deeply cut channel of the great river, so as to give off a series of isolated ridges cutting up the opposite bank into wild mazes or limestone hills. The soil here is dry and barren, the vegetation scanty and stunted, the valleys are mere water worn ravines or bed-flooded torrents, and the population is crowded into large villages which lie scattered at great distances among the inhospitable rock. The chief range of the western mountains is known as the Chit Pahár, from the whiteness of its exposed nummulitic beds. To the north lies the fertile valley of Chach, one of the rare oases which relieve the wildness of this savage waste. A minor range ends in the black cliffs of Attock an important ferry and fortress on the Indus. Smaller lines of hills cover the remainder of the area, in too great numbers for special description.

Of the rivers of Ráwal Pindi, the INDUS claims first rank. It bounds the District along its whole western edge. After entering in a narrow channel from Hazára, it suddenly expands to a breadth of more than a mile, dividing the fertile plains of Chach and Yusafzai, and embracing many wooded islets in its placid stream. At Attock it

contracts once more, as it rushes under the dark rocks of Jalália and Kamália; while below, it again becomes a broad lake at Bágh Niláb, and yet again narrows to pass through the beetling gorge of the Mokhad Hills. At Mokhad it becomes navigable for steamers, and immediately passes beyond the borders of Ráwal Pindí. In 1884, an iron-girder railway bridge across the Indus, with a sub-way for ordinary traffic, was completed at a point about three miles south of Attock fort. The Indus does not at present afford any facilities for irrigation, but were a canal cut through the Chach plain, it is believed that a considerable area might be thus watered. The average depth of the Indus at Attock is 17 feet in the winter and 50 feet in the summer. Its average fall between Attock and Kálábágh (in Bannu) is 20 inches per mile.

The JEHLAM (Jhelum) on the eastern frontier (the *Hydaspes* of Greek and Roman writers) is equally picturesque, though less important for navigation. It rises in Kashmír, and passing through the Bara Múla Pass, skirts Ráwal Pindí District from its northernmost point to its southern boundary, a distance of about 70 miles. It flows, throughout, between lofty mountains and precipitous rocks, with a clear and swift stream, but interrupted by numerous rapids, which render it incapable of navigation above Dangalli. Timber, however, is floated down in large quantities from Kashmír. Below Dangalli, 40 miles east of Ráwal Pindí town, the river becomes navigable. A good mule road has been recently made along the right bank of the Jehlam at an average elevation of 100 feet above the river, bringing the town of Jehlam into direct communication with the new suspension bridge on the Murree and Kashmír road at Kohála. The Jehlam forms no islands in Ráwal Pindí District, nor is it used for irrigation, its steep and rocky sides forming an insurmountable obstacle even to the smallest cuts.

The next river in importance is the SOHAN, which receives the drainage of the central portion of the District. Taking its rise within a few miles of Murree, it flows down deep valleys for the first 10 miles of its course, till it reaches the plains near the old ruined fortress of the Ghakkars at Pharwála, whence it takes a south-westerly course throughout the entire length of the District. It is crossed by a fine bridge 3 miles to the east of Ráwal Pindí town, and finally joins the Indus 10 miles below Mokhad. The bed of the river is for the most part sandy, with an occasional mixture of stiff clay, except in the upper portion, where it is composed of large boulders and rocks. Quick-sands are numerous, and often dangerous, in the lower parts. No ferries are maintained on the Sohán, and the river is fordable at all seasons, except after heavy floods. Its waters are diverted to a small extent for mills, and to irrigate low-lying lands; but its violent

floods are an insuperable obstacle to the erection of any works of a permanent character

The only other river requiring notice is the HAROH, which flows in the same direction as the Sohān, but more to the westward. Dehouching from the Hazāra hills near Khānpur, it takes a westerly course towards the Gandgarh hills passing 9 miles north of Hasan Abdal, and eventually falls into the Indus, 12 miles below Attock. Numerous small cuts afford irrigation to a large tract of country in the neighbourhood of Usman Khatar and Hasan Abdal. The stream also affords motive power to several flour mills.

Forests — The forests of Rāwal Pindī consist of two divisions, namely, the hill forests of Murree and Khātā *tahsil*, and the *rahal*s or Government reserves which were found to be without owners at the time of settlement, and were accordingly marked out as Government wastes. These *rahals* are situated in the plains portion of the District, in *tahsils* Rāwal Pindī, Pitehjang Attock and Pindī Gheb.

The hill forests are characterized by pine and oak as the chief products. In the extreme north of Murree *tahsil*, *Pinus excelsa*, *Quercus dilatata* and *incana*, together with *Populus alba* and *ciliata*, *Cedrela toona*, *Ulmus Wallichiana*, *Celtis australis*, *Acer villosum* and *pictum*, *Asculus indica*, are found in the higher forests while south of Murree grow *Pinus longifolia* and *Quercus incana* with some *Annulata*, *Pyrus Acacia modesta*, *Pistacia integerrima*, *Zizyphus Jujuba*, *Eugenia Jambolana*, *Dalbergia Sissoo*, *Olea cuspidata*, etc. The lower Khātā forests present the curious mixture of *Pinus longifolia* and *Dodonaea viscosa*, with hardly any other tree or bush. The pine forests (*longifolia*) are very liable to destructive fires, often lit by villagers with the intent of burning off the thick layers of pine needles which destroy the grass. The chief brushwood plants are *Indigofera heterantha*, *Berberis aristata*, *Carissa diffusa*. The pine (*chit*) is largely used for building, while the oak, acacia, olive, and other hard woods are utilised in large quantities for fuel. Hitherto the Government and villagers have had a kind of partnership, the former claiming all trees of spontaneous growth, while the latter have liberty to graze their cattle everywhere they please, and to cut wood for domestic purposes without restriction. Trees for building are granted free on application to *tahsildars*. The sale only is prohibited.

The reserves on the plains (*rahals*), nine in number, with a total area of 66,971 acres, consist, with one exception, of hills standing out from the surrounding country. The largest of these, Margalla, with an area of 24,362 acres is the south side of the range where the Hazara Hills come abruptly to an end. Its highest point is 5200 feet, from 3500 feet upwards pine occurs, but below this the vegetation is the same as

elsewhere in the plains' reserves, namely, *Acacia modesta*, *Acacia Catechu*, and *Olea ferruginea*. Peculiar to Margalla are *Mallotus philippinensis*, which forms occasionally dense thickets; also *Buxus sempervirens* or the boxwood tree. Of brushwood, there are *Dodonæa*, *Justicia adhatoda*, *Prinsepia utilis*, *Celastrus spinosus*, *Carissa diffusa*, etc. *Dodonæa* burns well when green, and is a good roofing material, as white ants do not eat it.

Of a total area of 649 square miles in Rāwal Pindi District under the Forest Department in 1882, 104 square miles were 'reserved' forest (*rakhs*), and 171 square miles 'protected' hill forest, while 374 square miles were unreserved. A few wild products are obtained in the forests, but in such small quantities as hardly to deserve the name of market articles: flower buds of the *kachnār*, used as food and for pickles; wild pomegranate seeds for medicinal purposes; fir oil (from the trees); gum, honey, and wax; and various small fruits, such as blackberries, raspberries, sloes, cranberries, and wild pears. The only people who live by pasturing cattle in the forests are Gūjars, who, to the number of about 200, bring down large flocks of goats and sheep from Kāgān and the distant mountains to graze during the winter months in the more genial climate of Murree and the adjacent hills. With the approach of summer they retire to the higher ranges.

Minerals.—Rāwal Pindi is not rich in minerals. A beautiful veined marble (*abri*) is found in Kawagāh hill, and can be worked into cups; but the cost is high, owing to the hardness of the stone and the scarcity of skilled labour. A sulphur mine, formerly worked by the Sikhs, exists at Zohra village, north-east of Rāwal Pindi town. Petroleum is found in small quantities at Ratta Hotar, near the same locality, 13 miles from Rāwal Pindi town, and also at Sadkal on the road from Fatehjang to Campbellpur. In 1882, two wells and seven borings yielded 5000 gallons of oil. Gypsum is found in considerable quantities along the southern part of the hills, but is not utilized. Lignite is occasionally met with in small quantities in the hills, and an inferior description of anthracite is found in small quantities in Pindi Gheb *tahsīl*, near the banks of the Indus. Quite recently, true coal has been discovered in several villages, and has been worked by the Punjab Northern State Railway. It has only been found in or near the surface, in wedge-shaped pockets which gradually taper out and disappear in shale. Gold-washing is carried on in the sands of the Indus and several of its tributaries. The gold-washers earn but a precarious livelihood, estimated to average about the wages of a common day-labourer.

Wild Animals.—Tigers, which were numerous thirty years ago, are now almost extinct. Leopards are, however, still common in the hills, and wolves, hyænas, jackals, and foxes are found all over the District.

Barking deer, rovine deer, and *uril* are found in the more secluded and inaccessible tracts. Small game are scanty. Hares are found in all the low hills and in most ruines and sparsely cultivated tracts, four kinds of partridges are met with but not plentifully. There are a few pheasants and jungle fowl near Murree. Among migratory birds are *obara* sand grouse, duck snipe geese coulon and quail. Good *mahasir* fish are to be caught in the Indus and in the Sohán Haro and Kurang streams. Fishing as a sole means of livelihood is nowhere practised except on the Indus. The poisonous varieties of serpents are scarce and deaths from snake bite are rare. Hawking is a favourite pastime with natives. Several leading chiefs and native gentlemen keep a large number of hawks, and an establishment of trained falconers.

History—Few Districts in India can claim so long a period of authentic history as Ráwal Pindi for although it does not share in the mythical glories of the *Mahábhārata* it contains many of the towns connected with the great events of Alexander's Punjab campaign, and is accordingly enshrined in the pages of Arrian and Pliny. Its earliest inhabitants appear to have been the Tukkas a Turanian race who held the greater part of the Sind Ságar Doab and gave their name to the town of Takshásila (the *Taxila* of Greek geographers). Alexander found it 'a rich and populous city the largest between the Indus and Hydaspes' and its site has been identified in the ruins of DERI SHAHAN or SHAH DERI, which lie to the north of the Margala Pass in this District. Fifty years after Alexander's invasion the people of Taxila were subject to the King of Magadha and a rebellion on their part was put down by Prince Asoka afterwards the famous Buddhist Emperor of Upper India. The notes of the two great Buddhist pilgrims from China during the middle ages show us that Taxila remained a place of peculiar sanctity until the period of Muhammadan conquest. Many relics of ancient temples are still to be found in the District and legend connects their sites in several cases with important events in the life of Buddha.

When the Musalman invasions first draw the veil which hangs over Indian history from the era of Alexander down to the 11th century we find the country around Taxila in possession of the Ghakkars a tribe who are described by Ferishta as mere savages addicted to the grossest forms of polyandry and infanticide. In 1008 Mahmud of Ghazni was met on the plains of Chach by the forces of the Rajput confederacy under Prithwi Rájá and his victory was almost averted through the impetuous attack of 30 000 Ghakkars. But the battle ended in the total defeat of the Rajputs and all Upper India lay helpless at the feet of the Musalman conqueror. Mahmud however, appears to have left the Ghakkars in quiet possession of their mountain home,

and to have pressed on to the occupation of more fertile regions. The Ghakkars are next heard of in 1205, when the reverses of Shaháb-ud-dín Ghori in Kharizm encouraged them to rise in revolt against their Muhanmadan suzerain, and to ravage the Punjab up to the very gates of Lahore. But the Sultán returned unexpectedly to India, defeated the rebellious Ghakkars with great slaughter, and compelled them to embrace the faith of Islám. Shaháb-ud-dín did not live to profit by their conversion; for on his way home to his western dominions he was surprised on the farther bank of the Indus by a Ghakkar detachment, who swam the river and murdered him at night in his tent. Under subsequent rulers, the country maintained its character for turbulence, being always ready for revolt whenever the misfortunes of the reigning prince afforded a favourable opportunity.

Bábar attacked the Ghakkar capital of Pharwála, and he gives an interesting account of its capture in his autobiography. It was strongly situated in the hills, and was defended with great bravery by its chief Háti Khán, who escaped from one gate as the Mughal army marched in at the other. Háti Khán died by poison in 1525; and his cousin and murderer, Sultán Sárang, made submission to Bábar, who conferred upon him in return the Putwár country. Thenceforth the Ghakkar chieftains became firm allies of the Mughal dynasty, whom they were able to aid efficiently in their struggle with the house of Sher Sháh. During the flourishing period of the Delhi Empire, the family of Sárang retained their territorial possessions and high social status in the Punjab; but with the decay of the central power they fell a prey, like so many of their neighbours, to the aggressive rule of the Sikh confederacy.

In 1765, during the total paralysis of the Mughal government, Sardár Gújar Singh Bhangi, a powerful Sikh chieftain, marched from Lahore against the last independent Ghakkar prince, Mukarrab Khán, whom he defeated outside the walls of Gujrát. Mukarrab retired beyond the Jehlam, where he was soon treacherously murdered by his own tribesmen; but the traitors forthwith quarrelled over their spoil, and fell one by one before Sardár Gújar Singh. The Sikhs ruled Ráwal Pindi with their usual rapacity, exacting as revenue the last coin that could be wrung from the proprietors, who were often glad to admit their tenants as joint-sharers, in order to lighten the incidence of the revenue. Gújar Singh held the District throughout his life, and left it on his death to his son, Sáhíb Singh, who fell in 1810 before the power of the great Ranjít Singh. Another Sikh Sardár, Milka Singh, fixed upon the site of Ráwal Pindi town, then occupied by an insignificant village, for his headquarters. In spite of Afghán inroads, and the resistance of the Ghakkars, he soon conquered on his own account a tract of country round Ráwal Pindi worth three *lákhs* of

RAWAL PINDI DISTRICT

rupees (£30,000) He died in 1804, and his estates were confirmed to his son, Jūn Singh, by Ranjit Singh, until 1814, when upon Jūn Singh's death, they were annexed to the general territory of Lahore. The Murree (Marri) and other hills long retained their independence under their Ghakkar chieftains, but in 1830 the Sikhs succeeded in reducing them after a bloody struggle, by which the population was almost decimated, and the country reduced to a desert.

In 1849 Rawal Pindi passed with the rest of the Sikh dominions under British rule, and though tranquillity was disturbed by an insurrection four years later, its administration was generally peaceful until the outbreak of the Mutiny in 1857. The long anarchy and internecine strife of Sikh and Ghakkar could not be forgotten, especially in a wild and lonely region, where British organization extends with difficulty to the remote gorges and scattered hamlets of a rocky labyrinth. The events of 1857 offered an outlet for the smouldering passions of ancestral feud, and the Murree (Marri) Hills became the scene of an attempted insurrection. The authorities received information from a faithful native of a projected attack upon the station, in time to concert measures for defence. The ladies who were present in large numbers, were placed in safety, the Europeans and police were drawn up in a cordon around the station, and when the enemy arrived, expecting no resistance, they met with a hot reception which caused them to withdraw in disorder, and shortly after to disband themselves. The District has since experienced no serious commotion, but crimes of violence are frequent.

Population—In a District so extensive and so rugged as Rawal Pindi, it is naturally difficult to conduct an enumeration of the people with minute accuracy, and there are grounds for doubting the correctness of all statistics prior to the Census of 1868. An enumeration in 1855 returned the total population as 553,750. In 1868, the total number was ascertained to be 711,256 showing an increase for the thirteen years of 157,506 persons, or 28 per cent. Though the long period of peace and prosperity which Rawal Pindi has enjoyed since the British occupation would suffice to account for a large augmentation of numbers, a considerable part of this apparent increase must be set down to under enumeration in 1855. The last enumeration in 1881 returned the population at 820,512, showing a still further increase of 109,256, or 15.3 per cent, in the thirteen years since 1868. This increase, although largely due to the natural excess of births over deaths, is also in great part owing to immigration caused by the extraordinary demand for labour in connection with the Punjab Northern State Railway, and transport arrangements for the Kabul campaign.

The general results of the Census of 1881 may be summarized

as follows:—Area of District, 4861 square miles; towns 8, and villages 1639; number of houses, 124,896, namely, occupied 102,283, and unoccupied 22,613; number of families, 162,052. Total population, 820,512, namely, males 449,287, and females 371,225. The high proportion of males, 54·7 per cent., is due to the large immigration of labourers from other Districts, leaving their wives and families at home, and also to the considerable military element. Average density of population, 169 persons per square mile, varying from 68 per square mile in Pindi Gheb, to 275 per square mile in Ráwal Pindi *tahsíl*. Number of towns or villages per square mile, 0·34; persons per town or village, 498; houses per square mile, 26; persons per house, 8·02. Classified according to sex and age, the Census thus returns the population—under 15 years, males 176,126, and females 150,820; total children, 326,946, or 39·8 per cent. of the population: 15 years and upwards, males 273,161, and females 220,405; total adults, 493,566, or 60·2 per cent.

Religion.—In religion, Ráwal Pindi is a stronghold of Muhammadanism, as many as 711,546, or 86·96 per cent. of the inhabitants, being returned as adherents of Islám. The Hindus are scantily represented by 86,162 persons, or 10·50 per cent. of the inhabitants; while the once dominant Sikhs number no more than 17,780 persons, or 2·16 per cent. The remainder consist of—Christians, 3822; Jains, 1033; and Pársís, 169. As regards the ethnical divisions of the people, the Bráhmans of Ráwal Pindi number 18,523 persons; but in this extreme northern corner, surrounded by an overwhelming Musalmán element, and engaged in commerce or agriculture, the Bráhmans find little scope for their priestly character, and indulge in many practices which would scandalize their stricter brethren in the south. Yet they are quite as minutely sub-divided as elsewhere into minor clans, each of which has its acknowledged rank in the social scale, and refuses to eat or intermarry with the inferior classes. The Rájputs are the strongest body numerically, having a total of 145,536 souls: their customs, however, require no special notice, and they are almost exclusively Muhammadans in creed. The principal trading classes are the Khattris (41,135) and the Arorás (12,181), both retaining the old Hindu faith, and, with their co-religionists the Bráhmans, monopolizing the commerce of the District. They replace the Baniyás of Hindustán proper, and are considered quite their equals in rapacity and cunning. The Játs number 47,935, almost all Muhammadans, and keep up their usual reputation as careful and industrious agriculturists. In the eastern half of the District they form the principal labouring population. The Ghakkars, whose history has been already detailed, now amount to only 12,007 persons. They are a fine and spirited race, gentlemen in ancestry and bearing, and clinging under all reverses to the traditions

of noble blood. Though reduced to poverty in many cases by the Sikhs, they are still respected in the District as a native aristocracy, and would come to the front, for good or for evil, in any period of general disturbance.

The Muhammadan population by race, as distinguished from descendants of converts, consists of—Patháns, 36,465, Shaikhs, 25,524, Mughals, 25,169, and Sayyids, 20,422. The other tribes and classes are mainly descendants of Hindu converts, but are now almost exclusively Muhammadans by religion, with a slight Hindu or Sikh element. The principal of these tribes are—Anáns, 124,834 in number, Maniars, 41,701, Juláhas, 37,001, Gujars, 25,403, Kashmiris, 23,803, Tarkhans, 22,450, Chuhars, 22,046, Muchis, 20,385, Kumbhárs, 14,668, Félis, 12,384, Lohárs, 12,236, Nais, 11,996, Jhinwars, 8632, Sonars, 6523, Mirásis, 6205, Darzis, 6109, and Dhobis, 5751.

Town and Rural Population—The population of Rawal Pindi District is almost entirely rural, and the great bulk of the inhabitants are scattered in tiny hamlets over the face of the country. The Census Report returns eight towns, as being civil stations, municipalities, or cantonments. These are—RAWAL PINDI town, population (1881) 52,975, PINJI GHFB, 8583, HAZRO, 6533, FATEHJANG, 4875, ATROCK, 4210, MOAHAD, 4195, MURREE, 2489, and CAMPBELLPUR, 1467. The population of Murree during the height of the summer season rises as high as eight thousand. Of the 1647 towns and villages in the District, 621 contain less than two hundred inhabitants, 584 between two hundred and five hundred, 279 between five hundred and a thousand, 121 between one and two thousand, 26 between two and three thousand, 13 between three and five thousand, and 3 upwards of five thousand inhabitants.

Material Condition of the People—The people, as a rule are well off, the assessment of the land revenue is light, and the profits of the farmer are large. A holding of 15 acres of average land will enable a man to support his family in tolerable comfort. The number of large incomes, however, is not great. The ordinary expenditure of a well-to-do cultivator is estimated as varying from 18s per month in the western portion of the District to £1, 4s in the east. For this sum an ordinary family of, say, five persons can live comfortably. A shopkeeper, who has to buy what a cultivator supplies from his own garden plot, will spend from £1, 4s per month in the west to £1, 10s in the east of the District. The lowest sum upon which an adult can support life is 4s per month in the west, and 5s per month in the east of the District. The most ordinary social distinction among the people is that of *saku* or gentleman, and *zamindar* or cultivator. The Ghakkars, Rajputs, and Sayyids are considered as belonging to the former class, while the Játs and Awans may be looked upon as typifying the latter.

indigo blue, which tints the hands and faces of the wearers, giving them a wild and forbidding appearance. In these tracts, and generally in the western part of the District, the turbans worn are of vast dimensions, and look very imposing. In Khatar, and generally in the hilly tracts bordering on the Indus, sandals, called *lherz*, are worn instead of leather shoes. The women wear the same kind of costume as the men, with the exception of their trousers, which are generally of cotton, dyed blue, with red or yellow lines from top to bottom.

As regards occupation, the Census Report of 1881 returned the adult male population under the following seven classes—(1) Professional class, including all Government officials, civil and military, 17,209, (2) domestic and menial class, 7995, (3) commercial class, including bankers, merchants, traders, carriers, etc., 10,091, (4) agricultural and pastoral class, including gardeners, 145,611, (5) industrial and manufacturing class, including all artisans, 62,560, (6) indefinite and non-productive class, including general labourers, 27,151, (7) unspecified, 2544.

Agriculture—According to the Punjab Administration Report for 1883-84, out of a total District area of 4937¹ square miles, or 3,160,116 acres, 1,220,916 acres were under cultivation, 316,800 acres were cultivable, and 1,622,400 acres were uncultivable waste. The staple spring crop of the District is wheat, while *bajra* (spiked millet) forms the mainstay of the autumn harvest. The other crops are—gram, barley, and mustard seed in the spring, and *jodr* (great millet), Indian corn, cotton, and the common pulses in the autumn harvest. Rice is grown to a small extent in the Murree hills, but is of an inferior quality. The cotton too, though improved of late years, is still inferior, being grown only on unirrigated land. Wheat, gram, and rice are increasing in importance as staple products, while the inferior crops of *bajra*, *joar*, and Indian corn, on the other hand, are less cultivated than they used to be. The potato was introduced in the Murree hills shortly after annexation. Some years elapsed before its cultivation became general, but it is now recognised as a lucrative crop, and almost every hill village has its patch of potato cultivation. The people themselves consume the produce to a certain extent, but the greater part is sold in Murree or exported to the plains. Experiments have been made with tea, but in spite of great care and solicitude, every attempt to naturalize the shrub has failed. The area under the principal crops in 1883-84 is returned as follows—Wheat, 436,262 acres, *bajra*, 326,330 acres, Indian corn, 55,277 acres, gram, 36,959 acres, *joar*, 24,169 acres, pulses and other food grains, 67,237 acres, oil seeds, 108,314 acres, cotton, 16,036 acres, vegetables, 3160. Sugar cane, tobacco, drugs, spices, etc., are grown over small areas.

As almost every field in the District is more or less on an incline, the rain water rapidly drains away, without benefiting the soil, and it has

The dwellings of the people, even of the better sort, are mostly constructed of unburnt bricks, single-storied, and generally not more than 8 or 10 feet high. Except in the case of some of the Ghakkar gentry, and a few notabilities, a house constructed of burnt brick, and cemented with lime and mortar, is unknown. In the Mokhad hills and other localities, stone cemented with mud and unplastered is much used. In general, however, the houses are plastered with mud and cow-dung, having flat roofs. Across the rafters, the roof is covered with branches and leaves, upon which mud is beaten, well plastered with earth mixed with chopped straw, and above all a cow-dung coating. Glass windows and hinges are unknown; even in the best dwellings the doors revolve in wooden sockets, and are closed with a chain and rough padlock. The interior of the dwelling presents, even among the ordinary class of peasantry, an appearance of great comfort. Although the walls and floors are rough and uneven, they have a light-coloured appearance, from constant hand-rubbing with a mixture of light clay and cow-dung. The furniture ordinarily consists of a few pallets (*chirpái*), some stools, spindles, a grain receptacle, and a box or trunk for clothing, etc. An adjoining shed shelters the cattle and horses, and another the store of fodder. An enclosure, called *sahn* or *rehra*, forms a kind of compound; and this, with an adjacent higher one for sheep and goats, built of strong prickly thorns so as to keep out wolves, completes the habitation of one family. In each village are one or more *hijrás*, or general assembly rooms, where travellers are entertained, and all questions relating to the village or section of the village are discussed. A number of the foregoing clumps of dwellings, massed together, without the slightest regard for symmetry, so as to leave narrow lanes, scarcely wide enough to allow a laden donkey to pass; one or more *hijrás*; one or two neat mosques, and a clump of trees—the whole planted on a slightly elevated site above the level of the surrounding country—make up a rural village in Ráwal Pindi.

The ordinary food of the people consists chiefly of *bájrā* (spiked millet) during the winter months, and of wheat mixed with barley in the summer. In bad years, the poorer classes content themselves with a kind of pulse, called *bhakra*, which grows as a trailing creeper in great profusion. Meat, *ghí* (clarified butter), *dál*, spices, and vegetables are eaten, when they can be afforded. Ten per cent. of the population drink spirits; *charas* (an intoxicating preparation of hemp) is largely smoked. Kashmiris and Patháns drink tea.

The almost universal dress is white cotton of a coarse description, with an occasional blue turban and waistband, loose white trousers (*paijáma*), and leather shoes. In Chach and Mokhad, where the population is almost entirely Afghán, the dress of the lower orders is

indigo blue, which tints the hands and faces of the wearers, giving them a wild and forbidding appearance. In these tracts, and generally in the western part of the District, the turbans worn are of vast dimensions, and look very imposing. In Khatar, and generally in the hilly tracts bordering on the Indus, sandals called *kheri* are worn instead of leather shoes. The women wear the same kind of costume as the men, with the exception of their trousers, which are generally of cotton, dyed blue, with red or yellow lines from top to bottom.

As regards occupation, the Census Report of 1881 returned the adult male population under the following seven classes—(1) Professional class, including all Government officials, civil and military, 17,209 (2) domestic and menial class, 7905 (3) commercial class including bankers, merchants, traders, carriers, etc., 10,091, (4) agricultural and pastoral class including gardeners, 145,611, (5) industrial and manufacturing class, including all artisans, 62,560, (6) indefinite and non-productive class, including general labourers, 27,151, (7) unspecified, 2544.

Agriculture—According to the Punjab Administration Report for 1883-84, out of a total District area of 4937½ square miles or 3,160,116 acres, 1,220,916 acres were under cultivation, 316,800 acres were cultivable, and 1,622,400 acres were uncultivable waste. The staple spring crop of the District is wheat while *bajra* (spiked millet) forms the mainstay of the autumn harvest. The other crops are—gram, barley, and mustard seed in the spring, and *joar* (great millet) Indian corn, cotton and the common pulses in the autumn harvest. Rice is grown to a small extent in the Murree hills but is of an inferior quality. The cotton too though improved of late years, is still inferior being grown only on unirrigated land. Wheat, gram, and rice are increasing in importance as staple products, while the inferior crops of *bajra*, *joar* and Indian corn, on the other hand, are less cultivated than they used to be. The potato was introduced in the Murree hills shortly after annexation. Some years elapsed before its cultivation became general but it is now recognised as a lucrative crop, and almost every hill village has its patch of potato cultivation. The people themselves consume the produce to a certain extent, but the greater part is sold in Murree or exported to the plains. Experiments have been made with tea but in spite of great care and solicitude, every attempt to naturalize the shrub has failed. The area under the principal crops in 1883-84 is returned as follows—Wheat, 436,262 acres, *bajra* 326,330 acres Indian corn 55,277 acres, gram, 36,959 acres, *joar*, 24,169 acres, pulses and other food grains, 67,237 acres, oil seeds, 108,314 acres, cotton, 16,036 acres vegetables 3160. Sugar-cane, tobacco, drugs, spices, etc., are grown over small areas.

As almost every field in the District is more or less on an incline, the rain water rapidly drains away, without benefiting the soil, and it has

been necessary in most cases to retard its escape by a rude system of terraces, embanked at their lower extremity. A more ambitious work, requiring the co-operation of villages and expenditure of capital, is the embankment of ravines, which is practised to some extent both here and in the neighbouring District of Jhelam. Irrigation by any other mode is little employed, and the total irrigated area in 1883-84 was returned at only 34,421 acres. The manured lands yield two crops a year, or are sometimes sown for three consecutive harvests with wheat and *hijra* alternately, and lie fallow for the fourth; inferior soils are made to bear two crops in the same year (wheat, followed by *hijra*), and then recruit during the following twelve months. Rotation of crops in any higher form is unknown. The average produce per acre is given in the Government returns for 1883-84 as follows:—Rice, 654 lbs.; wheat, 680 lbs.; inferior grains, 658 lbs.; oil-seeds, 330 lbs.; and cotton, 98 lbs.

The peasantry are in comfortable circumstances; their houses are neatly furnished and fairly clean, and they are gradually extricating themselves from the village money-lender. Under Sikh rule, it is calculated that 50 per cent. of the cultivators were in debt; at present, only 10 per cent. are believed to be so involved. The tenures of the District are very varied, from the ancestral *samindāri*, or undivided holding with division of profits, to the modern occupancy right of tenants. Rents vary according to the nature of the soil and the caste and social status of the tenant. A tenant with occupancy rights pays a rent of 4s. 6d. an acre for average land; while a tenant-at-will pays 5s. 9d. for the same land. The ordinary range of rent may be put down at from 5s. to 6s. an acre for the higher class of tenants, and from 4s. to 8s. for the lower class. In many parts of the District, however, especially near Gújar Khán, all tenants alike pay their rent in kind, at rates varying from one-fourth to one-half of the produce. Both cash and grain rates for tenants-at-will are steadily rising; and many who at the time of the last Land Settlement paid only a one-fourth or a two-fifths share of the produce, are now glad to pay a one-half share. The Government land revenue assessment in 1883-84 amounted to £73,005, being at the rate of 1s. 2d. per cultivated acre.

Wages have increased from 50 to 75 per cent. since the Sikh rule. In towns they are paid in cash, unskilled labourers receiving from 3d. to 6d., and skilled labourers from 6d. to 1s. 3d. a day. The agricultural labourer generally receives his wages in kind. The *samindār* requiring extra labour obtains it from his neighbours who have no work of their own to do, and in return supplies them with food once daily. This system is called *lehtri*, and recourse is had to it for carrying on the operations of ploughing, sowing, and reaping. The other plan goes

by the name of *Idhar*, under it the *Lamuns* or village menials, or hilly men, or poor people from other estates, are employed to reap the harvest, and are paid in kind at the rate of one twentieth part of what they gather during the day. Prices were returned as follows in January 1884.—Wheat, 27 *seers* per rupee, or 4s 2d per cwt, barley and *joar*, 40 *seers* per rupee, or 2s 10d per cwt, *bajra*, 45 *seers* per rupee, or 2s 6d per cwt, Indian corn, 38 *seers* per rupee, or 2s 11½d per cwt, rice, 6½ *seers* per rupee, or 17s 4d per cwt.

Rawal Pindi is a considerable stock breeding District. The best horses are found in Fatehjang and Pindi Gheb *tahsils*, where the large size of the holdings in the hands of comparatively wealthy landholders gives greater facility for breeding. The horses are somewhat slight and small, but are well bred and fiery. Great difficulty, however, is experienced in inducing breeders to bestow sufficient care upon the young colts. They tie them up in close dark quarters, and put them to work while still too young. Most breeders find it too expensive to keep their colts for more than a year, and they sell them at this age to merchants from beyond the Indus. The breed, however, has much improved since the institution of the Rawal Pindi annual horse fair, at which large numbers are sold as remounts for the Native cavalry, though few are as yet found suitable for British cavalry regiments. Very fine mules are also bred in considerable numbers, and owing to the greater ease with which these animals are reared, and the earlier age at which they can be put to work, this is said to act detrimentally to horse rearing as being more profitable. In 1884, there were in the District 3228 branded brood mares—1090 for horse breeding and 2138 for mule-breeding. Twenty five horse stallions and 52 donkey stallions are stationed by Government throughout the District, at places where they are most in request. At the annual horse and mule fair in 1883, out of 1394 animals exhibited, 819 were sold. Prizes were awarded to the amount of £200. Camels of a fine breed are reared in several parts of the District. Rawal Pindi was formerly noted for its camels, and although the stock is said to have fallen off since the time of the Mutiny, it still contains a larger number of camels than any other District in the Punjab. Goats and sheep are reared, not so much for sale, as for the wants of the people themselves, and for the sale of the goats' hair and sheep wool, which is exported. The agricultural stock in the District in 1883-84 is returned as follows.—Cows and bullocks, 300,871, horses, 9296, donkeys, 33,258, sheep and goats, 417,144, and camels, 24,149.

Natural Calamities—In 1843-44, during the Sikh supremacy, Rawal Pindi was devastated by an incursion of locusts, which overran the whole country in enormous swarms, and for a while almost succeeded in depopulating the District. They appeared just in time to devour

the whole autumn crop of 1843; they remained for the succeeding spring crops; and at last they took their departure after utterly destroying the autumn harvest of 1844. Ráwal Pindi is still suffering from the remote effects of this terrible visitation. The Sikh authorities insisted upon realizing the utmost farthing of their revenue from the starving cultivators, who were obliged to have recourse to the trading classes, and so commenced a system of chronic indebtedness, which has not even yet entirely passed away. The tenures of land were completely revolutionized, to the great disadvantage of the proprietary class, as the Sikhs admitted tenants to share the burdens and privileges of the land-owners, in order the more readily to collect their exorbitant imposts. The British courts were for long flooded with litigation, arising from the disorganization of this unhappy period.

Commerce and Trade, etc.—So rugged a District as Ráwal Pindi has naturally but little commerce, and that little is concentrated at the head-quarters town and at Házro. The only productions that give rise to any large export trade are food-grains and oil-seeds; but this only happens in years of good harvests. During 1880, 1881, and 1882, grain was imported. In 1883 the export of grain was abnormally large. Among the imports are piece-goods from Amritsar and Calcutta, sugar and *gúr* from Jálándhar, hardware from Amritsar and Lahore, cotton from Districts south of Jehlam, salt from Pind Dádan Khán, indigo from Múltán, rice from Pesháwar and Swát. Trade with Kashmír is registered at two posts, Lakshman ferry and Murree. In 1882–83, the imports into Ráwal Pindi from Kashmír amounted to £116,959 in value, consisting principally of *charas*, *ghí*, rice, raw silk, shawls, timber, fruit, and dyes; the exports from Ráwal Pindi into Kashmír were valued at £55,577, principally piece-goods, metals, salt, and sugar.

Snuff of excellent quality is manufactured at Házro, and is exported to Kashmír and Amritsar. Cotton spinners and weavers of country cloth are found in almost every village; and in Fatehjang and Pindi Gheb coarse woollen blankets are manufactured, which find a market at Ráwal Pindi and Pesháwar towns. Soap is made at Ráwal Pindi, Pindi Gheb, and Fatehjang. Leather manufactures are of considerable extent, and there is also a large manufacture of oil. European industry is represented by a brewery at Murree, established in 1860. The beer is of excellent quality, and commands a ready sale. A gas-work has been recently established at Ráwal Pindi town. The gas is extracted from locally obtained petroleum; but owing to the limited supply of the material, the gas produced has been hitherto barely sufficient to light the barracks and hospital of one European regiment. The wealth resulting from long and settled peace finds its way into the hands of the cultivating classes, and is chiefly hoarded in the form of jewellery. A great horse fair is held annually at Ráwal Pindi town, at

which Government prizes are distributed, and animals from all parts of the Punjab are exhibited and sold

Means of Communication—The Grand Trunk Road was till recently the principal means of communication, its section within the District amounts to 100 miles. The other main lines of road are—Ráwal Pindi to Murree, 39 miles, the Kashmir road from Murree to Kohala, 20 miles, and the Ráwal Pindi and Kohát road, 66 miles. There are also unmetalled roads from Hassan Abdál to Abbottábad, Campbellpur to Lawrencepur, 9 miles, Pindi Gheb to Pind Sultáni, 20 miles, Ráwal Pindi to Kahuta *via* Kothi, 49 miles, Fátchjang to Kálábágh, 23 miles, to Talagang, $17\frac{1}{2}$ miles, and to Chakwal, $13\frac{1}{4}$ miles, and from Murree *via* Kothi and Karor to Ráwal Pindi, 54 miles. Total length of metalled roads in 1883-84, 135 miles, unmetalled roads 1123 miles. The Punjab Northern State Railway from Lahore to Pesháwar now enters the District from the Jehlam border, and runs a course parallel with the Grand Trunk Road to Attock, where the magnificent bridge over the Indus, completed in 1883, carries both the railway and road across the river. A branch line of railway runs from Rawal Pindi station to Kushalgarh. Total length of railways (1883-84), 166 miles. The Indus is navigable throughout its whole course of 96 miles through Ráwal Pindi District by native craft and becomes practicable for steamers below Mokhad. The Jehlam is not navigable in any portion of its course in Ráwal Pindi. Three telegraph lines traverse the District, namely, the main wire from Lahore to Pesháwar, a branch from Rawal Pindi to the hill station at Murree (Marri), and a line to Kohat *via* Kushalgarh.

Administration—The ordinary administrative staff of this extensive District comprises a Deputy Commissioner, a Judicial Assistant, 3 Assistant and 2 extra Assistant Commissioners, 1 Cantonment Magistrate, 7 *tahsildars*, 4 *munsifs*, and 9 honorary magistrates, besides the ordinary medical and constabulary officers. There are garrisons at Ráwal Pindi, Murree (Marri) Attock, and Campbellpur. The total revenue in 1872-73 amounted to £89,226 of which £68,659, or more than three fourths of the whole, was derived from the land tax. By 1883-84, the revenue had increased to £108,109, while the land tax remained stationary at £68,878. The other principal items of revenue are stamps, local rates, excise and opium. In 1883 the District contained 18 first class and 10 second class police stations, and the regular police numbered 1022 men of all ranks, being 1 constable to every 803 inhabitants and to every 4.7 square miles. Crimes of violence are still unhappily common, human life is lightly regarded by the wild tribes of the western gorges, and the ancestral blood feuds are only lulled for a while by the severity of English law. Murders prompted by conjugal jealousy are also of frequent occurrence. The District jail at Rawal Pindi and lock ups at Murree and Attock contained 11

total of 790 prisoners in 1883. The Salt Revenue Department has a preventive establishment maintained at 15 guard posts along 77 miles of the Indus, with the object of preventing the transit of cheap Kohát salt from the right to the left bank of that river.

Education is making satisfactory progress. In 1883-84, the Government aided and inspected schools under the Education Department numbered 133, with 8933 pupils. There are also 874 indigenous village schools in the District. In 1881, the Census Report returned 8899 boys and 516 girls as under instruction, besides 24,873 males and 763 females able to read and write, but not under instruction. Female education, especially, has made rapid strides of late years, through the benevolent exertions of Bedi Khem Singh, a native gentleman of Kallár, who has established 25 girls' schools in this District, besides others in Jehlam (Jhelum); they are chiefly attended by Hindu children, though there is also a fair sprinkling of Muhammadans. The Lawrence Memorial Asylum at Murree is devoted to the education of the children of European soldiers. There is a school for the benefit of the children of European residents at Murree in the hot season, which is transferred to Ráwal Pindi during the winter. There is also a Church of England and a Roman Catholic school for girls at Murree. Since 1882, schools for European boys and girls have been established in Ráwal Pindi town, where there is also a normal school for training teachers.

There are municipalities at Ráwal Pindi, Murree, Attock, Házo, Pindigheb, and Mokhad. The total revenue of these 6 municipalities in 1883-84 amounted to £16,477, being at the rate of 4s. 2½d. per head of their population.

Cantonments and Troops.—The principal military station in the District is the cantonment of Ráwal Pindi, situated within a mile of the city, on the opposite bank of the river Leh. At Murree there is a convalescent depôt, and within a four miles' radius of the sanitarium are camps Kuldannah, Thoba, Ghariál, and the Clifden depôt. There is also a small cantonment at Campbellpur; and the bridge of boats and ferry over the Indus are guarded by Fort Attock. The ordinary garrison of Ráwal Pindi during the cold weather consists of one battery of horse and one of field artillery, and three mountain batteries; one regiment of British and one of Native cavalry, two regiments of British and two of Native infantry, and a company of sappers and miners. Of these the mountain batteries are quartered in the gullies of Hazára District, and one British infantry regiment in the Murree Hills, with headquarters at camp Kuldannah during the hot season, while detachments of the artillery and cavalry, and of the other British infantry regiments, are quartered at camp Ghariál; so that all the British troops of the garrison pass a portion at least of the hot weather in the hills. Murree is garrisoned during the season by convalescents detached

from the Ráwal Pindi and Peshawar Divisions, and the married women and children are stationed at Clifden. Campbellpur is garrisoned by two batteries of artillery, and Fort Attock by detachments from the British infantry regiment quartered at Naushahra in the Peshawar Division, one of the Native infantry regiments at Ráwal Pindi, and the battery at Campbellpur. The cantonments and military posts of the District belong to the Ráwal Pindi Division, and the troops are under the command of the general officer commanding that Division. The Ráwal Pindi fort, which has five faces, with a bastion at each corner on which heavy guns are mounted, contains an arsenal and barracks for two companies of infantry or a heavy battery. There are good positions for defence on the east and west of the station. The south west side is covered by a network of *nalas*, which render approach from that direction very difficult. The head quarters of two companies of the 1st Punjab Volunteer Corps are at Ráwal Pindi. A cadet company is composed of the boys of the Murree Lawrence Asylum.

Medical Aspects—Ráwal Pindi has two rainy seasons, the first from January to March, and the second from July to August. During the winter, the weather is cold and even severe, but in summer the heat cannot be exceeded in any part of India. Notwithstanding the excessive heat of May, June, and part of July, the climate of Ráwal Pindi is noted for its salubrity, and the District is one of the healthiest for European troops in the Province. The climate of the Murree Hills is said to be peculiarly adapted to the English constitution. The average annual mean temperature in the shade at Ráwal Pindi is returned at 69.4° F, and at Murree, 56.1° F. In 1883 the maximum, minimum, and mean temperatures of the two stations were returned as follows—Ráwal Pindi—May—max 107.5°, min 59.1°, mean 82.1°, July—max 108°, min 68.7°, mean 87.5°, December—max 69.9°, min 30.5°, mean 50.8°. Murree—May—max 84.9°, min 43.8°, mean 66.8°, July—max 85°, min 57.4°, mean 70.4°, December—max 58.8°, min 29.9°, mean 44.4°. The average annual rainfall for a period of seventeen years ending 1882-83 is returned at 30.7 inches at Ráwal Pindi, and 47.1 inches at Murree. In 1883, 27.6 inches of rain were registered at Ráwal Pindi, and 37.5 inches at Murree. The principal disease of the District is fever, which exists in an endemic form. The total number of reported deaths from all causes in 1883 was 21,477, or at the rate of 26 per thousand. Of these deaths, as many as 16,738, or 20.40 per thousand, were assigned to fever alone. Nine charitable dispensaries afforded medical relief to 2291 in-door and 92,337 out-door patients in 1883. Cattle diseases are very prevalent, and carry off a large number of the live stock.

Ráwal Pindi—*Tahsil* in the north east of Ráwal Pindi District, Punjab, lying along the foot of the Murree (Marri) Hills. Area, 769

square miles, with 1 town and 442 villages; number of houses, 24,107, of which 18,024 are occupied and 6083 unoccupied; number of families, 27,089. Total population (1881) 211,275, namely, males 122,467, and females 88,808; proportion of males, 57·9 per cent. The high proportion of males is owing to the large military population of the Ráwal Pindi cantonment. Classified according to religion, the population consists of—Muhammadans, 165,731; Hindus, 35,502; Sikhs, 5886; Jains, 940; Christians, 3052; and Pársis, 161. Of a total area of 769 square miles, the average area under crops for the five years 1877–78 to 1881–82 was returned at 317 square miles, or 202,909 acres; the area under the principal crops being—wheat, 81,686 acres; *bájra*, 46,743 acres; Indian corn, 11,389 acres; barley, 11,224 acres; *moth*, 11,044 acres, *joár*, 7263 acres, cotton, 7657 acres. Revenue of the *tahsil*, £14,789. The administrative staff (including all the head-quarter officers of the Division and District) consisted in 1881 of the Commissioner of the Rawal Pindi Division, the Deputy Commissioner of the District, a Judicial Assistant Commissioner, 3 Assistant and extra-Assistant Commissioners, Judge of the Small Cause Court, *tahsildár*, 2 *munsifs*, and 3 honorary magistrates. These officers preside over 11 civil and 11 criminal courts. Number of police circles (*thánás*), 4; strength of regular police, 164 men; village watch or rural police (*chaukidárs*), 223.

Ráwal Pindi.—Town, municipality, large military cantonment, and administrative head quarters of Ráwal Pindi Division and District, Punjab; situated in 33° 37' N. lat., and 73° 6' E. long., on the north bank of the river Leh, a muddy, sluggish stream, flowing between lofty and precipitous banks, and separating the town from the cantonments.

The present town is of quite modern origin; but General Cunningham has identified certain ruins on the site of the cantonments with the ancient city of Gajipur or Gajmpur, the capital of the Bhatti tribe in the ages preceding the Christian era. Greek and other early coins, together with ancient bricks, occur over an area of two square miles. Known within historical times as Fatehpur Baori, Ráwal Pindi fell into decay during one of the Mughal invasions in the 14th century. Jhanda Khán, a Ghakkar chief, restored the town, and gave it its present name. Sardár Milka Singh, a Sikh adventurer, occupied it in 1765, and invited traders from the neighbouring commercial centres of Jehlam (Jhelum) and Sháhpur to settle in his territory. In the beginning of the present century, Ráwal Pindi became for a time the refuge of Sháh Shujá, the exiled Amír of Kábul, and of his brother Sháh Zamán. The present native infantry lines mark the site of a battle fought by the Ghakkars under their famous chief Sultán Mukaráb Khán in the middle of the last century. It was at Ráwal Pindi, on the 14th March 1849, that the Sikh army under Chattar Singh

RAI WAL PINDI TOWN

and Sher Singh finally laid down their arms after the battle of Gujrat. On the introduction of British rule, Ráwal Pindi became the site of a British cantonment, and shortly afterwards the head quarters of a Division, while its recent connection with the main railway system by the extension of the Punjab Northern State Railway to Peshawar has immensely developed both its size and commercial importance.

The population of Rawal Pindi town, civil station, and cantonment has almost doubled within the thirteen years between 1868 and 1881. In 1868, the total population was returned at 28,586, and in 1881 at 52,975, namely, males 35,985, and females 16,990. The population of the city proper, including the civil lines, increased from 19,228 in 1868 to 26,785 in 1881. Classified according to religion, the population of the town and cantonment in 1881 consisted of—Muhammadáns, 23,664, Hindus, 23,419, Sikhs, 1919, Jains, 904, and 'others' (nearly all Christians, with a few Parsis), 3069. Number of houses, 8029. The municipal revenue, which in 1875-76 amounted to £5129, had increased by 1883-84 to £11,984. It is mainly derived from octroi duties levied on articles of food brought within the city or cantonments.

The cantonments are separated from the native town by the little river Leh, and occupy the site of an ancient Hindu city (*vide supra*). The buildings cover an area of three miles in length by two in breadth. In 1868, the cantonments contained a total population of 9358, including English and native troops. Since the last Afghán campaign, Rawal Pindi has much increased in importance as a military station, and in 1881 the cantonments contained a total population of 26,190, or nearly three times the population of 1868. The garrison usually consists of one regiment of European cavalry, two regiments of European infantry, one regiment of Native cavalry, and two regiments of Native infantry, with two batteries of artillery (horse and field), increased in the cold weather by three mountain batteries, which in the summer occupy the hills north of Murree. An arsenal was established at Rawal Pindi in 1883. The cantonment contains several European shops.

The principal buildings of Ráwal Pindi station are the courts of the Commissioner and Deputy Commissioner, Cantonment Magistrate's court, Brigade Commissariat Transport offices, and office of the Paymaster, Punjab circle, all within the civil lines. The native town contains the *tahsil* building, police station, municipal hall, and city hospital, all situated at the point where the road from the cantonments, an extension of the *sadr bázár*, enters the city. At the same point are the large *sarat* or native inn, the Presbyterian Mission Church, and the Mission School. A large and handsome public garden is maintained by the municipality, and an extensive park, thickly planted with trees and shrubs, and intersected with winding paths and drives, has been

laid out by the District authorities near the jail. The park is a favourite evening and morning resort of the Europeans of the station. The garrison church, a large but unpicturesque building, contains a window in memory of the late Bishop Milman of Calcutta, who died and was buried at Ráwal Pindi in 1876.

The railway station, telegraph office, and post-office are all fine massive buildings. There are also the station club, three good European hotels, several European shops, and a branch of the Alliance Bank of Simla. The main *bázár* contains numerous good Parsi and other shops, and the office of the *Punjab Times*. At the entrance to the *bázár*, a fine archway has been erected in remembrance of Brigadier-General Massy; and a handsome and spacious market, built by Sardár Suján Singh at a cost of £20,000, perpetuates the memory of the same officer. The barracks and church are lit with gas manufactured from petroleum found in the District. The educational and charitable institutions at Ráwal Pindi include a normal school for training teachers, schools for European boys and girls, a civil hospital, and leper asylum. Ráwal Pindi is also the head-quarters of the Manager and other heads of Departments of the Punjab Northern State Railway. The fort, which also contains the arsenal, has five faces, with a bastion at each corner on which heavy guns are mounted.

The oldest portion of the town is its north-eastern corner, where the *bázárs* are narrow and crooked, after the fashion of most native cities of small size. But elsewhere the streets are broad, straight, handsome, and regular; and as a result of this, and of the excellent drainage and sanitary arrangements, Ráwal Pindi is said to present a cleaner appearance than probably any other town in Northern India. Trees have been freely planted, and give the station a very pleasing appearance.

A considerable portion of the trade of the Punjab with Kashmír passes through Ráwal Pindi, in 1882 amounting to as much as 31 per cent. of the import and 16 per cent. of the export trade of the Province with Kashmír. Wheat and other grains are largely collected at Ráwal Pindi and exported to other parts of the Punjab. Some of the commercial houses have very extensive dealings; and there are several native banking houses of high standing. There are no manufactures or industries of importance. The chief articles manufactured are *sísí*, a coarse kind of cloth, dyed blue and red and used for women's attire; cotton cloth, shoes, blankets, combs, and snuff. Oil, soap, and untanned leather jars (*kupás*) are also made. The great majority of the town population consists of Ghakkars, Bhattis, Awáns, Kashmíris, Khattris, and Bráhmans, the last two having a monopoly of the trade.

Ráya.—South-eastern *tahsíl* of Siálkot District, Punjab, extending along the bank of the river Rávi. Area, 476 square miles; towns

RAYACHOTI

and villages, 461, number of houses, 26,936, namely, occupied 23,907, and unoccupied 3029, number of families, 40,775 Total population (1881) 194,205, namely, males 104,472, and females 89,733, proportion of males, 53·8 per cent Classified according to religion, the population consists of—Muhammadans, 129,796, Hindus, 53,214, Sikhs, 11,084, Jains, 24, and Christians, 87 Average density of population, 408 persons per square mile Of the 461 towns and villages, 333 contain less than five hundred inhabitants, 97 from five hundred to a thousand, and 31 from one to five thousand inhabitants Of a total area of 476 square miles, the average annual area under crops for the five years 1877–78 to 1881–82 was returned at 268 square miles, or 171,279 acres, the principal crops being—wheat, 85,272 acres, barley, 17,749 acres, rice, 12,684 acres, Indian corn, 8353 acres, *joar*, 6712 acres, other food grains, 3173 acres, sugar cane, 8016 acres, cotton, 4910 acres, tobacco, 1182 acres, and vegetables, 1255 acres Revenue of the *tahsil*, £24,120 The administrative staff consists of a *tahsildar*, a *munsif*, and an honorary magistrate These officers preside over 2 civil and 2 criminal courts Number of police circles (*thanas*), 3, strength of regular police, 58 men, village watch or rural police (*chaukidars*), 497

Rayachoti—*Taluk* or Sub division of Cuddapah (Kadapa) District, Madras Presidency Lat $13^{\circ} 51'$ to $14^{\circ} 20' N$, long $78^{\circ} 28'$ to $79^{\circ} 10' E$ Area, 998 square miles Population (1871) 128,162, (1881) 92,541, namely, 47,376 males and 45,165 females, occupying 21,734 houses, in 1 town and 92 villages Hindus number 82,295, Muhammadans, 10,178, Christians, 63 and 'others,' 5 The *taluk* is the most central in the District The general appearance is that of a level with here and there some scattered granite rocks, and with a horizontal line of unbroken hills closing in the horizon to the north and east The soils are of different kinds, the red predominating The *taluk* is well provided with roads, all of which centre in the chief town, Rayachoti, where seven roads meet Rice and *sugga* (*Holcus spicatus*) are the principal products Manufactures are few, and are confined to indigo, common cloth, coarse blankets, and gunny bags Good pasture grounds abound all over the *taluk*, and except in very bad years there is no want of grazing A large portion of the *taluk* lies waste, owing to the cultivators having no capital with which to bring it under cultivation, and no market to which to take the produce when grown The cattle are small but hardy The *taluk* contained in 1883—criminal courts, 2, police circles (*thanas*), 11, regular police, 87 men Land revenue, £11,534

Rayachoti—Head quarters of Rayachoti *taluk*, Cuddapah (Kadapa) District, Madras Presidency Lat $14^{\circ} 4' N$, long $78^{\circ} 50' E$ Situated on the banks of the Mandavi river, with seven roads converging on it Population (1881) 4367, dwelling in 912 houses Hindus numbered

2634; Muhammadans, 1729; and Christians, 4. The town has little trade; weekly market and old temple. The annual car festival is attended by about 6000 persons.

Ráyadrug.—*Táluk* and town in Bellary District, Madras Presidency.
—See RAIDRUG.

Ráyagudda (or *Rájágudda*).—Kandh village in Jaipur *samindári*, Vizagapatam District, Madras Presidency. Lat. $19^{\circ} 9' 40''$ N., long. $83^{\circ} 27' 30''$ E.; 33 miles north-west of Párvatipur. Formerly residence of the Jaipur Rájá. Population (1881) 2039, occupying 468 houses. Hindus numbered 1970, mostly Uriya Brahmins; and Muhammadans, 69. Sub-magistrate's station, with thriving trade.

Ráyak.—Village and police outpost in the Garo Hills District, Assam; on the Someswari river. Considerable population engaged in fishing.

Ráyakottai.—Village in Krishnagiri *táluk*, Salem District, Madras Presidency. Lat. $12^{\circ} 31'$ N., long. $78^{\circ} 5'$ E. Population (1871) 1881; (1881) 1087, dwelling in 214 houses. Hindus number 976; Muhammadans, 102; and Christians, 9. Rayakottai was formerly a favourite place of residence for military pensioners, who have, especially since the famine of 1876–78, abandoned it in large numbers. North of the town stands the *durgam* (hill fort) Ráyakottai, one of the Baramahál fortresses, until recently occupied by troops. It commanded one of the most important passes, and its capture by Major Gowdie in 1791 was the first exploit in Lord Cornwallis' great march. The fort was ceded to the English by the treaty of 1792; and it was under its walls that the army of General Harris encamped in 1799, before entering Mysore territory on the way to Seringapatam. The remains of the fort (2449 feet above sea-level) still exist, as does also the European cemetery at the foot of the hill.

Ráyalcheruvu (*Ráyál's tank*).—Village in Naráinvaram *táluk* of Karwaitnagar *samindári*, North Arcot District, Madras Presidency. Lat. $13^{\circ} 30' 5''$ N., long. $79^{\circ} 27' 30''$ E. Population (1881) 257, dwelling in 52 houses. The village is noteworthy on account of its large tank, built, it is said, by Krishnadeva Ráyalu of Vijianagar. The *bund* (embankment), resting on two hills, is half a mile long, 70 feet high, and 120 feet broad. The village was once of some importance, being on the road from Tirupati to Conjevaram (Káncshivaram), but pilgrims now use the north-west line of Madras Railway.

Ráyan.—Town in Jodhpur State, Rájputána. Lat. $26^{\circ} 32'$ N., long. $74^{\circ} 17'$ E.; 27 miles north-west of Jodhpur city. A fort, situated on a rock about 200 feet above the plain, commands the whole town. Estimated population, according to Boileau, 5650; not returned in the Census Report of 1881.

Ráyapet (*Ráyapetta*, *Royapet*).—Suburb of the city of MADRAS.

RAYIVALASA—REHLI

41

Rayavalasa—Pass in Vizagapatam District, Madras Presidency Lat $18^{\circ} 15' N$, long $83^{\circ} 7' E$, leading from Kasipur or Kasimkota to Jaipur by the abandoned sanitarium of Galkhonda Crest of the pass, 2850 feet above the sea. The Mahārājā of Vizianagaram has a coffee estate here

Raygad—Town and fort in Kolāba District, Bombay Presidency—*See* RAIGARH

Re (correctly *Ye*)—River of Lower Burma rising near the Attaran, at the head of the valley formed by the laung nyo and Ma hlwai Hills—*See* YE.

Redi (or more properly *Yaswantgarh*)—Port and fort in Vengurla Sub division, Ratnāgiri District, Bombay Presidency, situated in lat $15^{\circ} 45' 15'' N$, and long $73^{\circ} 42' 30'' E$, 7 miles south of Vengurla, and 89 miles south by east of Ratnagiri town Population not separately returned by the Census of 1881 Average annual value of trade for the five years ending 1881–82, £3420—viz imports, £1990, and exports, £1430—*See* RAIRI

Re gyi (correctly *Ye gyi*)—Creek in Bassein District, Irawadi Division, Lower Burma—*See* YE GYI

Re gyi Pan daw (correctly *Ye gyi Pandaw*)—Town and head quarters of the Ye gyi township, Bassein District, Pegu Division, Lower Burma—*See* YE GYI

Rehli—Southern *tahsil* or revenue Sub division of Sagar (Saugor) District, Central Provinces, situated between $23^{\circ} 32'$ and $24^{\circ} 1' N$ lat, and between $78^{\circ} 12'$ and $79^{\circ} 8' E$ long Area, 1301 square miles, number of towns 3, and of villages 585, houses, 45,082, namely, occupied 38,207, and unoccupied 6875 Total population (1881) 168,870, namely, males 88,455, and females 80,415 Average density of population, 130 persons per square mile The adult agricultural population (male and female) is returned at 45,837, or 27.14 per cent of the total population of the Sub division, average area of available cultivated and cultivable land, 11 acres per adult agriculturist. Of the total area of the *tahsil* (1301 square miles), 421 square miles are held revenue free, while 880 square miles are assessed for Government revenue, of which 432 square miles are cultivated, 253 square miles available for cultivation, and 195 square miles uncultivable waste Total amount of Government land revenue, including local rates and cesses levied on the land, £14,591, or an average of 1s 0½d per cultivated acre Total rental paid by the cultivators, including cesses, £39,776, or an average of 2s 9½d per cultivated acre Rehli Sub division contained in 1883, 1 criminal and 2 civil courts, with 4 police circles (*thanas*), and 7 outpost stations, strength of regular police, 139 men, number of *chaukidars* or village police, 405

Rehli.—Town and municipality in Sagar (Saugor) District, Central Provinces, and the head-quarters of Rehli Sub-division; situated in lat. $23^{\circ} 38' N.$, and long. $79^{\circ} 5' E.$, 28 miles south-east of Sagar town, in a healthy and fertile country, 1350 feet above sea-level. Population (1881) 5230, namely, Hindus, 4589; Kabirpanthis, 54; Muhammadans, 481; Jains, 103; and 'others,' 3. Municipal income (1882-83), £442, of which £399 was derived from taxation, nearly entirely represented by octroi duties; average incidence of taxation, 1s. $6\frac{1}{4}d.$ per head of population. Chief manufacture, *gúr* or coarse sugar; which, with wheat, is largely exported. Markets are held twice a week, and skilled labour is readily procurable. The early Gond rulers were succeeded by a race of shepherds called Baladeo, who first settled at Khamaria, a mile off, but afterwards removed to Rehli, where they built a fort. The place next passed to the Bundela chief of Panna, Raja Chhatar Sal, who granted it with other territory to Bají Rao Peshwa, in return for his assistance against Muhammad Khan Bangash, the Governor of Farukhabad. The present fort was built by the Peshwa. It stands opposite the junction of the Sunar and Dehar rivers, on a height commanding the town, and encloses nearly 2 acres, once covered by Maratha buildings. In 1817, Rehli, with Sagar, was ceded to the British. The town has a handsome school-house, attended by 140 boys; a female school, attended by 32 girls; dispensary, and post-office.

Rekapalli.—Petty *taluk* of Godavari District, Madras Presidency. Rekapalli *taluk*, with Bhadrachalam, was transferred from the Central Provinces in 1884, and now forms a part of the Agency tract of Godavari District. Area in Rekapalli *taluk*, together with Bhadrachalam, 911 square miles; population (1881) 35,656, namely, males 18,220, and females 17,436, occupying 6973 houses in 261 villages. Hindus number 34,725; Muhammadans, 661; and Christians, 270.

Re-keng (correctly *Ye-kin*).—Chief town of Ye-kin circle, Henzada District, Lower Burma, and head-quarters of an Assistant Commissioner. —See YE-KIN.

Relangi.—*Zamindari* village in Tanuku *taluk*, Godavari District, Madras Presidency. Lat. $16^{\circ} 41' 10'' N.$, long. $81^{\circ} 41' 40'' E.$ Population (1881) 5058, occupying 814 houses. Hindus numbered 4851, and Muhammadans 207.

Remda.—Village in Bargarh *tahsil*, Sambalpur District, Central Provinces. Population (1881) 2511, namely, Hindus 2468, and non-Hindu aborigines 43.

Remuna.—Village in Balasor District, Bengal. Lat. $21^{\circ} 33' N.$, long. $86^{\circ} 59' E.$; 5 miles west of Balasor town. Celebrated for a religious fair held annually in February in honour of Kshirichora Gopi-

RENGAN—REOTIPUR

nath, ■ form of Krishna, it lasts about 13 days, and is from 10,000 to 12,000 persons. About £600 worth of goods consisting chiefly of toys, sweetmeats, fruits, vegetables, &c. etc. The temple of the god is an unsightly stone edifice with indecent sculptures. It is much frequented during the February, April, and November.

Rengan—Petty State in Rewa Kántha Bombay Presidency, 4 square miles. There are 8 chiefs. Estimated revenue, £ of £46, 2s is paid to the Gaekwár of Baroda.

Rengmá—Mountain group in the Nágá Hills, Assam, a portion of the range known as the Mikir Hills, lying between the Jamuna and Káháni rivers. Lat $26^{\circ} 15'$ to $26^{\circ} 30' N$, and 24° to $93^{\circ} 40' E$, height, between 2000 and 3000 feet above sea level. The slopes are steep and clothed with dense jungle and dense forest. The Rengmá Nagas by whom this tract is now inhabited, the least savage of the Nágá tribes, being scarcely distinguishable from the Mikirs, who occupy the tract to the north. They are from the more remote tracts of the Nágá Hills, lying to the south of the Dhaneswarí (Dhansiri) river, where some villages of them still survive.

Rengtípahár—Mountain range in the south of Cachar, Assam, running northwards from the Lushái Hills, and forming the watershed between the Sonái and Dhaneswarí rivers.

Rení—Town in Bikaner (Bickaneer) State Rájputána (1881) 5198, namely, Hindus, 3673, Muhammadans, 'others,' 541.

Reotí—Town in Bansdih *taluk*, Ballár District, North-Western Provinces, situated in lat $25^{\circ} 51' N$, and long $84^{\circ} 25' 13'' E$ from Bansdih town. Population (1881) 9933, namely, Hindus 1036, Muhammadans 1036. Reotí is the head quarters of the Rájputs, and presents a dirty and overcrowded appearance. The Rájput proprietors are non resident, and the resident Rájput *zamindars* have lost their hereditary influence as seven eighths of the town is owned by strangers. The main street runs east and west, and is a part of the Baríá Sahatwar road. A little manufacture of cloth, shoes and palanquins is carried on, but with this excepted it is a mere agricultural centre, with little or no trade. Population 1036, middle school, and post office. A small house tax is levied for sanitary and conservancy purposes.

Reotípur—Town in Zamániá *taluk* Ghazípur District, Western Provinces, situated in lat $25^{\circ} 32' 16'' N$, and $19^{\circ} E$, 8 miles south east of Ghazípur town, 10 miles east of Zamániá. Population (1881) 1036, namely, Hindus 577 and Muhammadans 577. Reotípur ■ 1

mud huts, remarkable solely for its population. It belongs to the powerful clan of Sakarwār-Bhūinhārs, the owners of the large Sherpur-Reotipur *táluk* or estate. Anglo-vernacular school.

Repalli.—*Táluk* or Sub-division of Kistna District, Madras Presidency. The *táluk* lies on the right bank of the Kistna river, extending from the sea to the Mangalagiri hills. Area, 644 square miles. Population (1881) 184,340, namely, 93,093 males and 91,247 females, occupying 31,415 houses, in 1 town and 147 villages. Hindus number 175,833; Muhammadans, 7014; Christians, 1467; and 'others,' 26. The surface of Repalli *táluk* is almost wholly composed of river alluvium, and some portions resemble Holland in lying below sea-level. It is well irrigated by anicut channels. In Repalli *táluk* are the ruins of Tsandavolu, a place of great antiquity, with a temple and Buddhist mound. Gold coins are frequently found here, and in 1874 some workmen came upon several masses of molten gold as large as bricks. In searching for concealed treasure, trenches have been dug in the village laying bare the solid masonry foundations of very extensive buildings. In 1883 the *táluk* contained—criminal courts, 2; police circles (*thínás*), 9; regular police, 74 men. Land revenue, £73,058.

Repalli.—Head-quarters town of Repalli *táluk*, Kistna District, Madras Presidency. Population (1881) 2998, namely, Hindus, 2769; Muhammadans, 227; and Christians, 2. Number of houses, 574. Fort in ruins, built in 1705 by the ancestors of the *zamíndár* or landowner who now occupies the precincts. Station of the *tahsildár*. Post-office.

Resalpur.—Village in Hoshangábád *tahsíl*, Hoshangábád District, Central Provinces. Population (1881) 2311, namely, Hindus, 2248; Muhammadans, 50; and non-Hindu aborigines, 13.

Re-tsu-daing (correctly *Ye-su-daing*).—Tidal creek in Thonegwa (Thún-khwa) District, Pegu Division, Lower Burma. — See YE-SU-DAING.

Revelganj.—Town in Sárán District, Bengal. — See GODNA.

Rewá.—The principal Native State in Baghelkhand, under the political superintendence of the Baghelkhand Agency of Central India; lying between 22° 39' and 25° 12' N. lat., and between 80° 46' and 82° 51' E. long. Estimated area, 10,000 square miles. Population (1881) 1,305,124. Bounded on the north by the British Districts of Banda, Allahábád, and Mírzápur, in the North-Western Provinces; on the east by part of Mírzápur District and by Native States in Chutiá (Chota) Nágpur; on the south by the British Districts of Chhatisgarh, Mandla, and Jabalpur (Jubbulpore), in the Central Provinces; and on the west by Maihar, Nagode, Soháwal, and Kothi States in Baghelkhand. The western and north-western portions of the State are occupied by

mountains, rising in three successive plateaux, or vast terraces, from the valley of the Ganges. Of these, the one lying to the north east, and styled by Franklin the "Bindhachal" or First Range, is the lowest, having an average elevation of only 500 feet above the sea, it is formed of horizontal strata of sandstone, the upper surface presenting an expanse of very great sterility. Little of this plateau however, is included within the limits of Rewá, the boundary of which on this side coincides nearly with the base of the second range, or Panna Hills. The elevation of these mountains is from 900 to 1200 feet above the sea. They consist of sandstone intermixed with schist and quartz, and, to the west, overlaid with limestone. Above this plateau nearly parallel to the brow, but more to the south east, rises the Káimur range. The Tons (south eastern) and its tributaries, which drain the second plateau, descend to the lower levels in cascades varying in height from that of Bilohi with 400 feet to that of Cháichai with 200. About a third of the country lying south east of the Káimur Hills constitutes part of the basin of the Son, a tract as yet almost unexplored. That great river, rising in the extreme south of Rewa, flows through the State in a north and north easterly direction, crossing the north eastern frontier into the District of Mirzápur. Its principal tributary is the Mahánadi, joining it on the left side, in lat $24^{\circ} 5' N$, and long $81^{\circ} 6' E$. The Tons running north east from Mauhar first touches the State in lat $24^{\circ} 25' N$, and long $80^{\circ} 55' E$, and draining the highlands, receives the Beher, the Biland, and several minor torrents. It holds a course generally north easterly, and passes in lat $25^{\circ} 1' N$, and long $81^{\circ} 51' E$, into the British District of Allahábád, its length in Rewa being 80 miles. None of the rivers are navigable'—*Condensed from Thornton*

The State is rich in minerals and forest produce. A seam of coal of good quality has lately (1882-83) been discovered by the Geological Survey Department at Umária a village in the *pargana* of Ramnagar, in the north western extremity of Rewá State, 37 miles from Katni station on the Jabalpur extension of the East Indian Railway. The coal has been tested and found to be a valuable fuel. The Katni-Umária section of the Biláspur Etawah Railway, to bring the coal fields in connection with the East Indian Railway system, has been sanctioned. Coal of even better quality has been found also in the valley of the Johilla river and at Sohágpur.

The prevailing classes of soil are *mair*, *sengawan*, *domat*, and *bhata*. *Mair* is a black soil, which retains water and moisture well, and needs no irrigation. It produces valuable crops of wheat and other grain. *Sengawan* is a whitish clay, suitable for crops of any kind. *Domat* (literally two soils) is *mair* and *sengawan* mixed, and it produces the crops of both varieties. *Bhata*, red dry soil, is the worst class, pro

ducing only inferior crops. Tanks are seldom constructed for irrigation. Owing to the want of embankments, many miles of undulating and cultivable land lie untilld.

The forests of Rewá, which formerly contained large stores of excellent timber—teak, *sál* (*Shorea robusta*), *khair* (*Acacia Catechu*), *saj* (*Terminalia tomentosa*), *tendu* (*Diospyros melanxylon*) — suffered greatly from indiscriminate felling by sleeper contractors during the rule of the late Maharájá. At present there is but little good timber in the State. A system of forest conservancy has been established, and considerable areas are now marked off as reserve forests. In 1883-84, 136 square miles were demarcated. There is a fair trade in lac (*Coccus Lacca*), and quantities of *mahuá* (flower of the *Bassia latifolia*), *burra* (*Quercus infectoria*), resin, and gums are yearly exported. The revenue derived from lac is estimated at £6000.

The Jabalpur extension of the East Indian Railway crosses the western boundary of the State, the stations of Satna and Dabhaura being in Rewá territory. The Great Deccan road passes through the State.

According to the family history kept in the Court Records, it appears that the original founder of this principality was Bilagar Deo or Biag Deo (hence the name Baghel), who, leaving his own country in Gujarát in 580 A.D., ostensibly on a religious pilgrimage, but in reality to seize whatever undefended territory he could, first made himself master of the fort of Murpha, and eventually of most of the country from Kálpi to Chandalgarrh, and married the daughter of the Rájá of Pihawán. Bilagar Deo was succeeded by his son, Kurun Deo, in 615, who added to his possessions a large portion of what at present constitutes Rewá, and called it Baghelkhand. He married the daughter of the Rájá of Mandla, and obtained in dower the famous fort of Bandogarh, to which he removed his court. The chiefship descended from father to son for many generations, with varying fortunes. In the time of Birbhan Ráo, the 19th Raja, who succeeded in 1601, the family of Humáyún Sháh, Emperor of Delhi, being forced by Sher Sháh to flee from Delhi, found shelter in Rewá territory.

In 1618, Vikramáditya succeeded and made Rewá his capital, building the fort and town. Abdút Singh, the 27th Rájá, was only six months old when his father died; and Hardi Sah, the Bundelá chief of Panna, taking advantage of his infancy, invaded Rewá, and took possession of the capital. The young chief and his mother fled to Partábgarrh, and after a time, with the assistance of the Emperor of Delhi, expelled Hardi Sah. Abdút Singh was succeeded by Ajít Singh, and he in turn by Jai Singh Deo, in 1809. It was during his rule that British influence was established in Baghelkhand, and the first formal treaty between the British Government and Rewá was made with Jai Singh Deo in 1812.

indian marauders invaded Mirzapur through who was believed to have abetted this enterprise to a treaty by which he was acknowledged as a vassal, and was brought under the protection of the British, to whose arbitration he bound himself to refer all disputes, and engaged to allow British troops to be stationed in his territories. To fulfil his obligations, and when a military force was sent to enforce the execution of the engagements, a second treaty was made confirming the first, thereby settling the relations of the Raja with the British.

He succeeded in favour of his son, Bishnath Singh, who was succeeded by his son, Raghuraj Singh. In 1847 the Maharaja abdicated and retired throughout his dominions. For his services during the Mutiny of 1857, the tracts of Sohaspur and Amarkantak were granted to Raghuraj Singh, who also received the distinction of Knight Grand Commander of the Star of India. The Maharaja was also granted a *sanad* of adoption and a personal salute of 19 guns. Raghuraj Singh died in 1880, and has been succeeded by his son, Bankatesh Raman Singh, during whose minority the State is under the management of the Political Agent and Superintendent of Rewa, who is assisted by a Council of 10 Sardars, members of the ruling family.

The population of Rewa State, according to the Census of 1881, was returned at 1,305,124, namely, 654,182 males and 650,942 females. Hindus numbered 971,788, Muhammadans, 31,107, Jains, 86, Christians, 28, Sikhs, 8, aboriginal tribes, 302,107. Hindus were classed—Brahmans, 206,173, Rajputs, 43,609, Ahirs, 61,586, Banias, 29,365, Kurmis, 78,764, and 'others,' 552,291. The aboriginal tribes were—Gonds, 139,626, and Kols, 162,481. The principal landholders are Brahmans, Rajputs, Kurmis, and Gondes, the two latter are cultivators as well as proprietors. Rent is generally paid in kind, and varies from one sixth to one tenth of the gross produce. The revenue of the State in 1883-84 from all sources amounted to £111,258, of which £70,609 was derived from the land. The State maintained in 1883-84 a force of 371 cavalry, 564 infantry, 6 field guns, and 77 artillerymen.

The average annual rainfall at Rewa for the three years ending 1875-76 was 59 inches, the rainfall in 1883 was 29.85 inches.

Rewa—Chief town of the State of Rewa in Baghelkhand, Central India. Lat $24^{\circ} 31' 30''$ N, long $81^{\circ} 20'$ E, 131 miles south west of Allahabad, and 182 north east of Sagar. Population (1881) 22,016,

namely, 11,010 males and 11,006 females. Hindus number 17,413; Muhammadans, 4581; and 'others,' 22. Thornton states that the town is surrounded by 3 ramparts, of which the innermost encloses the palace of the Mahárájá.

Rewadanda.—Town and port in the Alibágh Sub-division of Kolába District, Bombay Presidency; situated 6 miles south by east of Alibágh, in lat. $18^{\circ} 32' 50''$ N., and long. $72^{\circ} 58'$ E. Population (1881) 6908, namely, Hindus, 6072; Muhammadans, 493; Jains, 23; Christians, 28; Pársis, 2; and 'others,' 290. The town has many interesting remains of the Portuguese, whose last possession in the Konkan it was, especially the walls and fort of Korle surmounted by a tower. The harbour formed by the mouth of Kondalika river is small, but safe and deep (7 fathoms). The bar has 2 fathoms at low water of spring tides; the channel is sinuous. During the fine season steamers call almost daily, and large boats pass up to Robe, 18 miles distant. No road communication. Average annual value of trade for the five years ending 1881–82, £30,670 of imports, and £47,897 of exports. In 1881–82, the value of imports was £27,033, and of exports £37,833. Rewadanda is one of the five ports of the Alibágh Customs Division. Post-office; school.

Rewá Kántha (*The banks of Rewá or Narbadá*).—Political Agency subordinate to the Government of Bombay, established 1821–26, having under its control 61 separate States, great and small. Of the 61 States, 3 pay no tribute, 5 are tributary to the British Government (3 of these pay also tribute to the Gáekwár of Baroda), 1 to Chhota Udaipur, and the rest to the Gáekwár of Baroda. The States lie between $21^{\circ} 23'$ and $23^{\circ} 33'$ N. lat., and $73^{\circ} 3'$ and $74^{\circ} 18'$ E. long. Besides lands stretching about 50 miles along the south bank of the Narbadá, Rewá Kántha includes an irregular band of territory from 10 to 50 miles broad, passing north of the Narbadá to about 12 miles beyond the Mahí, and an isolated strip on the west lying chiefly along the left bank of the Mahí. Bounded on the north by the Mewár States of Dungarpur and Bánswáda; on the east by the Sub-divisions of Jhálod and Dohad of Panch Maháls District, Alí Rájpur, and other petty States of Bhopáwar Agency, and part of Khándesh District; on the south by Baroda territory and Surat District; and on the west by Broach District, Baroda State, Panch Maháls, Kaira, and Ahmadábád Districts. Extreme length from north to south, about 140 miles; breadth from east to west varying from 10 to 50 miles; area, 4792 square miles. Population (1881) 543,452. Revenue, about £160,000.

Physical Aspects.—In the outlying villages to the west along the Mahí, and in the north and south where Rewá Kántha stretches into the plains of Gujarát, the country is open and flat; but generally the Agency is hilly. Its two principal ranges are—(1) in the south, the

Rajpipla hills, the westmost spurs of the Sātpuras, forming the water parting between the Narbadā and Tapti valleys, and (2) across the centre of the Agency, the spurs of the Vindhya range running west from the sandstone crowned table land of Ratanmal, and forming the water parting between the Narbadā and the Mahi. In the 120 miles of the course of the Mahi through Rewa Kānthā, the country changes from wild forest clad hills in the east to a flat bare plain in the west. Its deep banks make the Mahi of little use for irrigation. Its stream is too shallow and its bed too rocky to allow of navigation. The Narbadā enters the Agency through a country of hill and forest with wooded or steep craggy banks. For the last 40 miles of its course, the country grows rich and open, the banks lower, the bed widens, and the stream is deep and slow enough for water carriage. For 8 miles it is tidal.

Geology—The Rewa Kānthā rocks belong to five classes—metamorphic, quartzite sandstone, cretaceous, trap, and nummulite. The Agency has a considerable store of mineral wealth. The chief precious stones are agate and carnelians, among ornamental stones are good specimens of white, yellow, and grey marble, and red, white, grey, and nearly black granite, and among paving stones, whitish sandstone found in large slabs.

Forests—A great part of Rewa Kānthā is covered with forest. The chief trees are *mahuā* (*Bassia latifolia*), teak, blackwood (*Dalbergia Sissoo*), tamarind, mango, *rayan* (*Mimusops indica*), *sadādo* (*Terminalia Arjuna*), *behedā* (*Terminalia belerica*), *timbarrun* (*Carissa carandas*), *bili* (*Ægle Marmelos*), *kher* (*Acacia Catechu*) etc. The forest reserves are of two kinds—State reserves, or tracts in the large forests where the State only can cut, and sacred village groves, where the finest timber is found. Most of the villages have two kinds of groves—one never cut except on emergencies, and the other less sacred and generally felled at intervals of 30 years. Except for wants of the State, or when the villagers are forced to make good losses caused by some general fire or flood, the fear of the guardian spirit keeps the people from cutting in their village groves. The forests were once famous for their large stores of high class timber. But of late years, from the stricter conservancy in the neighbouring Panch Mahāls District, they have been greatly cut down, and few large trees are now left.

Fauna—Tigers and leopards, though yearly becoming fewer, are still found in considerable number. Bears and wild hog are common. *Sambhar*, spotted deer, and *nilgai* are found over great part of the Agency, bison (*Bos gaurus*) in the extreme south-east. The painted and common sand grouse, red spur fowl, the pea fowl, the painted and grey partridge, and quail are common. Common, jack, and

painted snipe, black goose, cotton, whistling, common, and blue-winged teal are some of the water-fowls. The stores of fish in the larger rivers are made little use of. So great is the influence of the higher class of Hindus, that professional fishermen can practise their calling only by stealth.

History.—Under the first Anhilwára dynasty (746–942), almost all the Rewá Kántha lands were under the government of the Bárias, that is, Kolí and Bhíl chiefs. In the 11th, 12th, and 13th centuries, driven south and east by the pressure of Muhammadan invasion, chiefs of Rájput or part Rájput blood took the place of the Kolí and Bhíl leaders. The first established was the house of the Rájá of Rájpipla. In the 16th century, the Ahmadábád Sultáns brought under submission almost the whole of Rewá Kántha. In the 17th century, although a member of the Bábi family founded the State of Bálásinor, the power of the Gujarát (Guzerát) viceroys began to decline. The Maráthás soon spread their authority over the plains, and collected tribute with the help of military force.

The younger branches of the chiefs' families had from time to time been forced to leave their homes and win for themselves new States; and these, with the descendants of a few of the original chiefs, form the present landholders of the small estates of the Agency. Under the Maráthás, they plundered the country; and as the Gáekwár failed to keep order, the British had to undertake the task. In 1821, an agreement was concluded with the Gáekwár, under which the control of all the Baroda tributaries was vested in the Company. In 1825, the petty chiefs of Pándu Mewás came under British control. At the same time, the political control of Sindhia's Panch Maháls was made over to the Company, and Báriya State was transferred from the Bhopáwar Agency, Central India. The Political Agency of Rewá Kántha was established in 1826, to take charge of these territories. The States of Lunáwára and Sunth, which had been under British control since 1819, were afterwards transferred from the Mahi Kántha Agency. In 1829, the appointment of Political Agent was abolished, and the chiefs were left very much to themselves.

In 1842, the Political Agency at Rewá Kántha was re-established, and the criminal powers of the chiefs were classified. In 1853, the State of Bálásinor was transferred from the Kaira Collector; and Sindhia handed over for a period of ten years the administration of the Godra Panch Maháls. In 1862, the Panch Maháls were exchanged by Sindhia for country near Gwálor, and became British territory. Two years later, the Panch Maháls were removed from the control of the Agent, and formed into a separate charge. In 1876, the Panch Maháls were raised to the rank of a District, the officer in charge of it having control of the Rewá Kántha States.

Of the 61 States of Rewá Kántha, one, Rajpipla, is of the first class and is the most important and the largest of all. Its chief has been granted power of life and death and can try British subjects, but all the other chiefs are required to remit cases against such persons to the Political Agent. Five chiefs, Chhota Udaipur, Bariya, Sunth, Lunáwára, and Bálasinor, are of the second class, and have independent control within their own States. The 55 small States include Kadánr and Sanjeli (both of whom pay no tribute), and three groups of Mewás States. Sankhetia Mewas consists of 26 States, area, 311 square miles, population (1881) 53,214, revenue, £19,200. Pándu Mewas consists of 22 States, area, 138 square miles, population (1881) 20,312, revenue, £4700. Dorka Mewás consists of 3 States, area, 9 square miles, population (1881) 4576, revenue, £1100. Of the 61 States at the close of 1883-84, 16 were under the direct management of the Agency, the chiefs of three of these were minors.

Population — Until 1872, the Rewa Kántha people had never been enumerated. The Census of 1872 showed a total population of 505,732, and the Census of 1881, 543,452, namely, 280,208 males and 263,244 females, occupying 109,730 houses, in 3 towns and 1101 villages. Average density of population, 113.4 persons per square mile, number of houses per square mile, 24.9, number of villages and towns per square mile, 0.23, number of inhabitants per house, 4.95. Hindus number 368,069, Muhammadans, 21,401, aboriginal tribes, 152,720, Jains, 1040, Pársis, 220, and Christians, 2.

The Hindus are sub-divided according to caste into Brahmans, 19,537, Rájputs, 20,478, Chamars, 4622, Darzís, 1460, Nápits, 3193, Kunbis, 30,251, Kumbhárs, 3750, Lohárs, 3121, Mhárs, 15,102, Sutárs, 2396, other Hindus, 264,159. According to sect, the Muhammadans are returned as follows — Sunnis 19,882, and Shiás 1519.

Of the total population, persons following agricultural occupations or having interest in land number 240,058, and artisans, 24,680. Of the remaining 278,714 inhabitants, 12,623 carry on other miscellaneous callings, and 266,091 are returned as without occupation, this number represented children under age and females who perform no regular work other than household.

THE BHILS are found in large numbers, especially in the south east of Rewa Kantha. The Rewa Kántha Bhil is generally of middle size, strong limbed, muscular, and wonderfully active and dirty. As regards dress, the Bhils and Kolis are divided into two classes—*potadís* or waist cloth wearers, and *langotís* or loin cloth wearers. The former, besides a waist-cloth, wear a short coat, and a turban generally white, but sometimes red. A few, instead of the waist cloth, wear short drawers reaching to their knees. A Bhil woman usually wears a coarse

sári, a large petticoat, and a cheap bodice. Most of the Bhíls are cultivators, but their scanty crops do not suffice to support them for more than three or four months. During the rest of the year they depend on the sale of forest produce, timber, *mahuá* flower, honey, wax, and *lac*. The Bhíls are truthful, thriftless, superstitious, and fond of drink. They are wanting in forethought. As a rule, they live from hand to mouth, and are deeply indebted to the village trader, seldom receiving the full value of their labour and produce. Such is the Bhíl's love of spirits, that their religious and social rites almost always end in a great debauch.

A Bhíl's religion consists largely of a belief in charms. They worship female deities, known as *mátás*, represented by symbols, rather than images, by wooden posts, toy horses, earthen pots, wicker baskets, and winnowing fans. They believe in witches and in the evil eye. They have their wise men called *barwás*, exorcists, whose office is hereditary, and who are in special request during an epidemic.

The Bhíls have peculiar marriage customs. Sometimes the young couple arrange matters unknown to their parents. They disappear, and after hiding for some days in the forest, come back and declare themselves man and wife. The parents, as a rule, accept the situation; and after arranging the expenses (£6 to £8), the marriage is celebrated with the usual forms. If the matter is not quietly settled, a feud runs on between the families. Sometimes a woman boldly walks into the house of the man she wishes to marry, and declares that he is her husband. Should he be willing, she sends for the father, and giving £6 to £8, asks his consent. If the man is unwilling, he is in no way forced to make the woman his wife. If a Bhíl wishes to marry, and is unable to pay the wedding expenses, he contracts to serve his future father-in-law as a serf for a certain number of years, at the end of which he is entitled to the girl's hand, and to have all marriage expenses paid for him. During this period of servitude, he and the girl live as man and wife. Polygamy is allowed. Divorce is, as a rule, easily granted.

THE KOLIS are divided into 21 tribes, belonging to two great subdivisions, Talabda and Khant, so distinct that marriages between them are forbidden. The Ráthwa Kolís, originally settlers from Ráth in Alí Rájpur of Bhopáwar Agency, Central India, are found chiefly in the States of Báriya and Chhota Udaipur. They live in the forests and do not settle long in one place, moving from one tract to another, growing crops on clearing in the jungle. In their habits and ways of living they resemble the Bhíls. The Talabda Kolís, who think themselves superior to the other class, do not eat beef nor the flesh of any animal that has died a natural death. Most of the Kolís are cultivators, but idle and unskilful. Nearly as thriftless as the Bhíls, they are deeply indebted to the village trader, who, leaving them grain

enough for food, seed, and rent, takes the rest. They are cleanly in their habits, and not so simple as the Bhils. Both tribes are inveterate thieves, but the Kolis lay their plans with much more method, boldness, and cunning than the Bhils. They lie freely. The Kolis are less superstitious, and pay more respect to ceremonial observances. They worship all the Hindu gods, but chiefly Indra and Hatmal. They respect Brahmans, and employ them to conduct their religious ceremonies.

Polygamy is allowed among the Kolis. When a Koli wishes to get his son married, he generally, although the marriage may have been arranged long before, goes through the form of starting off to find a bride. After he has chosen a bride, and made all the preliminary arrangements, he is asked to dine with her father. During the dinner, the women of the bride's family strew grains of corn on the threshold, and as the boy's father is leaving the house, they rush at him as if to beat him, and he, making for the door, slips and falls. The boy's father's fall on the threshold of the girl's house is so important an omen that without it no marriage could prosper. Among Kolis, when a man dies leaving a widow, it is usual for his younger brother to marry her. But if she wishes to marry some one else, she can do so if her future husband pays back to the younger brother her deceased husband's marriage expenses. The Kolis burn their dead.

Trade—The trade of Rewá Kántha resembles in many respects that of the Panch Mahals. Both have a through traffic between Gujarat and Central India, and a local trade west with Gujarát and east with Rájputána, Central India, and Khándesh. While the opening of the railway through Gujarát has increased the local trade westwards, the through trade has dwindled, the old direct routes with their rough roads and heavy dues failing to compete with the easy railway journey by Bombay and Khandesh to Central India.

Administration—Civil courts have only lately been introduced into Rewá Kántha. Disputes were formerly settled by arbitration, and money lenders were allowed to recover their outstanding debts as they best could. As regards criminal justice, the Rewa Kántha authorities consist of *thanádárs*, with second and third class magisterial powers in the estates of the petty Mewás chiefs, the chiefs of Kadána, Sanjeli, Bhádarwa, Umeta, Bária, Balásinor, and Rájpípla, the Assistant Political Agent, and the Political Agent. No regular police is provided for the Mewás States, and the work is performed by the troopers of the Gáekwár's Contingent, who are stationed at the principal places. They carry the post, convey prisoners, and do miscellaneous work. The larger States maintain a police force of their own. Advantage was taken of several of the States being under management during the minority of their chiefs, to establish a system of federal police. But

the system had to be given up as each chief succeeded to his inheritance. In 1883-84, the strength of the police employed by the large States was 1023, of whom 116 were mounted. In the 27 prisons, 1999 prisoners were confined. The number of schools in 1883-84 was 71 for boys, with 5278 pupils; and 5 for girls, with 222 scholars. There are four libraries in the States of the Agency, and a printing press at Nándod for State purposes only. The average daily attendance at the 7 dispensaries was 387 in 1883-84.

Rewári.—North-western *tahsíl* of Gurgáon District, Punjab; consisting of an outlying hilly tract, almost separated from the remainder of the District by native territory. The soil is naturally sandy; but the industry of the Ahír inhabitants, and the copious well-irrigation, have turned it into a singularly prosperous country. Numerous streams flow through it from the Jaipur hills, the principal of which are the Sáhíbi and the Hánsaotí. Area, 426 square miles; towns and villages, 285; number of houses, 23,558, namely, occupied 16,211, and unoccupied 7347. Total population (1881) 142,555, namely, males 75,092, and females 67,463; average density, 334 persons per square mile. Classified according to religion, the population consists of—Hindus, 123,525; Muhammadans, 18,007; Jains, 985; Sikhs, 18; and Christians, 20. Of the 285 towns and villages, 215 contain less than five hundred inhabitants; 44 from five hundred to a thousand; and 25 from one to five thousand inhabitants. The only place with a population exceeding five thousand is REWARI town (23,972). The average annual area under crops for the five years 1877-78 to 1881-82 is returned at 234½ square miles, or 149,958 acres, the principal crops being—*bájra*, 69,394 acres; *moth*, 53,429 acres; barley, 31,058 acres; *joár*, 12,817 acres; wheat, 7622 acres; and vegetables, 3813 acres. Revenue of the *tahsíl*, £26,182. The administrative staff consists of a *tahsildár*, a *munsif*, and an honorary magistrate, who preside over 2 civil and 2 revenue courts. Number of police circles (*thánás*), 3; strength of regular police, 127 men; village watch or rural police (*chaukidárs*), 306.

Rewári.—Town and municipality in Gurgáon District, Punjab, and head-quarters of Rewári *tahsíl*; situated in lat. 28° 12' N., long. 70° 40' E., on the Delhi and Jaipur road, 32 miles south-east of Gurgáon town, at the junction of the Rewári-Firozpur and Rájputána-Málwá lines of railway. Rewári is an ancient town, but owes its present commercial importance to British rule. The débris of an earlier city cover a site known as Budhi Rewári, east of the modern walls. Local tradition attributes its foundation to Rájá Karm Pál, of unknown date. Even the present town has considerable antiquity, having been founded about 1000 A.D. by Rájá Reo, who named it after his daughter Rewáti. The native Rájás seem to have maintained a partial independence under the

Mughal Empire, renting their *parganá* at a fixed revenue. They also built the fort of Gokalgarh, near the town, now in ruins, but exhibiting marks of great strength. They coined their own money, one of the most cherished prerogatives of independent sovereignty in India, and their currency bore the name of Gokal Sikka.

On the collapse of the Mughal Empire, Rewari fell first to the Marathás and afterwards to the Jat Rájás of Bhartpur, who retained it till the cession of the Delhi territory in 1803. In 1805, the *pargana* was brought under direct British rule, and the town became for some time the head quarters of a District. A military cantonment was established at Dharawas near the civil station till 1816, when the troops were transferred to Nasirabad, and the civil head quarters removed to Gurgaon town. The security of British rule attracted large numbers of traders from the neighbouring Native States, for which Rewari formed a central emporium. The Rewari estate was taken from the chief of Bhartpur in 1805, and made over in farm to Tej Singh, whose descendants held this position till the Mutiny, although much impoverished by family quarrels, litigation, and extravagance. In 1857, Ráo Tula Rám, grandson of Tej Singh, represented the family, and he, on the outbreak of the disturbances, assumed the government of Rewari, collected revenue, cast guns, and raised a force with which he kept the turbulent Meos in check, without, however, casting in his lot with the British or actually joining the rebels. Finally, on the advance of a British force from Delhi, he and his cousin Gopal Deo fled on receiving a summons to the camp. Both died as fugitives, and the estate was confiscated.

Rewari town lies low, and in 1873 was partially inundated by an overflow from the Sahibi river, whose ordinary course is seven miles from the town, but it is well drained, and secure from all but very unusual floods. Population (1881) 23,972, namely, males 11,824, and females 12,148. Hindus number 14,687, Muhammadans, 8499, Jains, 763, Sikhs 10, and Christians, 13. Number of houses, 2806. Municipal income (1883-84), £3764, or an average of 3s 2d per head. The town is traversed from east to west by a broad and handsome street of shops constructed in 1864, and from north to south by several good roads, terminating on each side with a fine gateway. The houses and shops along the main streets are all of stone or brick, and many of them large, substantial, and of some architectural pretensions, outside the main streets, the thoroughfares are narrow and crooked, and the houses for the most part mud hovels. The chief streets and roads are well paved, lighted, and flanked with good surface drains, but the sanitary and conservancy arrangements in the bye streets and lanes is still defective, although improvements are being rapidly carried on out of surplus municipal income. A circular drive, well

metalled, and shaded with an avenue of trees, surrounds the town. To the south-west is a handsome tank built by Ráo Tej Singh, surrounded by temples, and bathing-places for both men and women, with stone staircases. Adjoining the tank, a large garden has been laid out as a public recreation ground. Another picturesque tank, surrounded by handsome mausoleums, is situated near the railway station. The principal buildings are the Government courts and offices, a handsome town hall, police station, post-office, large Government school, *sardí* or native inn, and a dispensary.

The brass and pewter vessels of Rewári are celebrated. Together with fine turbans, they form the principal manufacture of the town. Rewári, indeed, was formerly a depôt for supplying a great part of Rájputána. Since the opening of through communication by rail, Rewári no longer forms a regular halting-place between Delhi and the Native States, and the demand for its brass-ware has somewhat fallen off; but, on the other hand, an enormous trade in grain has from the same cause sprung up with distant parts of India. Situated as the town is, at the junction of two lines of railway, it cannot fail to increase steadily in commercial importance. Sugar is brought from Rohtak, the Doáb, and parts of Oudh, and exported westwards; while wheat, barley, and gram are collected from all the neighbouring country, and exported to Calcutta, Bombay, and Gujrát, and much barley is purchased for the breweries of Masuri and Naini Tál. Iron is imported in large quantities from Alwar for use in the manufactures of the town; and iron, with salt, forms the return trade to the North-Western Provinces. There are several banking and commercial firms of considerable importance, whose dealings extend to Bombay, Calcutta, the Central Provinces, and the north and west Punjab.

Rewás.—Port in the Alibágh Sub-division of Kolába District, Bombay Presidency. Lat. $18^{\circ} 47' 20''$ N., long. $72^{\circ} 58' 30''$ E.; 10 miles north-east of Alibágh. Population (1881) 919, occupying 149 houses. Chiefly fishermen, who live in low dirty huts. The houses of the cultivators are better built and clean. Average annual value of trade for the four years ending 1881–82, £8488—namely, imports, £2660, and exports, £5828. In 1881–82 the value of imports was £2060, and of exports, £412. Rewás is one of the five ports of the Alibágh Customs Division. Steamers from Bombay call daily at all states of the tide. Road communication with Alibágh.

Riah.—*Tahsíl* in Siálkot District, Punjab.—See RAYA.

Rian.—Town in Jodhpur State, Rájputána.—See RAYAN.

Riási.—Fort and town in the Jamu Division of Kashmír State, Northern India. Lat. $33^{\circ} 5' N.$, long. $74^{\circ} 52' E.$; lies on the left bank of the Chenáb (Chináb), on the last slopes of the southernmost Himálayan

range Thornton states that the fort crowns a conical rock, south of the town, and consists of a rectangular enclosure, whose lofty stone walls rose sheer from the steeply escarped sides of the hills, with a bomb proof tower at each angle. Two large tanks supply the garrison with water. A deep ravine separates the fort from a sandstone eminence of equal height, about a mile distant.

Ridhpur—Town in Amraoti District, Berar—See RITPUR

Rikheswar—Cantonment in Kumáun District, North Western Provinces—See LOHAGHAT

Rintimbur—Fort in Jaipur (Jeypore) State, Rájputána—See RAN THAMBHOR

Rioti—Town in Bansdih *tahsil*, Balha District, North Western Provinces—See REOTI

Riotipur—Town in Zamaniá *tahsil*, Gházipur District, North Western Provinces—See REOTIPUR

Ripu—One of the Dwárs or submontane tracts forming the Eastern Dwars of Goalpará District, Assam. Area, 242 square miles. Population (1881) 3040, forest area (reserved), 65.05 square miles, area under cultivation, 4.62 square miles. In 1870 the land was settled with the cultivators direct for a term of seven years. Since 1877 the settlement has been made on yearly leases, as in the rest of Assam.

Rishikund—Hot spring in Monghyr District, Bengal. It has been made a place of worship, and a reservoir has been built to collect the water into one pool which is about 140 feet square, and on the side most remote from the sources, overgrown with aquatic plants. The bottom of the pool is partly sandy, partly rocky, and the air bubbles rise from the surface over a space of about 30 feet wide and 140 feet long. Where the air bubbles issue from among sand they form a small cavity like a crater. When Dr Buchanan Hamilton visited this spring he found in the month of April, that the thermometer in the air stood at 72° F, in the water where it issued from the crevice of a rock, it rose to 110°, and in one of the craters to 114°. A fair is held at Rishikund once in three years. It is of no great importance, there being seldom more than 2000 people present.

Risod—Chief town of a *parganá* in Basim *taluk*, Basim District, Berar, originally known as *Rishi wut kshetr*, or 'The place of all the Rishis'. Lat 19° 58' 30" N, long 76° 51' E. Population (1867) 4716, not returned separately in the Census of 1881. Place of some commercial activity. In 1858-59, a plundering party of Rohillas, being brought to bay by a detachment of the Haidarabád (Hyderabad) Contingent at the walled village of Chichamba, near Risod resisted an infantry attack. This was the last fight of the kind in Berar. Charitable dispensary, first class vernacular school, police station. Large irrigation tank.

Ritpur.—Town in Morsi *táluk*, Amraoti District, Berár; 26 miles north of Amraoti town. Lat. $21^{\circ} 14' N.$, long. $77^{\circ} 52' E.$ Population (1881) 2538. Once a place of importance, having been the *tankha jágir* of Salábat Khán. The stone wall which surrounded the town fifty years ago has almost entirely disappeared. It is said to have then had 12,000 inhabitants, many of whom deserted it owing to the oppression of Bisenchand, *tálukdár* in the time of Námdár Khán. The principal buildings of interest are Rámchandra's temple, the Mánbháu building called Ráj Math, and the Government school. Good water is scarce at Ritpur, the people obtaining their drinking supply from Lálá's well.

Ritpur is the chief seat of the sect known as Mánbháu, founded by Kishen Bhát at PAITHAN (Nizám's Dominions). Kishen Bhát, the spiritual adviser of a Rájá who ruled at Paithan about the middle of the fourteenth century, was made an outcaste on account of his marriage with a low-born woman (a Mháng). The name of Mhángbháu, which has been corrupted to the present Mánbháu, and which he gave to his children, is derived from their mixed parentage. He promulgated a religious system which he disseminated far and wide by means of his sons. His doctrines repudiated a multiplicity of gods; and it appears probable that the hatred and contempt he endured arose from his endeavours to restore the monotheistic principle of Bráhmaism as taught in the Vedas. He inculcated the exclusive worship of Krishna, and taught his disciples to eat with none but the initiated, and to break off all former ties of caste and religion. The head of the sect is a Mahant, and with him are associated a number of priests. Its members are professed celibates, but this rule is by no means rigidly observed. Both men and women shave all hair from the head, and wear a black waistcloth, forming a kind of skirt, to show that, having devoted themselves to religion, they in their worldly conduct no longer recognise any distinction as to sex. They bury their dead. Kishen Bhát, the founder of this sect, is said to have obtained a magic cap, by wearing which he assumed the likeness of Krishna. This cap was at last forcibly taken from him and burnt.

The Census Report of 1881 returned 4111 Mánbháus in Berar, namely, 2193 males and 1918 females. Of the males 451 were of no occupation, and 1251 were beggars. Of the females 44·6 per cent. followed no specified occupation, and 38·9 per cent. were beggars. More than one-fifth of the male sex, and less than one-sixth of the female sex, were productively employed. Of these the great majority were engaged in agriculture. Eleven men and three women were *sahukars*; six men were carpenters; and 32 women were cotton-spinners, ginners, and thread-makers.

Riwari.—*Tahsil* and town in Gurgáon District, Punjab.—See REWARI.

Robertsganj—Southern *tahsil* of Mirzápur District, North Western Provinces, consisting of the plateau north of the Kaimur range, the Son (Soane) valley, the belt of hilly jungle which bounds the Son valley to the south, together with the Singrauli plain beyond. This tract comprises the most varied and picturesque scenery in the District Area, 2632 square miles, of which 435 square miles are cultivated Population (1872) 173,540, (1881) 226,318 namely, males 113,975, and females 112,343. Increase of population since 1872, 52,778, or 30.4 per cent in nine years. Classified according to religion, the population consists of—Hindus, 217,892, Muhammadans, 8323, Christians 88, and 'others,' 15. Of 1224 villages, 1146 contain a population of less than five hundred, 64 between five hundred and a thousand, and 14 between one and three thousand. No place has a population exceeding three thousand. Total area in 1881 paying Government land revenue or quit rent, 885.3 square miles, of which 276.8 square miles were cultivated, 167 square miles cultivable, and 441.5 square miles uncultivable waste. Total Government land revenue, £6355, or, including local rates and cesses levied on land, £6853. Rental paid by cultivators, £34,302. In 1884, the *tahsil* contained 1 civil and 1 criminal court. number of police circles (thands), 9, strength of regular police, 84 men.

Robertsganj—Village in Mirzapur District North Western Provinces, and head quarters of Robertsganj *tahsil*, situated in lat 24° 41' 24" N, and long 83° 6' 33", about 50 miles south east of Mirzápur town. Population (1881) 1161. The village and *tahsil* are named after Mr W Roberts, Collector of Mirzapur in 1846, and settlement officer of the District. The place is increasing in importance, and the improvement of the road connecting it with Ahraura station on the East Indian Railway is likely to benefit Robertsganj at the expense of other local trade centres farther north.

Roha—Sub division of Kolaba District, Bombay Presidency. Area, 200 square miles. Population (1872) 41,997 (1881) 44,835 namely, 22,525 males and 22,310 females, occupying 8300 houses, in 1 town and 132 villages. Hindus number 42,302, Muhammadans, 1869, and 'others,' 664. Roha is for the most part hilly, and contains the rich valley of the Kundalika river. The rice lands are well watered during the rainy season, but in the cold and hot months the supply of drinking water is defective. In the hill slopes and uplands, the soil is a mixture of earth and broken trap. In the level parts the soil varies from reddish to yellow or black. During the 22 years ending 1881 the rainfall averaged 115.8 inches. The Sub-division contains altogether 61,666 acres of cultivable land, 12,007 acres of uncultivable land, 29,469 acres of forest reserves, and 402 acres under grass. Of the Government cultivable land (60,943 acres), 41,771 acres were

in 1881-82 under actual cultivation, of which 955 acres were twice cropped. Principal crops—cereals and millets, 39,233 acres; pulses, 3179 acres; oil-seeds, 264 acres; fibres, 13 acres; and miscellaneous crops, 37 acres. The survey rates were fixed in 1863 for 30 years. In 1881-82, 6343 holdings were recorded with an average area of $8\frac{1}{2}$ acres, and an average rental of £1, 13s. In 1883, Roha Sub-division contained—criminal courts, 2; police circles (*thánás*), 3; regular police, 28 men. Land revenue, £10,719.

Roha (known as *Roha Ashtami*).—Chief town of Roha Sub-division, Kolába District, Bombay Presidency. Situated on the left bank of the Kundalika river, 24 miles from its mouth. Lat. $18^{\circ} 25' 5''$ N., long. $73^{\circ} 9' 25''$ E. Population (1881) 4894. Hindus numbered 3575; Muhammadans, 1061; Jains, 28; Christians, 9; Pársís, 4; and 'others,' 217. Roha is a great rice market for supplying Bombay city. Sea-customs office, school, post-office, and reading-room. The municipality, founded in 1865, had in 1883-84 an income of £566; incidence of taxation, 1s. $3\frac{1}{4}$ d. per head. The village of Ashtami, on the opposite bank of the river, is included within the municipal limits of Roha. In 1673, Oxenden called it Esthemy.

Rohar.—Chief seaport of Anjár division, Cutch, Bombay Presidency. Situated about 12 miles east of Anjár town. In 1818 the port was able to receive vessels of 70 tons, and had a hard sandy beach over which carts could pass close to the sea. Now only small boats do an insignificant coasting trade. A petty fort falling into decay. The water-supply has been improved by building a new reservoir.

Rohilkhand.—Division or Commissionership under the jurisdiction of the Lieutenant-Governor of the North-Western Provinces, lying between $27^{\circ} 35'$ and $29^{\circ} 58'$ N. lat., and between $78^{\circ} 2'$ and $80^{\circ} 28'$ E. long. The Division, which covers an area of 10,883 square miles, includes the six Districts of BIJNAUR (Bijnor), MORADABAD, BUDAON, BAREILLY (Bareli), PILIBHIT, and SHAHJAHANPUR, all of which see separately. Bounded on the north by Garhwál and Taráí Districts; on the east by Kheri and Etah Districts; on the south by Hardoi and Farukhábád; and on the west by Aligarh, Bulandshahr, Meerut, Muzaffarnagar, and Saháranpur Districts.

The population of Rohilkhand Division was returned by the Census of 1872 at 5,252,325. The last enumeration in 1881 disclosed a total of 5,122,557, showing a decrease of 129,768, or 2.5 per cent., in nine years. This decrease is attributable to the famine caused by drought in 1877-78, and to severe outbreaks of epidemic fever in 1878-79. The results of the Census of 1881 may be summarized as follows:—Area of Division, 10,883 square miles, with 46 towns and 11,281 villages; number of houses, 639,604. Total population, 5,122,557, namely, males 2,728,761, and females 2,393,796; pro-

portion of males, 53·2 per cent. Average density of population, 470·6 persons per square mile, varying from 329·2 per square mile in Pilibhit, to 638·6 per square mile in Bareilly District. Average number of persons per town or village, 452, number of towns or villages per square mile, 1·04, houses per square mile, 58·8, inmates per house, 8·0. Classified according to sex and age, the Census shows—under 15 years of age, males 1,048,769, and females 877,953, total children, 1,926,722, or 37·6 per cent of the total population. 15 years and upwards, males 1,679,992, and females 1,515,843, total children, 3,195,835, or 62·4 per cent.

Religion—Classified according to religion, Hindus number 3,921,989, or 76·5 per cent, Muhammadans, 1,192,263, or 23·2 per cent, Christians, 6304, Jains, 1456, Sikhs, 508, Buddhists, 15, Parsis, 21, and Brahmo, 1. Of the higher classes of Hindus, Bráhmans number 269,519, Rajputs, 221,096, Bhats, 7177, Banijás, 132,248, and Kayasths, 57,479. Of the lower or Sudra castes, the most important (numerically) are the following—Chamar, 616,724, Kurmi, 400,488, Kachhi, 320,059, Ahar, 231,657, Kahár, 165,328, Jats, 121,422, Gadaría, 104,999, Ahir, 91,460, Bhangi, 83,340, Barhai, 82,078, Máli, 72,573, Kumbhar, 68,948, Nai, 67,372, Dhobi, 62,001, Teli, 61,155, Koeri, 58,601, Lodhi, 58,368, Bhurji, 39,373, Gujar, 36,086, Pasi, 34,103, Sonar, 30,201, Lohár, 26,346, Tagar, 21,989, Dhanuk, 20,372, Gosám, 17,362, Kalwár, 12,073, and Kathik, 11,186. The Muhammadan population, according to sect, consists of—Sunnis, 1,773,141, Shiás, 18,942, Wahábís, 7, and unspecified, 173. Among the Muhammadan population are included the descendants of converted Rajputs, 6480, Mewatis, 8987, Tágás, 7002, Játs, 1042, and Gujars, 348. The Christian population consists of—Europeans, 2953, Eurasians, 252, Armenian, 1, and Natives of India, 3098.

Town and Rural Population—Rohilkhand Division contains 18 towns with a population exceeding ten thousand inhabitants, namely, Bareilly (Bareli), 113,417, Sháhjahanpur, 74,830, Moradábád, 67,387, Amroha, 36,145, Budáon, 33,680, Pilibhit, 29,721, Chandusi, 27,521, Sambhal, 21,373, Nagina, 20,503, Najibábád, 17,750, Tilhar, 15,351, Bijnour, 15,147, Sherkot, 15,087, Sahsawán, 14,605, Aonla, 13,018, Kiratpur, 12,728, Sarái Tarni, 11,586, and Chandpur, 11,182. Besides the foregoing there are also 28 minor towns, with an aggregate of 180,965 inhabitants, bringing up the total urban population to 731,996, or 14·2 per cent of the population of the Division. The 19 municipal towns contain an aggregate population of 538,361. Total municipal income (1883-84), £38,943, of which £32,959 was derived from taxation, average incidence of taxation, is 2½d per head of the municipal population. Of the 11,327 towns and villages, 4226 are returned as containing less than two hundred inhabitants, 4369 between

two and five hundred; 1988 between five hundred and a thousand; 560 between one and two thousand; 96 between two and three thousand; 43 between three and five thousand; 27 between five and ten thousand; 5 between ten and fifteen thousand; 4 between fifteen and twenty thousand; 6 between twenty and fifty thousand; and 3 upwards of fifty thousand inhabitants. As regards occupation, the male population are thus returned:—(1) Professional class, including civil and military, 45,307; (2) domestic class, 12,153; (3) commercial class, including bankers, merchants, traders, and carriers, 49,276; (4) agricultural and pastoral class, including gardeners, 1,277,499; (5) industrial and manufacturing class, including artisans, 315,178; (6) indefinite and non-productive class, comprising male children and general labourers, 1,029,348.

Agriculture.—According to the North-Western Provinces Administration Report for 1883–84, out of a total assessed area of 10,753 square miles, or 6,882,398 acres, 4,439,171 acres were under cultivation in that year; 1,753,822 acres were returned as grazing or cultivable land; and 689,405 acres as uncultivable waste. Of the cultivated area, 782,249 acres were artificially irrigated, namely, 74,677 acres from Government works, and 707,572 acres by private individuals, from wells, tanks, etc. Wheat forms the great food crop of the *rabi* or spring harvest, being grown on 1,033,088 acres in 1883–84, besides being mixed with barley and gram on 297,858 acres; barley and gram, either separate or mixed, occupy 566,605. For the *kharif* or autumn harvest, rice occupies 714,670 acres; Indian corn, 155,522 acres; millets, such as *bajra*, *jowar*, and *arhar*, 759,035 acres; pulses, 283,921. Of non-food crops, sugar-cane occupies 213,646 acres; cotton, 212,269 acres; opium, 19,546 acres; oil-seeds, 18,413 acres; indigo, 15,445 acres; and tobacco, 5309 acres.

The total male agricultural population in 1881 was returned at 1,265,800, made up as follows:—Landholders, 53,339; tenant cultivators, 1,025,127; agricultural labourers, 174,074; estate officers, 13,260. Number of cultivated acres to each male agriculturist, 3·48. The population entirely dependent on the soil, however, numbered 3,521,739, or 68·75 per cent. of the entire population of the Division. Total amount of Government land revenue assessment, including local rates and cesses levied on the land, £821,958, or an average of 3s. 11¼d. per cultivated acre. Total rental paid by cultivators, including rates and cesses, £1,481,947, or an average of 6s. 8½d. per cultivated acre.

Administration.—The gross revenue of Rohilkhand Division in 1883–84 was £980,683, of which the principal items were—land revenue, £695,182; stamps, £80,143; excise, £69,191; provincial rates, £88,033; assessed taxes, £15,979; registration, £5708. The land-tax is derived from 22,505 estates, paying an average Government assessment of £30, 16s. each. Protection to person and property is

afforded by 84 civil and revenue and 137 criminal courts, with a regular police force of 4288 officers and men, stationed in 101 police circles (*thanas*), besides a village watch or rural police of 11,250 *chaukidars*. There are altogether 8 jails and lock ups with an average daily prison population in 1883 of 2004, of whom 1825 were convicts.

Means of communication are afforded by 163 miles of the Oudh and Rohilkhand, and the Kumaon and Rohilkhand Railways, and by 2595 miles of metalled and unmetalled roads.

There are 858 Government and aided schools in the Division attended in 1883-84 by 28 545 pupils. This is exclusive of un inspected indigenous village schools. The Census of 1881 returned 35,091 boys and 1549 girls as under instruction, besides 90,157 males and 1965 females able to read and write, but not under instruction.

Medical relief is furnished by 30 hospitals and dispensaries, attended in 1883-84 by 7444 in door and 278,929 out door patients. Total number of deaths registered in 1883-84, 157,662, or a death rate of 30.7 per thousand.

Rohisa — Village in Junágarh State, Kathiawár, Bombay Presidency, situated 8 miles to the east of Una and about half a mile from the sea shore. Population (1881) 1658. When a Palitana chief ascends his *gad*, a stone is brought from Rohisa as a token that one of his ancestors conquered the place. About 3 miles to the north of Rohisa is the Chitrasar lake, excavated and built round.

Rohisála — Petty State in the Gohelwar *prant* or division of Kathiawár, Bombay Presidency, consisting of 1 village, with 2 separate tribute payers. Area, 1 square mile. Population (1881) 354. Estimated revenue, £310. tribute of £10, 6s is paid to the Gáekwár of Baroda, and 16s to the Nawab of Junágarh.

Rohna — Town in Arvi *tahsil*, Wardha District, Central Provinces. Lat 20° 32' 30" N, long 78° 25' E, 23 miles west by north of Wardha town. Population (1881) 2172, chiefly cultivators. Hindus number 1835, Jains, 83, Muhammadans, 70, and non Hindu aborigines, 186. The stream by the town has been embanked to avert floods, and a well attended market is held every Tuesday in its dry bed and on the bank. A large fair also takes place yearly at the end of January. The fort was built about a century ago by Krishnaji Sindhia, who held the town rent free from the Hyderabad and Bhonsla Governments, in consideration of maintaining 200 horsemen. Rohna has a village school, and in the neighbourhood are gardens of opium, sugar cane, and spices.

Rohri (or, as written by the natives, *Lohri*) — Sub division of Shikarpur District, Sind, Bombay Presidency, lying between 27° 7' and 28° 32' N lat, and between 68° 52' and 70° 15' E long. Area, including a part of Kohistan, 5410 square miles. Population (1881) 209 114. Bounded on the north and west on the north east and

east by the States of Baháwalpur and Jaisalmír (Jeysulmere), and on the south by Khairpur. Head-quarters at Mírpur.

Physical Aspects.—The Sub-division consists mainly of a desert known as the Registán, constituting a portion of the vast plain of Shikárpur. It is broken by sandhills, which are often bold in outline, and fairly wooded. A small limestone range in the south-west of the Sub-division runs from near Rohri town due north and south into Khairpur. The Indus is supposed to have once flowed past these hills near the ancient town of Aror, and to have been diverted into its present channel through the Bakhar Hills by some great natural convulsion. The Ren, said to be a former bed of the main stream of the Indus, is in the Registán. The principal canals in Rohri are—the new supply channel for the EASTERN NARA, 13 miles long and 156 feet wide at its mouth, with strong sluice-gates; the Eastern Nára in its course towards the south is cut up into numerous small streams, and abounds in quagmires and quicksands: the Lúndi, 16 miles long; Aror, 16 miles; Dahr, 26 miles; Masú, 32 miles; Korai, 23 miles; Maháro, 37 miles; Dengro, 16 miles. There are 57 *zamindári* canals, offshoots of the Government works. The *dandhs* are—the Dahri, 20 miles long; the Garwar, 10 miles; the Kadirpur, 12 miles; the Changhan, 20 miles. The forests of Rohri cover an area of 137 square miles; the most important trees are the *pípal* (*Ficus religiosa*), *ním* (*Melia Azadirachta*), *ber* (*Zizyphus jujuba*), *síras* (*Dalbergia latifolia*), *tali* (*Dalbergia Sissoo*), *bahan* (*Populus euphratica*), and *kandi* (*Prosopis spicigera*). The bush jungle consists for the most part of tamarisk. Game is abundant.

Population.—The total population of Rohri Sub-division in 1872 was returned at 217,515, of whom 176,789 were Muhammadans, 37,917 Hindus, 1853 Bhíls, 134 Sikhs, and 822 'others.' In 1881 it was returned, including a part of Kohistán, at 209,114, namely, 111,799 males and 97,315 females; occupying 41,167 houses, in 3 towns and 344 villages. Hindus numbered 27,409; Muhammadans, 167,915; Sikhs, 8888; Christians, 109; Pársis, 1; and aboriginal tribes, 4792. Average density of population, 38·6 persons per square mile. The inhabitants of the Registán are a strong, active, and temperate race. The chief towns are ROHRI, GHOTKI, and MÍRPUR. Eight fairs are held in the Sub-division, 5 in the Rohri, and 3 in the Ghotki *táluk*, with an attendance varying from 1000 to 3000 people. The towns of Rohri, Ghotki, Mírpur, Ubauro, and Pano Akil contain travellers' bungalows. The principal antiquities are the ruined town and fort of AROR, and the old stronghold of Mathelo, which is situated on rising ground about 45 miles north-east of Rohri town, and is said to have been founded by a Rájput about 1400 years ago. About 2½ miles from Rohri are the ruins of an ancient town called Hakrah, built on the extremity of a

ROHRI

rocky hill, which appears to have been gradually covered by the mud from the flood waters of the Indus, that even now flow over the spot. During the construction of the Sind, Punjab, and Delhi Railway, the ruins of the old Hindu city of Veujnot were discovered. The ruins are about 2 miles from the village and railway station of Reti, on the banks of the Ren, which is supposed to have been formerly the main channel of the Indus.

Agriculture—Two crops are raised in Rohri, viz—the *khari*, sown between March and July, and reaped between July and December, which includes cotton *jodr* (*Sorghum vulgare*), *bajra* (*Pennisetum typhoideum*), indigo, rice, oil seeds, vegetables, etc., and the *rabi*, sown between November and March and reaped in March and April, comprising wheat, gram, *dhanaya* (coriander), tobacco, wheat, rice, and barley. *Joad* and *bajra* form the staple articles of food. Of the total area, only 144,832 acres are under cultivation. Fruits and vegetables are extensively grown. Irrigation is carried on by means of canals which have already been enumerated. The floods of the Indus, or *lets* as they are called, are also a source of fertility, but when excessive, they cause great destruction to land and crops. Protective embankments have been erected in several villages. The fiscal settlement of the Sub division was begun in 1856-57 but not completed till 1871-72. The revised settlement was introduced into the Rohri *taluk* in 1881-82 for ten years, while the original settlement is still current in the other *taluks* of the Sub division. The average rate per acre assessed on cultivable land is Rs 3 10 (7s 3d) in Rohri *taluk*, Rs 1 12 (3s 6d) in Mirpur *taluk*, Rs 2 10 (5s 3d) in Ghotki *taluk*, and Rs 2 4 (4s 6d) in Ubauro. The principal tenure is the *maurusi* system under which the tenants possess a right of occupancy. The *zamindari* system also prevails to some extent. Land is held in *jagir* in every *taluk*, but the largest area is found in that of Rohri, viz 31,000 acres. In connection with the *jagirs*, must be mentioned the Sayyids of Bakhur and Rohri who have held lands in gift in this Sub division from about 1290 A.D. Additional grants were made to them in 1712 by Jihandar Shah. The conditions on which the Sayyids held their territory seem to have been (1) to pray for their imperial masters and (2) to guard the country from marauders. The privileges of the Sayyids were confirmed by the Kalhora sovereigns, but Mir Sohrab Khan Talpur commuted their land assessments and remissions for a fourth share of the revenue alienated to the grantees.

Manufactures, etc—Pottery, coarse cloth, and lime are the chief manufactures of the Sub division. The annual quantity of lime made is estimated at 25,000 *munds*, or about 900 tons. The towns of Ghotki and Khairpur Dharki are noted for their manufacture of pipe bowls, snuff boxes, scissors, and cooking pots. The most important exports

from Rohri are grain, fuller's earth, lime, oil, wool, fruits, silk cloth, and indigo. The imports are wheat, sugar, tobacco, *ghi*, metals, cotton cloth, salt, and shoes. The Sub-division also carries on a considerable transit trade in grain, sugar, molasses, wool, wine, iron bars and pots, and cotton. The total length of roads is 400 miles. The main trunk road is that which connects Haidarábád with Múltán. There are 25 ferries in Rohri Sub-division, of which 22 are on the Indus and 3 on the Nára. The Sind, Punjab, and Delhi (now the North-Western State) Railway traverses the Sub-division, with nine stations—Rohri, Sangi, Pano Akil, Mahaser, Ghotki, Sirhad, Mírpur, Khairpur Dharki, and Rehti.

Revenue.—The imperial revenue in 1873-74 amounted to £37,966; and in 1881-82 to £35,864, of which £33,250 was derived from the land-tax, £1171 from excise, £1443 from stamps, and £59 from fines and fees. The local revenue was £3710, derived from cesses on land and *sayer* revenue, fisheries, cattle pound, and ferry funds. The gross revenue was therefore £39,574. There is a special civil officer for the Sub-division, and a subordinate judge, who holds his court at Ghotki. The administration is carried on by an Assistant Collector with full magisterial powers. The total number of police is 248 men, or 1 to every 843 of the population. In 1881-82 there were 22 Government schools, with 1147 pupils, including one school for girls at Rohri town. The Sub division contains three municipalities, ROHRI, UBAURO, and GHOTKI; their aggregate receipts in 1883-84 amounted to £1828; the incidence of taxation per head of population varied from 8d. to 2s. 6d.

Climate.—The transition from the hot to the cold season is very sudden in Rohri. The average rainfall registered during twenty years ending 1881 was 5·6 inches. The prevalent diseases are fevers, ague, rheumatism, and dysentery.

Rohri.—*Táluk* of Rohri Sub-division, Shikárpur District, Sind, Bombay Presidency. Area, 1550 square miles. Including a portion (1135 square miles) of Kohistán, the Census Report of 1881 returned the population at 68,582, namely, 36,331 males and 32,251 females; occupying 14,623 houses, in 1 town and 66 villages. Hindus number 9753; Muhammadans, 51,643; Sikhs, 6393; aboriginal tribes, 723; Christians, 69; and Pársi, 1. The *táluk* contained in 1882-83—criminal courts, 2; police circles (*thánás*), 11; regular police, 63 men. Revenue (1882-83), £11,691. In 1882-83 the area assessed to land revenue was 35,362 acres; the area actually cultivated, 32,897 acres.

Rohri.—Town in Shikárpur District, Sind, Bombay Presidency; situated in lat. 27° 42' N., and long. 68° 56' E., upon the right or west bank of the Indus, on a rocky eminence of limestone interspersed with flints. Population (1881) 10,224, namely, 5361 males and 4863 females. Hindus number 3097; Muhammadans, 4882; Christians, 69;

THE INDIAN EMPIRE:

Its History, People, and Products

New Edition, 747 pages, with Map Price, 21s

BY SIR WILLIAM WILSON HUNTER, K.C.S.I.

'A marvellous combination of literary condensation and original research. It gives a complete account of the Indian Empire its history, peoples, and products, and forms a worthy outcome of seventeen years of labour, with exceptional opportunities for rendering that labour fruitful. Nothing could be more lucid than Sir William Hunter's exposition of the economic and political condition of India at the present time, or more interesting than his scholarly history of the India of the past.'—*The Times*

'Alone and unapproached as a complete, although necessarily condensed, account of India and its people.'—*The Westminster Review*

'Never before has the whole subject of Indian history been so adequately and intelligibly treated.'—*The Pall Mall Gazette*

'A compact body of information arranged and classified on correct principles.'—*The Acadamy*

'A model of combined lucidity, conciseness and comprehensiveness.'—*The Economist*

'It is not too much to say that no account of any country has been presented to the public which combines compactness, completeness and artistic literary skill in the same measure as is displayed by this remarkable volume. Many of its sections are based upon entirely new materials derived from local research.'—*The Pioneer* (India)

'Our great dependency is first viewed in its physical aspect, and we survey as if on a map in high relief the three regions into which its area naturally falls: the mountain system which forms an impenetrable barrier in the north, the river plains which, so to speak, nestle under the shadow of the Himalayas, and the table lands of the distant south. Passing from the work of nature to that of man, we behold, marshalled in stately procession, the various races which have successively modified India, so that the German public the high appreciation which it panagrams thus presented can hardly be overrated.'—*The Englishman* (Calcutta)

'This volume deserves from the English public the high appreciation which it has already received from English readers. It places before us, as upon a stage, the facts that form the key to the development of India and its people, its political, social, and geographical conditions, its trade, commerce, and agriculture. The arrangement is convenient for reference; the descriptions are clear and often fascinating, and several subjects, for example the history of Christianity in India, are here for the first time treated from the basis of local research. The work also affords a proof of the earnest desire of the British Government of India to improve the condition of the people of the great Empire, which had remained in a backward state under the East Indian Company.'—*Berliner Zeitung*

'What gives to this work its high value is first, the trustworthy statistical endeavour of the author to clearly trace back so far as possible within his limits, the existing conditions to their historical origin, and to present a realistic picture not only of India in the past, but also of what immediately lies before her. He has taken the utmost care to minutely make use of the best sources of information, and has thus succeeded in producing a work which is fascinating in the highest degree, and which can claim throughout to represent in essentials the present state of research.'—*Dr A. Weber in the Deutsche Literatur Zeitung*

TRUBNER & CO, LONDON

ROHRI TOWN

Parsi, 1, and aboriginal tribes, 2175 The Hindus, who are mostly of the Baniya caste, are engaged in trade, banking and money lending, while the Muhammadans are chiefly of the Kazi, Sayyid, Bhuta, Kori, Patoli, Muhána, Khali, Memon, Shaik, and Shikári tribes

Rohri is said to have been founded by Sayyid Rukn-ud-din Shah in 1297 The rocky site terminates abruptly on the west in a precipice 40 feet high, rising from the bank of the river, which during the inundation season attains a height of about 16 feet above its lowest level On the northern side is the mouth of the new supply channel for the NARA (EASTERN) (qv), 156 feet wide, which is provided with powerful sluice gates to regulate the supply of water, as required

Rohri, when seen from a little distance, has a striking and pleasing appearance, the houses being lofty, frequently four and five storeys high, with flat roofs surrounded by balustrades, some are of burnt brick, erected many years ago by wealthy merchants belonging to the place But the streets are in several parts very narrow, and the air close and unwholesome Rohri has road communication with Mirpur, Kandár, and Sangrar, and the main trunk road from Haidarabad to Multan also passes through it The town has derived a new importance as the station where the North Western State Railway (formerly the Sind, Punjab, and Delhi) crosses the Indus The passage is at present effected by steam ferries, but the magnificent iron bridge now under construction (1886) will complete the line between Karachi and Calcutta, via Lahore and Delhi The chief public buildings are the *mukhtidrar's* court, municipal commissioners' office, dispensary, police station, travellers' rest house, Government schools, post office, and cattle pound The police force for the protection of the town numbers 10 men

Rohri has a large number of Muhammadan places of worship One, known as the Jama Masjid, was built in 1564 by Fitch Khan, a lieutenant of the Emperor Akbar, it is a massive but gloomy pile of red brick, covered with three domes and coated with glazed porcelain tiles The other, the Idgah Masjid was erected in 1593 by Mir Musan Shah The War Mubarak, a building about 25 feet square, situated to the north of the town, was erected about 1545 by Mir Muhammad, the reigning Kalhora prince, for the reception of a hair from the beard of Muhammad This hair, to which miraculous properties are ascribed by the faithful, is set in amber, which again is enclosed in a gold case studded with rubies and emeralds, the gift of Mir Ali Murad of Khairpur The relic is exposed to view every March, a fact which the devotees are led to believe proceeds from supernatural agency Rohri possesses a municipality, established in 1855, and the town has, in consequence, been greatly improved both as regards health and

appearance. The municipal income in 1883-84 amounted to £1487; the incidence of taxation per head of population, 2s. 6d. The trade is principally in grain, oil, *ghí*, salt, fuller's earth, lime, and fruits. *Tasar* silk is manufactured, as well as gold and silver bracelets, and other ornaments. Paper of an indifferent quality is also made; but, as a whole, the manufactures are unimportant. Opposite to Rohri on the Indus is the small island of Khwája Khizr, containing the shrine of a saint who is revered alike by Muhammadans and Hindus.

Rohtak.—District in the Lieutenant-Governorship of the Punjab, lying between $28^{\circ} 19'$ and $29^{\circ} 17'$ N. lat., and between $76^{\circ} 17'$ and $77^{\circ} 30'$ E. long. Area, 1811 square miles. Population (1881) 553,609. Rohtak forms the south-eastern District of the Hissár Division, and is situated on the confines of Rájputána, beyond the southern boundary of the Punjab proper. It is bounded on the north by Jínd (Jhind) State and Karnál District; on the east by Delhi and Gurgáon Districts; on the south by Gurgáon District, Pataudi and Dujána States; and on the west by Hissár District and Jínd State. Rohtak stands twenty-seventh in order of area, and nineteenth in order of population among the 32 Districts of the Punjab. It comprises 1.70 per cent. of the total area, and 2.94 per cent. of the total population of the Province. It contains little more than half the average area of a Punjab District; but in extent of cultivation it ranks eighth, and in amount of revenue sixth, among the Districts of the Province. It is divided into four *tahsils*, of which Gohána comprises the northern, Jhajjar the southern, Samplá the east central, and Rohtak the west central portion of the District. At the point of junction of Jhajjar, Samplá, and Rohtak *tahsils* are situated the two estates of Dujána and Mahrana, comprising an area of $11\frac{1}{2}$ square miles, which form a portion of the territory of Dujána State, although completely surrounded by Rohtak villages. The administrative head-quarters of the District are at the town of ROHTAK, on the main road from Delhi to Hissár.

Physical Aspects.—The District of Rohtak lies in the midst of the level table-land separating the Jumna (Jamuná) and Sutlej (Satlaj) valleys, and is one of the few Punjab Districts which nowhere abuts on any one of the great rivers. Its surface is one unbroken plain, consisting of a hard clay, interspersed with light yellow sand, and covered in its wild state by a jungle of scrubby brushwood. Towards the south-west, the proportion of sand increases as the plain approaches the confines of the desert; but in the remainder of the District, cultivation has probably reached its utmost limit. Eastward, the land falls gradually towards the Delhi frontier, becoming low and swampy in the neighbourhood of the Najafgarh *jhil*, a marshy lake which forms the only natural reservoir for the drainage of the District. This *jhil*

itself lies within the boundaries of DELHI, but the Sahibi, a little *nala* flowing from the Ajmere (Ajmir) Hills, traverses a corner of Rohtak, and is the solitary stream of which the District can boast. During the rainy season it throws off numerous smaller watercourses, which irrigate and occasionally flood the surrounding country. The Rohtak and Butāna branches of the Western Jumna Canal supply water to the northern *parganas*, but the greater portion of the central plain is entirely dependent upon the uncertain rainfall. So absolutely level is the surface, that rain sinks in as it falls, and it is only by artificial means that the water can be enticed into the tanks which have been rudely excavated in the neighbourhood of every village. Their origin is of immemorial antiquity, and their pleasant fringe of trees and brushwood forms a characteristic feature in the otherwise monotonous landscape. The only exception to the general flatness is to be found on a part of the Gurgaon boundary, where a few low rocky hills crop up above the barren and sandy levels of the south eastern angle. Game is plentiful including wild hog deer and hare. Pea fowl, partridge, and small birds are to be met with throughout the year, and during the cold season wild geese, bustards, and flamingoes swell the list. Wolves are still common and a stray leopard is occasionally killed.

History—Rohtak was formerly included within the undefined boundaries of the region which bore the name of Haryana. The town of Mahim appears to have been its most important centre in early years, and is said to have been destroyed by Shahab ud din Ghorī, but restored in 1266. Little can be ascertained however, with reference to its annals before the year 1718, when the whole of Haryana was granted by the Emperor Farrukhsiyar to his minister, Rukhan ud daula. The courtier made over his title in turn to a Baluch noble, Faujdar Khan, who was created Nawāb of Farukhnagar in 1732. The Nawāb's dominions embraced the present Districts of Hissār and Rohtak, besides part of Gurgāon and a considerable region since annexed by the Sikh chieftains of Jind and Patāla. Faujdar Khān handed down his possessions to his son, who held them with varying fortunes till his death in 1760. That date coincides with the final collapse of the decaying empire, being the year in which Alamgir was murdered, and the titular Emperor Shah Alam ascended the throne of Delhi. His rule hardly extended beyond the city walls, and a period of anarchy set in. The next year saw the crushing defeat of the Marathās at Panipat, after which the Sikh adventurers began to change their policy from mere predatory incursions to conquest and settlement. The new Nawāb of Farukhnagar found his title from the first purely nominal, and in 1762 he was driven from his capital by the Jāt leader, Jawahar Singh of Bhartpur (Bhurlpore).

For the next twenty years, Hariána passed through the usual vicissitudes of Upper India in this anarchic time: now the Nawáb recovered for a time his hereditary dominions; now Najaf Khán bestowed them on one of his followers; and now again the husband of Begam Sumru of Sardhána (Walter Reinhardt) held part of them in fief. The Maráthás in 1785 put a stop for a while to these disorders; but even Sindhia was not able to repel the Sikh invasions, and in the end he was compelled to settle large portions of Hariána on the Sikh rulers of Kaithal and Jind. Meanwhile the military adventurer George Thomas had carved out a principality for himself from the remainder, and fortified his position in two strongholds at Georgegarh near Jhajjar, and Hánsi in the District of Hissár. In 1802, the Maráthás, under their French generals, succeeded in ousting Thomas; but the conquests of Lord Lake, a year later, laid the whole country, up to the Sutlej and the Siwálíks, at the feet of the British Government. In fact, however, the supremacy of the Maráthás west of the Jumna, in its upper course, had been little more than nominal; and some time elapsed before any practical measures were taken in the cis-Sutlej and Hariána regions.

The northern *parganás* of Rohtak were held by the Sikh chiefs of Jind and Kaithal, while the south was granted to the Nawáb of Jhajjar, the west to his brother the Nawáb of Dádri and Bahádurgarh, and the central tract to the Nawáb of Dujána. The latter, however, was unable to maintain order in his portion of the territories thus assigned; and the frequent incursions of Sikh and Bhatti marauders compelled the despatch of an English officer in 1810, to bring the region into better organization. The few *parganás* thus subjected to British rule formed the nucleus of the present District. Other fringes of territory escheated on the deaths of the Kaithal Rájá in 1818, and the chieftain of Jind in 1820. In the last-named year, Hissár and Sirsa were separated from Rohtak; and in 1824, the District of Pánipat (now Karnál) was erected into a separate charge.

Up to the year 1832, Rohtak was administered by a Political Agent under the Resident at Delhi; but it was then brought under the General Regulations, and annexed to the North-Western Provinces. On the outbreak of the Mutiny in 1857, Rohtak was for a time completely lost to the British Government. The Muhammadan tribes united with their brethren in Gurgáon and Hissár, and began a general predatory movement under the Nawábs of Farukhnagar, Jhajjar, and Bahádurgarh, and the Bhatti chieftains of Sirsa and Hissár. They attacked and plundered the civil station at Rohtak, destroying every record of administration. But before the fall of Delhi, a force of Punjab levies was brought across the Sutlej, and order was restored with little difficulty. The rebel Nawábs of Jhajjar and Bahádurgarh were captured and tried. The former was executed at Delhi, while his

neighbour and relative escaped with a sentence of exile to Lahore. Their estates were confiscated, part of them being temporarily erected into a new District of Jhajjar, while other portions were assigned to the Rajas of Ind, Patiala, and Nabha, as rewards for their services during the Mutiny. Rohtak District was transferred to the Punjab Government, and in 1860, Jhajjar was broken up, part of it being added to the territory of the loyal Rájás, and the remainder united with Rohtak.

Population—The territorial changes which followed so fast during the middle of the present century make it impossible to give any accurate comparative statement of the population at different periods, but by adding and subtracting the official returns for the various fluctuating *parganas* at either date, an increase is found on the constant portion, between 1846 and 1868, amounting to 61 per cent. So great an advance in little more than twenty years is scarcely credible, yet we must allow a very rapid rate of growth, as the more accurate figures of the enumerations taken in 1853 and 1868 show an increase of 20 per cent in fifteen years, which may be accepted as approximately correct. The Census of 1868 disclosed a total of 531,118. The last enumeration in 1881 returned the population of Rohtak District at 553,609, showing an increase of 22,491, or 4·2 per cent, in thirteen years.

The general results of the Census of 1881 may be summarized as follows—Area of District, 1811 square miles, towns and villages, 486, number of houses, 118,330, namely, occupied 74,813, and unoccupied 43,517, number of families, 553,609. Total population, 553,609, namely, males 296,224, and females 215,792. Average density of population, 306 persons per square mile, varying from 240 per square mile in Jhajjar *tahsil*, to 378 per square mile in Gohana. Number of villages per square mile, 27, persons per town or village, 1139, houses per square mile, 65, persons per house 7·4. Classified according to sex and age, the population comprises—under 15 years, males 107,211, and females 91,944, total children, 199,155 or 35·9 per cent of the population. 15 years and upwards males 189,013 and females 165,441, total adults, 354,454, or 64·1 per cent.

Religion—As regards religious distinctions, Rohtak is essentially a Hindu District, as many as 468,905 persons, or 84·6 per cent, being adherents of the ancestral faith. The Muhammadans here sink to 79,510 persons, or 14·3 per cent. Only 159 Sikhs are recorded, belonging chiefly to the ruling families. Jains number 5000, Christians and others, 35.

As regards ethnical distinctions, the Bráhmans number 58,211 persons, most of whom are engaged in agriculture, an occupation which they follow with much indolence and thriftlessness. The Rajputs amount to 7354 Hindus and 22,620 Musalmáns. Like their neigh-

bours, the Bhattis of Hissár and Sirsa, they still retain somewhat of the cattle-lifting reputation which they earned during the long anarchy of the Sikh and Maráthá struggle. The trading classes are represented by 41,470 Baniyás, a large number of whom profess the Jain creed. The majority of the people belong to the inferior castes, amongst which the Játs rank by far the first, forming more than one-third of the whole population. They are returned at 180,778 Hindus, and 1998 converted to Islám. The Játs keep up their usual reputation for painstaking agriculture; they are divided into two principal clans, which entertain towards one another a singular animosity. There is also a considerable sprinkling of Gújars (3032), Patháns (5155), and Balúchís (1986).

Town and Rural Population.—The District is noticeable for the very small number of minor villages, and the large proportion of towns with a population exceeding 4000. In 1881 there were 13 so returned—namely, ROHTAK, 15,699; JHAJJAR, 11,650; BUTANA, 7656; GOHANA, 7444; KALANAUR, 7371; MAHIM, 7315; BERI, 6695; BAHADURGARH, 6674; BARODA, 5900; MANDLANA, 5469; KANHAUR, 5251; SANGHI, 5194; and KHARKHANDA, 4144. These figures show a total of 96,462, or 17·4 per cent. of the District population; but they cannot be considered to represent the real urban population, since many of the above-named places are rather overgrown villages than towns strictly so called. As there were also 169 villages containing a population of more than 1000, out of a total of 486 for the whole District, the tendency for the agricultural body to aggregate in considerable clusters is very marked, and may perhaps be set down to the general insecurity of the country during the century which preceded the British occupation. Only 54 villages contained less than two hundred inhabitants; 134 contained from two to five hundred; and 129 from five hundred to a thousand.

As regards occupation, the Census Report of 1881 returned the adult male population under the following seven classes:—(1) Professional class, including all Government officials, civil and military, 7827; (2) domestic and menial class, 7803; (3) commercial class, including bankers, merchants, traders, carriers, etc., 5440; (4) agricultural and pastoral class, including gardeners, 100,216; (5) industrial and manufacturing class, including artisans, 48,721; (6) indefinite and non-productive class, including general labourers, 11,481; (7) unspecified, 7525. Urdu and Hindí are the languages in common use.

Agriculture.—Almost all the available land in the District is already under tillage, the returns for 1883–84 showing a total of 906,334 acres cultivated, with a narrow margin of 166,790 acres of cultivable waste, the balance consisting of 5198 acres of grazing ground, and 68,671 acres of uncultivable waste. In the central and southern

parganas, where the peasant is entirely dependent upon the runfall for his water supply, barley and gram form the staple spring crops, while *soar*, *bajra*, and cotton are the mainstays of the autumn harvest, but in the canal irrigated villages to the north and east, wheat is added to the list in spring, and rice or sugar cane in autumn. The area under the principal crops in 1883-84 is returned as follows—*soar*, 291,021 acres, *bajra*, 171,251 acres, gram, 166,701 acres, wheat, 61,311 acres, barley, 30,384 acres, *moth*, 24,833 acres, rice, 4452 acres, oil seeds, 2483 acres, cotton, 45,052 acres, sugar cane 11,781 acres, and indigo, 4011 acres. Irrigation is chiefly confined to the canal system, the depth of water below the surface, except on the low lying eastern border, being generally too great to permit the profitable working of wells. The total area irrigated in 1883-84 amounted to 119,408 acres, of which 110,991 acres were supplied from Government works and 8417 acres from private sources. The use of manure is on the increase, and the villagers are beginning to appreciate the value of a rotation of crops. Yet the District authorities are of opinion that cultivation has almost reached its highest point, and the land is reported to be in a condition of gradual impoverishment. The growth of cotton and hemp is increasing. The average out turn per acre in 1883-84 was returned as follows—Wheat 960 lbs, rice 787 lbs, barley, 522 lbs, gram, 308 lbs, indigo, 590 lbs, oil seeds, 192 lbs, and cotton, 236 lbs per acre. The agricultural stock of the District in 1883 comprised—cows and bullocks, 204,293, horses, 1218, ponies, 1644, donkeys, 10,889, sheep and goats, 59731, pigs, 10,727, and camels, 2332.

The mode of tenure known as *bhayachara*, or brotherhood, is the most common. Throughout the District, the villages are banded together by custom into an organized cluster (or *tappa*), which formerly owned the supremacy of one chief (or *tappadari*) village. The *tappa* includes all the communities immediately surrounding the central and supreme village without distinction of race or caste, and the league is thus in all probability a relic of some defensive arrangement, concerted during the period of Sikh and Bhatti incursions. In many villages, local custom subjects the non cultivating classes to a tax (called *lamunt*) in favour of the proprietors. By far the greater part of the soil is cultivated by tenants at will. Rents run as follows, according to the nature of the crop which the soil is fitted to produce—Cotton lands, from 1s 6d to £1 per acre, sugar cane lands, from 2s to £1, 4s per acre, wheat lands, irrigated, from 3s to £1, dry, from 2s to 9s per acre, other grains, dry land, from 6d to 8s per acre. The Government land revenue assessment in 1883-84 amounted to £94,834, or an average of 2s 0½d per cultivated acre.

Wages have risen of late years, the change being attributed to the

emigration of labourers (principally Chamárs), to find employment on the railway and the Sirhind Canal. Skilled workmen in towns are paid at the rate of from 6d. to 1s. per diem, and unskilled workmen receive from 3d. to 4½d. Agricultural labourers are generally paid in cash; as much as 4½d. per diem, with food, is sometimes given at harvest-time. In canal villages, labourers take their wages in kind, receiving one-third of the crop. Prices of food-grains ruled as follows on the 1st January 1884:—Wheat, 19 *sers* per rupee, or 5s. 11d. per cwt.; gram and barley, 26 *sers* per rupee, or 4s. 4d. per cwt.; *jodr*, 24 *sers* per rupee, or 4s. 8d. per cwt.; *bájra*, 20 *sers* per rupee, or 5s. 7d. per cwt.; and rice, 8 *sers* per rupee, or 14s. per cwt.

Natural Calamities.—Rohtak, like its neighbour Hissár, suffers greatly from drought. Nine-tenths of its area is entirely dependent on the rainfall, and scarcity from this cause pressed upon the District in 1824, 1830, 1832, and 1837. The severe famine of 1860–61 taxed the people to their utmost endurance; and the season of 1868–69 was a most disastrous one. Two successive crops, both of grain and fodder, had failed in the dry southern plain, and distress began to show itself early in 1868. Relief measures were at once adopted, and the total number of persons who received gratuitous assistance during the month of January 1869 amounted to 150,102. Famine works were also undertaken, and continued until August. Fears were at one time entertained for the succeeding autumn and spring harvests, but rain happily fell in time to save the District from such an aggravation of its misfortunes. The loss of cattle added to the misfortunes of the cultivating classes. Out of 350,100 head in the District, as many as 88,300, or more than 25 per cent., perished from starvation or disease.

Perhaps, however, the last famine in 1877–78, also caused by drought, was as disastrous, and certainly as ruinous as regards the loss of cattle. There was but little rain in June 1877, none in July or August, and only two inches in September, when it was too late to sow anything. Grass withered away from the face of the soil, the cattle began to die in large numbers in the autumn, and famine prices were soon reached. Highway robberies grew common, grain carts were plundered, and finally the *bázár* at Badli was attacked and plundered by the Játs of the place. The winter rains again failed, and the mortality among cattle became terrible; but no actual relief measures were set on foot. Fortunately, good rain fell at last in July and August 1878, and though the later rains were scanty, an abundant crop of fodder was obtained and a fair crop of grain. During the cold weather of 1877–78, the aspect of the country was desolate beyond description. There was literally no crop in the rain-land villages; in a ride of 20 miles not even two or three plots were to be seen. The grass had wholly disappeared, and nothing but thorns and weeds met the eye.

in the fields. The loss of cattle of agriculturists amounted to 176,000 in one way or another—by sale, deaths, or transfers, and it will take the District many years to recover from this. Ultimately, £8000 of the collections due in the spring of 1879 was suspended, which perhaps gave a little relief. Of this drought the people quote the following lines—‘An ox sold for a piece of bread, and a camel for a farthing, the year has destroyed the stock (root) of oven and buffaloes. The year has killed thirty four tribes (out of thirty six), two only, the trader and butcher, have survived, the one by use of his scales and the other by use of his knife.’

The people declare that the loss of cattle from famines is now much greater than it used to be, and, in so far as there are now no large grazing grounds in the District and the number of cattle has greatly increased this is true. But fodder is perhaps more carefully preserved than in former days, and famines from actual scarcity of food causing general starvation cannot occur. But again the traders though they keep by them larger stores of grain than formerly, speculate more freely, and export largely their relations also with the people themselves to the local markets. The recurrence of famines are more striven than they used to be. The revenue administration is the most important historical feature in the revenue administration of the District, of whose area only 13 per cent. is artificially protected against drought, and it affects the agriculturists to some degree in their social relations. The people of rain land villages strive to get a few acres of canal land to cultivate in years of drought, and so great is the burden of this to the dwellers in canal estates, that they will not marry their daughters into rain land villages, if they can help it.

Commerce and Trade, etc.—Rohtak is a purely agricultural District, whose produce hardly more than suffices for its home consumption. A small surplus of grain, cotton, and other raw materials is exported to Delhi, Meerut, and Sahāranpur, while piece goods, spices, iron, sugar, salt, and timber are imported in exchange. Trade is carried on both at permanent markets and religious fairs. There are no manufactures of more than local importance with the exception of ornamental turbans at Rohtak and saddlery at Kalānaur. Pretty pottery is made at Jhajar, and cotton cloth for home use is woven in large quantities. A branch of the new Firozpur-Rewāri Railway passes through Rohtak District for a distance of 12 miles. The District had 66 miles of metalled and 493 miles of unmetalled road in 1884, the Western Jumna Canal is not navigable in this part of its course.

Administration—The imperial revenue of Rohtak District amounted in 1872-73 to £93,310, of which £89,184, or 95 per cent., was derived from the land tax. There was also a local revenue of £7438, besides certain provincial dues which are not collected by separate Districts.

By 1883-84, the total revenue had fallen to £78,346, and the land-tax to £65,440. The administrative staff consists of a Deputy Commissioner, 2 extra-Assistant Commissioners, 4 *tahsildars*, and their subordinates. There were 9 civil and revenue and 23 criminal courts in Rohtak in 1883. The imperial and municipal police numbered 455 men of all ranks. The special village watch is supplemented in this District by a local custom, in accordance with which all able-bodied men of each community take their turn by lot as watchmen. The total number of persons brought to trial upon all charges in 1883 amounted to 1116. There is only one jail in the District, the average daily number of prisoners in which amounted to 236 in 1883.

Education is slowly progressing in Rohtak. In 1872-73 there were 2852 children receiving instruction. In 1883-84, there were in all (exclusive of indigenous village schools) 49 Government and aided schools under inspection by the Education Department, attended by 2914 pupils. The Census Report of 1881 returned 2864 boys and 33 girls as under instruction; and 13,814 males and 70 females as able to read and write, but not under instruction.

There are 6 municipalities, namely, Rohtak, Beri, Jhajjar, Khar-khanda, Bahádurgarh, and Gohána. The aggregate revenue of these towns amounted in 1883 to £3018, being at the rate of 1s. 1½d. per head of their population.

Sanitary Aspects.—The climate of Rohtak is considered healthy, except in the northern portions, where percolation from the canal produces malaria, and generates the same fevers and spleen complaints that are so common under similar circumstances in the adjoining District of Karnál. Small-pox also exists in an endemic form. The total number of deaths from all causes reported in 1883 was 14,171, or 25 per thousand of the population; but these figures are probably considerably below the truth. Four charitable dispensaries afforded medical relief to 812 in-door and 19,115 out-door patients in 1883. The average annual rainfall at Rohtak town for seventeen years ending 1882-83 was 18·8 inches. In 1883-84, only 14·4 inches were measured. No thermometrical returns are available. [For further information regarding Rohtak District, see the *Gazetteer of Rohtak District*, published under the authority of the Punjab Government (Lahore, 1884); *Report on the Revised Land Revenue Settlement of Rohtak District*, 1873-79, by Messrs. W. E. Purser and H. C. Fanshawe, B.C.S. (published 1880); the *Punjab Census Report* for 1881; and the several annual Administration and Departmental Reports of the Punjab Government.]

Rohtak.—West central *tahsil* of Rohtak District, Punjab; consisting of a sandy and almost waterless plain. Area, 587 square miles; towns and villages, 104; number of houses, 35,282, namely, occupied

23,792, and unoccupied 11,490, number of families, 35,962 Total population (1881) 171,215, namely, males 91,006, and females 80,209 Average density of population, 292 persons per square mile Classified according to religion, the population consists of—Hindus, 134,917, Muhammadans, 34,834, Jains, 1338, Sikhs, 95, and Christians, 31 Of the 104 towns and villages, 27 contain less than five hundred inhabitants, 31 from five hundred to a thousand, 40 from one to five thousand, and 6 upwards of five thousand inhabitants The average annual area under crops for the five years 1877-78 to 1881-82 is returned at 357 square miles, or 228 555 acres, the principal crops being—*joar*, 80,450 acres *gram*, 54,154 acres, *bajra*, 36,058 acres, wheat, 18,710 acres, *bailey*, 8543 acres, *moth*, 3411 acres, rice 1205 acres, cotton, 10,857 acres, and sugar cane, 4631 acres Revenue of the *tahsil*, £23,715 The administrative staff, including the District head quarters officers, consists of a Deputy Commissioner, Judicial Assistant Commissioner, Assistant Commissioner, *tahsildar*, *munsif*, and 2 honorary magistrates These officers preside over 5 civil and 6 criminal courts Number of police circles (*thanas*), 4, strength of regular police, 127 men, village watch or rural police (*chaukidars*), 219

Rohtak—Town and municipality in Rohtak District, Punjab, and head quarters of Rohtak District and *tahsil* Situated in lat 28° 54' N, and long 76° 38' E, 42 miles north west of Delhi, on the Hissar road Rohtak town dates from a remote antiquity, though little can now be recovered of its early history The ancient site, known as Khokra kot, lies a small distance north of the modern town Rebuilt, according to one tradition, in the time of Prithwi Ráj (1160 A D) according to another, as early as the middle of the 4th century During the stormy period which succeeded the decay of the Mughal Empire Rohtak fell into the hands of one chieftain after another It became in 1824 the head quarters of a British District, a position which it has since retained Population (1881) 15,699, namely, males 8155, and females 7544 Hindus number 8180, Muhammadans, 6928, Jains, 501, Sikhs, 62, and Christians, 28 Number of houses, 2622 Municipal income (1883-84), £756, or 1s per head The town is the centre of a local grain trade, but is of small commercial importance outside its own neighbourhood Manufacture of cotton turbans Court house, police station, *tahsil*, church, *dak* bungalow, post office, school house, dispensary, public garden An annual horse show is held at Rohtak in October, which, though only recently established, promises to become very popular

Rohtang—Pass in Kangra District, Punjab, over the Himálavan ranges Lat 32° 22' 20" N, long 77° 17' 20" E The pass lies between Koksár in Láhul and Palchán in Kulu A made road runs over it, practicable for laden mules and ponies The crest has an elevation

of only 13,000 feet above the sea—very much lower than that of most neighbouring passes. The range on either side rises to a height of 16,000 feet, while several peaks within 12 miles exceed 20,000 feet. The main road from Sultánpur and Kángra to Leh and Yárkand crosses this pass, and then proceeds by the valleys of the Chandra and Bhága to the Bára Lácha, whence it descends into Ladákh. The Rohtang pass is generally open fairly well until the end of December. The Beas (Biás) takes its rise at the summit of the pass from a spring called Biáskund, which is regarded with a certain amount of veneration by Hindus.

Rohtás.—See *post*, ROTAS.

Rohtásgarh.—Hill fort in Sháhábád District, Bengal, about 30 miles south of Sasseram town, overlooking the junction of the Koel with the Son (Soane) river. Lat. $24^{\circ} 37' 30''$ N., long. $83^{\circ} 55' 50''$ E. The principal place of interest in the District from an antiquarian point of view. It derives its name from Rohitáswa, son of Harischandra, a Hindu king of the Solar dynasty, whose image was worshipped on this spot till destroyed by Aurangzeb. Little is known concerning the persons who held the fort from Harischandra's time until 1539, the year of its capture by Sher Sháh, who immediately began to strengthen the works, but soon after selected a more favourable site at SHERGARH. Mán Singh, Akbar's Viceroy of Bengal, at the end of the 16th century, chose Rohtás as his stronghold; and two inscriptions in Sanskrit and Persian attribute to him all the buildings now existing. The remains of the fortress occupy a part of the table-land of Rohtásgarh, about 4 miles from east to west and 5 miles from north to south, with a circumference of nearly 28 miles. In 1848, Dr. Hooker ascertained its precise elevation to be 1490 feet. Much of the area is bare rock, but there is also a large quantity of red soil. The hill is accessible by 83 paths, of which four are called the great *gháts*, and the rest *ghátís*. The principal antiquities of Rohtásgarh are—two temples, said to have been built by Mán Singh, one of which is covered by a dome surpassing in lightness all the Hindu works that Dr. Buchanan-Hamilton had ever seen; a small mosque, ascribed to Aurangzeb; the palace or *mahál saráí*, with the building known as the *bará dwári* or twelve gates, where business was transacted. All these edifices are fully described in the *Statistical Account of Bengal*, vol. xii. pp. 209–212. (There is another famous Rohtás fort on the skirts of the Salt Range, in the Punjab. See under ROTAS, the spelling fixed by the Punjab Government.)

Rojhan.—Town in Rájanpur *tahsíl*, Dera Ghází Khán District, Punjab; situated in lat. $28^{\circ} 17'$ N., long. $68^{\circ} 19'$ E., on the west bank of the Indus, below Dera Ghází Khán town. Capital of the Mazári Balúchís, having been founded by Bahráam Khán, Tumándár or chief of that tribe, about 1825. The present chief has built a fine court-

ROJHI—RONAHI

for his own use as honorary magistrate, and a mosque and some tomb in memory of his father and nephew. Population (1881) 5656, namely, Muhammadans, 4319, Hindus, 1269, and Sikhs, 8.

Not separately returned in the Census Report of 1881. Manufacture of woollen rugs and nose bags for horses.

Rojhi (or *Rozi*)—Island, lighthouse, and temple in the State of Nawanagar, Káthiawár, Bombay Presidency. Situated at the mouth of the Nawanagar creek, 8 miles north of Nawanagar town on the southern shore of the Gulf of Cutch. The temple is dedicated to Charan woman with whom a *roz* or *nilgai* took shelter from the pursuit of a chief of Nagar, the woman refused to surrender it, and on its being forcibly killed, cursed its slayer and committed suicide. The lighthouse stands on a white round tower 42 feet above high water on the temple on the north east of the island. Lat $22^{\circ} 32' 50''$ N, long $70^{\circ} 1' 30''$ E. A white fixed light, visible 7 miles in clear weather. Built in 1867 by the chief of Nawanagar.

Rokha Jáis—*Pargana* and town in Rai Bareli District, Oudh—
See JAIS

Ron—Sub division of Dhárwar District, Bombay Presidency, situated in the north east corner of the District Area, 370 square miles. Population (1872) 73 503, (1881) 60 724, namely, 29 726 males and 30,998 females, occupying 11 644 houses in 1 town and 58 villages. Hindus number 56,090, Muhammadans, 4562, and others, 72. Ron Sub division is one stretch of rich black soil, without a hill or upland. The people are skilful, hard working husbandmen, and well to do. Water supply poor. The South Marathá Railway traverses the Sub division, with two stations—Alur and Mallapur. In 1881–82, out of the whole area held for tillage, 3452 acres were fallow or under grass, the principal crops being—grain, 159,843 acres, pulses, 10,518 acres, oil seeds, 9798 acres fibres 67,105 acres, and miscellaneous crops, 341 acres. In 1884 the Sub division contained—criminal courts, 2, police circle (*thana*), 1, regular police, 42 men, village watch (*chaukidars*), 114. Land revenue £16,447. Schools, 20.

Ron—Chief town of the Sub division of Ron, in Dhárwar District, Bombay. Lat $15^{\circ} 41' 30''$ N, long $75^{\circ} 11' 1''$ E, 55 miles north east of Dhárwar town. Population (1881) 5229. Seven black stone temples, in one of which is an inscription dated 1180. Post office.

Ronáhi—Town in Faizábád (Fyzabád) District, Oudh, situated 10 miles from Faizábád town, near the bank of the Gogra. Population (1881) 5210, namely, Hindus, 3418, Muhammadans, 1788, and 'others,' 4. Five Hindu and 3 Jain temples, *saras*, Government school. The Oudh and Rohilkhand Railway and the Faizábád road pass near the town.

Roorkee.—*Tahsil* and town in Sahāranpur District, North-Western Provinces.—*See* RUKKI.

Rori.—Town and municipality in Dabwālī *tahsil*, Sirsa District, Punjab. Lat. $29^{\circ} 43' N.$, long. $75^{\circ} 37' E.$; distant from Sirsa town 19 miles north-west. Population (1881) 3063, namely, Hindus, 1301; Sikhs, 887; Muhammadans, 740; Jains, 134; and Christian, 1. Number of houses, 369. Municipal income (1883–84), £62. The place is merely an agricultural village, or rather collection of hamlets, with little or no trade.

Roshnábád.—Estate or *zamindāri* in Tipperah District, Bengal. Area, 589 square miles, comprising 53 fiscal divisions. A permanently settled estate, belonging to the Rājā of Hill Tipperah, who pays an annual land revenue of £15,361.

Roshra.—Town in Darbhāngah District, Bengal.—*See* RUSERA.

Rotās.—Ruined fort in Jehlam (Jhelum) *tahsil*, Jehlam District, Punjab. Situated in the Salt Range, on a hill overlooking the gorge of the Kuhān Nadi, 11 miles north-west of Jehlam town, in lat. $32^{\circ} 55' N.$, and long. $73^{\circ} 49' E.$ The fort was built by the Afghān Sher Shāh about 1540, during the time of his usurpation of the throne of Delhi, as a check on the Ghakkar tribe. The walls extend for 3 miles, and encircle the rocks which command the entrance of the pass. Some parts have a thickness of from 30 to 40 feet. The total area enclosed by the fortifications amounts to 260 acres. One gateway still remains in excellent preservation; the rest has fallen into ruins, which form a most striking and picturesque group.

Rotāsgarh.—*See ante*, ROHTASGARH.

Rouk-thwa.—Stream which rises in the Paung-laung range in Taung-gú District, Tenasserim Division, Lower Burma.—*See* YAU-KTHWA.

Rozi.—Island, lighthouse, and temple in the State of Nawānagar, Kāthiāwār, Bombay Presidency.—*See* ROJHI.

Rudauli.—*Parganá* in Bara Banki District, Oudh; bounded on the north by the Gogra river, on the east by Mangalsi, on the south by Mawái Maholāra, and on the west by Basorhi and Daryābād. Area, 173 square miles, or 111,102 acres, of which 73,316 acres are cultivated. Population (1881) 98,868, namely, Hindus, 79,017; Muhammadans, 19,828; and 'others,' 23. Land revenue, £14,692. Of the 196 villages comprising the *parganá*, 86 are held in *tālukdāri*, 70 in *zamin-dāri*, and 40 in *pattidāri* tenure. Seven market villages; 9 village schools; post-office; police station, with 2 outposts.

Rudauli.—Town in Bara Banki District, Oudh, and head-quarters of Rudauli *parganá*; situated 37 miles south-east of the civil station, in lat. $26^{\circ} 44' 45'' N.$, and long. $81^{\circ} 47' 20'' E.$ Population (1881) 11,394, namely, Muhammadans 6378, and Hindus 5016. Number

of houses, 2233 The foundation of the town is ascribed to a Bhar chief, Rudra Mall A thriving commercial town, with daily markets, at which a brisk trade is carried on in grain, vegetables, cotton, and cloth A small house tax is levied for police and conservancy purposes

Rudra Himāla —Mountain peak in Garhwāl State, North Western Provinces Lat. $30^{\circ} 58' N$, long $79^{\circ} 9' E$, on the eastern frontier of Garhwāl, towards Chinese Tartary Thornton describes it as consisting of 5 huge snow covered summits, rising above a mass of bare rocky cliffs Elevation above sea level, estimated at 22,390 feet

Rudra Prayag —Temple in Garhwāl District, North Western Provinces Stands at the junction of the Mandakīni, draining the southern slopes of the Kedārnāth and Badrināth peaks, with the ALAKNANDA One of the five sacred *prajdgs* or confluences of the Hindus, and a halting place for pilgrims to Himachal Six miles above the junction of the Mandakīni and Alaknandā rivers, a dome shaped rock, 30 feet in height by 15 in diameter, bears the name of Bhīm ka-chulha or the Kitchen of Bhīm, a famous giant of Hindu mythology It is completely excavated, and has apertures at the top, where Bhīm used to place his cooking utensils The temple is small, and stands by the water's edge Elevation above sea level, 2200 feet

Rudrapur (Rudarpur) —Town in Gorakhpur District North Western Provinces Situated in lat $26^{\circ} 26' 40'' N$, and long $83^{\circ} 39' 35'' E$, on the Bathuā nala upon the Gorakhpur and Barhaj road, 23 miles south east of Gorakhpur town Population (1881) 9843, namely, Hindus 8840, and Muhammadans 1003 The *gola* or grain market, in the business part of the town, is the entrepot whence the grain and *gur* (syrup) of the neighbourhood are exported by river Except by river, the trade is purely local, and it is prevented from developing by a cordon of quagmires created by the rains, which for several months of the year prevents any wheeled communication with the rest of the District A small house tax is levied for police and conservancy purposes Within the limits of the town are the remains of an enormous fort, said to have been erected by the early Rajput settlers when threatened by the aboriginal Bhars before the recovery of the country by the latter (See GORAKHPUR DISTRICT) Fair in February attracts about 1500 persons

Rudrapur —Small village in the Tarāi District, North Western Provinces Lat $28^{\circ} 58' N$, long $79^{\circ} 26' 40'' E$, distant from Bareilly city 53 miles north, upon the Almora road Stands among fine mango groves. Population (1881) 812 Ruined temples and tombs, malarious climate

Rumpah —Hill tract in Godāvāri District, Madras —See RANPA

Runang —Pass in Bashahr (Bassahir) State, Punjab Lat $31^{\circ} 43'$

N., long. $78^{\circ} 28' E.$; lies over a range in Kunáwar, dividing the valley of Raskalang from that of Píjar. According to Thornton, the crest does not reach the limit of perpetual snow. Closed during the four coldest months, when the route runs along a circuitous and dangerous track by the side of the Sutlej. Elevation above sea-level, 14,500.

Run-za-lin (correctly *Yun-za-lin*).—River in the Tenasserim Division of Lower Burma.—See YUN-ZA-LIN.

Rupál.—Petty State and town in Mahi Kántha, Bombay Presidency. The State contains 11 villages; the area of land under cultivation is estimated at 21,000 *bighás*. Population (1881) 3497. The revenue is returned at £350; and tribute of £116, 9s. is paid to the Gáekwár of Baroda, and £36, 4s. to the Rájá of Edar. The chief of Rupál, Thákúr Mán Singh, is a Rehwar Rájput. Rupál is the chief town of the State. School.

Rúpar.—North-western *tahsíl* of Ambála (Umballa) District, Punjab; lying at the foot of the Simla Hills, and along the south bank of the Sutlej (Satlaj). Area, 277 square miles; towns and villages, 361; number of houses, 33,585, namely, occupied 25,496, and unoccupied 8089; number of families, 26,227. Total population (1881) 154,303, namely, males 88,046, and females 66,257. Average density, 557 persons per square mile. Classified according to religion, the population consists of—Hindus, 85,439; Muhammadans, 49,276; Sikhs, 19,341; Jains, 127; and Christians, 120. Of the 361 towns and villages, 271 contain less than five hundred inhabitants; 65 from five hundred to a thousand; and 24 from one to two thousand inhabitants. The only place with a population exceeding two thousand inhabitants is RUPAR TOWN (10,326). The average annual area under crops for the five years 1877–78 to 1881–82 is returned at 211 square miles, or 135,084 acres; the principal crops being—wheat, 46,275 acres; Indian corn, 22,159 acres; *joár*, 17,814 acres; gram, 11,048 acres; *moth*, 7559 acres; rice, 2456 acres; barley, 2212 acres; *bádra*, 1788 acres; cotton, 8426 acres; sugar-cane, 7139 acres; and indigo, 899 acres. Revenue of the *tahsíl*, £13,211. The administrative staff consists of a *tahsildár*, *munsif*, and 2 honorary magistrates, who preside over 4 civil and 3 criminal courts. Number of police circles (*thánás*), 2; strength of regular police, 39 men; village watch or rural police (*chaukidárs*), 408.

Rúpar.—Town and municipality in Ambála (Umballa) District, Punjab, and head-quarters of Rúpar *tahsíl*; situated in lat. $30^{\circ} 57' N.$, long. $76^{\circ} 33' E.$, on the south bank of the Sutlej (Satlaj), 43 miles north of Ambála city. The town is of considerable antiquity, formerly known as Rúpnagar. It was occupied about 1763 by Hari Singh, a Sikh chieftain, who seized upon a wide tract south of the Sutlej, stretching along the foot of the Himálayas. In 1792 he divided his estates

between his two sons, Charrat Singh and Dewa Singh, the former of whom obtained Rupar. The estates were confiscated in 1846, in consequence of the part taken by the family during the Sikh war of the preceding year. Rupar is important as being the site of the head works of the Sirhind Canal, and till recently the residence of a numerous staff of European officers, superintending the construction of the works. Population (1881) 10,326, namely, males 6171, and females 4155. Muhammadans number 5110, Hindus, 4708, Sikhs, 388, Jains, 109, and Christians, 11. Number of houses, 1673. Municipal income (1883-84) £665 or an average of 1s 3½d per head. Two important religious fairs—one Muhammadan, at the tomb of Shah Khalid, in the month of Jaishtha attracting 50,000 persons, the other, a Hindu bathing festival on the banks of the Sutlej in April, attended by an equal number of persons. Rupar is an important mart of exchange between the hills and plains, and carries on a considerable trade in grain, sugar, and indigo. Imports of salt from the Salt Range, re-exported to the hills in return for iron, ginger, potatoes, turmeric, opium, and hemp. Manufacture of cotton cloth, iron hooks, and other hardware. Assistant Commissioner's court, *tahsil*, police office, staging bungalow.

Rupbās —Town in Bhartpur State, Rajputāna. The town was founded by Rup Singh, a descendant of the Rājās of Chittorgarh, who became a Muhammadan, and was a constant attendant at the court of the Emperor Akbar. He built a palace in the Mughal style of architecture, with a large tank attached, both of which are still in existence. There are in the vicinity three colossal images of Baldeojsī, his wife, and Yudhisthira, two enormous monolith columns or obelisks, the inscriptions on which are illegible, and another colossal image, supposed to represent a Buddhist or Jain divinity. Dispensary and post office.

Rūpgarh —Fort in the Songarh Sub division of Nosari (Navasari) Division, Baroda State, Bombay Presidency. Situated about 15 miles south of the town of Songarh and about 35 miles east of Nosari station on the Bombay, Baroda, and Central India Railway, in a salient angle of the Baroda frontier. At one time the fort was useful for keeping the Bhils in check. A tank in the fort is supplied by a perennial spring, Lieutenant J. E. Gibbs, R. E., who visited it in 1875, attributes the presence of the constant supply of cold water with no motion or overflow to the condensation of the vapour of the daily sea breezes, as in the case of ponds on the South Downs of England.

Rupnagar —Town in Udaipur State, Rajputāna. Situated on the summit of the Aravallis, between the Desuri and Someshwar passes. Steep and precipitous hill sides render the village unapproachable from the north and east. Defended by outworks overlooking the plains and

the Desuri pass on the west and south. Founded about 1772, when the Solanki Rájputs of Desuri were finally driven out of that place by Márwár troops. The site seems to have been chosen solely for defence; there is no cultivation belonging to the town, nor is any revenue derived from it.

Rúpnagarh.—Town in Kishangarh State, Rájputána. Population (1881) 5665, namely, Hindus, 4053; Muhammadans, 857; and 'others,' 755.

Rúpnaráyan.—River of Bengal. The name given to the DHAL-KISOR after the confluence of the SILAI, which flows into it from Midnapur District. The course of the Rúpnaráyan, from where it first touches upon Húglí District to where it falls into the Húglí river opposite Húglí Point, in lat. $22^{\circ} 12' 30''$ N., long. $88^{\circ} 3'$ E., is generally south-easterly. Two miles south of Kailá *ghát*, its principal ferry, the Rúpnaráyan is crossed by the Midnapur High-Level Canal from Ulúbária. It is tidal throughout its entire course; and a heavy bore ascends as high as the mouth of the Bakshshí *khál*, the chief tributary of the Rúpnaráyan within Húglí District. The river is protected on its right bank, within Midnapur District, by a continuous embankment 29 miles 2373 feet in length; and it is also embanked all along its left bank, within Húglí District, from its junction with the Bakshshí *khál* to its union with the Húglí river. The bordering lands are more or less inundated by the spring tides in April and May, which leave behind destructive impregnations of salt, rendering them unfit for cultivation unless small defensive works are thrown up round the fields every year to keep the water out. Grass and *hógla* reeds are the ordinary produce, except in years when the rains set in and close early, when a late rice crop can be planted in September. The Rúpnaráyan is navigable throughout the year by native boats of 4 tons burden as far as Ghátál village, in Midnapur District. The river is not fordable at any season of the year within the limits of Húglí District.

Rúpnaráyan and Rasúlpur Canal.—Tidal canal in Midnapur, Bengal, extending from the Rúpnaráyan to the Rasúlpur river, in the Hijili portion of the District; divided into two reaches. The first reach is called the Bánká Canal, and runs from near the mouth of the Rúpnaráyan river to the Haldí river, a distance of 8 miles: top width, 72 feet; bottom width, 62 feet; depth, 8 feet. The second section is called the Tiropkiá Canal, and runs from the Haldí to the Rasúlpur river, a length of 18 miles: top width, 92 feet; bottom width, 64 feet; depth, 8 feet. These canals were completed and opened throughout on the 1st September 1873. They are intended for navigation only; and the tolls taken during the year 1873-74 amounted to £2797, 16s., while the miscellaneous révenue was £63, 18s. The deficiency for

the year, exclusive of interest, was estimated at £999, 6s. In 1881–82 the tolls amounted to £4653, and the miscellaneous revenue to £120.

Rupnath—Village in the *pargana* of Amul, in the Jaintia Hills, Assam, with a Hindu temple greatly frequented by pilgrims from the plains of Sylhet. In the neighbourhood are several caverns in the limestone formation extending for a great distance beneath the earth. Out of one of these a Chinese army is fabled to have marched to the invasion of India. In another, the hanging stalactites have been carved to represent the gods of the Hindu pantheon.

Rurkha Kalan—Town in Phillaur *tahsil*, Jalandhar (Jullundur) District, Punjab. Lat $31^{\circ} 7' 12''$ N, long $76^{\circ} 45' 30''$. Population (1881) 5492, consisting of Hindus, 3362, Muhammadans, 1189, and Sikhs 941. Number of houses, 950. Rurkha Kalan is a mere agricultural village, or collection of hamlets, with an insignificant trade in sugar, but otherwise unimportant. Primary school.

Rurki—Eastern *tahsil* of Saharanpur District, North Western Provinces, lying at the foot of the Siwalik Hills, along the western bank of the Ganges, and watered by the Ganges Canal, comprising the *parganas* of Rurki, Jawalapur, Manglaur, and Bhagwanpur. Area, 789 square miles, of which 356 square miles are cultivated. Population (1872) 242,696, (1881) 274,571, namely, males 151,524, and females 123,047. Increase of population since 1872, 31,875, or 13.1 per cent in nine years. Classified according to religion, the population consists of—Hindus, 189,734, Muhammadans, 82,989, Jains, 480, and 'others,' 1368. Of 433 villages, 271 contain a population of less than five hundred inhabitants, 99 between five hundred and a thousand, 58 between one and five thousand, and 5 upwards of five thousand. Total Government land revenue, £27,987, or including local rates and cesses levied on land, £31,362. Total rental paid by cultivators, including cesses, £57,921. In 1884 the *tahsil* contained 1 civil and 5 criminal courts, number of police circles (*thanas*), 7, strength of regular police, 104 men, village watch or rural police (*chaukidars*), 491.

Rurki—Modern manufacturing town, municipality, and cantonment in Saharanpur District, North Western Provinces, and head quarters of Rurki *tahsil*, situated in lat $29^{\circ} 52' 25''$ N, long $77^{\circ} 55' 40''$ E, on an elevated ridge overlooking the bed of the Solani river, 22 miles east of Saharanpur city. Population (1872) 10,778, (1881) 15,953, namely, males 9829, and females 6124. Classified according to religion, the population consists of—Hindus, 9574, Muhammadans, 4963, Jains, 121, Christians, 1159, and 'others,' 136. Municipal income (1883–84), £1462, of which £787 was derived from taxation, average incidence of taxation, 1s 2½d per head of the population (12,818) within municipal limits.

Before the commencement of the Ganges Canal works, Rúrki was a mere mud-built village on the banks of the Soláni; it is now a flourishing town with broad metalled roadways, meeting at right angles, and lined with excellent shops. In the centre of the town is a large open *chauk* or market-place. The Ganges Canal passes close to Rúrki, between high embankments. At a short distance above the town, it is carried over a lofty viaduct. Rúrki owes its chief importance to being the head-quarters of the Ganges Canal workshops and iron foundry, established in 1845-46, much extended and improved in 1852, and employing 850 hands in 1882. The Thomason Civil Engineering College, founded in 1847, for instructing natives and others in practical engineering, with a view to employment upon public works, had a total of 99 regular students in 1882. This institution is the largest and most important engineering college in India; and during its forty years of teaching may be said to have created an indigenous engineering profession. The men trained by its professors have supplied the working staff by which most of the great public works of British India have been executed. The building is spacious and handsome; and its staff is maintained at the highest point of efficiency. The students are partly English youths born in the country, partly Eurasians and natives; with special classes for soldiers, picked for their ability from the British regiments in India. The sappers and miners of the native army have been cantoned at Rúrki since 1853, and it has formed a station for British troops since 1860. The garrison numbers about 1000 men of all ranks. Church, dispensary, police station, post-office, *tahsíl*, mission school of Society for the Propagation of the Gospel. The low ground surrounding the town, together with the percolation from the canal, gives rise to fever and other malarious diseases; much, however, has been done to remedy this evil. Excellent meteorological observatory.

Rusera (*Roshra*).—Town and municipality in Darbhanga District, Bengal; situated on the east bank of the Little Gandak, just below the confluence of that river with the Bághmatí, in lat. $25^{\circ} 45' 8''$ N., and long. $86^{\circ} 4' 8''$ E. Population (1881) 11,578, namely, males 5534, and females 6044. Hindus number 11,196, and Muhammadans 382. Municipal income (1883-84), £519, of which £456 was derived from taxation; average incidence of taxation, $9\frac{3}{4}$ d. per head. Rusera town contains a police station, distillery, and perhaps the largest *bázár* in the District; seat of a large trade in grain, oil-seeds, saltpetre, *ghí*, cloth, and other articles. An aided English school was established here in 1870. Roads run from Rusera to Dalsinhsarái, Nágarbasti, Tájpur, Baherá *viâ* Hátí, and to Darbhanga *viâ* Hathauri, and to Rájghát on the Tiljúga. Before the change in the course of the Bághmatí, direct water communication was open to Darbhanga all the year round. In

1876-77, the total registered traffic of Rusera was valued at £197,000. The principal exports were—oil seeds, £100,000, tobacco, £15,000, and *ghi*, £12,000. The imports comprised food grain, £9000, salt, £49,000. Owing to an alteration in the system of registration, no later statistics of trade are available.

Rushikulya—River in Ganjam District, Madras Presidency. Rises in the Chinna Kimidi Mahiyas, in lat $19^{\circ} 55' 20''$ N, and long $84^{\circ} 20'$ E, and runs south east to Aska, where it is joined by the Mahanadi, thence south east and east till it enters the sea at Ganjam town, in lat $19^{\circ} 22'$ N, and long $85^{\circ} 7'$ E. Its length is about 115 miles, the principal towns on its banks being Suradā, Aska, Purushottapur, and Ganjam. It is spanned at Aska by a fine masonry bridge of 19 arches.

Russellkonda (called after Mr Russell, who was Commissioner here in 1835)—Town in Gumsar *taluk*, Ganjam District, Madras Presidency. Lat $19^{\circ} 56' 20''$ N, long $84^{\circ} 37' 34''$ E. Situated on the river Loharakandi, about 50 miles north west of Ganjam town. Population (1881) 2613, residing in 544 houses. Head quarters of the Special Assistant Agent for the Hill Tracts, and of 1 *taluk* Magistrate. Court houses, post office, school, dispensary, public bungalow, rest house, and prison for the hill convicts. It was at one time a military cantonment, but was abandoned in December 1863.

Rustam—Town in Shikarpur District, Sind.—See RASTAM.

Rutlam—State and town in the Central India Agency.—See RATLAM.

Rwa taung (correctly *Ywa taung*)—Town in Mye deh township, Thayet myo District, Irawadi Division, Lower Burma.—See YWA TAUNG.

Rwe (correctly *Ywe*)—One of the mouths of the Irawadi (Irrawaddy), the chief river of Lower Burma.—See YWE.

Rwon za leng—River in the Tenasserim Division of Lower Burma.—See YUN ZA-LIN.

S

Saádatganj—Town in Bara Banki District, Oudh, situated 14 miles north east of Bara Banki town. Founded by Rájá Surat Singh, the ancestor of the present *talukdár* of the *parganá* (Ramnagar), and named after the Nawáb Saádat Ali Khán, in whose reign it was built. A clean and well built town, with a considerable trade in grain. Population (1881) 3010, namely, Hindus 1629, and Muhammadans 1381. Number of houses, 537.

Sabarhad—Village in Khutahrn *tahsil*, Jaunpur District, North Western Provinces, situated in lat $26^{\circ} 1' 10''$ N, and long $82^{\circ} 44' 21''$.

E., eight miles north-east of Khutáhan town. Population (1881) 2533, the prevailing class being Muhammadans. Bi-weekly markets on Tuesdays and Saturdays.

Sabari (*Seberi, Severi, Savari*).—River, rising in the Eastern Gháts, in the Native State of Jaipur (Jeypore), Madras; rushes through a rocky channel in a succession of rapids till it enters the Upper Godávari District, Central Provinces, within which its course for 25 miles is free from obstructions. It falls into the Godávari in lat. $17^{\circ} 35' N.$, and long. $81^{\circ} 18' E.$

Sabáthu.—Cantonment in Simla District, Punjab.—See SUBATHU.

Sabay-yon (*Tsam-bay-run* or *Tsa bay-yún*).—Township in Bassein District, Irawadi Division, Lower Burma. Area, 661 square miles. Population (1881) 60,508. Gross revenue, £23,330. In the south-west the country is undulating. In the north and east the land is in places swampy, and rice cultivation is carried on; in other places it is covered with tree and grass jungle, passing, near the junction of the Dagá and Shwe-nyaung rivers, into good rice land again. In the north-east corner of the township, a large area has been rendered available for rice by an embankment. This township comprises 7 revenue circles. Head-quarters at Kyún-pyaw town.

Sábhár.—Village and ruins in Dacca District, Bengal; situated on the north bank of the Burigangá, a tributary of the Dhaleswarí, in lat. $23^{\circ} 50' 55'' N.$, and long. $90^{\circ} 17' 10'' E.$ Formerly the capital of the Bhuiyá Rájá Harischandra. In 1839, the only trace that remained of his residence was a heap of bricks and earth overgrown with jungle. Small trade in cloth and ironware.

Sabi.—River in Gurgáon District, Punjab.—See SAHIBI.

Sachín.—Native State within the British Political Agency of Surat, in Gujarát, Bombay Presidency. The villages constituting the State are much separated, some of them being surrounded by British territory, and others by portions of Baroda State. Sachín may, however, roughly speaking, be said to lie within the limits of the British District of Surat. It occupies an area of about 42 square miles, with a population (1881) of 15,721, namely, males 7371, and females 8350. Hindus number 13,214; Muhammadans, 2307; and Christians, 200. Number of houses, 3729; villages, 19. Irrigation is carried on from tanks and wells. The climate is healthy, and the usual cereals are cultivated, as well as cotton and sugar-cane. Yarn and coarse cloth are manufactured. A recently built breakwater at Dumas, and a causeway at Bhímpur, by keeping back sea-water, have contributed towards the reclamation of a considerable area of hitherto uncultivable salt land.

The Nawáb of Sachín is by descent a Habshi or Abyssinian. When his ancestors first came to India is doubtful; but they were long known on the western coast as the Sidis of Danda-Rájápur and Janjirá. They

were also the admirals of the fleets of the kings of Ahmadnagar and Bijápur, in the Deccan, whilst those dynasties lasted, and subsequently of the Mughal Emperors, being appointed to that office by Aurangzeb about 1660, with an annual assignment of £30,000 on the Surat revenues for their maintenance. On the decline of the Mughal Empire the Sidis became notorious pirates plundering the ships of all nations, except the English, whose friendship they appear to have early cultivated. The branch of the family who had their head quarters at the island of Janjirá remained chiefs of that place during the wars between Sivaji and the Mughals, also during the war between the Peshwa and the British Government.

During these wars different members of the family were alternately supported by either party as best suited its own interests. Towards the end of the last century, Balu Mia Sidi, the heir to the throne of Janjira and to the other possessions of the Sidis, was expelled from his dominions by a younger branch of the family (1784-91). He appealed for aid to the Marathas and the British. The Peshwa being desirous of obtaining Janjira, an arrangement was come to in 1791, by which Bálu Miá ceded to the Peshwá Janjirá in return for Sachin. Balu Mia duly got possession of his new State of Sachin, but when the Peshwa claimed Janjirá the Sidis who held it refused to give it up, and succeeded in maintaining their independence. Sachin remained in the hands of Balu Miá and his descendants, while Janjira is still held by the younger branch of the family who had ousted Bálu Mia, the Peshwa never having been able to establish his influence. Janjirá is reckoned a maiden fortress to this day. A full account of the transactions between the British, the Peshwa, and the rival sides of Janjira and Sachin, will be found in Aitchison's *Treaties* vol iv pp 324 *et seq*, ed 1876.

The present (1883-84) chief of Sachin is Nawáb Sidi Abdul Kádar Muhammad Yakut Khán, a Sunní Musalman, who is now a student at the Rajkumar College. During his minority the affairs of the State are administered by a British officer. The chief is entitled to a salute of 9 guns, and has power to try for capital offences, without the express permission of the Political Agent, his own subjects only. The family hold a title authorizing adoption, and succession follows the rule of primogeniture.

The survey and land settlement of the State were completed in 1882-83. On the whole, the rates are higher than in neighbouring British villages, but much lower than the *rajats* had hitherto paid. The gross revenue in 1883-84 amounted to £17,986, of which £12,051 was derived from the land tax. The usual village establishments of *pátels*, *havlildars*, *vettas* are kept up, with a *faujdar* to inquire into offences. In 1883-84 the State contained 15 schools.

with 944 pupils; only five villages were without schools. The average annual rainfall of the five years ending 1882-83 was 47·2 inches. The rainfall of 1883-84 was 35·7 inches.

Sachin.—Capital of Sachin State, Bombay Presidency; situated in lat. $21^{\circ} 3' 40''$ N., and long. $72^{\circ} 59'$ E., 9 miles south of Surat city. Population (1872) 722; not returned separately in the Census of 1881. Good roads connect it with Surat, with Lachpur, on the Mindhola, the former residence of the Nawábs, and with Sachin station on the Bombay, Baroda, and Central India Railway. The town contains the palace of the Nawáb, a small fort, court-house, jail, post-office, dispensary, *dharmśála*, etc. The roads are lighted and watered.

Sádábád.—Easternmost *tahsíl* of Muttra (Mathurá) District, North-Western Provinces; conterminous with Sádábád *parganá*. The *tahsíl* just touches on the Jumna in its south-western corner, but is intersected through its centre by the Jhirna or Kharon river, an important stream in the rains, but dry or almost so at other seasons. It drains a valley about two or three miles wide on each side, the boundary line of which is marked by denuded sandy slopes. Excepting the Jhirna valley, and the small area of Jumna ravines and *khadar* land, the *tahsíl* is extremely level and uniform. There are no other streams of any size, and *jhils* and marshes are few. The prevailing soil is *piliya*, interspersed with tracts of *bhúr* or sand, but the total area of the latter is insignificant. There is a little *úsar* in the west of the *tahsíl*, and the patches of waste that still remain are often covered with scrub jungle, and sometimes with *dhák* trees. There is no canal irrigation, and the area irrigated from *jhils* and ponds is insignificant, but that commanded by wells is exceptionally large. Cotton, owing to the suitability of the *piliya* soil for its growth, and the vicinity of Hathrás, the largest cotton mart in Northern India, is the crop most extensively grown. Barley, *joár*, and *arhar* are the other principal crops, and a considerable amount of hemp and indigo are also raised.

The total area of Sádábád *tahsíl* in 1881-82 was 180 square miles, of which 148 square miles were under cultivation, 19 square miles cultivable, and only 13 square miles uncultivable waste. Population (1881) 89,217, namely, males 49,110, and females 40,107; average density of population, 495 persons per square mile. Classified according to religion, there were in 1881—Hindus, 82,289; Muhammadans, 6598; and Jains, 330. Of the 127 towns and villages comprising the *tahsíl*, 70 contained less than five hundred inhabitants; 37 between five hundred and a thousand; and 19 between one and five thousand. The only place with upwards of five thousand inhabitants was Kursanda (6018). Of the total cultivated area at the time of the recent land settlement, 25,679 acres were cultivated by proprietors themselves as *sír* or homestead lands, 27,544 acres by

tenants with occupancy rights, 45,173 acres by tenants at will, while 749 acres were rent free land granted by *zámindars*, and 898 acres were cultivated gardens. Játs, Bráhmans, Rájputs, and Ahírs cultivate nearly the whole of the *sir* area, and from the same castes, with the addition of Chamárs and Gadarias, the tenantry is almost entirely recruited. Total Government land revenue (1881-82), £31,596, or, including local rates and cesses levied on land, £35,391. Total rental, including local rates and cesses, paid by cultivators, £46,173. The rates of rent paid by tenants at will are considerably higher than those paid by occupancy tenants, although the latter generally cultivate lands of a better quality, the difference in the rates being 11 per cent in the west of the *tahsil*, and as much as 15 per cent in the east. Sádabád *tahsil* contained in 1883, 1 criminal court, 2 police stations (*thanas*), a regular police force of 40 men, and a village watch or rural police of 236 *chaukidars*.

Sádabád — Town in Muttra (Mathurá) District, North Western Provinces, and head quarters of Sádabád *tahsil*, situated in lat $27^{\circ} 26' 13''$ N, and long $73^{\circ} 4' 42''$ E, on the Jhirna stream, at the junction of four important metalled roads connecting with it Muttra town, with Jalesar road station on the East Indian Railway, and with Agra and Aligarh towns. Population (1881) 3295. Sadabád was founded by Wazír Sádullá Khán, the minister of the Emperor Shah Jihán in the first half of the 17th century. On the British annexation in 1803, the town became the capital of a District and continued so till the formation of the present District of Muttra in 1832. The *tahsil* building, which occupies the site of a fort of Himmat Bahádur, is a small but substantial building, with a deep fosse, and pierced and battlemented walls. It occupies a commanding position, and, as it is supplied with a good masonry well in the courtyard, it is probably capable of standing a siege in an emergency. Sadabád was attacked by the Jat rebels during the Mutiny, and seven lives were lost in the defence before they were repulsed. The Hindu Rájput who led the defence was rewarded by a grant of a village in Aligarh District, and two of the Jat ringleaders belonging to Kursanda were hanged. The town contains a large Hindu temple with an architectural façade, and a handsome white mosque recently erected by the leading Muhammadan landholder. A bi-weekly market is held on Tuesdays and Saturdays. Rest house, police station, post office, and Anglo vernacular school. A small house tax raised for police and conservancy purposes realized £72 in 1881-82.

Sadalgi — Town in Belgaum District, Bombay Presidency, situated 51 miles north of Belgaum town, and 25 south east of Kolhápúr, in lat $16^{\circ} 33'$ N, and long $74^{\circ} 33'$ E. Population (1881) 7240. Coarse waistcloths, blankets, and women's robes are woven, but the chief

(Umballa) District, Punjab, situated in lat $30^{\circ} 23' N$, and long $77^{\circ} 16' E$, near the hills, 26 miles east of Ambála city Population (1881) 10,794, namely, males 5532, and females 5262 Muhammadans number 5847, Hindus, 4415, Sikhs, 408, and Jains, 124 Number of houses, 1756 Municipal income (1883-84), £560, or an average of 1s 0½d per head A town of great antiquity, dating back to the time of Mahmud of Ghazni, but now of no political importance Yearly fair at the shrine of Shah Kumais, a Muhammadan saint, lasting five days, and attended by about 20,000 persons Manufacture of coarse cloth, local trade in country produce Middle school

Sadiyá—The name formerly given to a tract of country stretching along the north bank of the Brahmaputra, on the extreme north east frontier of Assam The present *thana* or police circle of Sadiya, forming part of the Sub division of Dibrugarh, in Lakhimpur District has an area of 178 square miles Population (1881) 9415, dwelling in 74 villages and 1479 houses

Sadiyá—Village in Lakhimpur District, Assam, situated in lat $27^{\circ} 49' 45'' N$, and long $95^{\circ} 41' 35'' E$, on the right or north bank of the main stream of the Brahmaputra, about 70 miles above Dibrugarh Sadiya is the extreme north east frontier outpost of British India, and has always possessed much political importance It is supposed to have been one of the first places occupied by the Ahoms, when they invaded Assam from the direction of Burma In later times, the government of the surrounding country was administered by a viceroy of the Ahom kings, with the title of Sadiya Khoa When the Burmese occupied Assam, this title was conferred on a chief of the aboriginal tribe of Khámtis, whose office was confirmed on the annexation of Assam by the British in 1826 The Sadiyá Khoa furnished a military contingent of 100 men, and supported himself by forced contributions At the same time a British garrison was stationed at Sadiya, and subsequently, in 1835, when the exactions of the Khámti chief became intolerable, the civil administration was placed in the hands of the officer commanding the troops In 1839 the Khámtis rose in rebellion They cut off the outpost at Sadiyá and killed Major White, the commandant and Political Agent, together with the detachment of Sepoys At this time, Sadiya was described as an important place, with a population of 4000 souls It dwindled gradually into a very insignificant village, but is now becoming again a flourishing seat of trade The garrison generally consists of 1 European officer and about 150 men of one of the Assam regiments

In order to promote friendly relations with the neighbouring hill tribes of Khamtis, Mishmis, and Singphos, a fair is held annually at the time of full moon in the end of January or beginning of February

industry in the town and neighbourhood is sugar-making. A large area is cultivated with sugar-cane, and a considerable quantity of molasses is prepared here. Weekly market on Tuesdays. Government vernacular school.

Sadāshivgarh (*Sadāshivgad*).—Fort in North Kánara District, Bombay Presidency; situated in lat. $14^{\circ} 50' 25''$ N., and long. $74^{\circ} 10' 55''$ E., on the north side of the entrance to the Kálí or Kálá river. Sadāshivgarh fort is built on a flat-topped hill 220 feet high, with a steep and inaccessible face on the river side. The fortifications consist of a granite and mortar wall 20 feet high and 6 feet thick, enclosing a space of 10 acres. The wall has towers and openings for guns, and is surrounded by a moat. Except the battlements and part of the wall on the south, the whole is in fair repair. The fort has three out-works. One at the base of the south face, with its foundations under water; the second parallel to the verge of the east slope; and the third opposite the main fort, with a moat and battlements. At the southern corner of the hill are two Government bungalows.

Sadāshivgarh fort was built by a Sonda chief between 1674 and 1715. In 1752 the Portuguese declared war against the Sonda chief, and after a slight conflict carried the fort, which they greatly strengthened. In 1754 the Portuguese restored the fort to the Sonda chief. In 1763, Sadāshivgarh was taken by Haidar Ali's general, Fazl Ullá Khán. In 1783 a detachment of General Mathew's force was sent to occupy Sadāshivgarh. In 1799 it was garrisoned by Tipú's troops.

The village and port of Chitákul are situated at the foot of the hill occupied by Sadāshivgarh fort. Population (1881) 3939. Though now confined to the village itself, the name Chitákul originally included a considerable tract of land. Under the forms Sindabur, Chintabor, Cintabor, Cintapor, Cintacola, Cintacora, Chittakula, and Chitekula, the place appears in the writings of many authors, from the Arab traveller Masudi (about 900 A.D.) to the English geographer Ogilvy (about 1600). Custom-house, market, Roman Catholic church, vernacular school, old military guard-room and hospital, now used as rest-house and police station. Sadāshivgarh or Chitákul is one of the three ports of the Kárwár Customs Division. Average annual value of trade for the five years ending 1881-82—imports £1182, exports £8711; total, £9893. Value in 1881-82—imports £1585, exports £8772; total, £10,357.

Sádāt Masonda.—Village in Jaunpur *tahsíl*, Jaunpur District, $5\frac{1}{2}$ miles north-east of Jaunpur town, with which it is connected by an unmetalled road. Population (1881) 2707, chiefly well-to-do Sayyid Muhammadans. Small *bázár*; tri-weekly markets on Sundays, Wednesdays, and Fridays.

Sádhaurá.—Town and municipality in Náráingarh *tahsíl*, Ambála

(Umballa) District, Punjab, situated in lat $30^{\circ} 23' N$, and long $77^{\circ} 16' E$, near the hills, 26 miles east of Ambála city. Population (1881) 10,794, namely, males 5532, and females 5262. Muhammadans number 5847, Hindus, 4415, Sikhs, 408, and Jains, 124. Number of houses, 1756. Municipal income (1883-84), £560, or an average of 1s $0\frac{1}{2}d$ per head. A town of great antiquity, dating back to the time of Mahmud of Ghazni, but now of no political importance. Yearly fair at the shrine of Shah Kumais, a Muhammadan saint, lasting five days, and attended by about 20,000 persons. Manufacture of coarse cloth, local trade in country produce. Middle school.

Sadiyá—The name formerly given to a tract of country stretching along the north bank of the Brahmaputra, on the extreme north east frontier of Assam. The present *thana* or police circle of Sadiya, forming part of the Sub division of Dibrugarh, in Lakhimpur District, has an area of 178 square miles. Population (1881) 9415, dwelling in 74 villages and 1479 houses.

Sadiya—Village in Lakhimpur District, Assam, situated in lat $27^{\circ} 49' 45'' N$, and long $95^{\circ} 41' 35'' E$, on the right or north bank of the main stream of the Brahmaputra, about 70 miles above Dibrugarh. Sadiya is the extreme north east frontier outpost of British India, and has always possessed much political importance. It is supposed to have been one of the first places occupied by the Ahoms, when they invaded Assam from the direction of Burma. In later times, the government of the surrounding country was administered by a viceroy of the Ahom kings, with the title of Sadiyá Khoa. When the Burmese occupied Assam, this title was conferred on a chief of the aboriginal tribe of Khámtis, whose office was confirmed on the annexation of Assam by the British in 1826. The Sadiyá Khoa furnished a military contingent of 100 men, and supported himself by forced contributions. At the same time a British garrison was stationed at Sadiya, and subsequently, in 1835, when the exactions of the Khámti chief became intolerable, the civil administration was placed in the hands of the officer commanding the troops. In 1839 the Khámtis rose in rebellion. They cut off the outpost at Sadiyá and killed Major White, the commandant and Political Agent, together with the detachment of Sepoys. At this time, Sadiya was described as an important place, with a population of 4000 souls. It dwindled gradually into a very insignificant village, but is now becoming again a flourishing seat of trade. The garrison generally consists of 1 European officer and about 150 men of one of the Assam regiments.

In order to promote friendly relations with the neighbouring hill tribes of Khámtis, Mishmis, and Singphos, a fair is held annually at the time of full moon in the end of January or beginning of February.

The hillmen bring down caoutchouc, wax, musk, cloth, mats, *dáos* of hill-knives, and ivory, which they exchange for cotton cloth, salt, metal utensils, silver ear-rings, beads, brass wire, and opium. In 1876, the attendance of hillmen was estimated at 3000; the value of the articles they sold at £4910, and the value of those they bought at £4447. Latterly, the number of visitors to the fair has fallen off considerably. This is partly due to the ill-feeling existing between the Abar and Mishmi tribes, and partly, no doubt, to the novelty of the fair having worn off. The Deputy Commissioner of Lakhimpur is generally present at this fair, and advantage is taken of the occasion to distribute presents among the chiefs.

During the rainy season, steamers can proceed up the Brahmaputra as far as Sadiyá, and it is hoped that this place may at some future day become the starting-point of a through trade with China. It is almost certain that such a trade existed in the beginning of the last century. An Assistant Political Officer has recently been stationed at Sadiyá, to conduct political relations with the frontier tribes, especially the Abars and Mishmís.

Sadras (correctly *Satranja-patana*).—Town in Chengalpat *táluk*, Chengalpat (Chingleput) District, Madras Presidency. Situated in lat. $12^{\circ} 31' 25''$ N., and long. $80^{\circ} 12'$ E., about 43 miles south of Madras, and connected with it by the Buckingham Canal. Population (1881) 1107, inhabiting 177 houses. Sadras first became a trading settlement of the Dutch in 1647, and was long famous for the fineness of the muslin produced by its looms. The Dutch erected, close to the shore, a brick fort of considerable extent and pretensions to strength, of which the ruins still remain. There are also the remains of the houses of the officials. The old Dutch cemetery is within the fort, and is still maintained in decent order under treaty. The tombstones are curious specimens of the sculptor's art. The date of the oldest is 1679. There is a German Lutheran Mission church on the esplanade opposite the fort, and the Wesleyan Mission have also a small settlement here. The once bustling importance of the place has long departed. There are still a few looms, but the cunning which produced the once famous fabrics is lost. The English captured Sadras in 1795; and although it was temporarily restored to the Dutch, it has been an English possession since 1824. The Pálár river, which falls into the sea a few miles to the south, has silted up, and its bar cannot be crossed by sea-going ships. Sadras is now a petty place on the coast, with the open sea outside, and has long ceased to be a resort of maritime commerce.

Sadri (Large).—Town in the State of Udaipur, Rájputána; situated 51 miles east-south-east of Udaipur city, and 23 miles south-west of Nímach. Surrounded by a stone wall much out of repair, and defended

by a small fort on the hill above, now almost in ruins. A first class noble of the State resides here, and the town gives its name to his estate of 80 villages.

Sadri (Small) — Town in the State of Udaipur, Rajputána, situated about 62 miles east south-east of Udaipur city, and 13 miles south west of Nimach. The town is walled, and great quantities of bamboos and timber from the jungles to the south are brought here or sale.

Sadrpur — *Pargana* in Sitápur District, Oudh, bounded on the north by Biswán *tahsil*, on the east by South Kundri *pargana*, on the south by Bara Banki District and on the west by Mahmudábád *pargana*. Area, 108 square miles, or 69 086 acres, of which 48,410 acres are cultivated, 11 600 acres cultivable, 133 acres rent free, and 8943 uncultivable waste. The incidence of the land revenue demand is at the rate of 25 6½d per acre of cultivation, 25 0½d per acre of assessed area, and 15 10½d per acre of total area. Population (1881) 50,233 namely, males 26,729 and females 23 504. The 160 villages comprising the *pargana* have been constituted into 114 demarcated *mauzas*, of which 81 are held under *talukdari* and 33 under *samindari* tenure. Muhammadans form the principal proprietary body, owning 119 villages, Raikwárs hold 11, Seths 5, Janwár Rájputs 4, Panwars 4, Kashmirí Brahmans 4. The remaining 23 are chiefly held by Káyasths. The *pargana* is a poor one with only 2 villages containing upwards of 2000 inhabitants. No roads no large *bárs*, and no fairs.

Sadrpur — Town in Sitapur District, Oudh and head quarters of Sadrpur *pargana*, situated 30 miles south east of Sitapur town, but with no road or river communication with any other place. An insignificant town of (1881) 1622 inhabitants. Village school, market twice a week.

Sadullánagar — *Pargana* in Gonda District, Oudh. Bounded on the north by Utraula *pargana*, from which it is separated by the Kuwana river, on the east by Burhápára *pargana* on the south by Manikapur *pargana*, the Bisuhi river marking the boundary line, and on the west by Gonda *pargana*. The boundary rivers are fordable every few miles, except during the rains by men and cattle, and the more important tracks are furnished with rough bridges. Along the banks of both rivers runs a fringe of forest, varying from 3 miles to a few hundred yards in breadth, but containing little good timber. The *sál* trees, stunted by excessive crowding, never attain sufficient size to make them of any great value, and, except the *jamun*, which is plentiful and attains a fair growth, and is of use both for building and burning, the only other tree of consequence is the *mahuá*, whose flowers and fruit are pressed out for the manufacture of spirits and oil, and the wood

of which is largely employed in roofing the huts of the neighbouring villages. Game is not particularly plentiful. The centre of the *parganá* is a flat ugly plain, underwooded and covered with fair cultivation, alternating with tracts of the long *khar* grass. The soil is of a light dry loam. Water may be found almost anywhere at a depth of from 15 to 20 feet from the surface, and irrigation is very common both from wells and small tanks. Area, 103 square miles; cultivated area, 38,943 acres, or 59 per cent. of the whole. Of this, 29,640 acres are under *kharif*, 22,136 acres under *rabi*, and 12,833 under both crops, the balance being fallow. Owing to the extent of jungle, the population is, for Oudh, sparse, numbering (1881) 40,894, or 393 persons per square mile. Hindus number 30,961, and Musalmáns 9933.

Until quite lately, the greater part of the *parganá* was covered with dense jungle, the home of predatory bands; and most of the present tillage commenced with the purchase of parcels of land in *birt* from the later Rájás of Utraula. Some idea of the scantiness of the agricultural population at the commencement of the present century, when the practice of selling *birt* rights became for the first time common, may be gathered from the fact that in 1815 the Government revenue was only £69. From that time the advance becomes rapid and steady. In 1819 the demand had risen to £1331, and ten years later it reached £2406. With a few trifling variations, it remained at this amount till Rájá Darshán Singh in 1838 raised it to £3512, a figure which was never again attained under the Native Government. Shortly before annexation, it had fallen to little over £2000; and when we took over the District, Sadullánagar was assessed on the principle of half-profits at £2408. The progress of population and agriculture since that period has been exceedingly rapid; and in 1872, by a revised assessment, the Government land revenue was raised to £5607, with £152 on account of cesses. In consideration of the largeness of the enhancement, and in view of the fact that much of the land recently brought under cultivation was held on long leases at progressive rents, the increase was distributed over a period of ten years, and it was not proposed to take the full demand till 1883. Of the 112 villages in the *parganá*, 51 are held by *táluqdárs*, paying a revenue of £2924; while 61 villages, assessed at £2835, are held by *zamíndárs*.

Sadullánagar.—Village in Gonda District, Oudh, and head-quarters of Sadullánagar *parganá*; situated 28 miles north-east of Gonda town. Lat. 27° 5' 45" N., long. 82° 24' 51" E. Population (1881) 781. Founded in 1786 by Rájá Sadullá Khán of the Utraula family.

Sadullápur.—Village in Maldah District, Bengal. The chief descent or *ghát* to the holy stream of the BHAGIRATHI is at this place, to which the dead bodies of Hindus are brought from great distances

to be burned. A weekly market is held here, and a large annual religious trading fair in March, as well as on occasions of bathing festivals throughout the year. During the Muhammadan rule at Gaur, this was the only burning *ghât* allowed for the Hindus in Maldah District. It is held in great veneration by the Hindus on account of its antiquity as a burning *ghât* and bathing place.

Sadullapur.—Village on the right bank of the Chenáb, in the Punjab, the scene of an indecisive action between our troops, under Sir John Thackwell, and the Sikh general Sher Singh, in January 1849.

Safed Koh (*Sufed Koh*, *Safaid Koh*) — Range of mountains in Afghánistán, thus described by General Sir Charles MacGregor —

‘The range commences to the east of the Allah koh ridge, between Kabul and Ghazni, and then follows 34° of latitude for about 75 miles to longitude $70^{\circ} 35'$, when it splits into two main ridges, one going north east to the Khaibar and the Kabul river, the other, after a short turn to the east, continuing due east to the junction of the Kábul river with the Indus. During the first portion of its course, this range drains on the north into the Kabul river and on the south into the Kuram, and it continues to do this after its separation into two branches, though not with the same regularity, some of the easternmost drainage going direct into the Indus.

‘It is often of course quite arbitrary to say where one range commences and another ends, but I think in this case it will be best to say the Safed Koh commences from a few miles west of the Shutargardan Pass, between Kuram and Logar. This being the case, the first spur which it throws out to the north is that which forms the east watershed of the Logar river, and, dividing it from the Khurd Kábul river, ends at Bhútkhak.

‘The next spur is that between the Khurd Kabul and the Tezín rivers, over which are the Haft Kotál and Lataband Passes. This Wood calls the Karkacha range, or rather he confounds two distinct spurs in one under this name, but it may be doubted whether it would not more aptly be termed the Haft Kotál spur. Wood says that the ridge he calls the Karkacha drains west into the Logar and east into the Surkháb, but from Garden’s surveys we now know this to be a mistake, there being two rivers—the Khurd Kábul and Tezín—between the Logar and Súrkháb, which drain into the Kabul river, and which rise in the Safed Koh. Consequently it is an error to consider the mass of mountains between the Logar and Súrkháb one spur. After the spur between the Khúrd Kabul river and Tezín, another spur comes out from the main range, and after running north for about 30 miles to the north of Jagdalak, then turns to the east, and, running parallel with the Kábul river, ends at the junction of the Surkháb with that river. This spur drains into the Tezín on the west and the Surkháb on the

east, and, after its eastward bend, into the Kábul river on the north and the Súrkháb on the south.

'The other northern spurs of the Safed Koh to the east are not of so marked a character, but they run between the streams which, flowing down from it, join the Súrkháb or the Kábul river. Of these the principal are, commencing from the west, the Gandamak, Kárásí, Chiprial, Hisárák, Kote, and Mohmand.

'The spurs on the south of this range are not of such importance as those on the north. The first is the one which runs out from the Shutargardan Pass, and drains on the north and east into the Hazárdarakht and Hariáb streams; on the south, into another source of the Kuram. The second is the Paiwár ridge, which comes out from the Sítarám Peak and ends at the Kuram, draining into the Keria and Hariáb rivers on the west and the Paiwár on the east. Then again, to the east there are numerous short spurs, which shoot down to the south but do not reach the river, save in the form of detritus. These need not be mentioned further; and the only other spur requiring notice is the one which, coming out somewhat to the east of longitude $70^{\circ} 30'$, runs between the Kirmán Dára and the Kirmán stream.

'Wood places the western limit of the Safed Koh at long. $69^{\circ} 36' E.$, thus regarding its commencement as at very nearly the same point as I do—viz. just east of the Altimúr Pass over the Allah-koh range, in long. $69^{\circ} 30' E.$

'Judging from the accounts of Wood, Bellew, and Walker, the scenery would seem to be equal in grandeur and beauty on both sides of the range; and Wood in his description of the northern side falls into an error, when he says that looking towards the summit there are successive ranges, for the main range runs east and west, and throws its spurs to the north and south. Wood says the farthest peaks are bare and irregular, the nearest covered with pine-trees; and this tallies with the graphic description given by Bellew of its south aspect.

'Col. Walker says of the range—"Its highest point is the Sítarám Mountain, 15,622 feet above the sea, whence the range preserves a tolerably uniform level, perhaps nowhere less than 12,500 feet, until it again culminates in a double-peak mountain, whose summits average 14,800 feet. I have been unable to learn the local names of these peaks, or whether, like the Sítarám Mountain, they tell of a remote antiquity, when the country was ruled by Hindus long anterior to the origin of Muhammadanism. The offshoots of this range (*i.e.* the branches east of long. $70^{\circ} 30' E.$) have usually an east and west direction, and are remarkable for their parallelism with each other and with the parent range. The most important, though not the highest, of these stretches away to Attock, and is the southern boundary of the Pesháwar valley, dividing it from the system of valleys of which Kohát District is composed.

Before entering British territory, it forms the southern barrier of the Tirah valley ”’

According to Sir C MacGregor, the low hills of Jalalabád (ends of the north spurs of the Safed Koh) are barren, but the lofty ranges of Kund, Karlach, and Safed Koh are richly clad with pine, almond, and other trees. The appearance, he continues, of the valleys of the Safed Koh is a mixture of orchard, field, and garden. They abound in mulberry, pomegranate, and other fruit trees, while the banks of their streams are edged with a fine sward, enamelled with a profusion of wild flowers, and fringed by rows of weeping willows.

‘It is worthy of note that the Safed Koh presents in its south aspect the same glacial slopes of shingle which were observed by Griffiths on the south slopes of the spurs of the Hindu Kush, and which may also be noticed on parts of the hills north of the Peshawar valley. No mention is made by any authority of this peculiarity existing on the north of this range, or, I believe, of any other range.’

Saffraí—River in Assam, rising in the Naga Hills, and falling into the Disang river in Sibságar District, after a course of about $8\frac{1}{2}$ miles. Coal deposits exist near the source of the river, but the difficulties in the way of procuring labour and transport have, up to the present, prevented their being worked. Several tea gardens are situated on the banks or in the vicinity of the river, which is navigable for boats of 50 *maunds*, or about two tons burthen, during the rainy season as far as the Dhodar Ali road.

Safipur—*Tahsil* or Sub-division of Unao District, Oudh, lying between $26^{\circ} 37'$ and $27^{\circ} 2'$ N lat, and between $80^{\circ} 6'$ and $80^{\circ} 30'$ E long. Bounded on the north by Bilgram and Sandila *tahsils* of Hardoi District, on the east by Mohan *tahsil* of Unao, on the south by Unao *tahsil*, and on the west by Cawnpur District in the North Western Provinces. Area, 395 square miles, of which 231 are cultivated. Population, according to the Census of 1881, 194,001, of whom 169,733 are Hindus, and 24,254 Muhammadans. Number of males, 102,889, of females, 91,112, number of villages or towns, 373, average density of population, 491 persons per square mile. This *tahsil* comprises the three *parganas* of Safipur, Fatehpur Chaurasi, and Bángarmau. In 1883 it contained 1 criminal and 2 civil courts, number of police circles (*thánás*), 2, strength of regular police, 47 men, rural police or village watchmen (*chaukidars*), 634.

Safipur—*Pargana* of Unao District, Oudh. Bounded on the north by Sandila *pargana* of Hardoi District, from which it is separated by the Sai river, on the east by Asfán Rasulabád, on the south by Panar, and on the west by Fatehpur Chaurasi. Area, 132 square miles, or 84,530 acres, divided into 137 townships. A well wooded country. Soil chiefly loam and clay, staple crop, barley. Government revenue

£10,567, at an average rate of 2s. 6d. per acre. Population (1881) 68,258, namely, males 35,811, and females 32,447. Hindus number 59,151; Muhammadans, 9093; and 'others,' 14. The extent of land held under the different varieties of tenure is as follows:—*Tilukdāri*, 4249 acres; *pukhtadāri*, 240 acres; *pattidāri*, 37,168 acres; *zamindāri*, 36,181 acres; *bhāyāchāra*, 5531 acres; and Government villages, 1158 acres. Four large annual fairs, at one of which 15,000 persons assemble.

Safipur (or *Sāipur*).—Town in Unao District, Oudh, and headquarters of Safipur *tahsil* and *pargana*; situated in lat. $26^{\circ} 44' 10''$ N., and long. $80^{\circ} 23' 15''$ E., 17 miles north-west of Unao town, on the road leading thence to Hardoi. A flourishing, well-built town, containing 89 masonry houses, 14 mosques, and 6 Hindu temples. Population (1881) 7031, namely, Hindus, 4137; Musalmāns, 2880; and 'others,' 14. Daily market, with sales averaging £5500 a year. Flourishing school; police station. The town is said to have been originally founded by Sāi Sukal, a Brāhman, and is generally called after him, Sāipur. A religious mendicant subsequently came to the town, and was buried there, and the name was changed to Safipur in commemoration of the holy man. Sāi Sukal is said to have been defeated and killed in 1389 by Ibrāhīm of Jaunpur, who put his lieutenants in charge of the town, and whose descendants are the principal proprietors at the present day.

Ságar (*Saugor*).—District in the Chief Commissionership of the Central Provinces, lying between $23^{\circ} 4'$ and $24^{\circ} 27'$ N. lat., and between $78^{\circ} 6'$ and $79^{\circ} 12'$ E. long. Area, 4005 square miles. Population in 1881, 564,950 souls. Ságar is a District of the Jabalpur Division, lying in the extreme north-west of the Central Provinces. It is bounded on the north by Lālitpur District of the North-Western Provinces and the Native States of Bijāwar, Pannā, and Charkhārī; on the east by Pannā and Damoh District; on the south by Narsinghpur District and the Native States of Bhopāl; and on the west by Bhopāl and Gwalior States. The administrative head-quarters are at SAGAR TOWN.

Physical Aspects.—The District of Ságar occupies, with that of Damoh, the high Vindhyan table-land which stretches out in the north-west corner of the Central Provinces. The scarp of the Bhānrer range, rising abruptly from the valley of the Nerbada (Nerbudda), forms a natural boundary line, from which the District extends northwards in a vast plain broken here and there by hills, with a general slope towards the north-east. So, too, east of Ságar town the boundary is marked by a clear escarpment, but to the north and west no salient physical feature indicates the limits of the District.

The country is for the most part covered with trap; but on the

north, the Vindhyan sandstone runs down, broadening out opposite Kurai and gradually disappearing southwards, and on the east, the sandstone occupies a tract about 20 miles long and 5 broad, reaching from Garhákota to beyond Surkhi. Garhakota itself and a narrow strip of country as far south as Rehlí rest on limestone. The form of the trap hills distinguishes them at once from the adjoining hills of sandstone, their vegetation is also distinct, and the teak saplings which flourish on the trap rarely grow on the sandstone. The soil in the north and east of the District is a reddish brown alluvium. The south and centre are covered with black soil, on which wheat is grown in large quantities. But the cultivated plains are broken up by hills, rising singly or in groups, and by small ranges and plateaux, some of them covered with jungle, others stony and barren.

The principal streams are the Sunar, Beas (Bias), Dhupan, and Biná, all flowing in a northerly direction towards the valley of the Ganges. Sagar, however, contains no river of importance. Though several densely wooded tracts exist in the District, they yield no great quantity of the finer sorts of timber. The largest forest, the Ramna, a preserve to the north east of Garhákota, covering 8 square miles, produces teak and *saj*. Smaller forests to the south of the District, as Mohli near Rehlí and Tarhá Kish near Deori, supply teak, *saj* and bamboos. Towards the north, in Shahgarh, lie large tracts of wooded country, comprising *mahua* and *saj*, with some teak, and bamboos in abundance. About 2 square miles of this region form the Tigora reserve. The mineral wealth of the District is insignificant, but iron ore, of excellent quality, found near Hirápur, a small village in the extreme north east, affords occupation to a few smelting furnaces of the rudest character. In many parts, also, sandstone, well suited for building purposes, abounds.

History —The formation of Sagar into a District rests on no historical considerations. Until quite recent times, semi-independent rulers of small tracts have co-existed at various places, and while the southern half was governed from Rehlí, the northern half was subject to Dhámoni or Sháhgarh. Rehlí a village situated on elevated ground about 26 miles south east of Sagar town, appears to have been originally held by the Gonds, to whom succeeded a race of shepherds, known as Baladeos. The Baladeos first settled at Khamaria, a village 3 mile off, but in time they removed to Rehlí, where they built a fort. The place next passed into the hands of Rájá Chhatar Sál, the Bundelá chief of Panná, who made it over to Báji Rao Peshwá, in return for assistance in a war with the Subáh of Farukhábád. The Peshwa built the fort which now exists. The town of Sagar, after a similar history, at this time formed part of the dominions of Chhatar Sál. That chieftain died in 1735, and in addition to his previous gift to the Peshwa, left him

one-third of his kingdom, including Sagar town and a considerable portion of the present District. The territory thus acquired continued to be managed by agents of the Peshwá until 1818, when, on the downfall of the Peshwá's government, the southern part of Sagar District came under British rule.

The country to the north appears to have belonged to the great Gond kingdom of Mandla; and Dhámoní, 28 miles north of Sagar town, owes its origin to a scion of that line, named Surat Sá. About the end of the 16th century, Rájá Barsingh Deva, the Bundelá chief of the neighbouring State of Orchhá, defeated Surat Sá; and made Dhámoní the capital, from which he ruled the northern part of the District. His son Pahár Singh continued in power till 1619, when the country became a portion of the Delhi Empire. During the eighty years of Muhammadan rule which followed, Garola, Kuráí, and Khimlása rose to be places of importance. A succession of five governors from Delhi administered Northern Sagar, until about 1700, at the time of the decline of the Mughal Empire, the last of them, Nawáb Gháirat Khán, was defeated by Chhatar Sál, who thus for a short time united nearly the whole of the District under one rule. Dhámoní remained under his descendants until 1802, when Umráo Singh, Rájá of the neighbouring village of Patan, gained the fort by treachery. Six months, however, had not passed when he was himself defeated by the army of the Rájá of Nágpur, who annexed the country. In 1818, after the flight of Apá Sáhib, Dhámoní was taken by a British force under General Marshall.

Though Sháhgarh, 40 miles north-east of Sagar, came under British rule at a later period, its history is similar to that of Dhámoní. Originally part of the Gond kingdom of Mandlá, Sháhgarh also was seized by a Bundelá chieftain, Sháhman, who about 1650 killed Chintáman, the last Gond ruler. The line of Sháhman ended in 1798, when his descendant Khánjú was defeated by Mardan Singh, Rájá of Garhákota. In 1842, the son of Mardan Singh was succeeded by a nephew named Bakht Balí. This year was signalized by the outbreak known as the Bundelá insurrection. Jawáhir Singh of Chandrapur, being sued on account of decrees of the Civil Court, broke into open rebellion, and burned and plundered the towns of Khimlása, Kuráí, Naraolí, Dhámoní, and Bináiká. On hearing this, Delan Sá, a Gond chief living in the south of the District, also rose, and plundered Deorí and the surrounding country. The insurrection was quelled in the following year, chiefly through the efforts of Captain Hamilton; and Lord Ellenborough broke up the administration of the Sagar and Narbadá territories, and reorganized it on an entirely new footing.

In 1857 occurred the great rebellion, which led to the downfall of the Rájás of Sháhgarh. In June, when the Mutiny began, the regiments

stationed at Sagar were the 31st Native Infantry, commanded by Major Hampden, and the 42nd, commanded by Colonel Dalzell, with the 3rd Irregular Cavalry, and a few European gunners. The entire force was under the command of Brigadier Sage. On the 27th June, the officers, with the European artillery and residents of the station, by order of the Brigadier moved into the fort, taking all the arms they could collect, and the treasure from the District office. Shortly afterwards, the 42nd and the cavalry mutinied, and burned a good many houses, besides seizing all the treasure that had been left. The 31st, however, remained loyal, and made a demonstration against the mutineers, many of whom made off towards Sháhgarh. When the news of the rising got abroad, Mardan Singh, Rájá of Bhánpur, took possession of the present Sub division of Kuráí, Bakht Balí, the Rájá of Sháhgarh, seized Banda, Rehli, and Garhákota, and Adil Muhammad, Nawáb of Garhi Amrapur, occupied Ráhatgarh. In fact, these three divided the whole District between them. For eight months, affairs remained in this state, while the fort and town of Sagar were held by the Europeans, the whole surrounding country was in possession of the rebels. The latter never attacked the fort, and three engagements with the English forces at Sagar proved indecisive. At length, in February 1858, Sir Hugh Rose arrived with the Central India Field Force at Ráhatgarh, where, after totally defeating Adil Muhammad, he took and partially destroyed the fort. He next defeated the troops of Mardan Singh at Barodíá Naunagar, and having cleared the country round Ráhatgarh and Kuráí, marched to Sagar. Sir Hugh Rose then advanced to Garhákota, where he routed the followers of the Rájá of Sháhgarh, and seized the fort, in which the rebels had left a large quantity of treasure. Soon after, he met the remainder of Bakht Balí's forces at Madanpur and defeated them with great slaughter. By the beginning of March 1858, order was re-established throughout the District. The dominions of the Rájá of Sháhgarh were confiscated, and a portion of them added to the District of Sagar. Bakht Balí gave himself up, under the amnesty, at Marwára, and was sent as a State prisoner to Lahore.

Population—A rough enumeration in 1866 returned the population of Sagar at 498,642. The Census of 1872 returned a total population of 527,725, while the last enumeration in 1881 returned 564,950, showing an increase of 37,225, or 7.05 per cent, in nine years, of which 2.83 per cent represents the excess of registered births over deaths, while the remainder may be assigned to immigration. The results arrived at by the Census of 1881 may be summarized as follows—Area of District, 4005 square miles, towns 5, and villages 1837, number of houses, 155,711, namely, occupied 130,409, and unoccupied 25,302. Total population, 564,950, namely, males 294,795, and females 270,155, proportion of males, 52.2 per cent. Average density of

population, 141 persons per square mile; towns or villages per square mile, 46; persons per town or village, 307; houses per square mile, 32.56; persons per occupied house, 4.33. Classified according to sex and age, there are—under 15 years of age, males 114,422, and females 102,481; total children, 216,903, or 38.5 per cent. of the District population: 15 years and upwards, males 180,373, and females 167,674; total adults, 348,047, or 61.5 per cent.

Religion.—Classified according to religion, the population of Sagar District consists of—Hindus, 498,071, or 88.2 per cent.; Muhammadans, 25,396, or 4.5 per cent.; Jains, 16,432, or 2.9 per cent.; Kabírpánthís, 4606; Satnámís, 245; Christians, 1034; Pársís, 15; Sikhs, 5; Buddhists 2; and tribes professing aboriginal religions, 19,144, or 3.4 per cent. of the population. The total aboriginal population by race, as apart from religion, however, is returned at 45,699, or 8.1 per cent., consisting almost entirely of Gonds (29,407) and Saurás (16,109).

Among the recognised Hindu castes, Bráhmans number 45,408; Rájputs, 18,417; Bháts, 1983; Káyasths, 5453; and Baniyás, 6301. The lower-class Hindus, who comprise the great mass of the population, include the following castes—Chamár, 66,637; Lodhí, 45,053; Kachhí, 42,888; Ahír, 30,197; Kurmí, 25,921; Chandál, 14,757; Telí, 14,299; Náí, 13,580; Korí, 12,545; Dhimár, 12,203; Lohár, 9470; Basor, 9249; Kumbhár, 8514; Dhobí, 7844; Barháí, 6018; Sonár, 5233; Gadáriá, 3807; Kallár, 3626; Darzí, 3696; Málí, 1464; and Koshtí, 1147. The Muhammadan population, classified according to sect, comprise—Sunnís, 23,960; Shiás, 503; Wahábís, 14; and unspecified, 919. Of 1034 Christians, Europeans number 530; Eurasians, 56; Natives of India, 410; and unspecified, 38. By sect, Roman Catholics number 469; Church of England, 427; Presbyterians, 85; Lutherans, 13; Wesleyans, 4; others and unspecified, 36. A station of the Lutheran Mission was established at Sagar in 1878.

The best cultivators are the Kurmís, who immigrated from the Doáb about the beginning of the 17th century; and the Lodhís, who made their way to the Vindhyan table-land during the time of Aurangzeb. Though not tall, the inhabitants of Sagar are for the most part a sturdy race. The simple white cloth made in the country forms the dress in the hot season of the poorer classes. In the cold weather, they wear a thick cotton-padded coat, reaching below the knees. The favourite colour is the green *mahuá*, more particularly in the north of the District bordering on Bundelkhand, where green is regarded as the national colour. Cloth dyed with *ál* or madder is also much worn, especially by females. In the south, the population are peaceful and tractable. But towards the north, their character undergoes a change for the worse; and the Korís, a small caste dwelling on the borders near Native States, where they find protection if pressed by the police,

share with another caste called Khangars a notoriety for crime. No explanation can be given of the fact that Sagar contains more than one-third of the total number of the Jains in the Central Provinces. The prevailing language is Hindi, but Urdu is also spoken.

Town and Rural Population—Sagar District contains five towns with a population exceeding five thousand inhabitants, namely, SAGAR, population (1881) 44,416, GARHAKOTA, 11,414, DEORI, 7414, KHURAI, 5370, and RFHLI, 5230. The urban population thus disclosed amounts to 73,844, or 131 per cent of the District total. The foregoing towns are municipalities, with a total income in 1882-83 of £7491, of which £5872 was derived from taxation, mainly octroi duties; average incidence of taxation, 1s. 7d per head of the population within municipal limits. The 1837 villages below five thousand inhabitants are thus classified—1024 contain less than two hundred inhabitants, 575 between two and five hundred, 174 between five hundred and a thousand, 53 between one and two thousand, 10 between two and three thousand, and 1 between three and five thousand inhabitants.

As regards occupation, the Census Report divides the male population into the following six classes—(1) Professional, military, and official class, 7850, (2) domestic class, including inn and lodging house keepers, etc., 3686, (3) commercial class, including bankers, merchants, traders, carriers, etc., 6861, (4) agricultural and pastoral class, including gardeners, 98,488, (5) manufacturing and industrial class, including all artisans, 46,590, and (6) indefinite, non productive, and unspecified class, comprising general labourers and male children, 28,314.

Agriculture—Of the total area of 4005 square miles, only 1396 square miles were cultivated in 1883-84, while of the portion lying waste, 1220 square miles were returned as cultivable and 1389 square miles as uncultivable, 4519 acres were irrigated, entirely by private enterprise. Of the total area, however, 1007 square miles are held revenue free, leaving 2998 square miles liable to Government assessment, of which 1412 square miles were cultivated in 1883-84, 940 square miles were available for cultivation, and 646 square miles uncultivable. Wheat forms the staple crop of the District, grown in 1883 on 527,424 acres. Rice was grown on only 11,084 acres, while other food grains were grown on 236,414 acres. Oil seeds occupied 69,524 acres, cotton, 32,705 acres, and sugar cane, 3784 acres. The agricultural stock in 1883-84 consisted of—Cows, bullocks, and buffaloes, 289,379, horses, 4635; ponies, 14,024, donkeys, 3086, sheep and goats, 29,897, and pigs, 5502, while carts numbered 20,037, and ploughs 56,049. Cattle and buffaloes are bred to a large extent in the District, both for draught and carriage, and also for dairy purposes, especially the manufacture of *ghi*, and lately some bulls have been imported from Hissár and Mysore,

to improve the indigenous breed. The stock of sheep is small, and insufficient even for home consumption. The Chamárs and Gondes eat flesh when they get it, and are not particular about its condition. Wheat, barley, and *dál* form the food of the richer inhabitants; the poorer classes content themselves with *bájra*, *kodo*, *kutkí*, and often in seasons of scarcity subsist on the *mahuá* and other jungle fruits.

Of the adult male and female agricultural population in 1881 (namely 149,732), 7749 were returned as landed proprietors, 29,456 as tenants possessing rights of occupancy, 41,526 as tenants-at-will, 15,638 as assistants in home cultivation, 5991 as agricultural labourers, while the remainder is made up of graziers, tenants of unspecified status, estate agents, etc. Area of cultivated and cultivable land available for each adult agriculturist, 11·3 acres. The rent rates per acre for the different qualities of land in 1883 are returned as follows:—Land suited for wheat, 3s. 10½d.; inferior grains, 2s. 1½d.; oil-seeds, 2s. 7½d.; cotton, 2s. 7d.; rice, 4s. 9d.; sugar-cane, 5s. 9d. Total amount of Government assessment, including local rates and cesses levied on land, £47,339, or an average of 1s. 0½d. per cultivated acre. Total rental paid by cultivators, £116,000, or an average of 2s. 5½d. per cultivated acre. The ordinary prices of produce per cwt. were as follows:—Wheat, 4s. 2d.; linseed, 9s. 9d.; cotton, 30s. 9d.; rice, 9s. 6d.; sugar (*gír*), 12s. 3d. The wages per diem for skilled labour averaged 9d.; for unskilled labour, 3¾d.

Commerce and Trade.—Ságar is not the seat of any important manufacture. Large cattle fairs are held weekly at Kurái, and once a year at Garhákota. The other principal fairs take place at Bhápel, Pandalpur, and Rangir. The iron-ore, smelted near Hírápúr, goes principally to Cawnpur; but the chief export of the District consists of grain sent to Karelí and other stations on the Great Indian Peninsula Railway, for conveyance to Bombay. Principal imports—sugar and *kirána*, or grocery, from Mirzápur; and English cloth and piece-goods from Mirzápur, and from Bombay by way of Karelí. The town of Ságar was formerly the entrepôt of the salt trade with Rájputána. In 1883, 50 miles of made roads within the District were returned as of the 'first' class, 63 of the 'second,' and 21 of the 'third' class. The main lines of communication are—the road from Jabalpur *viâ* Damoh to Ságar, and thence *viâ* Ráhatgarh towards Indore, with travellers' bungalows at Ságar and Ráhatgarh; the road from Gwalior *viâ* Jhánsí and Lálitpur to Ságar, and thence towards Narsinghpur; the road from Ságar in a north-easterly direction towards Cawnpur, with a travellers' bungalow at Sháhgarh; and the road from Ságar in a north-westerly direction to Sironj in Sindhia's territory, and Mhow *viâ* Kurái. None of these roads is bridged and metalled throughout. A road connecting Ságar with the Great Indian Peninsula Railway at Karelí, and crossing

the Narbadī (Nerbudda) at the Burmān Ghāt, has been recently opened for traffic, and now forms the chief line of communication in the District. The District has no means of communication by water or rail.

Administration —In 1861, Sagar was formed into a separate District of the British Government of the Central Provinces. It is administered by a Deputy Commissioner, with Assistants and *tahsildars*. Total revenue in 1883-84, £68 376, of which the land yielded £44,429. Total cost of District officials and police of all kinds, £7586. Number of civil and revenue judges of all sorts within the District, 12, magistrates, 10. Maximum distance from any village to the nearest court, 28 miles, average distance, 26 miles. Number of police, District and town, 715, being 1 policeman to every 56 square miles and every 785 inhabitants. The daily average number of convicts in jail in 1883 was 127, of whom 13 were females. The number of Government or aided schools in the District under Government inspection in 1883-84 was 92, attended by 6145 pupils. The Census Report of 1881 returned 5625 boys and 592 girls as under instruction, besides 14,199 males and 416 females able to read and write, but not under instruction.

Medical Aspects —Through the greater part of the District the climate is considered moderate. Temperature in the shade in 1883 at the civil station—May, highest reading 111° F, lowest 67° F, July, highest 91° F, lowest 71° F, December, highest 79° F, lowest 44° F. The average annual rainfall is 45·7 inches, but in 1883 only 32·66 inches fell. Storms are rarely of such severity as to injure the crops. The prevalent disease of the District is an intermittent fever, which comes on after the rains, especially during the month of October. Bowel complaints also cause many deaths. In 1883, eight charitable dispensaries afforded medical relief to 57,402 in-door and out-door patients. The reported death-rate in the same year amounted to 36·68 per thousand of the population, as against an average of 40·80 per thousand for the previous five years. [For further information regarding Sagar, see the *Central Provinces Gazetteer*, by Mr (now Sir Charles) Grant (Nagpur, 1870); also the *Report on the Land Revenue Settlement of Sagar District*, 1856-1866, by Lieut Colonel J N H Maclean (published 1867), the *Census Report of the Central Provinces for 1881*, and the several annual Administration and Departmental Reports of the Central Provinces Government.]

Sagar (Saugor) —The central *tahsil* or Sub-division of Sagar (Saugor) District, Central Provinces, lying between 23° 5' and 23° 56' N lat., and between 78° 37' and 79° 21' E long. Area, 1067 square miles, with 1 town and 497 villages, and 46,640 houses. Population (1881) 196,980, namely, males 102,017, and females 94,963,

average density of population, 184·6 persons per square mile. The total adult agricultural population (male and female) numbers 36,490, with an average area of 13 acres of cultivated and cultivable land to each. Of the total area of the *tahsíl* (1067 square miles), 158 square miles are held revenue-free, while 909 square miles are assessed for Government revenue, of which 433 square miles are cultivated, 242 square miles available for cultivation, and 234 square miles uncultivated waste. Total amount of Government land revenue, including local rates and cesses, £16,363, or an average of 1s. 2½d. per cultivated acre; amount of rental paid by cultivators, including rates and cesses, £34,592, or an average of 2s. 4¾d. per cultivated acre. Sagar *tahsíl* contained in 1883, 6 civil and 9 criminal courts (including the District head-quarter courts), with 4 police circles (*thánds*), and 9 outpost stations (*chaukis*), a regular police force numbering 118 men, and a village watch or rural police of 452 *chaukidárs*.

Ságar (*Saugor*). — Principal town and head-quarters of Sagar (Saugor) District, Central Provinces. Lat. 23° 49' 50" N., long. 78° 48' 45" E. Sagar stands 1940 feet above sea-level, on the borders of a fine lake nearly a mile broad, from which it derives its name. The lake is said to be an ancient Banjára work; but the present city is only about two centuries old, and owes its rise to a Bundelá Rájá, who built a small fort on the site of the present structure in 1660, and founded a village called Parkotá, now a quarter of the modern town. Sagar was next held by Chhatar Sál, and formed part of the territory left by him on his death to his ally the Peshwá. Govind Pandit was appointed by the Peshwá to administer the country; and his descendants continued to manage it till shortly before it was ceded to the British Government by Peshwá Báji Ráo in 1818. During this period the town was twice plundered by Amír Khán and his army, and again by Sindhia in 1804. During the Mutiny of 1857, the town and fort were held by the English for eight months, during which time the whole of the surrounding country was in possession of the rebels, until the arrival of Sir Hugh Rose.

Sagar town is well built, with wide streets; and the large bathing *gháts* on the banks of the lake, for the most part surrounded with Hindu temples, add much to its appearance. Sagar was formerly the entrepôt of the salt trade with Rájputána, and still carries on a large trade with Mírzápur, importing sugar and *kirána*, or grocery, besides English cloth. Population (1881) 44,416, namely, males 22,556, and females 21,860. Classified according to religion, Hindus number 32,490; Muhammadans, 8992; Jains, 1144; Kabírpánthís, 699; Satnámís, 88; Christians, 975; Pársís, 15; Sikhs, 4; and non-Hindu aborigines, 9. Municipal income (1882-83), £4377, of which £3892 was derived from octroi; average incidence of taxation, 1s. 9d. per head.

SAGAR ISLAND

The existing fort at Sagar was completed by the Maráthás about a century ago, on an older site. It stands on a height north west of the lake, commanding the whole of the city and surrounding country, and consists of 20 round towers, varying from 20 to 40 feet in height, connected by thick curtain walls. It encloses a space of 6 acres, for the most part covered with old Maráthá buildings two storeys high. The British Government have constructed a magazine, a large building now used for medical stores, and a barrack for the European guard. The only entrance is on the east side. In 1820, a large building was erected for a mint about a mile east of the lake, where 400 men were employed in coining, but after ten or twelve years the business was transferred to Calcutta. The building is now used as the *tahsil*, and as the office of the Executive Engineer. Other edifices of importance are a large castellated jail, capable of containing 500 prisoners situated about half a mile east of the lake, and built in 1846 at a cost of £5000; the Deputy Commissioner's Court, on a hill overlooking the city and lake built about 1820, the Sessions Court house, a little to the north built in 1863 at a cost of £500, and the city *kotwali* or station house, under the western walls of the fort, built in 1856. Sagar had formerly a high school, affiliated to the Calcutta University established about 1828 by Captain James Paton, of the Bengal Artillery with the assistance of Rao Krishna Rao, a Maráthá gentleman. The high school has since been removed to Jabalpur, and has been replaced by a *zulf* school. The town also contains a vernacular middle class school several indigenous schools, and 5 girls' schools. In 1862 an unhealthy swamp lying north east of the lake, which cut off the quarter called Gopalganj from the rest of the city, was converted into a large garden with numerous trees and a piece of ornamental water at a cost of £3000. The civil station begins with the mint, about a mile east of the lake and extends thence for a mile, till joined by the military cantonments, which are in a north westerly direction for a few miles with the church in the centre. Before the Mutiny, the cantonments were exclusively garrisoned by Native troops, with a detail of European artillery. Since however, a European regiment and two batteries of European artillery, with a Native regiment of cavalry and one of infantry have been stationed at Sagar. The fort contains a large magazine and dépôt.

Sagar (Sangor) — Island at the mouth of the Hugli river Bengal $21^{\circ} 35' 30''$ to $21^{\circ} 56' 30''$ N., long $88^{\circ} 4' 30''$ to $88^{\circ} 14'$ E. A fair is held on the island about the middle of January, to which a large number of pilgrims, mostly women, from all parts of Bengal, resort from other parts of India, to wash away their sins in the waters of the holy stream. The religious ceremonies last for three

days, but the fair is continued for a longer period; a considerable trade is carried on in articles brought from Calcutta, mats from Eastern Bengal, and stoneware platters and cups principally from Chutiá Nágpur. At other times the island is very sparsely inhabited, though it is said to have been once well peopled. A writer in the *Calcutta Review* even asserts that 'two years before the foundation of Calcutta it contained a population of 200,000 persons, who in one night, in 1688, were swept away by an inundation.' Ságar Island has now been partially reclaimed, but the greater part is still covered with dense jungle, and infested by tigers and other wild beasts. Many attempts have been made to cultivate it, but until recently with small success. The Board of Revenue tried in 1813 to lease it to natives, but the attempt failed, and the island was subsequently taken over by an association, composed of Europeans and natives, rent-free for thirty years, and at a quit-rent of 1s. 6d. per acre thereafter. Previous to this, the island had been surveyed (1812) and found to contain 143,265 acres of dry land. Sub-leases were afterwards granted to several persons, but their efforts to clear the land were ineffectual.

During the years 1875-77, six allotments in the island were leased out by Government for a period of years free of revenue, on condition that special protective works against inundation, to be approved by Government, should be constructed and maintained by the grantees. The works have been carried out, and cultivation is once more spreading over these lands, which still form the subject of an annual inquiry.

Salt manufacture was conducted on the island for some time, but has been almost discontinued.

The only buildings of any importance in Ságar Island are the lighthouse, which was commenced as long ago as 1808, and the telegraph office at the north of the island. The Meteorological Department has an observatory on the south-west extremity of the island. The telegraph station lies below high-water mark, and is protected by a strong dyke. The average rainfall for the fifteen years ending 1881 was 73·85 inches. The cyclone of 1864 caused enormous destruction and loss of life on Ságar Island. The storm-wave, 11 feet above the level of the land, swept over the island with resistless force. At first it was reported that 90 per cent. of the population had perished; but it was afterwards ascertained that 1488 persons survived on the island out of a population, before the cyclone, of 5625.

Ságar.—*Táluk* in Shimoga District, Mysore State. Area, 663 square miles, of which 83, including *indáms*, are cultivated. Population (1871) 60,231; (1881) 59,210, namely, males 32,237, and females 26,973. Hindus number 54,277; Muhammadans, 1621; Jains, 3190; and Christians, 122. Land revenue (1881), excluding local cesses, £21,196; assessment per cultivated acre, 7s. 10½d. Ságar *táluk*

SAGAR TOWN—SAGRI

111

occupies the most westerly portion of Mysore, broken by the spurs of the Ghâts, and in parts only 8 miles distant from the sea. A great part of the area is overgrown with heavy timber trees, interspersed with grassy glades, amid which wander herds of bison and wild elephant. Products—areca nut rice, pepper, and cardamoms.

Ságar — Municipal town in Shimoga District, Mysore State, situated in lat $14^{\circ} 9' 50''$ N, and long $75^{\circ} 4' 20''$ E, on the left bank of the Varada river, 40 miles west north west of Shimoga town. Head quarters of *Ságar taluk*. Population (1881) 2284. Municipal revenue (1881-82), £223, rate of taxation is $1\frac{1}{2}$ d per head. A centre of the areca nut trade, and the residence of some wealthy merchants. Areca nut, pepper, sandal wood and products of the highlands are exchanged for cotton cloth and other articles from the seaboard.

Ságargarh (*Ságar, ad* or the 'Sea Fort') — Fortified hill and health resort in Kolaba District Bombay Presidency. Situated 19 miles south of Bombay city and 6 east of Alibágh, 1357 feet above sea level. The spur on which Ságargarh fort is built holds a somewhat central position in the range of hills that forms the backbone of Alibagh Sub division. On the east south and north it rises steeply from the forests and rice lands below. To the north west and west, beyond a narrow neck it stretches a bare waving hill top about two miles long and half a mile to a mile broad. Its height and nearness to the sea make it pleasantly cool during the latter part of the hot weather. There are two main roads to Ságargarh from the east and from the west. From the citadel the chief view is the sea to the north west, west, and south west. To the south is a rice plain and beyond the plain rise the bare Cheul hills. To the north stretches the Bombay harbour, the Prongs lighthouse and Kolaba. The chief buildings on the hill are two European bungalows.

Sagri — North-eastern *tahsil* of Azamgarh District North Western provinces, lying along the south bank of the river Gogra and comprising the four *parganas* of Sagri, Gopalpur Ghosi and Vathupur. The greater part of the country consists of good *bangar* land, but the *khadr* country, inundated by the Gogra and the Little Sarju or Tons, constitutes a considerable portion of its area chiefly in the centre and north-east. Gopalpur and Sagri *parganas* in the west are watered by the Little Sarju, and in the eastern half of the *tahsil* there are a few *taliks* which feed several large lakes or marshes, of which the principal are the Pakri Pawai Tal in Ghosi and the Rutor Tal in Gopalpur *pargana*. Only about one fourth of the cultivated area in Sagri and Sagri *parganas* is rice land. In the saturated *kachhar* tracts, a variety of spring crops can be raised. In the saturated *kachhar* tracts, a variety of rice known as *sokan*, which seems unable to grow elsewhere. Peas, vetches, and other *rabi* crops are grown after

the rice crop has been harvested. In the tracts nearest the rivers, barley and peas, and in places sugar-cane, are grown; but the other *kharif* crops, owing to the liability to injury from floods, rarely turn out well. Throughout the *kachhár*, the swamps and old beds of the Gogra and Little Sarju are filled with *tinni* or wild rice. In the *bángar* the usual *rabí* crops are grown along with sugar-cane, which is not, however, so profitable a crop here as elsewhere. A little poppy is grown in favourable places throughout the *tahsíl*. The chief markets are the Nainijor and Chapri *bázárs* on the Gogra, which, during the rainy season, are moved, the former to Bábá-ka-bázár, and the latter to Ausánpur, both on the south bank of the Little Sarju. Considering the nature of the tract, and the difficulties it presents, the *tahsíl* is fairly supplied with communications. The Azamgarh-Gorakhpur and Gházípur-Gorakhpur first-class roads pass through the centre of the *tahsíl*, meeting at Doharighát on the Gogra. The Azamgarh-Faizábád second-class road skirts the west of the *tahsíl*, through Sagrí and Gopálpur *parganá*. There are numerous third-class roads which join the above, and connect the larger towns and villages.

The total area of Sagrí *tahsíl* in 1881-82 was 592 square miles, of which 362 square miles were cultivated, 97 square miles cultivable, and 123 square miles uncultivable waste. Population (1881) 447,455, namely, males 226,037, and females 221,418; average density of population, 769 persons per square mile. Hindus number 395,737, and Muhammadans 51,718. Of the 1312 towns and villages in the *tahsíl*, 1072 contain less than five hundred inhabitants; 162 between five hundred and a thousand; 63 between one and two thousand; and 14 between two and five thousand. The only place with upwards of five thousand inhabitants is Dúbárí (7502). Of the total cultivated area, about 49 per cent. in Sagrí and Gopálpur, and 38 per cent. in Ghosí and Nathúpur, is cultivated by the proprietors as *sír* or homestead land. The tenant population is chiefly low caste, nearly all the high-caste landholders having retained their proprietary rights. In Sagrí and Gopálpur the average area of holdings held by tenants with occupancy rights is $2\frac{1}{2}$ acres, and of tenants-at-will $1\frac{1}{2}$ acres. In Ghosí and Nathúpur the average holdings are $3\frac{1}{2}$ acres by tenants with occupancy rights, and less than 2 acres by tenants-at-will. Total Government land revenue (1881-82), £42,293, or including local rates and cesses levied on the land, £50,259. Amount of rental paid for cultivators, including rates and cesses, £91,719. Sagrí *tahsíl* contained in 1883, 1 criminal court, 7 police stations (*thánds*), a regular police force of 84 men, and a village watch or rural police of 694 *chaukidárs*.

Sáh.—Large village in Gházípur *tahsíl*, Fatehpur District, North-Western Provinces; situated in lat. $25^{\circ} 52' 55''$ N., and long. $80^{\circ} 45' 46''$ E., 7 miles from Fatehpur town, and 5 miles from Gházípur.

SAHAR—SAHARANPUR

113

Population (1881) 3385, principally Ahírs Old fort, said to have been built by a Bais Rájput, post-office, school, and bi-weekly market

Sahár—Town in Chhata *tahsil*, Muttra (Mathura) District, North Western Provinces, situated in lat $20^{\circ} 37' 45''$ N, and long $27^{\circ} 37' 45''$ E, on the left bank of the Agrá Canal, 7 miles south of Chhátá town. Population (1881) 2776 Sahár was the seat of Thákúráján, who built for the father of Suraj Mall, the first of the Bhartpur Rájás, who built for himself a handsome residence here, now to a great extent in ruins. The town contains several old houses with carved stone gateways, of some architectural pretensions. A number of handsomely carved pillars, the remains of an ancient temple, have been dug up, and are now in the Muttra Museum. A weekly market is held on Wednesdays, and the town contains a police station, post office, and a good school. A small house tax is raised for police and conservancy purposes.

Saháranpur—District in the Lieutenant Governorship of the North Western Provinces, lying between $29^{\circ} 34' 45''$ and $30^{\circ} 21' 20''$ N lat, and between $77^{\circ} 9'$ and $78^{\circ} 14' 45''$ E long. Area, 2221 square miles. Population in 1881, 979 544 souls. Saháranpur is a District in the Meerut (Merath) Division. It is bounded on the north by the Siwálík Hills, which separate it from Dehra Dun District, on the east by the Ganges, separating it from Bijnáur District, on the south by Muzaffar Nagar District, and on the west by the river Jumna (Jamuná), separating the head quarters are at SAHARANPUR CITY.

Physical Aspects—Saharanpur forms the most northerly portion of Doáb or alluvial table land which stretches between the channels of the Ganges and the Jumna. The Siwálík Hills rise above it on the northern frontier. Their slopes are rugged and abrupt, pierced by numerous passes, and crowned by jagged summits which often assume most fantastic shapes. At their base stretches a wild submontane overgrown with forest or jungle and intersected by innumerable main torrents, which leap foaming down from the hills on their way to join the waters of the Jumna and the Ganges. These two arterial streams themselves descend into the plain through recent ravines, which rapidly give way to high banks of clay, and pass from the mountain region into the level table land.

of the intermediate forest belt lies the general plain of the elevated upland tract, in whose friable soil the great rivers themselves wide and shifting courses, at a depth of about 60 feet above the general surface. The broad valleys thus excavated are well watered and fertile, but the great central plateau lies high, with a general elevation of 900 feet above the sea, while

numberless small ravines drain off its scanty moisture towards the low land on either side.

The highest cultivation has, nevertheless, been rendered possible throughout the District by two splendid engineering achievements, the GANGES and the EASTERN JUMNA CANALS (*qq.v.*), both of which take their origin within the boundaries of Saháranpur. The latter work was originally planned and in part executed by All Mardan Khán, the celebrated minister of Sháh Jahán, but it was not finally completed till the year 1830. The difficulties attending the upper part seem to have been beyond the resources of Musalmán engineering, and the canal is believed to have never flowed beyond one season until its reconstruction by the British under Sir P. Cautley, R.E. Colonel Colvin believes that 'the task of maintaining the passage across the mountain torrents at its head was found to be so great, that the canal was abandoned (by its native projectors) almost as soon as formed, and that the repeated attempts at reparation afterwards were only efficient for a season, and were overcome by the increasing difficulties.' The Eastern Jumna Canal, as it now exists, is entirely a work of British engineering. The Ganges Canal was opened in 1855. Both these canals run through the whole length of the District, from north to south, and have converted large portions of its central plateau into stretches of unbroken cultivation.

The District is everywhere thickly studded with flourishing villages and populous towns. The waste lands are small in amount, except in the hilly northern region; and cultivation is spreading on every side, under the fostering influence of peaceful government, and the successful issue of the irrigation schemes. The general aspect of the country is indicative of steady progress and comparative wealth, though the land is still capable of bearing a considerable increase of population without undue pressure on its resources.

Besides the two great boundary rivers, Saháranpur is intersected by the Hindan, West Káli Nadi, and Soláni rivers, which, with a number of minor tributary streams and hill torrents, ultimately fall into the Ganges or Jumna. The surface of the country has a general slope from north to south, with a fall from 1489 above sea-level at the Trigonometrical Survey Station at Mohand, at the foot of the Siwálík Hills, to 832 feet at Deoband in the south.

The mineral products are insignificant. In the middle and southern portions, *kankar*, or impure carbonate of lime, occurs in spongy nodules in the subsoil; limestone tufa, too, is occasionally found. To the north, the substratum consists of shingle and boulders, gradually giving place to sandstone, which at Mohand appears on the surface. Stone, hard enough to be used for building, is scarce. Pieces of sufficiently strong consistency for this purpose may be picked out of

SAHARANPUR

the Siwalik standstone. But although most of the houses at Hardwar and Kankhal are constructed of materials so procured, the quantity obtained is not large enough to defray the expense of carriage to a long distance, and building stone is generally obtained from Agra.

Wild Animals—Tigers are still numerous in the forest belt along the foot of the Siwalik Hills, and in the *khádar* of the Ganges. Leopards abound, and three varieties are distinguished in the District. Wild cats, lynxes, hyænas, and wolves are common. During the rains wild elephants frequently descend from the Siwaliks to feed, and they often come as far as the Ganges valley, ten miles south of the hills, where they cause much destruction to the crops. Several varieties of deer, and the antelope and *nigdi*, are also found. Poisonous serpents are not numerous, and the Siwalik python, which grows to an immense size, appears to be harmless, and confines its depredations to the lower animals. The most valuable of the edible fish are the *rohú*, *mahásir*, *anardi*, *sol*, and *chitwá*. Fish are tolerably abundant in the larger rivers, but measures are said to be needed to prevent their wholesale destruction near the canal heads.

History—The portion of the Doab in which Saháranpur is situated was probably one of the first regions of Upper India occupied by the Aryan colonists, as they spread eastward from their original settlement in the Punjab. But the legends of the *Mahabharata* centre around the city of Hastinapur, in the neighbouring District of MEERUT, and it is not till the 14th century of our era that we learn any historical details with regard to Saháranpur itself. The town was founded in the reign of Muhammad Tughlak, about the year 1340, and derived its name from a Musalmán saint, Shah Haran Chishti, whose shrine is still an object of attraction to Muhammadan devotees. At the close of the century the surrounding country was exposed to the ravages of Timur, who passed through Saháranpur on his return from sack of Delhi, and subjected the Hindu inhabitants to all the usual horrors of a Mughal invasion. In the year 1414, the tract was conquered by Sultán Sayyid Khizr Khán on Sayyid Salim, and in 1526, he marched across it on his way to Pánapat. A few Mughal nobles still trace their origin to his followers. A year later, the town was founded by the zealous missionary Abdul Kaddu, and efforts were the means of converting to the faith of Islam many Rájput and Gujjar neighbours. His descendants ruled the country until the reign of Akbar, and were very influential in bringing the Musalmán element by their constant zeal in prosecuting the Augustin age of the Mughal Empire, Saháranpur was a summer resort of the court and the nobles, who were attracted by the coolness of its climate and the facilities which it offered.

for sport. The famous empress Núr Mahál, the consort of Jahángir, had a palace in the village which still perpetuates her memory by its name of Núrnagar; and under Sháh Jahán, the royal hunting seat of Bádsháh Mahál was erected by Alí Mardan Khán, the projector of the Eastern Jumna Canal. Unhappily, the canal was permitted to fall into disuse during the long and disastrous decline of the Mughal power, and it was never of much practical utility until the establishment of British rule.

After the death of Aurangzeb, this region suffered, like the rest of Upper India, from the constant inroads of warlike tribes and the domestic feuds of its own princes. The first incursion of the Sikhs took place in 1709, under the weakened hold of Bahádur Sháh; and for eight successive years their wild hordes kept pouring ceaselessly into the Doáb, repulsed time after time, yet ever returning in greater numbers, to massacre the hated Muhammadans and turn their territory into a wilderness. The Sikhs did not even confine their barbarities to their Musalmán foes, but murdered and pillaged the Hindu community with equal violence. In 1716, however, the Mughal court mustered strength enough to repel the invaders for a time; and it was not until the utter decay of all authority that the Sikhs once more appeared upon the scene.

Meanwhile the Upper Doáb passed into the hands of the Sayyid brothers of Bárha, whose rule was more intimately connected with the neighbouring District of MUZAFFARNAGAR. On their fall in 1721, their possessions were conferred upon various favourites in turn, until in 1754 they were granted by Ahmad Sháh Duráni to Najíb Khán, a Rohillá leader, as a reward for his services at the battle of Kotila. This energetic ruler made the best of his advantages, and before his death (1770) had extended his dominions to the north of the Siwálíks on one side, and as far south as Meerut on the other. But the end of his rule was disturbed by incursions of the two great aggressive races from opposite quarters, the Sikhs and the Maráthás. Najíb Khán handed down his authority to his son, Zábíta Khán, who at first revolted from the feeble court of Delhi; but on being conquered by Maráthá aid, was glad to receive back his fief through the kind offices of his former enemies, then supreme in the councils of the Empire. During the remainder of his life, Zábíta Khán was continually engaged in repelling the attacks of the Sikhs, who could never forgive him for his reconciliation with the imperial party. Under his son, Ghulám Kádir (1785), the District enjoyed comparative tranquillity. The Sikhs were firmly held in check, and a strong government was established over the native chieftains.

But upon the death of its last Rohillá prince, who was mutilated and killed by Sindhia in 1788, the country fell into the hands of the

SAHARANPUR

11

Marathás, and remained in their possession until the British conquest. Their rule was very precarious, owing to the perpetual raids made by the Sikhs, and they were at one time compelled to call in the aid of George Thomas, the daring military adventurer who afterwards established an independent government in Hanána. Indeed, the internal quarrels of this confused period are too complicated for brief narration, and it must suffice to say that the country remained practically in the hands of the Sikhs, who levied black mail under the pretence of collecting revenue.

After the fall of ALIGARH and the capture of Delhi (1803), a British force was despatched to reduce Saháranpur. Here, for a time, a double warfare was kept up against the Marathás on one side and the Sikhs on the other. The latter were defeated in the indecisive battle of Charáon (24th November 1804), but still continued their irregular raids for some years. Organization, however, was quietly pushed forward, and the District enjoyed a short season of comparative tranquillity, until the death of the largest landowner, Ram Dáyal Singh in 1813. The resumption of his immense estates gave rise to a Gujúr revolt, which was put down before it had assumed very serious dimensions. A more dangerous disturbance took place in 1824, a confederacy on a large scale was planned among the native chiefs, and a rising of the whole Doáb might have occurred had not the premature eagerness of the rebels disclosed their design. As it was the revolt was only suppressed and the fall of their ringleaders.

From that period till the Mutiny, no events of importance disturbed the quiet course of civil administration in Saháranpur. News of the rising at MEERUT was received early in May 1857 and the European women and children were immediately despatched to the hills. Measures were taken for the defence of the city, and a garrison of European civil servants established themselves in the Magistrate's house. The District soon broke out into irregular rebellion, but the valiant spirit showed itself rather in the form of internecine quarrels amongst the native leaders than of any settled opposition to British government. Old feuds sprang up anew, villages returned to their ancient enmities, bankers were robbed, and money lenders pillaged, while the local officers continued to exercise many of their functions, and the chief offenders by ordinary legal process. On the 2nd of September of the Native infantry at Saháranpur mutinied and fired on their officers, but without effect. Shortly afterwards, a small body has arrived, by whose assistance order was partially restored. On December 1857, it was found practicable to proceed with a general assessment of the District, and the population appeared to be more respectful. In fact, the mutiny in Saháranpur was merely

an outbreak of the old predatory anarchy, which had not yet been extirpated by our industrial *régime*, and there was little indication of any popular aversion to British rule.

Population.—The earliest Census, which gives the population of the District with its present area, was that of 1853; the number of inhabitants then amounted to 801,325. By 1865 the population had increased to 869,176, or 389 to the square mile. In 1872 the enumeration disclosed a further increase to 884,017 persons. The last Census in 1881 returned the total population at 979,544, showing an increase of 178,219, or 22·1 per cent., in the 28 years since 1853. The increase since 1872 was 95,527, or 10·8 per cent. in 9 years.

The results of the Census of 1881 may be summarized as follows:—Area, 2221·4 square miles; towns 10, and villages 1595; number of houses, 91,977. Total population, 979,544, namely, males 530,427, and females 449,117; proportion of males, 54·1 per cent. Average density of population, 441 persons per square mile; number of towns and villages, 72 per square mile; persons per town or village, 610; houses per square mile, 41·4; inmates per house, 10·6, a larger number than in any other District of the Province. Classified according to sex and age, there were in 1881—under 15 years of age, boys 197,979, and girls 165,806; total children, 363,785, or 37·1 per cent. of the District population: 15 years and upwards, males 332,448, and females 283,311; total adults, 615,759, or 62·9 per cent. The preponderance of males is chiefly due to the former prevalence of infanticide, a practice which all the vigilance of the Government has not yet been able entirely to check. In 1881, out of a total of 122,464 of the suspected castes (Rájputs, Gújars, Tágás, Játs, Ahírs, and Ahárs), the females numbered only 48,752, or 39·8 per cent.

Religion.—As regards the religious classification in 1881, Hindus are returned at 653,272, or 66·7 per cent.; Muhammadans, 317,535, or 32·3 per cent.; Jains, 6673; Christians, 1793; Sikhs, 269; and Pársis, 2. Of the higher Hindu castes, Bráhmans numbered 47,288. Rájputs numbered 28,798, of whom only 11,540, or 40 per cent., were females. They are one of the castes suspected of infanticide, and in many villages the provisions of the Infanticide Act are strictly enforced. In physique, the Rájputs are a fine hardy race, but their lawless spirit has given much trouble. The Baniyás or trading castes were returned at 32,622, amongst whom the Agarwálas form by far the largest sub-division. Bháts numbered 2067, and Káyasths 1587. The other or Súdra Hindu castes numbered 540,910, comprising the great mass of the population. The most numerous of them were the Chamárs, reckoned at 174,956. Next in number come the Gújars, a race of supposed Tartar origin, almost peculiar to the northern Doáb, who are returned at 57,376. They are

SAHARANPUR

a turbulent race, addicted to cattle lifting, and are also among the clans suspected of female infanticide, the proportion of females among them being under 40 per cent. Kahars number 42,915, Kachhis 28,807, Bhangis, 28,740, Mális, 25,108, Tagás, 16,345, Kumbhás, 15,511, Barhás, 13,450, Jats, 13,998, Gadáriás, 10,837, Lohars, 8549, Nais, 8516, Koris, 6647, Ahírs, 5904, Sonárs, 5449, Dhobís, 4078, and Lodhs, 2982.

The Musalmáns are partly descendants of the various early invaders, partly native converts from Hinduism. Amongst the former, the Sayyids, Mughals, and Patháns are the most numerous. Those of Hindu origin still retain many of their old practices and prejudices, while their trade classes are assuming the rigid character of castes. The religious opinions of the people have been much shaken by the influences of civilisation, but Christianity has made little progress amongst them, nor does the faith of Islám now gain many converts. There were in 1881, 28,070 Muhammadans returned in the District as of respectable Hindu descent, namely, Rajputs, 12,843, Gujars, 14,207, Tágás, 893, Játs, 90 and Mewátis 37. By sect the Muhammadans of Saháranpur consist of Sunnis 314,855, and Shiás, 2680.

The Christian population comprises—Europeans 1291 Eurasians, 166, and natives of India 336. The American Presbyterian body has a missionary station at Saháranpur, established in 1836, and another at Rúrki, established in 1856.

Town and Rural Population—Saháranpur contains a considerable urban population. In 1881, ten towns were returned as containing upwards of five thousand inhabitants, namely SAHARANPUR, 51,194, DEOBAND, 22,116, RÚRKÍ 15,953, JAWALAPUR, 15,196, GANGOH, 2,089, MANGLAUR 9990, RAMPUR, 7951, AMBEHTA 6392, KANKHAL, 338, and LANDHAURA 5764. These ten towns contain an aggregate of 160,483 inhabitants or 16.7 per cent of the total population of the District. The four municipal towns of Saharanpur, Hardwar, Deoband, and Rurki contain an aggregate population of 234 Municipal income (1883-84), £9553 of which £7588 was levied from taxation, average incidence of taxation, 1s. 1½d per £100. The 1605 towns and villages are thus classified according to size: 7 are mere hamlets with less than two hundred inhabitants, 558 between two hundred and five hundred, 385 between five hundred and a thousand, 146 between one and two thousand, 24 between two and three thousand, 15 between three and five thousand, 5 between five and ten thousand, 3 between ten and twenty thousand, upwards of twenty thousand inhabitants. As regards occupation, the Census divides the male population into six classes—(1) Professional, military, and official class,

16,502 ; (2) domestic class, including inn and lodging-house keepers, 3999 ; (3) commercial class, including bankers, merchants, traders, carriers, etc., 13,624 ; (4) agricultural and pastoral class, including gardeners, 180,709 ; (5) manufacturing and industrial class, including artisans, 94,838 ; and (6) indefinite, non-productive, and unspecified class, comprising general labourers and male children, 220,755.

Agriculture.—In 1883–84, out of a total area of 1832½ square miles, or 1,172,692 acres, assessed for Government revenue, 848,924 acres, or 72·4 per cent., were under cultivation, of which 97,314 acres were irrigated from Government canals, and 54,607 acres from wells and tanks, while 697,003 acres were unirrigated. Of the uncultivated area, 186,907 acres were returned as grazing lands or available for cultivation, while 136,861 acres were uncultivable waste. The *rabi* or spring harvest is sown in October, and reaped in March ; and the *kharif* or rain harvest is sown in June, and gathered in October. The chief spring products are wheat and barley (415,949 acres in 1883–84), pulses (65,858 acres), sugar-cane (40,062 acres), and oil-seeds (2792 acres). The staples of the rain harvest are rice (96,929 acres), *joár* and *bájra* (81,974 acres), and vegetables. The cultivation of cotton was carried on very largely during the prevalence of high prices caused by the American war ; but in 1883, the area under cotton had shrunk to 47,352 acres. Indigo, on the contrary, has been grown in greater quantities since the introduction of canal irrigation has rendered its out-turn less precarious than formerly. Cereals are, however, the principal products of the total cultivated area. A Government botanical garden was established in the town of Saháranpur in 1817, and has proved eminently successful, both from a scientific point of view, and in the practical work of naturalizing useful plants, trees, and fruits.

The condition of the peasantry is comfortable ; but many of the Musalmán proprietors, in their disdain of personal toil, have carried sub-division of shares to such an excess that they have sunk into a position more impecunious than that of the labouring class. Until lately, the non-proprietary cultivators held their lands by customary tenure, at low fixed rates, which were not liable to enhancement ; but the *zamíndárs* have now begun to exercise their legal right of raising the rent, and the labourers are fast losing their customary privileges. Many estates have been transferred to new proprietors since the Mutiny ; and, unfortunately, in a large number of cases they have fallen into the hands of money-lenders, who are usually absentees, and make very indifferent landlords.

The landed estates of Saháranpur District are all held under *zamíndári*, *pattidári*, or *bháyachára* tenures. *Zamíndári* tenures are those in which the whole land is held and managed in common, and the

rents and profits of the estate are thrown into one common stock and divided among the several proprietors, whose rights are estimated according to fractional shares. Perfect *pattidari* is that tenure wherein the whole lands are held in severalty by the different proprietors, all of whom are jointly responsible for the Government revenue, though each is theoretically responsible only for the quota represented by the proportion of the land he holds. *Bhayachara* or imperfect *pattidari* is where portions of the land are held in severalty, and portions in common, with a joint responsibility for the Government demand. In this case, the revenue is primarily made up from the rents of the common lands, and the remainder by a cess proportioned to the holdings in severalty, and calculated either by custom or on a fixed scale.

Of the total male adult agricultural population (176 194) of Saharanpur, 51,651 are returned as landholders, 901 as estate servants, 79 929 as cultivators, and 43 713 as agricultural labourers. Average area cultivated by each male adult agriculturist, 4 68 acres. The total population, however, dependent on the soil numbers 477,847, or 48 78 per cent of the District population. The total Government land revenue assessment, including local rates and cesses levied on the land, amounted in 1881 to £139,100, or an average of 3s 5½d per cultivated acre. Rental paid by cultivators, £197,524, or an average of 4s 9½d per cultivated acre. Rents are still to a great extent paid in kind, and in 1882 only 57 per cent of the tenants paid in cash. The best lands rent at from 10s 6d to 12s an acre, and the poorest from 3s 9d to 4s 6d, average rates, from 7s 6d to 9s. Wages have risen about 60 per cent during the past ten years, owing to the large demand for labour on the canals and railways and at the Rûrkî workshops. In 1884, bricklayers and carpenters received from 7½d to 9d per diem, blacksmiths, 7½d, common labourers, 3d. The ordinary prices of food grains in 1884 were as follows—Wheat, 20 *sers* the rupee, or 5s 7d per cwt, barley, 24½ *sers* the rupee, or 4s 6½d per cwt, *joar*, 27 *sers* the rupee, or 4s 2d per cwt, gram, 27 *sers* the rupee, or 4s 2d per cwt, best rice, 8½ *sers* the rupee, or 13s 3d per cwt, and common rice, 11¼ *sers* the rupee, or 9s 6d per cwt.

Natural Calamities—The capricious rainfall in the mountain tract to the north often causes sudden floods on the Ganges and the Jumna, yet inundations of importance seldom occur. Villages, however, are sometimes transferred from one bank to the other by shifting of the channel, as many as 330 being liable to fluvial action in some one or other of its forms. Drought visits the District with great severity, famines due to this cause having occurred in 1837, in 1860, and in 1868-69. On the last occasion, almost all the autumn crops were lost, except in the irrigated region, the area of which exceptionally in

creased by 40,995 acres. In July and August 1869, the price of *joár* and *bájr*a rose as high as 8 *seers* the rupee, or 14s. per cwt. Relief measures were undertaken early in that year, and for 77 days an average of 2948 persons were employed upon famine works, while 161 persons received gratuitous aid at poorhouses. These figures show that the distress was not nearly so severe as in neighbouring Districts. The opening of the Sind Punjab and Delhi Railway, during the scarcity, contributed to allay the danger of starvation. The spread of irrigation has done much to secure Saháranpur from the extremity of famine in future years; while, as regards communications, it compares favourably with any District in the North-Western Provinces.

Commerce and Trade, etc.—The commerce of Saháranpur is chiefly confined to its raw materials, and especially to food-grains, in which it possesses a thriving and increasing trade. Its manufactures consist of coarse cloth, jewellery, sweetmeats, wood-carving, and leather-working. There are several cotton-pressing mills. The Rúrki workshops, recently transferred by the Government to a private company, employ over 1000 workmen. Among the articles produced are steam-engines, pumps, printing presses, lathes, and mathematical instruments. Besides its direct value as a source of income, this establishment is of great importance as a training school for native artisans. The Thomason Civil Engineering College, also situated at Rúrki, is a most useful institution; in 1871, no fewer than 112 students qualified for the public service. A large horse fair is held here every year, in connection with which an agricultural exhibition was established in 1881. A large annual horse fair is also held at Hardwár. The District is well supplied with means of communication. The Grand Trunk line of the Delhi and Punjab Railway runs for a distance of 42 miles within its boundaries, with stations at Deoband, Saháranpur, and Sarsáwa. A branch of the Oudh and Rohilkhand Railway now also forms a junction with the Punjab line at Saháranpur. There are also several excellent metalled roads, one of which leads by a tunnelled passage to Dehra. Total length of roads in 1883-84, 417 miles. Much traffic passes by the Ganges Canal. The Thomason College contains an English printing press, and there are three native presses in the District.

Administration.—In 1806, the land revenue amounted to £33,522; by 1850, it had risen to £105,844; and in 1883, it reached the sum of £118,066. The increase is due in great part to the benefits derived from canal irrigation. The other principal items of revenue in 1883-84 were—Stamps, £17,432; excise, £11,876; provincial rates, £14,568; assessed taxes, £4071; and registration, £1552. The District is under the civil jurisdiction of the *munsifs* of Saháranpur and Deoband, from both of whom appeals lie to the Judge of Saháran-

pur In 1883 there were 14 civil and revenue and 20 magisterial courts open. The regular and town police in 1883 numbered 861 officers and men, or 1 policeman to every 257 square miles and every 1135 inhabitants. The cost was £8043, of which £5539 was defrayed from provincial revenue. The regular force was supplemented by 1727 village watchmen (*chaukidars*), or 1 to every 567 inhabitants. In the same year, 1046 persons were convicted for all offences, being 1 person in every 936 of the population. Saharanpur contains 1 District and 2 subsidiary jails, the average daily number of prisoners in which was 312 in 1883, of whom 6 were females.

Education has been spreading slowly of late years. In 1860 there were 399 schools, with 5639 pupils, taught at a cost of £1559. In 1871 the number of schools had fallen to 381, but these had a total roll of 7934 children, while the sum expended on education had risen to £3674. In 1883-84 there were altogether 166 schools under inspection by the Education Department, attended by 5133 pupils. This is exclusive of private and uninspected schools, for which no materials exist. But the Census Report of 1881 returned 8176 boys and 352 girls as under instruction, besides 24,928 males and 524 females able to read and write, but not under instruction. There is an excellent school in connection with the American Presbyterian Mission, and the towns of Deoband and Saharanpur are noted for their superior Arabic and Persian schools. The District is divided into 4 *tahsils* and 15 *parganas*, which contained 2066 estates in 1883-84, each paying an average Government revenue of £57 per annum.

Medical Aspects—The climate of Saharanpur is the same as that of the Doab generally, modified by its northern position and the cool breezes from the neighbouring hill country. The cold weather arrives earlier and lasts longer than in the lower Districts, but the summer months are tropical in their excessive heat. The mean monthly temperature at Rurki in the north of the District, near the Siwalik Hills, for a period of 19 years ending 1881 was as follows—January, 56° 3' F, February, 60° 8' F, March, 70° 2' F, April, 81° 5' F, May, 87° 6' F, June, 90° 5' F, July, 84° 9' F, August, 83° 8' F, September, 82° 7' F, October, 75° 1' F, November, 64° 3' F, December, 57° 0' F, average for the year, 74° 6'. The average rainfall at Saharanpur town for a period of about 35 years is returned as follows—January, 1.32 inch, February, 1.49 inch, March, 1.19 inch, April, 0.42 inch, May, 0.78 inch, June, 4.46 inches, July, 12.45 inches, August, 9.46 inches, September, 3.87 inches, October, 0.47 inch, November, 0.17 inch, December, 0.50 inch, total, 36.58 inches. Rurki, from its nearer proximity to the hills, has a rainfall averaging about 5 inches heavier than that of Saharanpur town. Fever and small pox are the principal

diseases of the District. The total number of deaths registered in 1883-84 was 29,946, or at the rate of 29·62 per thousand, as against an average of 38·03 per thousand for the previous five years. Seven dispensaries in 1883-84. afforded medical relief to 981 in-door and 54,710 out-door patients. [For further information regarding Saháranpur, see the *Gazetteer of the North-Western Provinces*, vol. ii., Meerut Division, part i., pp. 130-334, by Mr. E. T. Atkinson, C.S. (Allahábád Government Press, 1875). Also *Report of the Settlement of Saháranpur District* between 1857 and 1863, by Mr. Vans Agnew, published 1870; the *Census Report of the North-Western Provinces and Oudh* for 1881; and the several annual Administration and Departmental Reports of the Government of the North-Western Provinces.]

Saháranpur.—North-western *tahsil* of Saháranpur District, North-Western Provinces, lying between the Siwálik Hills and the river Jumna (Jamuná), and comprising the four *pargandás* of Saháranpur, Faizábád, Muzaffarábád, and Haraura; watered by the Eastern Jumna Canal, and traversed by the Sind Punjab and Delhi Railway. Area, 618 square miles, of which 441 square miles are assessed for Government revenue, and 353 square miles are cultivated. Population (1872) 253,606; (1881) 292,293, namely, males 155,318, and females 136,975. Increase between 1872 and 1881, 38,687, or 15·2 per cent. in nine years. Classified according to religion, there were in 1881—Hindus, 176,269; Muhammadans, 113,563; Jains, 1829; and ‘others,’ 632. Of the 472 towns and villages in the *parganá*, 300 contain less than five hundred inhabitants; 128 between five hundred and a thousand; and 43 between one and five thousand. The only place with upwards of five thousand inhabitants is Saháranpur town (59,194). Government land revenue, £33,315, or including local rates and cesses levied on land, £37,418. Rental paid by cultivators, including rates and cesses, £67,244. In 1883, Saháranpur *tahsil* contained (including head-quarter courts) 3 civil and 10 criminal courts, 5 police circles (*thánás*), a regular police force of 203 men, and a rural police or village watch of 459 *chaukidárs*.

Saháranpur.—City, municipality, and administrative head-quarters of Saháranpur District, North-Western Provinces; situated in lat. 29° 58' 15" N., and long. 77° 35' 15" E., on a low site on both sides of the Damaula Nadí. Population (1872) 43,844; (1881) 59,194, namely, males 31,506, and females 27,688. The Muhammadans, although they form only 32·3 per cent. of the District population, predominate largely in Saháranpur town, where they number 32,449, or 3·3 per cent. of the total District population. Hindus number 24,854; Jains, 1277; Christians, 562; and ‘others,’ 52. Municipal income (1883-84), £4299, of which £3786 was derived from taxation, mainly octroi.

The city lies in a low and moist situation, and until recent

drainage reclamations were effected, was exposed to the malarious influences from an unwholesome marsh on the west. About one half the houses are built of brick or masonry, and the number of substantially built dwellings and shops is annually increasing. The principal market place is a scene of busy trade. The station of the Sind Punjab and Delhi Railway, opened to Sahāranpur in 1869, is the place of departure from the railway for travellers to the hill sanitarium of Mussoorie (Masuri). A branch of the Oudh and Rohilkhand Railway from Moradābād to Saharanpur was opened throughout early in 1886. Besides the District head quarters courts and offices, the principal official buildings consist of the *tahsil*, an old Rohilla fort now used as an office, police station, post office, dispensary, telegraph office, and jail. St Thomas' Church was consecrated in 1858. Two or three hotels and a travellers bungalow are situated near the railway station. A handsome new mosque, on the plan of the Jama Masjid at Delhi, has been erected within the last few years by the Muhammadan community, who, besides being the most numerous, form the most influential body. Saharanpur is the head quarters of the Jumna Canal Establishment, the site of a mission of the American Presbyterian Church, and a station of the Great Trigonometrical Survey. The trade of the town, which is considerable, consists chiefly in grain, sugar, molasses, and country cloth. The Government botanical gardens, established in 1817, cover an area 3000 feet long by 2000 feet broad, and are laid out with many fine walks and carriage drives. A large horse fair and an agricultural exhibition, steadily increasing in importance, is held every spring. Sahāranpur was long notorious for malarious diseases, but the drainage operations and other sanitary works have effected a very marked improvement in this respect.

Sahāspur (*Sahispur*)—Town in Dhampur *tahsil*, Bijnaur (Bijnor) District, North Western Provinces, situated in lat $29^{\circ} 7' 40''$ N, and long $78^{\circ} 40' 15''$ E, on the Moradābād and Hardwar road, 28 miles south east of Bijnaur town. Population (1881) 6338, namely, Muhammadans 5134, and Hindus 1204. Bi-weekly market. A speciality of the town is the weaving of a superior quality of cotton cloth, in pieces 5 yards long by 1 yard wide, which sell for 10s. Station on the northern extension of the Oudh and Rohilkhand Railway.

Sahāswān—*Tahsil* and town in Budaun District, North Western Provinces.—See SAHISWAN.

Sahatwār—Town in Bānsdih *tahsil*, Ballia District, North Western Provinces.—See MAHATWAR.

Sahāwar—Town in Kasganj *tahsil*, Etah District, North Western Provinces, 24 miles north east of Etah town. Population (1881) 4065, namely, 1793 Hindus and 2272 Muhammadans. Police station, school, post office. Founded by Rājā Naurang Deb, a Chauhān.

Rájput, who called it Naurangábád after his own name. On being attacked by the Musalmáns, the Rájá fled to Sirhpura, and the inhabitants who remained were forcibly converted to Islám. Shortly afterwards, Naurang, assisted by the Rájá and the people of Sirhpura, expelled the Musalmáns, and changed the name of the town to Saháwar. The place is now far from flourishing; small local *bázár*, bad communications. Tomb of Faiz-ud-dín, a *fakír*, forms the only object of interest. Police station, post-office, and village school. A small house-tax is raised for police and conservancy purposes.

Sahet Mahet (or *Srávasti*).—A vast collection of ruins in Gonda District, Oudh; situated in lat. $27^{\circ} 31' N.$, and long. $82^{\circ} 5' E.$, on the south bank of the Rápti river, 10 miles from Balrámpur, and 6 from Ikauna. These ruins have been identified by General Cunningham as the remains of the ancient city of Srávasti, whose site had been conjecturally fixed by Lassen within a few miles of the spot, but on the opposite bank of the river. The following account has been prepared by Mr. W. Hoey for the present edition of *The Imperial Gazetteer*.

The name Srávasti is said to have been given to the city by an eponymous founder, a mythical king Srávasta of the Solar race. A connection has been suggested between the name of the city and that of the river, but without good grounds. We have the Sanskrit names Srávasti for the city and Airavati for the river, standing side by side with the Pali names Sawatthi and Aciravati respectively. The latter appears softened in the form Ahiravati which the Rápti bears in its course through the hills. The same name appears as Irawadi in Burma. Airavati was the name of Indra's female elephant.

Nothing is known of Srávasti till the time of Buddha, when it appears as an important city, the capital of Uttara Kosala. The king was then Parasenáditya, son of Aranemi Brahmadatta. This king had a son named Jeta by his Kshattriya wife Varshika; but he married a second time a Bráhman slave girl, Mallika, of Kapilavastu, by whom he had a son, Virudháka, who succeeded him. It is probable that she also bore him another son, Seger Sandalitu, who eventually became king in Tibet. Parasenáditya's treasurer was Sudatta, surnamed Anathapindika because of his charitable care for fatherless children. He, during a visit to Rájágriba, met Buddha and was converted to the new faith, returned to Srávasti, purchased a garden from prince Jeta, prepared to build a *vihára* for the master's reception, procured the deputation of Sariputta to superintend the erection, completed it, and finally induced Buddha to come and receive the gift for the Order. Jeta had meanwhile declared for the new creed and added to the building, so that when Buddha came he named the monastery Jetavana Anáthapindikáráma, 'Jeta's garden Sudatta's pleasure ground.' The coupling of the two names has continued to this day in all Buddhist writings.

Sudatta is known in the Pali books as 'Mahasetthi,' the great treasurer (*setthi*) *par excellence*. Now, if we insert this name, we read, 'Jetavana Mahasetthi ārama' or, dropping the superfluous words, as we drop 'church' or 'chapel' when speaking of St Paul's, St Margaret's, and so on, we have the place named Jeta Mahasetthi. It is not hard to see how this eventually shortened into Set Mahet. This was the ancient name, and people still speak of the ruins of the Jetavana as Set. It was this name which was recorded in the settlement maps after annexation, and it is so written in the village records.

The Jetavana was one of the most famous, as well as one of the most sacred, places in Buddhist eyes, because Buddha here spent many of the periods of retreat in his long career. The two chief tenements within the garden enclosure were the Gaudhakuti and the Kosamba Kuti, both of which seem to have been identified by General Cunningham with propriety. Recent excavations have exposed many other undoubtedly ancient buildings, and show that there is a large field which would amply repay research. Near the place where probably stood the eastern gate, there has been opened a *stupa* which contained the begging pot and alms bowl, and also the ashes of a monk. The last were found in a porcelain bowl enclosed in a casket. These seem to be the ashes of Sariputta, the great apostle and the architect of the Jetavana. We learn from Tibetan sources that he died at Nalanda in Lower Bengal. He was cremated. The disciples brought his ashes, pot, and bowl to Buddha, who carried them to Srāvastī, and gave them to Sudatta, whom he instructed to build a *stupa* over them.

Buddha found many teachers of rival faiths and philosophies already established at Srāvastī. Their names and something of their tenets are known, but the most important was Nirgrantha Jñātaputti, the Mahavira of the Jains. It is not exactly clear that he ever met the last named in the course of controversy, but he met the others and worsted them. One of the distinguished teachers, Purna Kātyāya, committed suicide. Jainism lingered on in Srāvastī after Buddhism had vanished, and, as the Jains allege that their third patriarch Sobhnāth or Somnāth was born here, and they have a clinging veneration for a mound called after him, they still make pilgrimages occasionally to the spot. During recent excavations, this mound was opened, the walls of certain old buildings exposed, and many images were found. Other Jain temples were found not far off. All these Jain remains are within the city. The famous Jetavana lies wholly without the city, and it is not unlikely that it was the existence of other faiths already dominating the popular mind which placed Sudatta under the necessity of buying a garden outside the city for which he had to pay gold coins sufficient to cover the area he needed. It is clear that Srāvastī was not only the capital of a kingdom, but the centre of free thought and philosophic speculation.

It was at Srāvastī that Visakha Mátawī, the standing type of the noble Buddhist matron, lived. She built a *vihāra* for Buddha here. It was also here that Devadatta died during an attempt he made on the master's life ; and here two remarkable attempts were made to blast Buddha's reputation by charges of incontinency. And it was also here that he made his most remarkable conversion, that of Angulimāla. Any one reading the Buddhist scriptures cannot fail to be struck with the number of discourses, rulings, and precepts delivered at Srāvastī, nearly all at the Jetavana. The Jatakas, or birth-stories, told by Buddha are in all 498, and of these 416 were told at Srāvastī, and of these 416 not less than 410 in the Jetavana.

Parasenādyita was a staunch friend of Buddha ; but his son Virudhāka usurped the throne, and combined with Ambharisha, the prime minister's son, to persecute the Buddhists. To this they were led by a desire to gratify private resentment against the Sakyas of Kapilavastu. Virudhāka marched out with an army to wreak his wrath, but Buddha succeeded in inducing him to retreat. A second time he went unopposed to the Sakya town, effected an entry by fraud, massacred the people, and brought away 500 youths and 500 virgins. He slew the former and tried to force the latter to enter his harem, but they would not : so them too he slew near the walls of Srāvastī.

Buddha now foretold that within a week Virudhāka and Ambharisha would be burned up. Virudhāka signalized his return to Srāvastī by murdering Jeta. He then built himself a pleasure house in the waters of a tank and stayed there with Ambharisha and his women, for as he thought long enough. On the last day the women had left, and the king and his companion were about to leave, when the rays of the sun, acting through a magnifying glass, which was lying on a cushion, set fire to it and to the pavilion. In the conflagration the king and his evil adviser perished. Thus closed this line of sovereigns.

In the second century B.C., the Buddhist patriarch Rahulata died at Srāvastī, and the Jetavana is said to have supplied a sect of doctors to the Fourth Buddhist Synod ; but we know nothing of the history of the city until Fa-Hian visited it in 410 A.D. It is true that between 275 and 319 A.D. a king of Srāvastī is mentioned named Khiradhar, and his nephew is said to have succeeded him, but they cannot have had any power. Fa-Hian found about 200 families living in the city. Hiuen Tsiang, who visited the place in the beginning of the seventh century, found it completely reduced to ruin, and only a few monks lingering at the deserted monasteries.

From this period all knowledge ceases. Local tradition connects Suhar Deo, who successfully opposed Sálār Masáúd at Bahráich, with Sahet Mahet ; but tradition is here very lame. The *Saulat-i-Masáúdi*, which gives the only account we have of this campaign, clearly describes

Suhar Deo is belonging to Sujhāuli, and the same book mentions Rai Saet as a separate individual. Besides this, a stone bearing a long Sanskrit inscription, which was discovered in the course of recent excavations, gives a line of nine kings ending with Suhirdah (of which Suhar Deo is clearly a corruption), and their capital, though not yet clearly read, is certainly not Sahet Mahet, but will probably be found to be Guwārich.

The following more ornate account is quoted from Mr W C Benett, C S, in the *Oudh Gazetteer*, pp 281-286. It is not necessary to agree with all Mr Benett's dates and statements, in order to appreciate his work. See also General Cunningham's *Geography of Ancient India*, pp 407-414 (ed 1871).

'The foundation of the city is attributed to Srāvastā, an old king of the Solar-race, the ninth in descent from Manu, at a time beside which the most ancient myths are comparatively modern. From him was derived the name Srāvastī, which appears in the Prākṛit forms Sawattha, Sāvanta, and Shrávanta, and has since been corrupted into Sahet. Though the words do not at first look alike, it is probable that the names of the river and the town, Sahet Mahet and Rāptī, were once the same, viz. Sharāvati, and derived from Savitrī, the sun god. At the mythical era of the *Rāmāyana*, Srāvastī was the capital of Uttar Kusala, the northern province of Rama's empire, which, on the division of the kingdom at the death of that hero, fell to the share of his son Lava. At the commencement of the historical age, in the 6th century before Christ, we find it still one of the six principal kingdoms of Madhyadesha or Central Hindustān. It was then bounded on the south by Saketa, or Ajodhya, and on the east by Vaishali, the modern Behar and Benares, so it probably contained at least the present Districts of Bahraich, Gonda, Basti, and Gorakhpur. The king, Parasenāditya, who is given in the *Vishnu Purāna* as great grandson of Buddha, and who was very probably connected in race with the princely prophet, was an early convert to the new faith, and invited its founder to the Kalandaka Vihara in the Venuvana at Srāvastī. Here, or in Ajodhya, Buddha spent the greater number of the rainy seasons, during which he used to rest from his missionary labours, nor did he finally leave the place till he started on that journey to Bengal which ended in his attainment of nirvāna. During his lifetime, Sudatta, the prime minister, built the Jetavana, a magnificent monastery, whose ruins lie to the south west of the capital. On the death of Parasenāditya, his son Virudhāka succeeded, and showed himself a bitter enemy to the faith, he crowned many acts of oppression by including 500 Buddhist virgins in his harem. For this it was predicted that on the seventh day he should be consumed by fire. To falsify the prophecy, he and his court spent the day in boats on the pond to the south of the city, but

the waters fled back, the earth yawned, and the guilty monarch disappeared in a supernatural flame.

'From' this time, Srāvasti remained one of the principal seats of Buddhist learning; and 12 centuries afterwards, the Chinese pilgrim collected with reverence the traditions of his faith which lingered round the sacred city. At the end of the 2nd century B.C., Rahulata, the sixteenth of the Buddhist patriarchs, died here after having imparted his secret lore to the king's son, Sānghananadi; and at the Fourth Buddhist Synod, convened by the so-called Emperor Kanishka, the Jetavana furnished one of the three principal sects of Sthavíras or Buddhist doctors.

'The greatest political importance ever reached by this State was in the reign of Vikramáditya, who, in the middle of the 2nd century A.D., overthrew the mightiest king in India, the Ghaváhana of Kashmír; and as ruler of a vast dominion stretching from Pesháwar to Málwá, and from Málwá to Bengal, assumed with some show of right the title of Emperor of Jambudirpa or the Indian continent. Contrary to the traditions of his capital, he was a bigoted adherent of the Bráhmānical religion; and the legends connected with his rebuilding of the sacred places at Ajodhya and Debi Pátan show how low the fortunes of that creed had fallen in these parts when he lent it his powerful support. Both were a complete jungle, and he restored the localities of the birth of Ráma and of his passage to heaven by measurements from the *Rámáyana*. His identifications probably are the base of the topography of the present day. The remains of this monarch's tank and temple still exist at Debi Pátan. His death appears to have been followed by open disputes between the rival faiths; and the story that a distinguished Buddhist, Vasubandhu, worsted the Bráhmāns in argument, may refer to a more material victory, especially as we find that his still more distinguished predecessor, Man or Nita, had been worsted in argument by the Bráhmāns under Vikramáditya.

'The Ajodhya tradition,' says Mr. Benett, 'preserves the correct story of the fall of this dynasty. It relates that after a glorious reign of eighty years, Vikramáditya was visited by a Jogi, Samudra Pál, who, after exhibiting several remarkable miracles, induced the monarch to allow his spirit to be temporarily transferred to a corpse. The royal body was no sooner vacant than Samudra Pál projected his own spirit into it, and refused to evacuate. By this disreputable trick, he obtained the throne of Ajodhya and Srāvasti, which he and his descendants retained for 17 generations. The fact contained in this singular legend is that Samudra Gupta, who reigned for the first forty years of the 3rd century A.D., overthrew the local dynasty and himself reigned in their stead. The period of eighty years, as the duration of the rule of Vikramáditya and his descendants, is exceedingly probable; and it is

singular, though much weight cannot be attached to the coincidence, that from Samudra Gupta to Gayáditya, the last of the Aditya monarchs of Kanauj, there are exactly seventeen names of the great Vaisya Emperors who governed Northern India

'The Chinese pilgrims did not, of course, omit to visit so sacred a city Fa Hian in the commencement of the 5th century found it inhabited by 200 poor families, and the grand building in decay, and 150 years later, when Hiuen Tsiang arrived, the desolation was complete, and only a few monks haunted the ruins

'It was destined, however, to recover for a while before it finally disappeared from history, and it is here that I must refer to its connection with the origin of a third religion, that of the Jains The third of their Tirthankáras, Shambhú Nath, was born at Sávatthi, both his immediate predecessors and both successors were born at the neighbouring city of Ajodhya. There is still a small Jain temple dedicated to Sobha Náth I have no doubt that Sobha Nath and Shambhu Náth, Sávatthi and Sravasti, are the same, and that this was the birthplace of the third Tirthankára The eighth of these supernatural beings was born at Chandrapur, and this place is always identified in local tradition with Sahet Mahet, as I shall have occasion to remark when I come to the *Mahábhārata* legend Since the best authorities differ by about 1500 years as to the probable date of these patriarchs and their very existence is a fair subject for doubt, I shall not venture to conjecture on their connection with the rise of a strong Jain kingdom in the 9th and 10th centuries Of this dynasty little more is known than of that of Vikramáditya, one great victory throws them into the full light of history, and an interesting legend accounts for their downfall Local tradition gives the following list of names —(1) Májura Dhvaja, (2) Hansa Dhvaja, (3) Makara Dhvaja, (4) Sudhanya Dhvaja, (5) Suhral or Suhel Deo or Dal These are diversely reputed to have been either Thirus, or of some Rajput house Considering the almost certain origin of the modern Rájputs, the two accounts may both be true, but as they were Jains, some confusion about their caste is easily intelligible What is utterly baffling is that the second and fourth are the heroes of one of the episodes of the Drigvijaya section of the *Mahábhārata* The only monarch who is really historical is the last, whose capital was at Srávasti, and who had a fort at Asokpur or Hatla or Raza, about half way on the road between Gonda and Faizabád The tradition connecting him with Dumbria Dih is clearly transferred from the recollections of the subsequent Dom dynasty When Sálár Masáud crossed the Gogra, he met Suhel Dal at Hatla, and the Jains were apparently defeated, though the place is still revered as the scene of the martyrdom of a distinguished Muhammadan officer The invaders pushed to the north, and, if tradition is to be believed, fought another great battle under the walls

of Sahet Mahet, which contains the tomb of another martyr. Finally, after a long occupation of the country, the decisive battle was fought at Bahraich, where the Musalmáns were completely exterminated. In the indecisive conflicts and prolonged encampment in a hostile country, in all, in fact, but its denouement, the story bears a strong resemblance to that of the Pathán conquest of Utraula in the time of Sultán Sher Sháh Súr.

'It is related that only about forty years after this victory the Jain house fell. The last king, whose name is not given, was passionately devoted to the chase, and returned one evening just as the sun was setting. It would have been a sin to eat after sunset, and the queen, in order to secure the royal supper, sent up to the roof the exceedingly beautiful wife of his younger brother. The experiment succeeded, and the sun stayed to enjoy the sight as long as she stood there. When the feast was over, she descended, and the sun at once disappeared. The astonished king inquired the cause, and was determined to see with his own eyes the wonder-working beauty. His incestuous passion was punished by the ruin of his State, and amidst a terrific storm the whole city was turned bottom upwards. The modern name Sahet Mahet, says the legend, is descriptive of this inversion. This story is valuable as putting beyond reasonable doubt the first religion to which these kings belonged—the inability to eat after sunset, which is the point on which the whole turns, being derived from the Jain reluctance to sacrifice insect life.

'The chronology is also not without its value, and I have no doubt points to the conquest of the country by the first of the great Rahtor kings of Kanauj, Srí Chandradeva. In the last half of the 11th century, he made a pilgrimage to Ajodhya and Kusála (*i.e.* Gonda); and with a Kshattriya prince, pilgrimage is often another word for military expedition—"na Kshattriya ka bhagat na músal ka dhanuk"—"You cannot make a saint of a Kshattriya, or a bow of a rice pestle." An inscription of his descendant, the ill-starred Jái Chandra, has been found at Ajodhya.

'With the Ghori conquest of India, the history of Sahet Mahet comes absolutely to an end, and it only remains for me to notice one more local legend. Everywhere in the neighbourhood, it is told that the real name of the city before its overthrow was Chandrikápurí or Chandripur; and that it was here that Hansa Dhwája reigned, and Arjuna gained his very unheroic victory over the brave and beautiful Sudhanía.

'All that now remains of this once famous city is the great fortress on the banks of the Rápti, with a smaller ruin to the south-west, a lofty mound due south on the Balrámpur and Bahraich road, and numerous small piles of bricks, probably the remains of ancient *stupas*,

scattered here and there within a distance of 2 miles of the main city. The fortress is in shape a semicircular crescent, with the concave side facing the river, and is completely surrounded by solid brick walls, the highest remains being to the west, where the ruins of the river bastion are still 50 feet in height. The ordinary walls vary from a greatest elevation of 40 feet on the western front to a lowest of 20 feet along the east and south east. The interior is covered with jungle, so dense in parts as hardly to admit of the passage of an elephant, and broken into undulations by the remains of temples and palaces underneath. All the principal buildings were in the western half, and it is there that the undergrowth is the thickest, only ceasing along two or three broad streets which have been left bare, and indicate the chief features of the old city. The main street runs right through the centre, and is built so as to command a view of the great mound Orá Jhár from one end to the other. To the south it debouches by one of the principal gateways, and at the north it ends in a small square, containing among other lofty remains the two principal mounds, which may be identified with the Sudattas house and the Angulimati, a *stupa* mentioned by Hiuen Tsiang. The dense brushwood, and the possibility that the city which he saw may have been considerably altered by the later Jain dynasty, renders the application of that traveller's descriptions a difficult and hazardous task, but I am inclined to conjecture that his palace of Parasenaditya was situated among the mounds of the south eastern corner, where now stands the small Jain temple.

The next principal building mentioned by him, both in his *Life* and in the *Siyu ki*, is the Hall of the Law built by that monarch for Buddha, which would have been situated between the palace and the main street while Prajapati's Vihara would have formed the whole or part of the long and even line of buildings which face the west of the street. The north west corner of the ruin contains a large open space with a small pond in its centre, and a nearly straight road running from it to another southern gateway, and converging with the main street on the Orá Jhár. The eastern half has no very important remains, though the surface is broken everywhere with the *debris* of houses, and it was here probably that the common people had their quarters. The walls are pierced with numerous gateways, the principal being at either end of the main street and the north eastern bastion, and in the middle and southern corner of the west wall.

At the distance of half a mile from the south west gate, and separated from the main town by swamps, which probably mark the course of the old moat, is another considerable ruin, identified by Hiuen Tsiang with the old Jetavana, one of the most famous monasteries in India. It is a singular fact that this feature is exactly repro-

duced in the remains of Rāngi in Rāi Bareli, where a similar oblong ruin lies at the same distance and direction from the main town. The remainder of the Chinese pilgrim's measurements seem to have been taken from this point; but it is difficult to select among the numerous mounds the remains of the great Vihāra and its rival the idol temple. Nearly a mile to the east of the Jetavana is the high congeries of bricks known, as is the Mani Parbat at Ajodhya, by the name Orā Jhār or "basket shakings," and supposed to be the place where Rāma's labourers emptied out their baskets of earth. This is identified with some probability by General Cunningham with the Purvavarāma built by the lady Vaisākha in honour of Buddha. The top is protected by the tombs of two Muhammadan saints, but General Cunningham cleared one of the sides, and found four pilasters of an exceedingly ancient style of architecture. From the fact that two of the chief thoroughfares of the city so converge as to command a view of this mound, I should conjecture that it was more ancient than the plan of the present remains, and consequently one of the oldest monuments left in the neighbourhood. As yet very little is known of this very interesting ruin, which must contain relics that would do much to elucidate some of the darkest and most interesting periods of Indian history. I was once able to spend a few days in excavating, and dug more than 20 feet deep into the crown of the Angulimatia *stupa*; but beyond disclosing a square building of 24 feet each way, with a partition wall down the centre, and a second wall running all round the building at a distance of 4 feet, I discovered nothing of interest. It is somewhat difficult to get labourers, as the neighbouring villagers have a superstitious dread of interfering with the old city, and will not even enter it after sunset. A storm of thunder and lightning, which came on when I encamped there on a second occasion, was interpreted as a manifest token of the demons' displeasure with the man who had violated their haunts.'

Sāhibganj.—Town in the Dāman-i-koh tract of the Santāl Parganās District, Bengal; situated in lat. $25^{\circ} 14' 30''$ N., and long. $87^{\circ} 40' 3''$ E., on the deep channel of the Ganges, which at all seasons runs close under the town, and contiguous to the station on the loop-line of the East Indian Railway. Owing to its favourable position, Sāhibganj, although only founded so recently as 1862, has become of late years a great depôt for the exchange of traffic between the river and the rail, and has attracted to itself trade before localized at Bhāgalpur, Pirpainti, Rājmahāl, and other marts of less note. Population (1881) 6512, namely, Hindus, 4776; Muhammadans, 1424; and 'others,' 312. Municipal income (1883-84), £685; incidence of taxation, 1s. 0 $\frac{3}{4}$ d. per head. In 1876-77, the total registered trade of Sāhibganj was valued at more than £450,000, including exports, imports, and in many

cases re-exportations. Local produce is received by river from the trans-Gangetic tracts of North Malda, Purniah, and Bhágalpur, while European goods come up by rail from Calcutta, to be distributed in the same Districts. In 1876-77, the principal items under the former head were—indigo, £86,000, oil seeds, £38,000, rice, £28,000, hides and stone, £27,000 each, wheat, £17,000 and under the latter head—cotton piece goods, £38,000, salt, £12,000.

A registration station was first established at Sáhíbganj in 1872, to ascertain the amount of river traffic passing along the Ganges between Lower Bengal on the one hand and Behar and the Upper Provinces on the other. During the three years 1872-74 the average number of laden cargo boats passing Sáhíbganj both ways was about 33,000, the total weight of the cargoes amounted to about 10 million *maunds*, or say 360,000 tons a year. The down stream traffic is by far the larger of the two, especially during the latter half of the year, when the river is in flood. Nearly half the down stream traffic consisted of the single item of oil seeds, which amounted to nearly 100,000 tons a year, sent chiefly from the Behar marts of Revelganj and Patná. Next came wheat, pulses and gram sugar and saltpetre but none of these exceeded 20,000 tons a year. The up stream traffic predominates during the first half of the year, the boats being often towed up by rope from the bank, assisted by sails. The chief cargoes were rice about 100,000 tons a year, and salt, 40,000 tons. In 1876-77 the total number of boats that passed the registration station was 43,020, thus classified—up-stream, 12,379 laden and 9179 empty, down stream, 18,419 laden and 3043 empty.

Sáhíbganj—Civil station of Gayá District, Bengal. Lat. $24^{\circ} 47' 58''$ N, long $85^{\circ} 2' 45''$ E. Adjoins GAYA TOWN, of which it forms a part. Total population of Gayá with Sáhíbganj (1881) 76,415, namely, Hindus, 60,181, Muhammadans, 16,161, Christians and 'others,' 73. Municipal income (1883-84), £5971.

Sáhíbganj—Village in Muzaffarpur District, Bengal situated on the river Bayá, a spill channel of the Gandak, from which it is about 4 miles distant, 30 miles north west of Muzaffarpur town. Large *bázars*, with trade in oil seeds, wheat, pulses, and salt, exported by means of the Gandak, chief manufacture, shoes. Two schools. Roads to Motiháti, Motipur, and Lilganj.

Sáhíbganj—Village and produce depot in Rangpur District, Bengal. Trade in rice and mustard seed.

Sáhíbganj—Village and police station in Bardwán District, Bengal. Lat. $23^{\circ} 26' 20''$ N, long $87^{\circ} 52' 45''$ E. Population (1881) under 5000.

Sáhíbganj—Village on the river of the same name in Bákarganj District, Bengal. Exports of rice, molasses, and *sundri* wood, imports of salt, oil, tobacco, cloth, and pulses.

Sáhibi (*Sabi*).—Hill stream in Gurgáon District, Punjab; rises in Rájputána near the Sámbar Lake, flows through the Riwári tract, and empties itself into the Najafgarh *jhíl* or lake on the borders of Delhi District. It frequently submerges the land near the foot of the hills, which thus becomes extremely rich and fertile. The water is utilized by means of numerous dams, which force it to spread over the face of the country, and check the violence of its course near the hills.

Sahispur.—Town in Bijnaur (Bijnor) District, North-Western Provinces.—See SAHASPUR.

Sahiswán.—*Tahsíl* of Budáun District, North-Western Provinces, stretching inward from the north bank of the Ganges, and comprising the *parganá*s of Sahiswán and Kot. Area, 473 square miles, of which 328 square miles are returned as cultivated. Population (1881) 192,131, namely, males 103,861, and females 88,270; average density of population, 406 persons per square mile. Classified according to religion, Hindus number 163,018; Muhammadans, 28,962; Jains, 107; and 'others,' 44. Of the 441 towns and villages in the *tahsíl*, 333 contain less than five hundred inhabitants; 75 from five hundred to a thousand; 31 from one to five thousand; and 2 upwards of five thousand inhabitants. Land revenue (1881-82), £21,364, or including local rates and cesses levied on land, £23,980. In 1884, Sahiswán *tahsíl* contained 1 civil and 1 criminal court; number of police circles (*thán*s), 3; strength of regular police, 50 men.

Sahiswán.—Town and municipality in Budáun District, North-Western Provinces, and head-quarters of Sahiswán *tahsíl*; situated in lat. 28° 4' 20" N., and long. 78° 47' 20" E., about a mile from the left bank of the Maháwa river, 20 miles from Budáun town. Population (1872) 17,063; (1881) 14,605, namely, males 7375, and females 7230. Classified according to religion, there were in 1881—Muhammadans, 7715; Hindus, 6855; Christians, 30; and 'others,' 5. Municipal income (1883-84), £708, of which £584 was derived from taxation; average incidence of taxation, 9½d. per head. Tri-weekly markets are held on Mondays, Thursdays, and Saturdays. Good unmetalled roads connect the town with Gunnaur, Bisaulí, Bilsí, and Ujhání; but the trade of the place is inconsiderable, and there is no manufacture. The *keora* or screw-pine is largely cultivated in the neighbourhood for the sake of the scent that is extracted from its flower. The public buildings include a masonry bungalow, used as a residence and court-house by District officers on tour; a *tahsíl* office, *munsif's* court, distillery, good *sardái*, Government charitable dispensary, school-house. A large mound marks the site of an ancient fort, said to have been built by one Rájá Sahasra-Báhu.

Sáhiwál.—Town and municipality in Sháhpur *tahsíl*, Sháhpur

District, Punjab, and former capital of a native chief Situated in lat. $31^{\circ} 58' N$, and long $72^{\circ} 22' E$, on the left bank of the Jehlam (Jhelum), 20 miles south of Sháhpur town Founded, according to tradition, by Gul Bahlak, one of the ancestors of the Baluch chiefs who held the neighbouring country until the time of Ranjit Singh Population (1881) 8880, namely, Hindus, 4813, Muhammadans, 3881, and Sikhs, 186 Number of houses, 2130 Municipal income (1883-84), £784, or an average of 1s $9\frac{1}{2}$ d per head of the population The town is badly built, and surrounded by a stagnant marsh, which gives rise to much malaria, but strenuous efforts have been taken to abate this evil Sáhíwál carries on a brisk trade in cotton, grain, and *gñi* with Multan (Mooltan) and Sukkur (Sakkar), and is one of the chief commercial towns in Shahpur District The merchants act as bankers and money lenders for the cultivating classes, while many of them farm estates on their own account Manufactures of hardware, of turnery in wood and ivory, and lacquered ware Town hall, dispensary, police station, school house, *sarai*

Sahpau — Town in Sádábád *tahsil*, Muttra (Mathura) District, North Western Provinces, situated in lat $27^{\circ} 26' 13'' N$, and long $78^{\circ} 10' 49'' E$, 7 miles west of Sadabád town, and close to Jalesar road station on the East Indian Railway Population (1881) 3635 Police station and post office Bi weekly markets on Sundays and Wednesdays A small house tax is raised for police and conservancy purposes

Sahuks — Petty State in the Jhaláwár division of Káthiáwár, Bombay Presidency, consisting of 1 village, with 1 tribute payer Area, 6 square miles Population (1881) 920 Estimated revenue, £265, of which £51, 18s 10 is paid as tribute to the British Government, and £6, 10s to the Nawáb of Junagarh

Sahyadri — Mountain range in Bombay Presidency The term Sahyádri is applied to the entire system of the WESTERN GHATS (*qz*) from the Gápti river to Cape Comorin, but more especially to the ranges in the coast Districts of the Deccan The Sahyádri hills in this sense commence in Khándesh District, and run south and south west, as far as Goa, with scattered continuations to the Pál Ghát Ratnágiri may be taken as an example of the coast Districts The range here forms the continuous eastern boundary, running parallel to the sea It varies in height from 2000 to 3000 feet, though some of the peaks attain an altitude of 5000 feet The summits of the Sahyádri hills, both above and below the main range, are often crowned or girded by large massive basaltic rocks These, with little aid from art, can be made fortresses most difficult to reach, and to look at, almost impregnable Many of them have springs of the finest water, and in all a supply can be secured in cisterns and reservoirs The Sahyádris are

crossed by numerous passes, and by a few made roads constructed by the British Government. On the crest of these passes, the scenery is grand. Mountains rise behind mountains three or four thousand feet high, covered with trees, except where the black rock is too solid even for the hardiest shrub to take root. Both at the opening and the close of the south-west monsoon, tempests and thunder-storms are common. West of the Sahyádrí hills, which on that side rise precipitously from base to crest, the country is comparatively low, and the plateaux are seldom more than 500 feet above the sea-level. The lower hills are for the most part bare and treeless. The east face of the Sahyádris gradually slopes down to the table-land of the central plateau of the Madras Presidency, from 1000 to 3000 feet above sea-level.

The Sahyádrí hills in their geological relations have a wider application, and include, as stated above, the whole Western Gháts from the Tápti to Cape Comorin in the extreme south of the peninsula. The authors of the official *Geology of India* (Messrs. Medlicott and Blanford) have described the Sahyádrí hills in this sense as follows:—‘The Sahyádrí range consists to the northward of horizontal or nearly horizontal strata of basalt and similar rocks, cut into a steep scarp on the western side by denudation, and similarly eroded, though less abruptly, to the eastward. The highest summits, such as Mahábaleshwar (4717 feet), are perfectly flat-topped, and are clearly undenuded remnants of a great elevated plain. South of about 16° N. lat., the horizontal igneous rocks disappear, and the range is composed of ancient metamorphic strata. Here there is in some places a distinct connection between the strike of the foliation and the direction of the hills; but still the connection is only local, and the dividing range consists either of the western scarp of the Mysore plateau, or of isolated hill groups, owing their form apparently to denudation. Where the rocks are so ancient as those are that form all the southern portion of the Sahyádrí, it is almost impossible to say how far the original direction of the range is due to axes of disturbance; but the fact that all the principal elevations, such as the Nilgiris, Palnis, etc., some peaks of which rise to over 8000 feet, are plateaux and not ridges, tends to show that denudation has played the principal share in determining their contour. The southern portion of the Sahyádrí range is entirely separated by a broad gap (the PALGHAT, *q.v.*), through which the railway from Madras to Beypur passes.’ See also the article GHATS (Western).

Sai.—River of Oudh, rising in Hardoi District in lat. $27^{\circ} 10'$ N., and long. $80^{\circ} 32'$ E. (Thornton), between the Gúmíti and the Ganges. It flows in a tortuous south-easterly direction through Oudh, passing Rái Bareli and Partábgarh towns, enters the North-West Provinces in Jaunpur District, and falls into the Gúmíti on its right or south bank a

few miles below Jaunpur town Navigable in the rains for country boats of 10 tons burden as far as Rái Bareli town Captain Wilford mentioned that this river 'is called *Sambu* and *Sukti*, and in the spoken dialects, *Sye*, because it abounds with small shells' This is really the case, as I have repeatedly observed while surveying or travelling along its banks They are all fossil, small, and embedded in its banks, and appear here and there when laid bare by the encroachments of the river, they consist chiefly of cockles and periwinkles' Wilford identifies the *Sai* with 'the *Sambus* of Megasthenes,' but the *Sambus* is mentioned by Arrian as a tributary of the *Jumna* Arrowsmith's old map of India, '50 kos to the degree,' compiled chiefly from military sources, showed a cross communication between the *Sai* and the *Gumti* some distance above Lucknow This does not appear in later maps

Saidábád—*Tahsil* in Muttra District, North Western Provinces—
See SAYYIDABAD

Saidápet—*Taluk* or Sub division of Chengalpat (Chingleput) District, Madras Presidency Area, 342 square miles Population (1881) 204,580, namely, males 102,676, and females 101,904, occupying 29,558 houses, in 3 towns and 271 villages Hindus number 189,475, Muhammadans, 9266, Christians, 5723, and 'others,' 116

The general appearance of the country is flat and uninteresting, with here and there ridged or conical hills of no great elevation The soil is of various qualities, being, as a rule, better in proportion to its distance from the sea Sandy, red, ferruginous, and alluvial soils represent the degrees of progressive fertility Weaving is carried on in several villages In one or two villages red handkerchiefs and Muhammadan cloth are manufactured for export, chiefly to Penang and Singapur Surrounding, as it does, Madras city, the Saidápet *taluk* is well supplied with roads The chief are the Great Southern Trunk Road, the High Western Trunk Road, and the Great Northern Trunk Road The Madras and South Indian Railways also traverse the *taluk* Water carriage is not wanting through the low lying sandy tract on the coast, the Buckingham Canal runs along the whole length of the coast

In Saidápet *taluk* are situated the Red Hills and Chembrambákam tanks—See MADRAS CITY The Red Hills tank or reservoir, which affords the main water supply to Madras city, is distant 8 miles from Madras The tank itself derives its supply from the Cholavaram tank, which in its turn is fed by an embankment across the Cortellár river, 22 miles from Madras The Chembrambákam tank is a large irrigation reservoir about 14 miles from Madras, formed by an embankment 7100 yards in length, connecting high ground on one side with a rocky spur on the other It is provided with 8 irrigation sluices, and with 3 masonry

weirs aggregating 1192 feet in length, while its capacity is 2799 million cubic feet, and the area of its water-spread 8.95 square miles. The tank is an old native work, and the improvements consist of the extension of its capacity, and the increase of its water-supply. The chief sources of its supply are from anicuts across the Cortelliár and Cooum rivers. In 1883-84, the area irrigated and revenue derived was—first crop, 12,868 acres; revenue, £3982: second crop, 5652 acres; revenue, £1511: total revenue, £5493. The surplus revenue of the year was £2454.

In 1883-84, the Saidápet *táluk* contained 1 civil and 4 criminal courts; police circles (*thánás*), 10; regular police, 223 men. Land revenue, £25,892.

Saidápet (*Sydapet*).—Chief town and administrative head-quarters of Chengalpat (Chingleput) District, Madras Presidency, and a station on the South Indian Railway; situated in lat. 13° 1' 32" N., and long. 80° 15' 40" E., 5 miles from Madras city. Population (1881) 4917, inhabiting 568 houses. Hindus numbered 4655; Muhammadans, 199; and Christians, 63.

The well-known Government model farm at Saidápet was established in 1865, under the Governorship of Sir William Denison. From the beginning it was fortunate in the appointment of Mr. Robertson as its first superintendent. Many important agricultural experiments have been made, and some have produced encouraging results, indicating the general direction in which improvements can be effected in the agriculture of the Madras Presidency. Attention has been given to subsoil drainage, improved tillage, the restoration of exhausted soils, and the proper utilization of irrigation water; the fertilization of arable soils by the use of lime, saltpetre, oil-cake, poudrette, and other manures available in Southern India, but now unused by the *ráyats*; the introduction of new crops, suited to the climate of India and adapted for cultivation under an improving agricultural practice, such as maize, Sorghum *saccharatum*, Carolina rice, Guinea grass and other grasses, New Orleans cotton and other superior varieties of cotton, tobacco, etc.; the production of live fences, in view of affording protection, shelter, and fuel; the introduction of water-lifts, barn machines, carts, ploughs, cultivators, cattle hoes, reaping knives, etc., of improved construction; and the improvement of similar kinds of machines and implements now in use in this country; improvement of the live-stock of the country by careful breeding and feeding, and by acclimatizing new breeds, etc.

In order to extend the practical utility of these experiments, a school of agriculture was opened in connection with the farm in 1876. A class of 30 pupils joined in the first year, of whom 9 came from the Bombay Presidency. A handsome building, used

as an agricultural college and museum, has been erected. A chemical laboratory is attached to it, and a veterinary hospital has been opened. Income from the Saidápet farm (1883-84), £4546, expenditure, £9221, showing a loss to Government of £4675. The farming operations at Saidápet have now been given up by Government, except so far as required for the practical instruction of the pupils in the agricultural school.

Saidnagar—Town in Jaláun District, North Western Provinces—*See* SAYYIDNAGAR.

Saidpur—*Taluk* in Shikárpur District, Sind, Bombay Presidency—*See* SAYYIDPUR.

Saidpur—Town in Farídpur District, Bengal—*See* SAYYIDPUR.

Saidpur—*Tahsil* and village in Gházípur District, North Western Provinces—*See* SAYYIDPUR.

Saidwála—Town in Montgomery District, Punjab—*See* SAYYID WALA.

Sáifganj—Town in Purniah District, Bengal, situated in lat $25^{\circ} 32' N$, and long $87^{\circ} 37' 36'' E$, 20 miles distant from Purniah town. The population of Sáifganj itself is under 2000, but it is closely surrounded by suburban villages, which bring up the total number of inhabitants to about 10,000. The town contains a vernacular school, and a police outpost, there are also 3 Muhammadan mosques, a Hindu *math* or temple built in 1822, and two old tanks excavated in 1807 and 1822 respectively. The value of rice annually exported from Sáifganj is estimated at £25 000, and that of mustard at £5000, the number of blankets annually manufactured is valued at £600. Sáifganj was founded about 150 years ago by the Nawáb Sáif Khan, and is now one of the most populous places in Purniah. It is the head quarters of the sheep breeding trade of the District.

Sáifganj Pirwaha—Village in Purniah District, Bengal. Lat $26^{\circ} 13' 55'' N$, long $87^{\circ} 15' 51'' E$, 38 miles distant from Purniah town, and 16 from Basantpur.

Sailána (*Sillána*)—Native State in the Western Málwá Agency, Central India. Area, 114 square miles. Population (1881) 29 723, namely, males 15 579, and females 14,144, occupying 6128 houses, in 69 villages. Hindus number 19,910, Muhammadans, 1508, Jains 901, Sikhs, 15, Bhils, 7169, Moghúás, 212, and Míráás, 8. Estimated revenue of the chief, £14 800, *jágirs*, £11,640, lands held for charitable purposes, £13 920. This State originally formed a part of RATLAM. On the death of Kesari Singh, Rájá of Ratlam, in 1709, his eldest son, Mán Singh, succeeded to the lands forming the present State of Ratlam, and Jái Singh, his second son, to Sailána. An annual tribute of £4200 was formerly paid to Sindhrí but is now assigned to the British Government in part payment of the Gwalior Contingent, under

the same conditions as the tribute of Ratlam. The present Rájá of Sailána, Dúli Singh, is a Rahtor Rájput, and was born about 1838. He receives a salute of 11 guns. The military force of the State consisted, in 1881–82, of 3 field guns, 15 artillerymen, 40 horse, and 225 foot. In 1881–82, 1207 *maunds* of opium and 199 *maunds* of cotton were produced.

Sailána (Sillána).—Chief town of Sailána State, Western Málwá Agency, Central India. Situated 12 miles north-west of Ratlam, and 6 miles west of Namli station on the Málwá line of the Rájputána-Málwá Railway. Lat. $23^{\circ} 30' 30''$ N., and long. $75^{\circ} 0' 45''$ E. Population (1881) 4224. Post-office and dispensary.

Sailu.—Town in Wardhá District, Central Provinces.—*See SELU.*

Sáin.—Mountain range in Sirmur (Sarmor) State, Punjab, lying between $30^{\circ} 37'$ and $30^{\circ} 51'$ N. lat., and between $77^{\circ} 15'$ and $77^{\circ} 29'$ E. long. Thornton states that its length is about 25 miles, running from north-west to south-east. This range divides the basin of the Julal from that of the Giri. Estimated elevation above sea-level, from 6000 to 8000 feet.

Sáinkherá.—Town in Gádarwára *tahsíl*, Narsinghpur District, Central Provinces. Population (1881) 2549, namely, Hindus, 2331; Muhammadans, 116; Jains, 8; and non-Hindu aborigines, 94.

Saint George, Fort.—*See MADRAS CITY.* Lat. $13^{\circ} 4' 45''$ N., long. $80^{\circ} 20'$ E.

Saint Thomas' Mount (Farangi-malai).—Town in Saidápet *táluk*, Chengalpat (Chingleput) District, Madras Presidency; the headquarters of the old Madras artillery, and still one of the most important military stations in the Presidency. Lat. $13^{\circ} 0' 18''$ N., long. $80^{\circ} 14' 11''$ E. Population (1881) 15,013, namely, 7404 males and 7609 females. Hindus number 10,645; Muhammadans, 1902; Christians, 2416; and 'others,' 50. Number of houses, 2264. The town possesses a fine church, several chapels, numerous military buildings, including a handsome artillery mess-house, post-office, and cantonment magistrate's court. It is a pretty place, and well kept. The *bázár* and native huts are hidden away to the eastward, which adds to the favourable impression made on the visitor who sees it for the first time. The church, standing at the southern end of the parade-ground, is one of the best-looking edifices of its kind in the country. It is seated for 500 men and 80 officers and their families. There are, besides, a Wesleyan chapel at the foot of the Mount steps, a Roman Catholic chapel for the European troops, and another small Roman Catholic church, 74 feet long by 25 wide, built in 1764 by the boatmen of Madras, and dedicated to the 'Presentation of the Blessed Virgin.' The soil is gravelly, and the health of the station is exceptionally good, epidemic cholera being of rare occurrence. The garrison consists of 2 field

batteries, with a half battery of garrison artillery, and a detachment of Native infantry

The 'Mount' itself is a granite and syenite rock, about 220 feet above sea level, overlooking the cantonment. The ascent is made by a flight of some 200 steps. On its summit stands the curious old Portuguese church of 'The Expectation of the Blessed Virgin'. This is built over the spot where the Portuguese in 1547 discovered the celebrated Mount Cross, attributed to the legendary evangelism of Saint Thomas. Lucena gives the following account of the finding of the Cross — 'It was met with on digging for the foundations of a hermitage amid the ruins which marked the spot of the martyrdom of the Apostle Saint Thomas. On one face of the slab was a cross in relief, with a bird like a dove over it, with its wings expanded as the Holy Ghost is usually represented when descending on our Lord at His baptism, or on our Lady at her Annunciation. This cross was erected over the altar at the chapel which was built on the new sanctuary.' Dr Burnell (*Indian Antiquary*, 1874 p 313) says 'This account is, no doubt, accurate, for the Portuguese on first visiting the mount found the Christian church in ruins, and occupied by a native *fakir*. The description of the slab is also accurate. It does not appear what cause had destroyed the Christian community here, but it probably was owing to the political disturbances attending the war between the Muhammadans of the north and the Hindu kingdom of Vijayanagar.' Referring to an Italian account (in the 17th century) of the Cross and the Mount festival, Dr Burnell continues 'The cross is built into the wall behind the altar in a church on the Great Mount, which is served by a native priest under the Goa jurisdiction. An annual festival is held here, which brings a large assemblage of native Christians to the spot, and causes an amount of disorder which the European Catholic clergy of Madras have in vain tried to put down.'

In Anglo Indian history, and notably in the wars of the Karnatik, Saint Thomas' Mount was a place of great importance. The battle fought here on the 7th February 1759 was one of the fiercest struggles of the Franco British wars in India. It is thus described by Mr Crole — 'Colonel Calliaud had been summoned from the south to assist in raising the siege of Madras. He took post at the Mount, with his right at a deserted little temple at the north east of the present parade-ground, and his left supported by a house called Carvalho's garden, where he posted four pieces of cannon. His troops included the contingent brought by the Company's partisan Muhammad Isaf, and consisted of 2200 horse, 2500 foot, and 6 cannons. Of these, however, only 1500 natives, 80 Europeans, and 12 artillerymen were possessed of the slightest discipline. Lally's forces aggregated 2600, half of whom were Europeans, and all disciplined. He had, besides, 8 guns,

possessing a great superiority in weight of metal. The fight lasted from early morning till five P.M., when the enemy, to Colonel Calliaud's intense relief, retreated. The latter had ammunition sufficient to have lasted for about a couple of minutes more.' 'On the 20th March 1769, Haidar Ali, who had marched within 5 miles of Madras, met Mr. Dupré, the senior Member of Council, and here the disgraceful treaty of the 2nd April was signed. In 1774, at the suggestion of Colonel James, the Mount was established as the headquarters of the artillery. The garrison of the Mount formed the major part of the force (under Sir Hector Munro) that ought to have saved Baillie in 1780. During its absence, only five companies of Sepoys and 4 guns had been left for the protection of the Mount, and a temporary earthwork was raised to strengthen the place against attack. This has long been levelled, but a slight depression crossing the plain midway between Palavaram and the Mount indicates the position of what went by the name of the Maráthá Ditch.'—*Chengalpat District Manual*, p. 73.

According to Dr. Burnell, the date of the cross tablet and its Pehlevi inscription is probably about the 8th century.

Saint Thome (*Maláipur, Mylapore*).—Suburb of MADRAS CITY (*q.v.*). Lat. $13^{\circ} 2' N.$, long. $80^{\circ} 19' E.$ Known as Little Mount, where, according to tradition, St. Thomas, the Apostle of India, was martyred, and on which stands a Roman Catholic church.

Sáipur.—Town in Unao District, Oudh.—*See* SAFIPUR.

Sáiri.—Village in the Simla Hills, in a part of the Patiala hill territory; situated in lat. $31^{\circ} 6' N.$, long. $77^{\circ} 6' E.$, on a ridge crossed by the road from Kálka and Kasauli to Simla *viâ* Subáthu, 10 miles from Simla station. Staging bungalow. Elevation above sea-level, 4971 feet.

Sakala.—Ruins in Jhang District, Punjab.—*See* SANGALA.

Sakaldiha.—Town in Chandauli *tahsil*, Benares District, North-Western Provinces; situated in lat. $25^{\circ} 20' 28'' N.$, long. $83^{\circ} 19' 08'' E.$, 6 miles north of Chandauli town, and 20 miles east of Benares city. Population (1881) 2880, mostly Muhammadans, Bráhmans, and Barhaulia Rájputs. Markets are held on Mondays and Thursdays, for the sale of grain, cloth, vegetables, fish, sweetmeats, and brass and iron vessels. The town also contains a considerable number of shops, a fort built by Achal Singh, four sugar manufactories, two mosques, four temples, police station, post-office, and English and Hindu schools. The Sakaldiha station on the East Indian Railway is 2 miles distant from the town. A small house-tax is raised for police and conservancy.

Sákar Pathár.—Sanitarium in Poona (Puna) District, Bombay Presidency; situated 4 miles south of Lonauli station on the south-east extension of the Great Indian Peninsula Railway. Sákar Pathár is

a raised plateau 3000 feet above sea level. The plateau is extensive and fairly wooded, with good building sites on the west, close to the edge of the Sahyadr hills. The water supply is from a little lake on the plateau, with an area of three acres. The lake is calculated to hold about 3,000,000 gallons, or 12,000 gallons a day for 250 days. In 1883, Government sanctioned the establishment of a sanitarium at Sâkar Pathâr, and leases were granted on the same terms as those at Matheran. No applicant is to be allotted more than one site, and each is bound to build a house within three years or to forfeit his claim.

Sakeswar (*Sukesar*)—Mountain in Khushâb *tahsil*, Shâhpur District, Punjab, the highest peak in the SALT RANGE. Situated in lat 32° 33' N, long 71° 58' E, 25 miles east of Miânwâli town. A fine well wooded hill, forming the terminal point in which two divergent spurs of the range reunite. Upon its summit stands the sanitarium for Shâhpur and Miânwâli, at an elevation of 5010 feet above sea level, with plenty of excellent building space available. Wild olive trees are abundant, and the oak thrives well. According to daily meteorological observations made by the Civil Surgeon of Shâhpur between the middle of June and the middle of October 1866, the average temperature of Sakeswar was 75° F, or one degree less than summer heat in England. The climate of Sakeswar, and indeed of the whole of the higher parts of the Salt Range, is believed to be well adapted for Europeans, and very favourable in cases of dysentery and phthisis, which, as a rule, do not derive any benefit in the Himâlayan sanitarium. The great drawback to Sakeswar is the scarcity of good drinking water. There are, however, many places in the neighbourhood where excellent water is procurable, and by having recourse to tanks, a sufficiency of water could be stored for a considerable number of people.

Sakhar—Sub-division, *tâhuk*, and town in Shikârpur District, Sind, Bombay Presidency—See SUKKUR.

Sakhera (or *Sankheda*)—Town in Baroda State, Bombay Presidency. Population (1881) 4661. The only object of interest is an old fort which surrendered to a small force of British troops in 1802. Customs house, Gujarâthi school, and two *dharmshtas*. The calico printing and dyeing of Sakhera have a local celebrity, and considerable taste is shown in wood carving.

Sakhi-Sarwar—Famous Muhammadan shrine in Derâ Ghâzi Khan *tahsil* and District, Punjab. Lat 30° N, long 70° 10' 30" E. The shrine crowns the high bank of a hill stream, at the foot of the Sulaimân range, in the midst of arid desert scenery, 'well adapted for the residence of those who desire to mortify the flesh.' Founded in honour of Saïdî Ahmad, afterwards known as Sakhi Sarwar, the son of an immigrant from Baghdâd, who settled at Sirkot, 12 miles east of Multân, in the year 1220. Saïdî Ahmad became a devotee, and having performed a

very remarkable series of miracles, was presented by the Delhi Emperor with four mule-loads of money, with which the Sakhi-Sarwár shrine was erected. A handsome flight of steps leads from the bed of the stream to the building, constructed at the expense of two Hindu merchants of Lahore. The buildings include—the mausoleum of Sakhi Sarwár himself; a monument of Bába Nának; the tomb of Massamát Bíbí Bhái, wife of Sakhi Sarwár; and a *thakúrdwára*. They thus comprise a curious mixture of Hindu and Muhammadan architecture, and are frequented by devotees of all religions. The guardians of the shrine are the descendants of Sakhi Sarwár's three servants, among whom the revenues accruing from the offerings are divided in 1650 shares, the descendants of one servant receiving 750 shares, of another 600 shares, and of the third 300 shares. Throughout the year, the shrine forms the resort of numerous mendicants, Hindu and Muhammadan.

Sakit.—Ancient and decaying town in Etah District, North-Western Provinces. Lat. $27^{\circ} 26' 10''$ N., long. $78^{\circ} 49' 15''$ E. Population (1881) 5435, consisting of 3809 Hindus and 1626 Muhammadans. Sakit stands on an isolated site, 12 miles south-east of Etah town. Its hill was once crowned by a fort; but now only the remains of a large mosque, erected in the 13th century, testify to the former supremacy of the Muhammadan element. On the highest part of the existing town rises a half-finished modern temple, remarkable for its Saracenic arches, supported on slender pillars of richly carved Agra stone—an ambitious work commenced by a commissariat servant (who enriched himself during the Sikh war), but died before its completion. The town clusters around this temple, which, from its conspicuous position, forms a landmark for many miles around. The principal road enters Sakit over a ravine by a fine new bridge, constructed out of the foundations of the old fort. Handsome *bázár*, lined by good shops with flat and pointed ornamental fronts. Trees line the roadway and afford a pleasant shade. The *sardí* is now in ruins; the roof of the old mosque is broken down; and the water of the handsome well has become brackish. New brick-built police station on the site of the old fort; post-office; Anglo-vernacular school. Small trade in cotton, grain, and indigo seed. Numerous inscriptions on mosques. Bahlol Lodi died at Sakit in 1488; and Ibráhim Lodi planted a colony of Kont Musalmáns here in 1520.

Sakkampattí.—Town in Tenkási *táluk*, Tinneveli District, Madras Presidency. Population (1881) 5945. Hindus number 5559; Muhammadans, 289; and Christians, 97. Number of houses, 1327.

Sakkaraikottai.—Town in Rámnád *táluk*, Madura District, Madras Presidency. Lat. $9^{\circ} 21'$ N., long. $78^{\circ} 55'$ E. Population (1881) 3464, dwelling in 501 houses.

Sakleshpur (lit. 'town of the fragmentary Ishwara')—Municipal village in Hassan District, Mysore State, situated in lat $12^{\circ} 57' 20''$ N, and long $75^{\circ} 50' 31''$ E, on the right bank of the Hemavati river, 23 miles west of Hassan town. Population (1881) 1354. Head-quarters of the Manjarábád *táluk*, and the centre of the coffee trade. The Hemavati is here crossed by an iron girder bridge, carrying the road by which the coffee of the highlands is borne to the seaport of Mangalore.

Sákoli—Eastern *tahsil* or Sub division of Bhandará District, Central Provinces. Area, 2033 square miles, with 2 towns and 823 villages, and 54,363 houses. Population (1881) 272,481, namely, males 135,362, and females 137,119. Deducting an area of 697 square miles, comprising 17 *samindáris* or petty chiefships, with a population of 41,731, the area of the British portion of the Sub division amounts to 1336 square miles, with 2 towns and 608 villages, and 46,444 houses. Population 230,750, namely, males 114,177, and females 116,573, average density, 172.7 persons per square mile. The total adult agricultural population (male and female) in 1881 numbered 77,414 in the Government lands, the average area of available cultivated and cultivable land being 6 acres for each adult agriculturist. Of the total Government area of 1336 square miles, 384 square miles are held revenue-free, while 952 square miles are assessed for Government revenue, of which 420 square miles are cultivated, 179 square miles are cultivable, and 353 square miles are uncultivable waste. Total amount of Government land revenue in 1883, including local rates and cesses levied on land, £16,952, or an average of 1s 2½d per cultivated acre. Total rental paid by cultivators, including rates and cesses, £27,163, or an average of 1s 11½d per cultivated acre. Sákoli *tahsil* contained in 1883, 1 civil and 1 criminal courts, with 3 police circles (*thánas*) and 7 outpost stations, a regular police force numbering 108 men, and a village watch or rural police (*chaukidárs*) numbering 794 men. Sákoli village is situated in lat $21^{\circ} 15'$ N, and long 80° E.

Sakrand—*Táluk* of the Naushahro Sub division, Haidarabád, (Hyderábád) District, Sind, Bombay Presidency. Area, 1390 square miles. Population (1872) 53,566, (1881) 52,075, namely, males 27,947, and females 24,128. Hindus number 3950, Muhammadans, 45,694, Sikhs, 2406, Christians, 2, and aboriginal tribes, 23. Number of houses, 9216, in 111 villages. Much of the land in the eastern portion is covered with sandhills. Revenue, £1624. The *táluk* in 1882-83 contained—criminal courts, 2, police circles (*thánas*), 5, regular police, 32 men. Area assessed for land revenue, 42,305 acres, under actual cultivation, 35,847 acres.

Sakráypatna (or *Silrepatna*)—Village in Kadúr District, Mysore State, situated in lat $13^{\circ} 26'$ N, and long $75^{\circ} 58' 5''$ E, 15 miles by

road north-east of Chikmagalur. Population (1871) 1866; not separately returned in the Census Report of 1881. The site of an ancient city locally identified with the capital of Rukmangada, a king mentioned in the *Malakshasta*. The objects now extant include—a monument to Honbilla, a watchman whose life was sacrificed in order to preserve the neighbouring **AVYANKERE TANK**: a huge gun: and an immense slab of stone, 12 feet square and several inches thick, supported on four pillars. In historical times, Sakraypatna passed through the hands of several families of local chiefs, until annexed to the Hindu kingdom of Mysore in 1600. A large fair is held weekly on Fridays. At the annual car festival of Ranganath 3000 rams are sacrificed in honour of the god.

Sakri.—River of Bengal, rising in Hazaribagh District, and flowing in a generally northerly direction through Gaya and Patna Districts. In Hazaribagh it has a drainage basin of 810 square miles; and being the central stream in a low well-cultivated valley, it receives from all sides numerous feeders. It has a distinct water system, and preserves its own name while it passes through Gaya and Patna Districts on its way to join the Ganges in Monghyr. Throughout its course it is much used for irrigation.

Sakse.—Fort and Customs Division, Kolaba District, Bombay Presidency.—*See* SANKSHI.

Sakti.—Native State, at the eastern limit of Bilaspur District, Central Provinces, to which it is now attached. Population (1881) 22,819, chiefly Hindus, residing in 117 villages and 3055 houses; area, 115 square miles, of which 41 are cultivated and 47 returned as cultivable waste. Density of population, 198 persons per square mile. Sakti was originally one of the Garhjat States attached to Sambalpur District. It consists of a curved strip of level country, partly open, partly covered with forest, skirting the base of a range known as the Gunji Hills. Chief products—rice, wheat, oil-seeds, and cotton, besides a small quantity of forest produce, consisting of lac, resin, gum, and *makani* fruit. The chief is a Raj-Gond, and pays a tribute of £35. At present, however (1884), the State is under direct British administration. Total revenue for 1883–84, £1680, of which about £1000 was derived from land revenue; expenditure, £1718. In 1872, only 22 persons were returned as able to read and write, or as being under instruction; but since the State has been taken under Government management, a considerable impetus has been given to education, and there are several flourishing village schools. Several good roads connecting the State with neighbouring *amindaris* have been constructed, and are reported to be the best fair-weather roads in Bilaspur. Good dispensary. Sakti town lies in lat. 22° 0' 30" N., and long. 83° E.

Salambha.—Village in Nuh *taluk*, Gurgaon District, Punjab; situated

in the midst of a large saline tract, known as the Nuh *maháls*, near the foot of the Mewát Hills, north of Sonah. The salt formerly manufactured here bore the general name of Salámbha salt, but was produced in ten separate places within this region. It was made by the evaporation of brine drawn from wells together with the washings of saline earth, and was of very inferior quality, containing large amounts of magnesia and other ingredients besides the pure chloride. The total quantity manufactured in 1871-72 was 203,182 *maunds*. The manufacture, however, has now entirely ceased in this tract, the local product having been driven out of the market by the superior and cheaper Sambhar lake salt.

Sálandi (properly *Sálnadi*) —River of Orissa, Bengal, so called from the *sál* forests which it traverses. It rises in the southern slope of the Megháسانی Mountain in Morbhanj State, and in its upper course is a black water river with high banks and a bottom of muddy sand. For miles the Sálandi flows through one continuous grove of palms and bamboos, it is navigable for country boats as high as 6 miles from its junction with the Butarani. Its lower course bifurcates into a network of streams interlaced with those of the Matái, a river bringing down the drainage of the country between the Kánsbáns and the Sálandi, and after a tortuous course falling into the Dhámrá near its mouth. The area of the catchment basin of the Salandi is 250 square miles, the maximum discharge in flood time, 60 000 cubic feet, and the average cold weather discharge, 260 cubic feet.

Saláya —Port in Nawánagar State, Káthiawár, Bombay Presidency. Saláya is the port of Khambháia, from which town it lies about 9 miles north. Population (1881) 2773. It is probably the best port (with the exception of Bombay and Karáchi) on the west coast of India. Owing to the excellence of the harbour, it would make a good terminus for any further extension of the railway. The trade of the country inland would be attracted hither, and shipments might be made direct to and from Europe. The port has two entrances, one between Kárumbhár island and the mainland, narrow and deep, and the other between Kárumbhár and Dháni Bet, about a mile broad. The harbour is perfectly sheltered on the east and north east by Nárerá Bet and Kárumbhár, and to the west and north west by the Dháni Bet. On the north west corner of Kárumbhár island, a lighthouse built of coral, 30 feet high, with an ordinary fixed white light, has recently (1884) been erected by the Nawánagar State. The shores of both the mainland and the island are fringed with large coral reefs. The chief exports are *ghee*, which is usually sent to Cutch, and cotton to Bombay. The imports are cotton seed from Gujarát ports, dates from Basra and Maskat, and timber from the Malabar coast. The port of Salaya was classed among the regular harbours by the Mughal government, and

appears in the list of ports in the *Mirat-i-Ahmadi* as belonging to Islámnagar (Nawánagar). Post-office and vernacular school.

Salbái (*Salbye*).—Village in Gwalior State, Central India; situated 32 miles south-east of the fort of Gwalior, in lat. $25^{\circ} 51' N.$, long. $78^{\circ} 19' E.$ Celebrated for the treaty concluded here in 1782 between the British Government and the Maráthá Confederacy, at the close of the struggle for the Peshwáship which took place after the death of Madhu Ráo Ballal. That treaty provided for the surrender to the Peshwá of Bassein and other territory captured by the British during the war; and the cession to the British of Salsette, Elephanta, Karanj, and Hog islands off Bombay. Under the third article of the treaty, the right of the British to the town and *parganá* of Broach was fully recognised, but these were conferred by Government upon Sindhia in consideration of his services, upon the condition that British trade should be free and unmolested. (*See Aitchison's Treaties and Engagements*, vols. iii. and iv., ed. 1876.)

Sálbaldi.—Village and hill on the Márú river; situated in lat. $21^{\circ} 26' N.$, and long. $77^{\circ} 59' E.$, 5 miles north of Morsi, partly in Ellichpur District, Berar, and partly in Betúl District, Central Provinces. Celebrated on account of two springs, one very cold, the other warm. When Sítá was deserted by Ráma, she is said by local tradition to have come to Sálbaldi, and to have given birth here to two sons, Kusa and Lava. This tradition would identify Sálbaldi as the scene of the hermitage of Valmiki, whither Sítá, when pregnant, was banished by Ráma.

Sálbet (*Shialbet, Searbet, Shalbet*).—Island situated about 2 miles from the coast of Káthiáwár, Bombay, in lat. (centre) $20^{\circ} 54' 30'' N.$, and long. $71^{\circ} 33' 30'' E.$, 8 miles east-north-east of Jafarábád and 17 miles from Mowah Point. The island is in an impoverished state. Population (1881) 289. It is about three-quarters of a mile long on its sea-face, and a little more than half a mile broad. Old fortifications stand on its north-west and south points, the latter being strongly constructed. The island is of sandstone, and is included within the State of JAFARABAD. A well in the centre supplies good water. Sálbet was formerly a famous piratical stronghold, and might, according to Taylor (*Sailing Directory*, p. 360), be made a safe harbour. Such a refuge is much wanted along the south coast of Káthiáwár. After the island of Diu was acquired by the Portuguese, they seem to have established themselves at Sálbet and elsewhere on the coast. When, however, the Portuguese power in the northern part of their dominions was curtailed by the fall of Bassein (1739), they were obliged to withdraw from outlying posts like Sálbet and concentrate their efforts on the defence of Diu.

Salem (*Selam*, properly *Shelam*, which is perhaps a corruption of Chera, the name of the ancient monarchy in which the District was

embraced) —British District in the Madras Presidency, lying between 11° N and $12^{\circ} 54'$ N lat, and between $77^{\circ} 33'$ and $79^{\circ} 6'$ E long Area, 7653 square miles Population, according to the Census of 1881, 1,599,595 persons Salem District is bounded on the north by Mysore (Maisur) and North Arcot, on the east by Trichinopoli, and by South and North Arcot, on the south by portions of Coimbatore and Trichinopoli, and on the west by Coimbatore and Mysore. The administrative head quarters are at SALEM TOWN

Physical Aspects —Except towards the south, the District is hilly, with large plains lying between the several ranges The chief of these ranges are the Shevaroy's (highest point, 5410), the Kalráyans (about 4000), the Melagiris (4580), the Kollimalais (4663), the Pachamalais (about 4000), the Yelagiris (4441), the Jevádis (3840), the Vaththalamais (about 4000), the Erivánis and Valasaimalais (about 3800), the Bodamalais (4019), the Thopur hills, the Thalamalais There are also innumerable detached peaks and smaller ranges

The District has been described as comprising 'three distinct tracts of country, known as the Talághát, the Báramahál, and the Balághát The Talághát division, as its name implies, is situated below the Eastern Gháts on the level of the Kárnátuk generally, and in soil and climate differs but little from the neighbouring Districts of Trichinopoli and South Arcot The Báramahál division includes the whole Salem face of the Ghats and a wide tract of country at their base, and the Balághát is situated above the Gháts on the tableland of Mysore' Of the Hosur taluk, only one half to the north is really Balághát, the southern half lying considerably below the level of the Mysore plateau Hosur itself is about 3000 feet above the sea Dharmapuri is about 1500 feet, and Krishnagiri from 1500 to 2000 feet above sea level Tirupatúr and Uttankarai lie in one basin, and average slightly over 1350 feet above sea level At Salem there is a considerable drop, the town of that name being only 947 feet above the sea The climate is generally dry, and in the northern portions cooler than in the south, the climate of Hosur being as temperate as that of Bangalore

The chief river of the District is the KÁVERI (Cauvery), from the left bank of which a large area in Námakal is irrigated The PALAR only flows through a few miles of the northern corner of the Tirupatúr taluk, where it does nearly as much harm as good, as little use is made of the water, and the town of Vánimbadi lies at the mercy of its floods In 1874, a considerable portion of this town was washed away, and it is only a question of time when the remainder, hitherto preserved at considerable cost, will follow The PENNER, rising in Mysore territory, flows through Hosur and Krishnagiri to Uttankarai, where, near the South Arcot frontier, it is joined from north and south by the Pambár and Vánir, minor streams. The Sanathkumaranadi traverses

Hosúr and Dharmapuri, in the latter *táluk*, near Marandahalli, being tapped with profit to *ráyats* and Government. The fertility of the Atúr *táluk* is chiefly due to the Vasishtanadi and Swethanadi, which flow eastward into South Arcot. There are, besides these, numerous tributaries of the Káveri. A small traffic is carried on the Káveri in basket boats, and timber is occasionally floated down. The water of these rivers is utilized either by anicuts thrown across their beds, or by channels which tap the banks. The channel system is very extensively worked in the Paramathi division of the Námakal *táluk*. The fisheries of the District, although they make a considerable total, are individually insignificant, consisting of the right of fishing in the different Government tanks, which is purchased for sums varying from 10s. to more than £20.

The District forests are of considerable value, but there is some reason to fear that they have been overworked, with a view to immediate profit rather than ultimate revenue. The forests, situated for the most part on the hills or in the valleys formed by them, cover an area of more than 2000 square miles. There is a considerable amount of evergreen forest on the summit of the higher ranges; and on the outer slopes of most of the hills there is a fair amount of deciduous forest, with many valuable varieties of trees. The Jevádi and Yelagiri hills contain some valuable timber, and a large portion of the Shevaroyis is clothed with middling-sized jungle. Sandal-wood is found. The most valuable forest is the belt of *vengai* (*Pterocarpus Marsupium*) on the hilly tracts which fringe the Káveri in the south of the Hosúr *táluk* and towards Pennagaram. Reserves and plantations have been formed for the supply of fuel to the railway, but at the present stage the experiment is not sufficiently advanced to admit of an accurate estimate being formed of its utility. Jungle produce, such as honey, beeswax, bark for tanning and dyeing, soap-nut, fibres, medicinal roots, etc., are collected by the Malayális and other jungle tribes; in some cases this right is rented out. Lac is found in the Hosúr jungles, and both in the hills and on the plains the tamarind is a considerable source of revenue.

Wild animals are daily diminishing in numbers, as each hillman carries a gun and shoots for food everything that comes in his way, regardless of sex, age, or season of the year. Bison and even elephants are occasionally seen on the Jevádis. Leopards and bears are to be found in most of the hilly tracts. *Sámbar* deer may be found towards Pennagaram, and in a few places in the Hosúr *táluk*. Hyænas, antelope, deer of several kinds, wild hog, a species of armadillo, and a few wolves complete the catalogue. Pea and jungle fowl, duck, teal, snipe, francolin, etc., can be had in season.

The geology has been only partially examined. The formation is

mostly gneissic, granite and trap dikes cropping up occasionally. The principal varieties of rock belonging to the gneiss which occur in the eastern part are, in the order of their importance and extent of development—(1) Hornblendic schists and rocks, (2) Quartzo felspathic gneiss, massive or schistose, (3) Talcose and chloritic rocks (generally schistose, rarely massive), (4) Magnetic iron beds, (5) Crystalline limestones. Magnesite veins occur chiefly at the Chalk hills (so miscalled) near the foot of the Shevaroy. Pot stone is found in several places (*Vide* Vol IV, Part 2, *Mem Geo Sur of India*). Magnetic iron occurs in practically inexhaustible quantities. Corundum and chromate of iron are also obtainable. The washings of some rivers yield gold, notably the Penner (more correctly Ponníár, so named on account of its golden sands). It is probable that gold may exist in the Hosur *idluk*, where it borders on Mysore. There is no coal. Lime is available in sufficient quantities to serve as a flux in iron smelting.

History—The ancient history of the northern and southern parts of Salem District must be treated separately, as they formed parts of different kingdoms. The northern part was included in the kingdom of the Pallavas, who flourished in the fifth century A.D., and apparently long before, at their capital Conjevaram. When the Pallavas were finally overthrown by the Chola kings of Tanjore, in the ninth century A.D., this part of the country was the only portion remaining to them of their once extensive kingdom. The Pallavas were the excavators of the monolithic 'Rathas' at the Seven Pagodas, which fact points to the early supremacy of the dynasty. The Buddhist tope at Amravati may also be attributed to this dynasty. The boundaries of their kingdom, when at its zenith, probably extended from the Narbadá and the borders of Orissa on the north to the southern Penner on the south, and on the west from the northern extremity of the Western Ghats to the Bay of Bengal on the east.

The southern portions of Salem originally formed part of the ancient kingdom of Conga. This kingdom was confined within the limits of the present Districts of Salem and Coimbatore. A Tamil manuscript with the title of *Conga desha Rajakkal*, or the 'Chronicle of the Kings of the Conga Country,' professes to give their history from about the commencement of the Christian era down to the beginning of the seventeenth century. The kings enumerated belong to two dynasties, the earlier line being of the Solar, and the later line of the Gangá race. The Solar race began with seven kings of the Ratha tribe, the name of the first being Vira Raja Chakravarti. The capital during this period was Skandápura. Conga, including the south of the modern District of Salem, was a seat of the manufacture of the finest steel from a very early age. It has been conjectured that the

ancient Egyptians used Indian steel for the tools with which they carved their hieroglyphs on obelisks and temples. It is recorded that when Alexander the Great was in India, Porus made a present of steel to him.

Under the second or Gangá dynasty the limits of the kingdom were greatly extended towards the north-west. The list of these kings given in the chronicles agrees, with very few variations, with the pedigree compiled from their published land-grants. The cause of the extinction of the earlier dynasty is not recorded; but probably the last Solar king lost his life in an attack on the Gangá chieftain of southern Mysore, who followed up his advantage by seizing the vacant throne of Conga. The third king of the Gangá dynasty, Hari Varmá, removed the capital from Skandapura to Talkád about 290 A.D.

The second period of the ancient history of Salem extends from the conquest of Conga by the Cholas, down to the rise of the Ballála kings of Karnata, a period of about two centuries. The Ballála kings may be regarded as the rulers of the kingdom from about 1069 A.D. Eight kings of this line ruled over Karnata, which included Salem. The latter District then became tributary to the kings of Vijayanagar about 1350, and continued to form part of their empire till their overthrow in 1565. Even after this downfall, all the southern portion of Vijayanagar was left in the hands of the old kings, forming still a very extensive dominion.

About the beginning of the seventeenth century Salem became a dependency of Madura. It was visited and mentioned by Robert de Nobilis in 1623. During the next century, Salem comes into prominence in connection with Haidar Ali's wars, many of the operations being conducted within the present District. In 1760, Haidar seized the BARAMAHÁL, and made it a rallying point for his troops on their way to the war in Arcot. In 1767, the English, Nizám Ali, and the Maráthás, jointly attacked Haidar, and an English force attempted the reduction of the Baramahál, but without success. Nizám Ali then deserted the English and went over to Haidar. After a period of desultory warfare, confined chiefly to the Baramahál, Nizám Ali made overtures of peace to the English, and by a treaty in 1768 joined them, again abandoning Haidar. During this period the English captured in rapid succession most of the fortified places of Salem and Coimbatore Districts. Subsequently, Colonel Wood, who was in command of the English force, met with a series of reverses; and was superseded by Colonel Lang. This, however, did not prevent Haidar from retaking all the places previously captured by the English, and finally peace was concluded in 1769.

War broke out again with Haidar in 1780, and continued after his

death in 1782. Peace was concluded with his son Tipú in 1784. This only lasted till 1790, when war again broke out, chiefly owing to Tipu's attack on Travancore. An English force under Colonel Kelly invaded the Baramahal, which by the next year was almost completely in the hands of the English. The remaining operations, which were not connected with this part of the country, terminated in the treaty of 1792, by which, among other cessions, the whole of the present District of Salem (except the Hosur *táluk*) comprising what was known as the Talághát and Baramahal, fell to the English. After the final defeat and death of Tipú in 1799 the Hosur *táluk*, known as the Bálaghát, also came into the possession of the English under the provisions of the Partition Treaty of Mysore.

The District of Salem, as at present composed, contains 9 *taluks*, of which two are directly under the Collector, three under the Sub Collector, two form the Head Assistant's charge, and two the charge of the general Deputy Collector. Its limits are now identical with those of 1799 except that the Kangundi *samindari*, north of the Palar, was finally transferred to North Arcot in 1808.

Administrative History — Immediately on the acquisition of the Talághát and Baramahal, Colonel (then Captain) Read was placed in charge, with Captains Graham, MacLeod, and Munro (afterwards Governor of Madras) as his assistants. He at once addressed himself to the survey of the District, and to the introduction of a uniform revenue system, which was fairly launched throughout this portion of the District in 1796, as a *rājatwari* system to be confirmed for ever. This, however, met with no favour at head quarters where the idea of leases on the *samindari* system had been resolved on. The *samindari* system was formerly unknown in Salem, but the Government ordered it to be introduced. In 1799, Read, with Munro as his secretary, followed the tide of war into Mysore, and never returned to the District. A new administrator succeeded them, and so faithfully carried out orders, that by 1805 the *samindari* system was in full force every where, except in the Bálaghát, which escaped owing to its being a recent acquisition, and, after being leased out for two years to two natives, was finally surveyed in 1804 since which time it has prospered. Great losses followed on the overthrow of Read's settlement. The 205 estates paying 16 *laks* of rupees (say £160,000) in 1805 had by 1821 been so reduced in value that they only paid 8 *laks*, which in 1836 fell to 5 *laks*, and in 1850 to 4½ *laks*, or say £45,000.

Various causes, into which it is needless to enter here, were at work to bring about this result, and a series of remedies, unsuccessful because they did not go to the root of the mischief, were tried. Of one thing, however, there can be no doubt, viz that notwith

standing all Read's care and zeal, he had in many cases over-assessed the soil. The *zamíndárs* had, before 1813, to some extent given satisfactory evidence that this was so, by reducing rates on 'wet' lands throughout by one-sixth, and on 'dry' land from one-eighth to one-fifth. The end soon came. Before the *zamíndarí* system had been in existence for five years, those in authority began to hesitate. Their first step in retreat from the false position which had been taken up was made in 1809, when, failing bidders for estates sold for arrears, the Collector was empowered to bring them under his own management, a policy extended in 1813 by permission to buy in such estates at auction on behalf of Government. This politic step was afterwards modified by a restriction of the bid to the amount of the arrears.

On such estates coming under Government management, the District officers had opportunities for more closely studying the causes which led their owners into bankruptcy, consequent on which the conviction became fixed that, to insure stability of revenue, a reduction in the demand was needed. This, however, was only done in a hesitating and partial manner. Thus, in 1816, the assessment in the southern part of the District was reduced generally by 10 per cent.; and in 1818, the Collector was empowered to make a discretionary reduction not exceeding 30 per cent. These benefits touched the *ráyatwárá* lands only, and rightly so; for, apart from the fact that a reversion to the State as the direct landlord is the most important factor in securing prosperity to the tenantry of the District, the *zamíndárs* were even on equitable, much less on legal, grounds entitled to no consideration whatever, as, in fixing the *peshkash* (revenue) payable by them, the cultivated land alone had been taken into account, all the waste being made over free and for ever. In the present day it is hard, with telegraphic communication, and Salem within half a night's journey from Madras, to realize the darkness in which the authorities formerly were as to the state of the District. Even Munro, when Governor of Madras, than whom no one then living took more interest in the District, was ignorant of important changes which had been introduced into the revenue system.

The one thing plainly perceptible to the Madras authorities was that the revenue was diminishing and uncertain; the causes were unknown, or if known, wrong deductions were drawn from the facts. To stimulate the extension of cultivation, the suicidal panacea of the *kául* tenure was resorted to in 1822. *Kául*, ordinarily signifying an agreement of any kind, in the sense in which it is here used, indicates a tenancy under which the *ráyat*, on taking up fresh lands, pays no assessment for the first year, half rates for the second, and full rates for the third year. The terms of the tenancy may vary from this, but the principle is the same. The result was a foregone conclusion.

Rajats already holding over assessed or fully assessed lands snapped greedily at the bait, and for the first two years or more, as the case might be, all went on prosperously, but in the year when Government should have reaped the full benefit of their concession, the *rajats* turned round and relinquished their new holdings. Many were the recipes devised to avert the necessary consequence of the measure. The *kaul* tenure was prohibited unless the *pattā* land was retained, the *rajats* should only resign good and bad lands in equal proportions, and might not cling to the one and despise the other. The system was doomed from its birth, and received its death blow in 1850. As regards the over assessed lands, the percentage reductions of 1816 to 1818, above referred to, affected the whole tract rateably, but had no operation towards effecting a reduction in cases where individual fields or holdings were over taxed. Further reductions, but still only in the nature of a percentage reduction, were made in 1858 and 1859, and in respect of garden lands in 1864. But it was not until 1869 to 1874, when the new settlement now in force was introduced, that the Government demand was universally fixed on equitable and scientific principles. Under this revision, the area under cultivation has risen from 1,050,000 acres, assessed at £173,000, to 1,667,459 acres, assessed at £219,629.

Tenures — The District contains three *pālayams* or *zamindāris* of importance — Sulagiri, Bagalur, and Berikāi all in the Hosur *tāluk*. There are also 148 *mittās* and a few *jāgirs*. But the predominant tenure is *rāyatwārī*, the tenant being liable to ejectment by the Government only in case of failure to pay his revenue. Every year he has the option of throwing up his holding or any field in it, and his assessment is fixed for thirty years. A *mittidār* has the right of collecting the *paimaish tirai* or settled rent, a share of which he pays to Government as *peshkash*. The tenure cannot be reconverted into *raiyatwari*. If the *mittidār* is in arrears, his right to collect the *tirai* can be sold by Government, which does not itself enter the market as a buyer. The *mittidārs* are addicted to leasing their villages, often selling them in shares and the lessees again sub letting, the Hindu system of undivided families multiplies the *mittadārs*, their middlemen, etc., the latter and the sublessees often get into debt, their rights in the villages being sold by the civil courts, Musalman inheritance so works in a couple of generations as to produce, instead of one original *mittidār*, twenty or thirty such, all owning different shares in the village, according to sex and relationship, — these and other causes all combined often render the *raiyat* uncertain as to who his landlord is. Perhaps two or three persons will at one and the same time, under colourable rights, distrain or attempt to distrain his property. For these reasons, the position of the *raiyat* in *mittā* villages is unenviable.

Added to this, he neither shares in the equitable revision of assessment which takes place in Government lands each thirty years, nor in the annual *jamdābandi* remissions, granted by Government when drought, flood, excess of rain, blight, or other accidents impoverish their tenants. If the decision of the civil courts is rightly interpreted to mean that *rāyats* in *mittās* are liable to ejection from year to year, this is not known to the landlords, or if they know it, they do not act on it.

Population.—In 1800, the population was returned at 612,871; in 1835, at 905,190; in 1850, at 1,195,367. Since that time, quinquennial Censuses have been taken; and in 1871, the first regular Census showed a population of 1,966,995, or an average of 5 persons to each house. The last Census, taken on the 17th February 1881, disclosed a total population of 1,599,595; so that in the decade since 1871 there was a decrease of 367,400, or nearly 19 per cent., due to the famine of 1876–78, when Salem was one of the Districts in which the distress was most severely felt. The pressure was felt in every *tāluk*, but the centre of distress was in the Bálāghāt, Hosūr *tāluk* alone losing 31·74 per cent. of its inhabitants. Krishnagiri, Dharmapuri, and Uttankarai *tālucs* lost between 28 and 29 per cent.

The results of the Census of 1881 may be summarized as follows:—Area of District, 7653 square miles, distributed into 9 *tālucs* or Sub-divisions. Classified according to sex, there were—males 778,483, and females 821,112. Classified according to age—under 15 years, boys 301,383, and girls 306,138; total children, 607,521, or 37·9 per cent. of the population: 15 years and upwards, males 477,025, and females 514,897; total adults, 991,922, or 62·1 per cent. of the population: persons of unstated age, 152.

The density of population was 209 persons per square mile, as compared with 257 in 1871. In point of density, Salem ranks as the fourteenth District in Madras Presidency. Number of towns, 14; of villages, 3958; occupied houses, 311,393; unoccupied houses, 33,009. Towns and villages per square mile, 0·519; occupied houses per square mile, 41; persons per occupied house, 5·1.

According to religion, Hindus numbered 1,531,855, or 95·77 per cent. of the total population; Muhammadans, 51,092, or 3·19 per cent.; Christians, 16,567, or 1·04 per cent.; Buddhists, 18; Jains, 46; and 'others,' 17. The majority of the Hindus, in the proportion of 2 to 1, professed the Sivaite as opposed to the Vishnuite faith; the other sects are only fractionally represented. The Sivaites numbered 998,853, and the Vishnuites 506,945. The Hindus were sub-divided according to caste as follows:—Brāhmans (priests), 28,393; Kshattriyas (warrior caste), 3175; Shetties (traders), 22,512; Vellālars (agriculturists), 376,221; Idaiyārs (shepherds), 57,530; Kammālars (artisans),

43,343, Kanakkans (writers), 2529, Kaikalars (weavers), 77,994, Vanniáns (labourers), 391,287, Kushavans (potters), 11,949, Satanis (mixed castes), 40,335, Shembadavans (fishermen), 14,950, Shanans (toddy-drawers), 45,157, Ambattans (barbers), 17,086, Vanans (washermen), 20,142, Pariahs (out castes), 211,856, and 'others,' 167,396

The Muhammadan population by race, as distinguished from descendants of converts, consisted of—Labbays, 5409, Arabs, 9, Mughals, 27, Mappilas, 5, Pathans, 945, Syjids, 1187, Shaikhs, 4532, and 'others, 38,978'. According to sect, the Muhammadans were returned—Sunnis, 41,916, Shiás, 879, Wáhabís, 8, and 'others,' 8289

The Christian population included—British born subjects, 80, other British subjects (not British born), 74, and other Europeans or Americans, 26. Eurasians numbered 445, native Christians, 15,782, and 'others,' 160. Adopting another method of classification, there were—Roman Catholics, 14,172, of whom 13,856 were native converts, Protestants, 707, and 'other Christian sects,' 1688. Since 1871, the Christian population has increased by 21½ per cent

As regards occupation, the Census distributed the male population into six main groups—(1) Professional class, including State officials of every kind, 15,187, (2) domestic servants, inn and lodging keepers, 4492, (3) commercial class, including bankers, merchants carriers, etc, 9611, (4) agricultural and pastoral class, 390,430, (5) industrial class, including all manufacturers and artisans, 99,858, and (6) indefinite and non productive class, comprising general labourers, male children, and persons of unspecified occupation, 258,905

Emigration is not considerable, but a few coolies go to Ceylon, the French colonies, and Burma. Large numbers seek work in the neighbouring Districts. Those who go beyond the adjoining Districts do not take their women. The balance of emigrants and immigrants, according to the Census returns, leaves a gain to Salem of about 6000

Of the 3972 towns and villages in 1881, 1957 contained less than two hundred inhabitants, 1180 from two to five hundred, 512 from five hundred to one thousand, 225 from one to two thousand, 63 from two to three thousand, 22 from three to five thousand, 9 from five to ten thousand, 2 from ten to fifteen thousand, 1 from fifteen to twenty thousand, and 1 more than fifty thousand

SALEM, the chief town, is situated on the Tirumanimuttar, about 6 miles from the foot of the Shevaroys. It is a municipality, with a population (1881) of 50,667, and a revenue of £3592 in 1883-84. The following are the other towns—VANNIABADI (15,426), TIRUPATUR (14,278), SHENDAMANGALAM (12,575), KRISHNAGIRI (8856), ATUR (8334), RASIPUR (7969), DHARMAPURI (7090), AMMAPET (7003);

TIRUCHENGOD (5889); HOSUR (5869); NAMAKAL (5147); THATHAVANGARPET (4591); EDAPADI (3942).

Reading-rooms or literary associations have been established at Salem, Yercaud (Yerkád), Hosúr, and Tirupatúr, and all other principal towns. The chief source of charity is the Thopur Chattram Fund, from which *sardís* (native inns), etc. are being provided all over the District. Those at Salem, Thopur, Jollarpet, Atúr, and Tirupatúr are among the best. Besides the hospital and dispensary at headquarters, there are 11 dispensaries scattered over the District, and scarcely a large village is without its own cleaning and sanitary staff. Salem contains no shrine to compare in magnificence with those of Madura, Tanjore, or Srirangam; but pilgrims crowd to the sacred springs on the Tírtamalai, to Hanumatírtam on the Penner, to the pagoda at Hosúr, to the Adipadinettu at the falls of the Káveri (Cauvery), and to the festivals at Dharmapuri, Mecheri, Tiruchengod, Namakal, and other places. The chief shrines where the Malayális worship are on the Shevaroy's and the Chitterimalai hills near Harúr. There are printing presses in the Collector's office and in the central jail. A private press, called the Patriot Press, publishes a local newspaper in vernacular bi-monthly.

Agriculture.—Of the total area of the District, about 4,020,377 acres are occupied by Government villages, inclusive of *ináms*, the remainder being in *mittá* or *pálayam* villages. The total number of villages in the District is 3958, with 4722 hamlets, excluding those uninhabited, which number 745 and 623 respectively. According to the last quinquennial return, the cultivable area belonging to Government, exclusive of land reserved for public purposes, was 1,667,459 acres, assessed at £219,629. Holdings occupied 1,014,316 acres, assessed at £159,801. The number of registered *ráyats* was 245,484, with 47,477 sub-tenants, making a total of 292,961. The *pattas* numbered 161,870, of which 102,116 were single and 59,754 joint.

The staple crops are rice and *ragí* (Eleusine corocana), the latter being almost exclusively the food of the labouring class. The yield is assumed, for purposes of assessment, to be 641 Madras measures of paddy or unhusked rice, and 347 Madras measures of the other three staples for the Talághát *táluks*, the out-turn in the Báramahál and Bálághát *táluks* being the same for paddy, but somewhat less on the average for dry grains. *Ragí* grows to perfection in the Bálághát, and above the average in the Báramahál. *Kambu* or spiked millet (*Pennisetum typhoideum*) is about the same as in the Talághát; but gram, though remarkably fine, is an uncertain crop, and yields little more than half as much as the other staple grains. In 1883–84, cereals and millets occupied 935,795 acres; pulses, 218,299 acres; orchard and garden produce, 8225 acres; drugs and narcotics, 8639 acres; condi-

ments and spices, 11,182 acres, starches, 426 acres, sugars, 2864 acres, oil seeds, 74,553 acres, indigo, 2538 acres, fibres, 20,669, of which 18,692 were under cotton total, 1,283,190 acres

The greater portion (82 per cent) of the classified area of the District consists of red soil, the *regar* or black cotton soil occupying 16 per cent (in the northern *taluks*, 20 per cent), and exceptional or permanently improved land, 2 per cent. A pair of oxen could manage a farm of 3 acres of 'dry,' but not more than an acre of 'wet' land. 'Wet' land is almost invariably ploughed by four, five, or six pairs of oxen working together in the field. If the owner has not enough of cattle of his own, he must hire or borrow them. On a holding of 2 acres of 'wet' and 3 acres of 'dry' land, the net profit in a fair year would not probably exceed £6 per annum, or about 10s a month. The position of the poorer cultivators may be gauged from the fact that they will desert their farms in numbers if a wage of 8s. a month is not assured them. The majority of the peasantry are in debt. The habit of indebtedness is so ingrained in their nature, that if they all started fair to-morrow, 50 per cent would be in debt again in a year.

One man is held to be sufficient for the ordinary daily labour on a farm of 3 acres of 'wet,' or 6 acres of 'dry' land, if assisted in the heavy work of planting, weeding, reaping, and threshing. His wages would be 480 measures of grain per annum = £1, 5s, plus an annual money payment of 6s (the wages in the northern being lower than in the southern *taluks*). Twenty-seven measures of seed are required for an acre of 'wet,' and 6 measures for an acre of 'dry' land. Irrigated crops are weeded twice if sown broadcast, but once only if transplanted, 'Dry' crops are weeded only once. Manuring is applied, as a rule, by treading in leaves on 'wet,' and penning out sheep on 'dry' land. For 'wet' lands, the average is 120 bundles of wild indigo or other leaves per acre, and this is supplied annually to all fields thought worth manuring. Eight pens of 200 sheep each, at a cost of 4 measures of grain per diem, is the usual allowance per acre for 'dry' lands. The implements said to be required for a farm of 3 acres of irrigated or 6 acres of 'dry' land are a plough, 2 *mamuts*, an axe and chopper, three small weeding hoes, and three sickles. The highest Government 'wet' rate in the District is £1, 8s per acre and the lowest is £1, 3s 1½d, exclusive of local cesses, the highest for 'dry' lands being 10s, and the lowest 6d. The cost of cultivating an acre of good black loam is about 18s on irrigated, and 7s 6d on unirrigated lands in the northern *taluks*, the rates in the Talághat being somewhat higher, or 18s 6d and 9s 6d respectively.

The normal rates of wages for unskilled labour are—for men, 3½d, for women, 2½d, for children (male or female), 1½d. The Wadder

or navy caste get twice as much, but they generally do taskwork, by which they gain more than by daily wages. The wages of a working goldsmith vary with the value of the materials, but may be taken on an average at 1s. per diem. A blacksmith gets 1s.; a carpenter from 1s. to 1s. 3d.; bricklayers from 9d. to 1s. 3d. The rates of wages of unskilled labour in 1883-84 varied from 3½d. in towns to 2½d. per diem in villages; and of skilled labour from 1s. 1½d. in towns to 9d. a day in villages.

During the ten years ending 1874, the prices at Salem town per *garce* of 9360 lbs. avoirdupois, in February and March, when the *râyats* sell, averaged £10, 6s. for rice, and £11, 10s. for *cholam* or great millet (*Sorghum vulgare*). The price of produce at the end of 1883-84, per *maund* of 80 lbs., was—rice, 5s. 0½d.; *ragi* (*Eleusine corocana*), 2s. 1d.; *cholam*, 2s. 5½d.; *kambu*, 2s. 2½d.; *varagu* (*Panicum miliaceum*), 2s.; wheat, 6s. 6¾d.; gram, 4s. 0¾d.; salt, 6s. 0½d.; sugar, 7s. 1d.; cotton, 16s. In 1883-84, the live stock and implements of agriculture were—buffaloes, 43,674; bullocks, 191,541; cows, 273,137; asses, 4770; goats, 293,895; sheep, 412,692; horses, 450; mules, 13; ponies, 1868; pigs, 15,904; carts, 8893; and ploughs, 108,653.

Natural Calamities.—In May 1872, and again in May 1874, the District suffered from cyclones which, though they did not, owing to absence of cultivation in those months, do much damage to crops, caused terrible mortality among cattle, and breached several tanks. In the autumn of 1874, heavy floods occurred, notably in the Pálár and the basin between the Pálár and the Yelagiri hills. Many tanks were breached, and much property was damaged. The railway line was destroyed in several places, and a considerable portion of the town of Vániambádi was swept away. The excessive north-west monsoon of 1877 drowned the crops. In 1878, another great fall of rain fell east of the Mukanármalai, and washed away the railway embankment. The cyclone of November 1880 played havoc in the Atúr *táluk*. Every anicut was washed away, as also the large bridge on the trunk road near Thalaivásal; some 20 tanks were breached and many houses destroyed. The flood came in the day-time, and only six lives were lost. The damage done was estimated at £5000.

Blight is not uncommon in Salem, and locusts, caterpillars, and other insects devour the crops. The Pálár, when in flood, occasionally causes loss to the river-side landholders; and breached tanks, especially when a chain of tanks gives way together, cause damage, but more generally to property than to life.

The severest famine of early years was that of 1833, when prices rose 71 per cent.; 1845-46 was a year of high prices, as also was 1857-58. In the famine of 1866, the following prices were reached between September and December:—Rice, 15s. to 17s. 6d. per cwt.;

cholam, 8s 6d. to 12s per cwt by Government for the needy

But this and all previous famines on record are dwarfed by the terrible calamity of 1876-78. There had been signs and warnings by which this might have been foreseen. The north east monsoon failed both in 1873 and 1874. In 1875, the north east monsoon was almost a total failure especially the latter part of it and in 1876, the south west and north-east monsoons, on both of which the District depends for its water supply failed almost completely. The pinch began to be felt in October 1876, but people still hoped. By November, the failure of the monsoon became an established fact. Grain dealers took alarm, and prices rose at a bound. In August 1877, inferior rice had risen to a rupee (2s) for 11 lbs and other grains when procurable were nearly the same price as in ordinary years. The price of rice from 20 lbs to 30 lbs for 1 rupee, the keen distress may be realized. During the first thirteen months of famine the mortality was 180,000. It is estimated that altogether the District lost 10 per cent of its population. Distress may be said to set in when normal prices are doubled, any rise beyond that rate involving famine.

One result of the late famine was to call attention to the neglected means of storing water. The Palar and Kaveri (Cauvery) might be utilized to a far greater extent than at present and the Penner (Ponniyár) carries untold wealth into the Bay of Bengal. In so far as the increased wealth of the population gives them more reserve to draw upon in time of scarcity improved irrigation might do much for the District, but it cannot render certain a capricious rainfall, on which the majority of the tanks depend and it cannot secure grass for the middle of the 16th century, the whole District was more or less a failure. The neglect of forestry is probably responsible for much. In the middle of the 16th century, it is not now easy in many places to find shade for a noon-day. Were it not for the railway this last famine would probably have carried off a half of the population instead of the 204,590 who died from insufficient food, and the subsequent diseases consequent on it.

Industries and Trade—The chief industry of the District is weaving, which is carried on in almost every large town or village. The principal towns of Salem and Rázipur are especially noted. Carpets of great and superior workmanship are made in the Salem jail. Good steel are made, but only on a small scale, an attempt to develop the mineral wealth of the District by European capital having failed to the cost of charcoal. In Salem town there are several iron wares are famed for temper and finish throughout India. Cotton, hides, indigo, saltpetre, salt, grains, areca nut, coir,

jungle produce, coffee, clothes, etc., pass freely in and out of the District, but there is no trustworthy information regarding the value of imports and exports.

Communications.—There are about 1633 miles of road in the District, on which the expenditure in 1883-84 was £13,656; but the state of the roads is not good. The south-west line of the Madras Railway runs for a distance of 131 miles within the District. The principal hill passes are—the Chengama Pass, by which South Arcot is reached from Singárapet; the Morúrpatti *ghát*, which lies between the Sheva-roys and the Thopur Hills; the Thopur and Mukanúr *ghát*, through which traffic reaches Dharmapuri from the south-east and east; the Ráyakottai Pass, which gives access from Krishnagiri to the Bálághát; the Manjanadi and Kottáipatti Passes, by which Uttankarai is accessible from Salem and Atúr respectively, on the south; the Anchittai *ghát*, almost impracticable, by which the Bálághát portion of the Hosúr *táluk* communicates with the valley of the Káveri.

Administration.—The imperial revenue of the District for 1883-84 was £261,292, of which land revenue contributed £212,051. Excise came next with £30,388; and stamps, £16,271. The other items of receipt are small, the forests being credited with only £9880. The total revenue in 1805-06 is returned at £191,786, of which the land yielded £182,348; in 1850-51 the total revenue was £196,693, and the land revenue £177,535; in 1870-71 the total revenue was £302,091, and the land revenue £232,191.

There are at present 36 magistrates' courts and 10 civil courts, including those of the revenue officers, covenanted and uncovenanted, empowered to hear rent suits. The number of covenanted officers is 5, including the Assistant Collector, who has no separate charge. Exclusive of village watchmen, the District police in 1883-84 consisted of 2 officers, 18 inspectors, and 1032 constables, or 1 policeman to every 7·24 square miles and every 1549 of the population. A special police, raised to control the spirit of outrage which was evidenced by the Salem riots, consisted of 1 inspector and 202 constables. It is not likely to be permanently retained. The District has 1 central and 17 subsidiary jails, containing (in 1883-84) 5113 prisoners, and costing £4266.

The education of the masses is chiefly got at the *payal* schools, where elementary teaching is given after a time-honoured but unscientific fashion. In 1871, according to Census returns, there were only 190 schools in the District; but this cannot be supposed to include the *payal* schools. The Local Fund Act, passed in 1871, gave a stimulus to popular education by providing the funds for its extension; and in 1883-84 there were 511 schools, either belonging to Government or aided, which were attended by 9368 pupils. In the returns furnished

for the first edition of this work, it was estimated that about 7200 children receive elementary education from unaided *payal* schools. The Census Report of 1881 returned 18,032 boys and 1091 girls as under instruction, besides 50,349 males and 2857 females able to read and write, but not under instruction. Regarding missionary effort, the field is divided between the London Mission, the French priests under the Vicar Apostolic of Pondicherry, and, to a small extent, the Lutheran Evangelistic Mission. The Roman Catholics outnumber the rest.

Medical Aspects—The average monthly rainfall for 22 years ending 1881, as registered at Salem town, was as follows—January, 36 inch, February 0.09 inch, March, 0.85 inch, April, 2.17 inches, May, 4.34 inches, June, 3.15 inches, July, 3.89 inches, August, 5.26 inches, September, 6.15 inches, October, 6.94 inches, November, 2.26 inches, and December, 0.62 inch. yearly average, 36.08 inches. The average mean temperature for 12 years ending 1881 was 80.6° F, ranging from 75.3° F in December to 86.8° F in April. On the lower hill ranges, fever prevails for a great part of the year. Strangers, especially if they drink the water, are most liable to attack, though the anæmic faces and enlarged spleens of the acclimatized population show that they have by no means an immunity from the scourge. In the plains, during the rainy season, large tracts are liable to a peculiarly weakening sort of fever, which in some years causes considerable mortality. The cause of this is not exactly known, as the fever does not always appear under given conditions, and occasionally one particular locality, noted for fever, may be free, while another, reputed for healthiness, may become the scene of an epidemic. Cholera rages through the District at times. The virulence of the disease may be estimated from one example. In 1875, in the village of Kanakampatti, in three days 52 died out of a population of 200. The deaths from cholera, in 1875-76, were 15,487, in 1876-77, 45,162, and in 1877, from July to November, 8002. The last outbreak in 1883 was attended with a loss of 5015 lives. Small pox has to a great extent been stamped out, though during the famine, when the population was peculiarly predisposed to disease, exceptional mortality occurred. Dengue was prevalent in the latter part of 1872. Leprosy is not common. Cattle disease is rarely absent, rinderpest and foot and mouth disease being the most common forms. [For further information regarding Salem, see the *Manual of Salem District*, by Mr H. Le Fanu, C.S., 2 vols (Madras Government Press, 1883). Also the *Manual of the Administration of the Madras Presidency*, 3 vols (Madras Government Press, 1885), the *Madras Census Report* for 1881, and the several annual Administration and Departmental Reports of the Madras Government.]

Salem—West central taluk of Salem District, Madras Presidency,

lying between $11^{\circ} 23'$ and $11^{\circ} 59'$ N. lat., and $77^{\circ} 49'$ and $78^{\circ} 34'$ E. long. Area, 1072 square miles. Population (1881) 327,178, namely, males 159,902, and females 167,276; occupying 61,612 houses, in 3 towns and 488 villages. Hindus number 314,101; Muhammadans, 7313; Christians, 5739; and 'others,' 25. The *táluk* is very diversified in aspect, containing hill and dale, untilled tracts and prosperous cultivation. Among the products of the *táluk*, mention should be made of coffee, tea, and indigo. The great mass of the agricultural classes are poor. The trading classes are somewhat better off. Weaving is carried on to a great extent; but the weaver class suffered cruelly in the famine of 1876-78. Jewellers, cloth merchants, and grain merchants drive a good trade. The south-west line of Madras Railway traverses the *táluk*. In 1883 the *táluk* contained 2 civil and 4 criminal courts; police circles (*thánás*), 19; regular police, 355. Land revenue, £40,347.

Salem (*Selam*).—Chief town of Salem District, Madras, and a municipality, with the courts of the District Judge, Magistrate, and *munsif*, a central jail, 2 churches, memorial hall, schools, hospital, etc. Lat. $11^{\circ} 39' 10''$ N., long. $78^{\circ} 11' 47''$ E. Population (1881) 50,667, namely, males 24,584, and females 26,083. Hindus number 44,614; Muhammadans, 4669; Christians, 1382; and 'others,' 2. Nearly 90 per cent. of the population are Hindus. The town is straggling and extensive, being about three miles long and two broad. The river Tirumani-mutár divides the native town into two quarters. The Europeans live in a suburb named Hastampatti. The railway station lies in another suburb, Suramangalam, $3\frac{1}{2}$ miles distant. On the eastern side is Salem proper, where most of the merchants and officials live; on the south is Gugai, the weaving quarter. The western side comprises the fort (now no longer existing) and Shevapett, the latter named from a fair held there on Thursdays. Adjacent to the fort are most of the public buildings. The *mahál* in the fort was originally the palace or residence of one of the tributary chiefs of Salem. Salem is a busy trading place, with a considerable weaving industry. The town is clean, and well cared for. Its old notoriety for endemic fever and cholera has disappeared before the sanitary improvements of the municipality. The town is prettily situated, 900 feet above sea-level, in a long valley with the Shevaroy Hills towering above. These hills are only 6 miles distant, and the ascent to the plateau is only 7 miles. Though never a place of any military strength, its position in a much contested District has made it the scene of frequent fighting. It was first captured by Captain Wood in 1768. The municipal income of Salem in 1883-84 was £3592; incidence of taxation, 1s. 5d. per head of population within municipal limits.

Salem (*Chinna Salem*, or *Little Salem*).—Village in Kallakurchi

taluk, South Arcot District, Madras Presidency Lat $11^{\circ} 38' N$, long $78^{\circ} 55' 30'' E$ Population (1881) 4855, dwelling in 785 houses

Sáletekri—*Zamindári* or revenue free estate in Balághát District, Central Provinces, comprising 38 villages, area, 284 square miles, chiefly hilly Population (1881) 5809 By far the greater part of the *zamindari* is uncultivable hill and jungle At the time of settlement, only 7 villages, with an area of $12\frac{1}{2}$ square miles, entered into engagements for the full period of settlement, the remainder being included in jungle lands, the assessment on which is revised about every three years With the exception of a few villages lying along the banks of the Son (Soane), the whole estate lies from 1800 to 2000 feet above sea level The chief is a descendant of one of the old Gond families, whose principal wealth used to be derived from periodical forays upon the villages in the plains The country produces timber and bamboos of all descriptions This chiefship was probably one of the grants made for guarding the passes of the hill country, and has remained in the same family for many generations The principal village is 50 miles south east of Burha

Salimpur—Town in Lucknow District, Oudh, situated 20 miles from Lucknow city, on the road to Sultanpur Population (1881) 2078, including some adjacent hamlets Picturesquely situated on broken and high ground overlooking the Gumti river, the approach to it lying across a ravine spanned by a long bridge built since British annexation Small Government school

Salimpur—Village in Amroha *tahsil*, Moradabad District, North Western Provinces, situated in lat $29^{\circ} 5' 45'' N$, and long $78^{\circ} 41' E$ Population (1881) 2685 Weekly market on Thursdays Numerous ruins of temples and tombs exist in the neighbourhood

Salimpur - Majhauri—Two adjacent villages in Deoria *tahsil*, Gorakhpur District, North Western Provinces — See MAJHAULI-SALIMPUR

Sálkhiá—Northern suburb of HOWRAH, the chief town of Húgli District, Bengal The inhabitants are largely engaged in river traffic, and as labourers in the docks, mills, and East Indian Railway Sálkhiá also contains a large number of shopkeepers and a permanent market Along the river side are several dockyards A ferry steamer plies daily between Sálkhiá and Calcutta

Sálnadí—River of Bengal — See SALANDI

Salon—*Tahsil* or Sub division of Rái Bareli District, Oudh, lying between $25^{\circ} 49'$ and $26^{\circ} 19' N$ lat., and between $81^{\circ} 16'$ and $81^{\circ} 39' E$ long, and comprising the three *parganas* of Salon, Parshádepur, and Rokha Jais Bounded on the north by Digbijárganj *tahsil*, on the east by Ráipur and Partábgarh *tahsils*, on the south by Fatehpur District in the North Western Provinces, and on the west by the Rái

Bareli tahsíl. Area, 433 square miles, or 277,101 acres, of which 143,294 acres are under cultivation. Population (1881) 245,232, namely, males 121,151, and females 124,081. Hindus number 215,969; Muhammadans, 29,240; Jains, 13; and 'others,' 10. Average density of population, 566 persons per square mile. Number of towns and villages, 457, of which 125 are *tálukdári*, 139 *samindári*, and 193 *pattidári*. Land revenue, £28,678. In 1885, Salon *tahsíl* contained 1 criminal court; number of police circles (*thánás*), 4; strength of regular police, 31 men; village watch or rural police (*chaukidárs*), 781.

Salon.—*Parganá* in Rái Bareli District, Oudh; recently transferred from Partábgarh District. A picturesque and interesting tract, bounded on the south by the Ganges and on the north by Parshádepur *parganá*. It is also watered by the Sáí river, and is covered with jungle, in which the Náin *tálukdárs* and other freebooters in the time of native rule built their forts. Wild cattle were formerly found in large numbers. The banks of the river are steep and covered with brushwood. Area, 225 square miles, or 144,193 acres, of which 89,224 acres are under cultivation. Land revenue, £14,790. Population (1881) 127,122, namely, males 63,225, and females 63,897. The Kanhpuria clan of Rájputs are the principal landholders, owning 98 out of the 287 villages comprising the *parganá*. Of the 287 villages, 47 are *tálukdári*, 109 *samindári*, and 131 *pattidári*.

Salon.—Town in Rái Bareli District, Oudh, and head-quarters of Salon *tahsíl* and *parganá*; situated on the road from Partábgarh to Rái Bareli town, in lat. $26^{\circ} 1' 40''$ N., and long. $81^{\circ} 29' 50''$ E. Pleasantly situated amid groves of mango and palm trees. Formerly a flourishing place, but now much reduced. Population (1881) 4777, namely, 2492 Muhammadans and 2285 Hindus, residing in 1026 mud-built and 85 masonry houses. Ten mosques; one Hindu temple. Government school. Average annual *bászár* sales, £1000. Salon was in ancient times a famous stronghold of the Bhars, the aboriginal rulers of the country. Attached to the town is a revenue-free estate worth £2500 a year, granted as an endowment by the Emperor Aurangzeb, and confirmed by the British Government. The present holder of the estate is Sháh Muhammad Mehndi Atá.

Sálor Hirapur.—Village in Wardhá *tahsíl*, Wardhá District, Central Provinces. Population (1881) 2431, namely, Hindus, 2251; Muhammadans, 89; Jains, 57; and non-Hindu aborigines, 34.

Salsette.—Large island to the north of Bombay, forming the Salsette Sub-division of Thána District, Bombay Presidency; extending 16 miles from Bhandára northwards to the Bassein inlet, and connected with Bombay Island by bridge and causeway. Lat. $19^{\circ} 2' 30''$ to $19^{\circ} 18' 30''$ N., and long. $72^{\circ} 51' 30''$ to $73^{\circ} 3'$ E. Area, 241 square miles. Population (1872) 93,324; (1881) 108,149, namely, males 58,540.

and females 49,609, occupying 16,869 houses, in 3 towns and 110 villages. Hindus number 74,736, Muhammadans, 7036, and 'others,' 26 377. Along the centre of the island, from north to south, runs a broad range of hills, which after subsiding into the plain near Kurla, crops up again in the southernmost point of the island at Trombay. The central and highest, Thána peak, is 1530 feet above sea level, on the north is a detached, sharp peak, 1500 feet high. Spurs from the main range run west towards the sea, while the low lands are much intersected by tidal creeks, which especially on the north west split the sea face of the Sub-division into small islands. There are no large fresh water streams, but the supply of water from wells is of fair quality, and pretty constant. The staple crop is rice, and most of the uplands are reserved for grass for the Bombay market. The coast abounds in cocoa nut groves, and the palmyra palm grows plentifully over most of the island. This beautiful island is rich in rice fields, diversified by jungles and studded with hills. The ruins of Portuguese churches, convents, and villas attest its former importance, and its antiquities at Keneri still form a subject of interest. Eighteen estates, consisting of 53 villages, were granted in Salsette by the East India Company, some freehold, and others on payment of rent, and liable to assessment. The lines of the Great Indian Peninsula Railway, and of the Bombay, Baroda, and Central India Railway, traverse the Sub division.

Seized by the Portuguese early in the 16th century, Salsette should have passed to the English, together with Bombay Island, as part of the marriage portion of the queen of Charles II. The Portuguese in 1662, however, contested its alleged transfer under the marriage treaty, and it was not till more than a century afterwards that possession was obtained. The Maráthás took it from the declining Portuguese in 1739. The English captured it from the Maráthás in December 1774, and it was formally annexed to the East India Company's dominions in 1782 by the treaty of Salbái.

Salsette affords a deeply interesting field for the geologist and natural historian, and it occupies several paragraphs in the official *Manual of the Geology of India*. It will ever be associated with the name of Victor Jacquemont, as it formed the scene of his last labours, and from its jungles the brilliant Frenchman carried away the fever of which he shortly afterwards died at Bombay.

The cave architecture of Salsette deserves notice. The great *chaitya* at Keneri, however, is pronounced by Fergusson to be merely a bad copy of the Karli cave. It belongs to the beginning of the 5th century, but nine of its *sthras* seem to be of earlier date. Salsette had, however, a sanctity of its own early in the 4th century as containing a tooth of Buddha, at the period, says Fergusson, 'when these relics were revol-

tionizing the Buddhist world—at least at two diametrically opposite points of the coast of India, at Puri, and in this island. It may have been in consequence of the visit of this relic that the island became holy; and it may have been because it was an island that it remained undisturbed by the troubles of the mainland, and that the practice of excavating caves lasted longer here than in any series above described. Be this as it may, the caves here go straggling on till they fade by almost imperceptible degrees into those of the Hindu religion. The Hindu caves of Montpezir, Kanduti, and Amboli are so like them, and the change takes place so gradually, that it is sometimes difficult to draw the line between the two religions.'

Of the total area of 241 square miles, 37 square miles are occupied by lands of alienated villages. In 1879-80, the holdings numbered 8808, with an average area of $6\frac{1}{2}$ acres, paying an average Government assessment of £1, 12s. 3d. In 1880-81, 23,243 acres were under actual cultivation, of which 234 acres were twice cropped. Cereals and millets occupied 22,094 acres, of which 21,952 acres were under rice. In 1884, the Sub-division contained 4 civil and 9 criminal courts; police circles (*thánás*), 2; regular police, 197 men, inclusive of police at head-quarters. Land revenue (1883), £14,723. The average annual rainfall for the thirteen years ending 1881 was 97·6 inches. Head-quarters at THANA.

Salt Range.—Hill system in Jehlam (Jhelum), Sháhpur, and Bannu (Bunnoo) Districts, Punjab, deriving its name from its extensive deposits of rock-salt. Lat. $32^{\circ} 41'$ to $32^{\circ} 56' N.$, and long. $71^{\circ} 42'$ to $73^{\circ} E.$ The main chain commences in the lofty hill of Chel, 3701 feet above the sea, which is formed by the convergence of three spurs cropping up from the Jehlam river, and divided from the Himálayan outliers only by the intervening river valley. The most northern of these spurs rises abruptly from the river bank at Sultánpur, and runs nearly parallel with the Jehlam at a distance of 25 miles, till it joins the main chain after a course of 40 miles. It bears the local name of the Níli Hills. The second spur, known as the Rotás range, runs half-way between the Níli Hills and the river, parallel with both. It contains the famous fort of Rotás, and the hill of Tilla, the sanitarium of Jehlam District, with an elevation of 3242 feet above sea-level. The third or Pabbi spur rises south of the Jehlam river, dips for a while on approaching the river valley, and rises once more on the northern bank, till it finally unites with the two other chains in the central peak of Chel. Thence the united range runs westward in two parallel ridges, till it culminates in the mountain of Sakeswar, in Sháhpur District, which has an elevation of 5010 feet above sea-level. Between these lines of hills, and topped by their highest summits, lies an elevated and fertile table-land, picturesquely intersected by ravines and peaks. In

its midst nestles the beautiful lake of Kallar Kahár. The streams which take their rise in the table land, however, become brackish before reaching the lowlands.

The beds of salt, from which the range derives its name, occur in the shape of solid rock on the slopes of this table land, and form the largest known deposits in the world. The mineral is quarried at the MAYO MINES, in the neighbourhood of the village of Kheura, a few miles north-east of Pind Dádan Khán, in Jehlam District, at WARCHA in Sháhpur, and at KALABAGH in Bannu District. The great bulk of the salt is excavated from the Mayo Mines, which, during the 35 years ending 1883-84, have yielded a total out turn of 40,712,943 *maunds*, or about 18,750 tons, paying a Government revenue in the shape of duty of £8,103,984. The supply is practically inexhaustible. In 1883-84, of an entire out turn of 1,605,671 *maunds*, or 57,886 tons, from the Salt Range, 1,332,064 *maunds*, or 48,763 tons, were from the Mayo Mines. The total receipts in the shape of duty in 1883-84, from the Mayo, Warcha, and Kalábagh mines, amounted to £330,832, and the charges to £27,879, leaving a net revenue of £302,953. The construction of a permanent bridge across the Jehlam river at or near Pind Dadan Khán, in place of the present bridge of boats, now under the consideration of Government, will bring the Mayo Mines into direct railway communication with the rest of India, and avoid the delay and loss at present caused by transhipment.

Coal also occurs in the Salt Range both in oolitic and tertiary strata, the former at Kalabágh, employed as a fuel for the Indus steamers, and the latter between Jalálpur and Pind Dádan Khan. It is of inferior quality, however, consisting of a brown lignite, difficult to set on fire, and yielding a very large proportion of ash.

From Jehlam District, the Salt Range stretches into Sháhpur and Bannu. The long spur which projects into Shahpur terminates in the hill of Sakeswar, and comprises a number of separate rock bound alluvial basins, the largest of which, the Sun and Ahabbakki valleys, occupy the northern half, while the south consists of a broken country, cut up into tiny glens and ravines by a network of limestone ridges and connecting spurs. In the northern portion of the range, the drainage gathers into small lakes, and trees stud the face of the country, but southward, the streams flow through barren and stony gorges, interspersed with detached masses of rock, and covered with the stunted alkaline plants which grow on soil impregnated with salt. The Bannu portion of the range runs north westward towards the Indus, which it meets at Mára, opposite KALABAGH, and rising again on the western side, is continued in the KHATTAK MAIDANI HILLS. The scenery throughout the Range is rugged and often sublime, but wanting in softness and beauty. In many parts it becomes simply barren and

uninviting. Besides salt and coal, many other valuable minerals occur in these hills.

Salt-Water Lake (or *Dhápá*).—Lake in the District of the Twenty-four Parganás, Bengal; situated about 5 miles east of Calcutta, between the Húglí and Bidyádhari rivers, and covering an area of about 30 square miles. Lat. $22^{\circ} 28'$ to $22^{\circ} 36'$ N., and long. $88^{\circ} 25' 30''$ to $88^{\circ} 30' 30''$ E. It contains a section of the Inner Sundarbans Passage for boats bound to Calcutta *viâ* Bálíágháta. The neighbourhood of the Salt-Water Lake is intersected by innumerable watercourses and rivers, which flood the country at spring-tides. A part of the lake is now in course of reclamation, by the sewage of Calcutta being deposited in it.

Salumbar.—Town in the State of Udaipur (Oodeypore), Rájputána; situated 30 miles south of Udaipur town. Population (1881) 5574, namely, Hindus 4831, and Muhammadans 743. The residence of the most powerful of the feudatories of the State, the head of the Chandáwat clan of Rájputs. Salumbar gives its name to an estate comprising 109 villages. A masonry wall surrounds the town, which is protected on the north by lofty and picturesque hills, one of which, immediately overlooking it, is surmounted by a fort and outworks still in good repair. An artificial lake, overlooked by the chief's palace, lies to the west of the town.

Sálúr.—*Táluk* or Sub-division and *zamíndári*, Vizagapatam District, Madras Presidency. Area, 64 square miles. Population (1881) 80,466, namely, males 39,756, and females 40,710. Hindus number 79,701; Muhammadans, 727; Christians, 3; and 'others,' 35. Number of houses, 17,255; villages, 155. The *zamíndár* was originally feudatory to Jaipur (Jeypore), and afterwards to Vizianagram. The last-named confiscated the *zamíndári* in 1774, but the Company restored it to the old family twenty years later. The *zamíndár* pays a *peshkash* or fixed revenue of £3599; total rental, £11,588.

Sálúr.—Chief town of Sálúr *táluk* and *zamíndári*, Vizagapatam District, Madras Presidency. Lat. $18^{\circ} 30' 40''$ N., long. $83^{\circ} 14' 50''$ E. Population (1881) 11,856, namely, males 5746, and females 6110. Hindus number 11,426; Muhammadans, 425; Christians, 3; and 'others,' 2. Number of houses, 2564. Sálúr is the residence of the *zamíndár*. Sub-magistrate's court, post-office, dispensary, and good school.

Salwín (*Salween*).—River of Burma, with a general north and south course. The source of this river has never been explored; but the best authorities agree in stating that it is in proximity to the source of the Irawadi (Irrawaddy), far up in the snowy range which lies eastward of Assam in lat. 28° N., and forms part of the Himálayan system of mountains. After traversing Yunan,

a Chinese Province, and the Shan and Kuren of States lying south of it, the Salwin enters Lower Burma at its extreme north eastern corner, and for some distance, as far as the Thaung yin river, marks the eastern limits of the Province. In this part of its course, the Salwin is a broad, swift stream, navigable by boats, and flowing between high, densely wooded mountains. Farther south, these gorges become narrower, and near the mouth of the Thaung yin, the breadth of the stream contracts so much that at places its bed does not occupy more than 30 yards.

A few miles lower down, and about 100 miles from the sea, are the great rapids, formed by a bar of rocks stretching completely across the river, and impassable even by canoes during the dry season. In the rains, when the Salwin is swollen by the vast volume of water brought down from the extensive tract of country which it and its tributaries drain, the current is so strong and the violence of its efforts to pass the rocky ledge so great, that even massive logs of timber are dashed to pieces. Farther south are other but less formidable rapids, impassable in the rains. Below, there are numerous islands and shoals covered during the floods, when the water rises 30 feet. A few miles lower down, after the Salwin has received the Yun za lin from the west, the hills on the eastern bank recede, and those on the western diminish considerably in altitude, and the river traverses a more open and level country, with outcrops of limestone on both banks, rising abruptly out of the plain into lofty serrated ridges.

At Maulmain, the Salwin receives from the eastward the GYAING, formed by the junction of the Hlaing bwe and the Haung tharaw, and the ATTARAN, which joins the Gyaing at its mouth. Here the Salwin splits into two mouths—the northern, flowing between Bi lu gyun and the old town of Martaban, is unnavigable now by reason of sandbanks, but some centuries ago was the principal entrance. The southern branch flows past Maulmain, and falls into the sea at Amherst by a mouth 7 miles wide. By this channel vessels of the largest size can reach Maulmain, but navigation is rendered difficult by the shifting of the sands.

Vast quantities of teak from British and foreign forests are annually floated down the Salwin, and shipped at Maulmain for export. The timber is dragged into the forest streams by elephants, marked, and then washed in the rains into the Salwin, by which it is carried down in whirling masses until checked by a rope stretched across the river at Kyo dan, about 56 miles above Maulmain. Large numbers of salvors assemble here in the season, and raft as many logs as they can, to be claimed by the owners, who pay salvage.

The area of the Salwin basin is 62,700 square miles, it is 800 miles in length, but seldom more than 100 miles in breadth. The upper part

is conterminous on the east with that of the Me-kong or Cambodia river; lower down, it is bounded by the Meinam river, which belongs to Siam. The length of the main stream of the Salwin is estimated at 750 miles.

Salwin Hill Tracts.—British District in Tenasserim Division, Lower Burma; extending from the northern frontier southwards to Kaw-ka-rit on the Salwin river, and occupying the whole of the country between that river on the east and the Paung-laung Mountains on the west. On the north it is bounded by Karen-ní (Kareng-nee), on the east by Zin-me, on the south by Amherst and Shwe-gyin, and on the west by Shwe-gyin and Taung-ngú (Toung-ngoo). Estimated area, 4646 square miles. Population (1881) 30,009 souls. From the annexation of Pegu until 1872, the Hill Tracts formed a Sub-division of Shwe-gyin District, but in that year they were erected into a separate jurisdiction. The administrative head-quarters are at PA-PUN.

Physical Aspects.—The whole country is a wilderness of mountains. Even the valley of the Yun-za-lin, the principal river after the Salwin, is, strictly speaking, only a long winding gorge. The direction of the mountains, of which there are three principal ranges, is generally north-north-west and south-south-east, but the spurs from the main system appear to be thrown in bewildering eccentric masses. The slopes are so precipitous, and so densely wooded, that the passage by laden animals is in many places impossible, and that of travellers on foot difficult and fatiguing in the extreme. It is through these hills that Shan caravans come down annually to Rangoon and Maulmain; and with the exception of the routes used by them, there are no roads over which laden bullocks can pass, baggage being carried on men's shoulders.

The country is drained by three principal rivers—the SALWIN, the YUN-ZA-LIN, and the BI-LIN—fed by numerous mountain torrents rushing down narrow ravines, over rocks and boulders, on their way to the larger streams, which partake of the nature of their impetuous tributaries, and dash themselves in foam over masses of rock, or whirl in wild eddies through ravines shut in by beetling crags and gigantic forest trees, covered with brilliant flowers or creepers. When these rivers emerge into the low country they entirely lose their picturesqueness, and sink into muddy streams, with no trace left of their former state but the rapidity of their currents. The Yun-za-lin is navigable in the dry season as far as Pa-pun. Within the limits of this District, the Bi-lin is impracticable, except for rafts and small boats. The Salwin is impeded by impassable rapids.

In the mountainous region the soil is reddish clay. Outcrops of gneist shale are met with in places, also indurated sandstone. Limestone occurs in isolated cavernous hills and along the Livehlok range,

where it contains large quantities of rich galena. A lead mine has been opened on the Lavehlok, the working of which had not, up to 1882-83, been regularly commenced. The valley of Yun za lin is extensive, and contains vast quantities of valuable timber. The soil is rich loam in parts, and nearer the river appears to be alluvial clay and very fertile. Great facilities exist for irrigating the land in this valley, as perennial streams flow down at right angles to the river at short intervals.

The population in 1872 was returned at 26,117, in 1877, at 26,649, and in 1881, at 30,009, namely, males 15,509, and females 14,500. Number of villages, 209, occupied houses, 6387, unoccupied houses, 57. Average density of population, 6.46 persons per square mile. Classified according to age, there were—under 15 years, boys 6497, and girls 6007, total children, 12,504 or 41.7 per cent of the population. 15 years and upwards, males 9012, and females 8493, total adults, 17,505, or 58.3 per cent.

According to religion, the population was thus distributed in 1881—Buddhists, 5100, Nat worshippers or persons of indigenous religion, 24,738, Hindus, 35, Muhammadans, 105, and Christians, 31. By race, the inhabitants are almost entirely Karens, a few Shans are settled in the neighbourhood of Pa pun. The eastern portion of the Hill Tracts was formerly inhabited by Yun Shans, whence the name Yun za lin, but the majority of these were carried away by Alaungpaya to what is now the Syriam township of Pegu.

Silwin District contains no town. The head quarters station, Pa pun, contains less than a thousand inhabitants. The remaining villages, 208 in number, are small, and of no importance, 158, or 75.6 per cent, contain less than two hundred inhabitants, 46 between two and five hundred, and 4 between five hundred and one thousand.

Agriculture—Of the total area of 4646 square miles, only 21 square miles were returned in 1883-84 as under cultivation, and 3116 as cultivable waste. The chief crops are rice and areca nuts. In 1883-84, 437 acres were under rice (excluding the *taungyas*), 1524 acres under areca nuts, and 34 acres under mixed fruit trees. The cultivation is almost entirely carried on in *taungyas* or nomadic clearings in the hills, except near Pa pun, and in the areca nut groves, which are permanent. Area (1883-84) under *taungya* cultivation, 11,270 acres, total area under actual cultivation, 13,265 acres.

The revenue is raised almost entirely from the land and capitation taxes, and amounted in 1883-84 to £1964, of which £940 was land revenue. Area of reserved forests, 70 square miles. The education of the District is carried on by the Buddhist priests. Dispensary at the head quarters station Pa pun, number of patients treated (1883-84), 2814. Rainfall (1883), 127.19 inches.

Administration.—The District is administered by a Commissioner, stationed at Pa-pun, on the Yun-za-lin. Under him are an extra-Assistant Commissioner and the *thúgyí* of the six circles of Pa-pun, Kaw-lú-do, Kaw-ka-rit, Ka-daing-tí, Me-waing, and Win-pyaing. The District in 1883–84 contained 2 civil and 2 criminal courts. The average distance of each village from the nearest court is 25 miles. For some years after the country became British territory, it was in a very unsettled state, but the risings were speedily quelled. In 1867, fresh and more serious disturbances broke out. A chief named Dípa attacked and plundered the villages, and threatened Pa-pun; and from that time dacoities or gang robberies became frequent. This District forms the basis of operations of those who have purchased the right to fell timber in the vast teak tracts beyond the Salwín river. These foresters come up with large sums in cash, which they require for the payment of their workmen, or for dues to the various chiefs; and in consequence, the whole of the neighbouring country beyond the borders has become the haunt of men who acknowledge no fixed authority, but collect in bodies under some daring leader, fall upon the foresters, and attack the villages of the District. In order to remedy this, the Salwín Hill Tracts were separated from Shwe-gyin in 1872, and formed into a distinct administration, and the police were considerably strengthened. The Commissioner of the District is *ex officio* Superintendent of Police, and in 1883–84 had a force under him of 19 subordinate officers and 232 men, of whom 12 were river police; of these, 156 were Karens, who work well but will not serve for long. The constabulary is quartered at Kaw-lú-do, at Kyauk-nyat, and Da-kwin on the Salwín, with a strong reserve at Pa-pun. [For further information regarding the Salwín Hill Tracts, see the *British Burma Gazetteer*, 2 vols., compiled by authority (Rangoon Government Press, 1879 and 1880); the *British Burma Census Report* for 1881; and the several annual Administration and Departmental Reports of the Government of Burma.]

Samadhiála.—Petty State in the Gohelwár division of Káthiáwár, Bombay Presidency; consisting of 1 village with 2 separate tribute-payers or shareholders. Area, 1 square mile. Population (1881) 957. Estimated revenue, £800; £51 is paid as tribute to the Gáekwár of Baroda, and 16s. to the Nawáb of Junágarh.

Samadhiála Chabhária.—Petty State in the Gohelwár division of Káthiáwár, Bombay Presidency; consisting of 2 villages, with 5 separate tribute-payers or shareholders. Area, 62 square miles. Population (1881) of the State, 1414; and of Samadhiála Chabhária village, 689. Estimated revenue, £650; £189, 2s. is paid as tribute to the Gáekwár of Baroda, and £38, 18s. to the Nawáb of Junágarh.

Samadhiála Cháran.—Petty State in the Gohelwár division of Káthiáwár, Bombay Presidency; consisting of 1 village, with

2 separate tribute payers or shareholders Area, 6 square miles
Population (1881) 135 Estimated revenue, £80, no tribute is paid

Samadhpur—Village in Khutáhan *tahsil*, Jaunpur District, North Western Provinces, situated in lat $26^{\circ} 3' 55''$ N, long $82^{\circ} 31' 3''$ E. Population (1881) 2020, chiefly Muhammadans The village was originally called Bánsapurwa, owing to its site being covered with bamboos, subsequently named Samadhpur from Samadh Páik, the ancestor of the present *zamindár*, by whom the village was peopled Bi weekly markets on Tuesdays and Fridays

Sámaguting—Frontier outpost station and former head quarters of the Nágá Hills District, Assam, situated in lat $25^{\circ} 45' 30''$ N, and long $93^{\circ} 46'$ E, on a tributary of the Dhaneswarí (Dhansiri) river, 2477 feet above sea level, about 67 miles south of Golághát in Sibságar District Sámaguting was chosen as a British station in 1867, but abandoned in favour of Kohima in 1878, as being better situated for the supervision of the Nagás, the site more healthy, the water supply secured by an aqueduct, and the garrison strongly stockaded The country round Sámaguting is inhabited by the Káchá tribe of Nagás Rainfall, 63 inches

Sámalkot—Town in Cocanáda *táluk*, Godávarí District, Madras Presidency —See CHANARLAKOTA

Sámarkha—Town in Kaira District, Bombay Presidency Lat $22^{\circ} 36'$ N, long $73^{\circ} 2'$ E. Population, including numerous hamlets (1872), 5231, not separately returned in the Census Report of 1881

Sambalpur—British District in the Chief Commissionership of the Central Provinces, lying between $21^{\circ} 2'$ and $21^{\circ} 57'$ N lat, and between $83^{\circ} 16'$ and $84^{\circ} 21'$ E long Area (exclusive of the petty Native States attached to the District), 4521 square miles Population in 1881, 693,499 souls The seven attached Native States of KAROND or KÁLAHANDI, RAIGARH, SUPANGARH, PATNA, SONPUR, RAIRAKHOL, and BAMRA (all of which see separately) have a total area of 11,897 square miles, and a population of 960,461 souls Total area of British District and Feudatory States, 16,418 square miles, total population, 1,653,960 souls Inclusive of the attached States, Sambalpur is bounded on the north by Chutá Nágpur, on the east and south by Cuttack District, Bengal, and on the west by Bilaspur and Ráipur Districts It is the easternmost District of the Chhatisgarh Division The administrative head-quarters are at SAMBALPUR TOWN

Physical Aspects—Though included in the Chhatisgarh Division, Sambalpur forms no part of Chhatisgarh proper, either geographically or historically The *khálsa* or Government portion of the District lies along the valley of the Mahánadí, and constitutes a centre round which are clustered the feudatory States and chiefships of BAMRA, KAROND,

in crossing the moat and forcing the Samlái gate. After a fierce contest, the Maráthás captured the fort, and carried off Jeth Singh and his son Maháráj Sá as prisoners to Nágpur. Bhúp Singh, a Maráthá *jamáddár*, was left to administer Sambalpur on behalf of the Nágpur Government. Soon, however, he assumed an independent position; and when a large force was sent from Nágpur to compel his obedience, he called in the aid of the Ráigarh and Sárangarh people, and routed the Maráthás at the Singhora Pass. A second force was sent from Nágpur, and assisted by Chamrá Gáonthiyá, whose enmity Bhúp Singh had provoked by plundering his village, seized the pass, and almost annihilated Bhúp Singh's army. The conquered chief fled to Sambalpur, and, taking with him the Ránís of Jeth Singh, made his way to Kolábirá. While there, he implored the help of the British on behalf of the Ránís; and Captain Roughsedge, with a portion of the Rámgarh local battalion, was sent to Sambalpur in 1804. Raghuji Bhonsla, the Rájá of Nágpur, however, remonstrated with the British Government for thus interfering with a country he had fairly conquered, and the British restored Sambalpur to him.

For some years, the District continued under Maráthá rule, while Jeth Singh and his son remained in confinement at Chándá; but Major Roughsedge pleaded their cause so energetically, that in 1817 Jeth Singh was restored to power. He died in the following year. After some months, during which the British Government held the country, Maháráj Sá, his son, was made Rájá, though without the feudal superiority of his predecessors over the other chiefships; while Major Roughsedge was established at Sambalpur as Assistant Agent. Maháráj Sá died in 1827, and his widow, Rání Mohan Kumári, succeeded. Disturbances immediately broke out, the most prominent of the rebels being Surendra Sá and Govind Singh, both Chauháns and pretenders to the chiefship. Villages were plundered to within a few miles of Sambalpur; and though Lieutenant Higgins drove off the rebels, it became necessary for the Agent, Captain Wilkinson, to proceed from Hazáribágh to Sambalpur. After hanging some of the insurgents, Captain Wilkinson deposed the Rání, and set up in her place Náráyan Singh, a descendant by a woman of inferior caste from Baliár Singh, third Rájá of Sambalpur. Náráyan Singh accepted his elevation very unwillingly, foreseeing the difficulties which followed immediately on the withdrawal of the British troops. Balabhadra Sá, the Gond chief of Lakhanpur, was the first to rise, but at length he was killed at his refuge in the Bará Pahár hills.

In 1839, Major Ouseley became Assistant Agent at Sambalpur; and in the same year great disturbances occurred, caused chiefly by Surendra Sá, who claimed the throne as being descended from Madhukar Sá, fourth Rájá of Sambalpur. In 1840, he and two of his relations murdered

the son and father of Daryáo Singh, chief of Rámpur, and were sent as life prisoners to the jail of Chutrá Nágpur. In 1849, Náráyan Singh died without male issue, and Sambalpur, lapsed to the British Government. The first acts of the new rulers were to ruse the revenue assessments by one fourth, and to resume the land grants, religious or otherwise. The Brahmans, a powerful community in Sambalpur, went up in a body to Ráncól to appeal, but gained no redress. In 1854, a second land settlement again raised the assessments every where by one fourth. Such a system of exaction and confiscation produced its natural results. When the Mutiny broke out three years later, the sepoy released Surendra Sá and his brother from jail, who immediately proceeded to Sambalpur. Nearly all the chiefs at once joined them, though Govind Singh the rival pretender of 1827, held aloof.

Surendra Sá established himself with a large force in the ruins of the old fort, but was induced to give himself up to Captain Leigh. Soon afterwards however, he escaped, and joined the rebels in the hills. From that time to 1862, the British troops in vain endeavoured to hunt him down. The most daring atrocities were committed by his band. Villages friendly to the Government were plundered and burnt, Dr Moore a European officer was murdered and Lieutenant Woodbridge was killed in a fight on the Bará Pahár, and his head carried off. The proclamation of amnesty failed to win the submission of the rebels. In 1861, Major Impey was placed in charge at Sambalpur, and adopted a conciliatory policy. By lavish rewards to the chiefs who gave themselves up, he succeeded in dispersing the rebel band, and procuring the surrender in May 1862 of Surendra Sá himself. The next year, however, the disturbances recommenced. Sambalpur had recently been incorporated with the Central Provinces, and the opportunity was seized of the first visit of Mr Temple, the Chief Commissioner, to present a petition praying for the restoration of native rule in the person of Surendra Sá. This was followed by the rising of Kamal Singh, one of Surendra Sá's captains during the rebellion, and by the recurrence of aggravated outrages. At length on 23rd January 1864, Surendra Sá was finally arrested. No legal proof of his complicity with the rebels was forthcoming, but he was placed in confinement with some of his relations and adherents as a dangerous political offender, and since then profound peace has reigned throughout the District.

Population — The Native States attached to Sambalpur District are elsewhere noticed in their respective places. (See KAROND, SONPUR, RAIKAKHOL, RAIGARH, BANRA, PATNA, and SARANGARH.) The following statistics will therefore be confined to the *Khilsa* country—the British District. A rough enumeration of the population was taken in 1866, but its results cannot be relied on in this District. The Census of 1872 disclosed a population of 523 034 persons. The

last enumeration in 1881 returned a total population of 693,499, showing an apparent increase of 170,465 persons, or 32·6 per cent., in nine years. The increase of registered births over deaths accounts for 13·1 per cent. of the increase, the balance being attributed almost entirely to defective enumeration in 1872, especially in the *samíndarí* tracts.

The results arrived at by the Census of 1881 may be summarized as follows:—Area of District, 4521 square miles, with 1 town and 3256 villages; number of houses, 168,381, namely, occupied 160,359, and unoccupied 8022. Total population, 693,499, namely, males 346,549, and females 346,950. Average density of population, 153 persons per square mile; towns and villages per square mile, 0·72; persons per town or village, 213; houses per square mile, 35·5; persons per house, 4·3. Classified according to sex and age, there are—under 15 years, boys 157,661, and girls 150,836; total children, 308,497, or 44·5 per cent. of the population: 15 years and upwards, males 188,888, and females 196,114; total adults, 385,002, or 55·5 per cent.

Religion.—Classified according to religion, the population of Sambalpur District consists of—Hindus, 632,747, or 91·2 per cent.; Kabírpánthís, 10,120; Satnámis, 212; Kumbhípathías (only found in Sambalpur District), 692; Muhammadans, 2966; Christians, 110; and tribes professing aboriginal religions, 46,652. The total aboriginal population by race as apart from religion, however, is returned at 231,520, namely, Gonds, 57,327; Savars or Sauras, 65,845; Baigás, 40,696; Kurás, 18,643; Kandhs, 16,672; Kols, 40,696; Kawárs, 2303; and Bhíls, 421.

Among the recognised Hindu castes, Bráhmans number 21,828; Rájputs, 5644; and Káyasths, 2159. The lower-class Hindus, who comprise the great mass of the population, include the following castes:—Gaur, 79,079; Gándá, 78,622; Koltá or Kolitá, 67,102; Keut or Kewát, 27,453; Telí, 22,250; Máli, 10,824; Chamár, 9523; Dumál, 9006; Dhobí, 7387; Panká, 6637; Ghasiá, 6543; Lohár, 6557; Kumbhár, 6148; Kallár, 6061; Náí, 4828; Banjárá, 4370; Korí, 3486; Marár, 2596; Kurmí, 2156; Koshtí, 1941; Sonár, 1895; and Mahár, 1286.

Town and Rural Population.—The population is entirely rural, and Sambalpur town (population in 1881, 6658) is the only place which contains upwards of five thousand inhabitants. Of the 3256 villages, no less than 2064 are mere hamlets with less than two hundred inhabitants; 923 contain between two hundred and five hundred; 244 between five hundred and a thousand; 21 between one thousand and two thousand; 3 between two thousand and three thousand; and 1 between three thousand and five thousand inhabitants.

As regards occupation, the Census Report divides the male popula-

tion into the following six classes —(1) Professional class, including civil and military, 5206, (2) domestic class, including inn and lodging house keepers, 2597, (3) commercial class, including bankers, merchants, traders, carriers, etc., 3917, (4) agricultural and pastoral class, including gardeners, 166,420, (5) manufacturing and industrial class, including all artisans, 31,845, and (6) indefinite, non productive, and unspecified class, comprising general labourers and male children, 3299

Agriculture—Of the total area of 4521 square miles in the British District, only 1125 square miles were cultivated in 1883-84, and of the portion lying waste, 888 square miles were returned as cultivable, while 2508 square miles are uncultivable. Of the total area, however, 161 miles are held revenue free, leaving 4360 square miles assessed for Government revenue, of which 1018 square miles were cultivated, 880 square miles available for cultivation, and 2462 square miles uncultivable waste. Even of this area, 2891 square miles are comprised within 20 estates or *zamindari* chiefships, paying a quit rent or tribute of only £1401, or an average of one penny per cultivated acre. The Government land revenue proper is derived from 1469 square miles, of which 498 square miles are cultivated, 37 square miles available for cultivation, and 934 square miles uncultivable waste. Total Government land revenue with local cesses, excluding the *zamindaris*, £10 196, or an average of 7½d per cultivated acre. Irrigation in 1883-84 was practised on 79515 acres, entirely by private enterprise.

Rice forms the staple crop, and in 1883 occupied 579,991 acres. No wheat is grown, but other food grains were produced on 61,748 acres, while 31563 acres were devoted to oil seeds, 33,484 acres to cotton, and 9449 acres to sugarcane. The agricultural stock in 1883-84 was thus returned—cows, bullocks, and buffaloes, 222,053, horses, 684, ponies, 963, sheep and goats, 39,202, pigs, 1063, while carts numbered 12,138, and ploughs 51,177.

Of the adult male and female agricultural population in 1881, namely, 252,419, landed proprietors were returned as numbering 4411, tenant cultivators, 147,745, assistants in home cultivation, 262, agricultural labourers, 33,651, the remainder being made up of graziers, tenants of unspecified status, estate agents, etc. Area of cultivated and cultivable land available for each adult agriculturist, 5 acres. The ordinary price of rice in 1883-84 was 3s per cwt. Skilled labourers earn from 6d to 8d per day, and unskilled labourers 2½d to 3d per day.

Trade and Commerce—The manufactures of Sambalpur are few and unimportant. The Koshits, however, weave *lasar* silk cloth of an even texture and unfading lustre, and the Kánwárs manufacture vessels of brass and bell metal. Nearly every village also contains weavers of

coarse cotton cloth, and the Sonárs make rude ornaments of gold and silver. The principal exports from the District are rice, oil-seeds, raw sugar, stick-lac, *tasar* silk, cotton, and iron. Principal imports—salt, refined sugar, European piece-goods, cocoa-nuts, muslins, fine cloths of native make, and metals. The chief trade is with Cuttack and Mírzápur. In the Orissa famine of 1866–67, no less than 30,178 *maunds* (about 1100 tons) of rice, valued at £10,171, were exported to Cuttack. None of the roads in Sambalpur are bridged or metalled. The chief lines of communication are the roads from Sambalpur town to Raipur *viâ* Sankra on the Jonk river; and to Cuttack *viâ* Rairákhól and Angúl. Tracts also lead from Sambalpur to the Biláspur frontier, by Padmapur and Chandrapur, to Bínka, and towards Ránchí. The Mahánadi affords means of communication by water for 90 miles.

Administration.—In 1861, Sambalpur was formed into a separate District of the British Government of the Central Provinces. It is administered by a Deputy Commissioner, with Assistants and *tahsildárs*. Total revenue in 1883–84, £22,445, of which the land yielded £11,387. Total cost of District officials and police of all kinds, £9537; number of civil and revenue judges of all sorts within the District, 8; magistrates, 9. Maximum distance from any village to the nearest court, 66 miles; average distance, 25 miles. Number of regular and town police, 365, costing £4721; being 1 policeman to about every 12·4 miles and every 1900 inhabitants. The daily average number of convicts in jail in 1883 was 127, of whom 11 were females. The number of Government or aided schools in the District under Government inspection in 1883–84 was 136, attended by 7817 pupils. The Census Report of 1881 returned only 3434 boys and 171 girls as under instruction, besides 10,114 males and 298 females able to read and write, but not under instruction.

Medical Aspects.—The average temperature in the shade at the civil station during 1883 is returned as follows:—May, highest reading 116·2° F., lowest 75·3° F.; July, highest 101·3° F., lowest 72·3° F.; December, highest 79·7° F., lowest 46·8° F. The rainfall for that year amounted to 78·51 inches, the average being 57·5 inches. The climate of Sambalpur is considered very unhealthy. The prevailing disease is fever, especially from September to November. It proves most fatal to new-comers, natives as well as Europeans. Bowel complaints are also common and deadly, and cholera appears nearly every hot season, owing to the gatherings at the temple of Jagannáth at Purí. In 1883, two charitable dispensaries afforded medical relief to 21,035 in-door and out-door patients. The death-rate per thousand in 1883–84 was returned at 26·19, the mean of the previous five years being 26·07, but these figures cannot be trusted. [For further information regarding Sambalpur, see the *Central Provinces Gazetteer*, by Mr. (now Sir

Charles) Grant (Nágpur, 1870) Also the *Report of the Land Settlement of Sambalpur District*, between 1872 and 1877, by Mr A M Russell, published 1883, the *Central Provinces Census Report* for 1881, and the several annual Administration and Departmental Reports of the Central Provinces Government]

Sambalpur—*Tahsil* or Sub division of Sambalpur District, Central Provinces Area, 1500 square miles, with 1 town and 1499 villages, and 69,418 houses Population (1881) 297,361, namely, males 147,973, and females 149,388, average density of the population, 169 1 persons per square mile Of the total area of the *tahsil*, 893 square miles are comprised within nine *zamindari* estates or chiefships, which pay only a nominal tribute or quit rent, while 135 square miles are held entirely revenue free The Government revenue paying lands occupy an area of 730 square miles, of which 241 square miles are cultivated, 14 square miles are cultivable, and 475 square miles are uncultivable waste Total adult agricultural population, 67,462, or 40 17 per cent of the whole population in the *khalsa* or Government tract Average area of cultivated and cultivable land available for each adult agriculturist, 3 acres Total Government land revenue, including local rates and cesses levied on land, £3960, or an average of 5d per cultivated acre Sambalpur *tahsil* contained in 1883, 5 civil and 7 criminal courts (including the District head quarters courts), with 4 police stations (*thánds*) and 11 outpost stations, a regular police force numbering 97 men, and a village watch or rural police of 715 *chaukidars*

Sambalpur—Principal town and administrative head quarters of Sambalpur District, Central Provinces The town is situated in lat 21° 27' 10" N, and long 84° 1' E, on the north bank of the Mahánadi, which, during the rainy season, becomes nearly a mile broad, but at other times flows in a small stream 50 yards in width Opposite the town and station, the river bed is a mass of rocks covered with thick *jhídu* jungle, on each side the banks are richly wooded with mango and other groves, while to the south rises a stately background of lofty hills Population (1872) 11,020, (1881) 13,939, namely, males 6658, and females 7281 Hindus number 10,619, Muhammadans, 1298, Kumbhípathís, 79, Kabírpanthís and Satnámís, 6, Christians, 104; and tribes professing aboriginal religions, 1833 Municipal income in 1882-83, £1808, of which £1531 was derived from taxation, average incidence of taxation, 2s 3½d.

The town proper has been much improved since 1864, when a cart could only with great difficulty pass through the main street To the north west lie the ruins of the fort—a crumbling stone wall on the river face, and a few mouldering bastions The moat can still be traced, but no gateway remains except that of Samláí, near the temple of the goddess of that name, who was apparently the tutelary divinity of

Sambalpur. Within the fort stand several other temples, the principal of which are those of Padmeswari Devi, Bará Jagannáth, and Anant Sajjá, all built during the 16th century. They are of uniform design, and remarkable neither for elegance nor solidity. Beyond the fort extends the Bará Bázár, originally a mere market-place, but now a populous suburb. Besides the Government court-house and the Sub-divisional office on the river bank, the principal buildings are the Commissioner's circuit-house, post-office, a jail lately built on the standard plan, and 2 *saráis*, as well as a handsome terrace-roofed market-place. A native gentleman has lately built a dispensary with female wards, and a District schoolhouse. Till recently, cholera visited the town almost every year, owing chiefly to the influx of pilgrims returning from Purí. Of late, however, sanitary precautions have done much to prevent the epidemic, and the increase of vaccination is gradually restraining the ravages of small-pox.

Sambhal.—*Tahsíl* of Moradábád District, North-Western Provinces, lying in the plain country between the Sot and the Ganges, conterminous with Sambhal *parganá*. It is about 32 miles long by 15 miles broad, and consists of two great natural divisions, the *katehr* or 'hard,' and the *bhúr* or sandy tracts. Their border-line runs north-east and south-west, down the centre of the *tahsíl*, parallel to the course of the Sot. The low lands of that river form a belt of from two to three miles wide, right through the *katehr* tract. The soil of the *katehr* is described as of a dark colour, assimilating in appearance to *matiyár*; and some villages in which it predominates are among the finest in the District. The *bhúr* or sandy tract consists of ridges of loose, soft sand, alternating with extensive flats of more cohesive soil, in which there is a very slight admixture of loam. All over the *bhúr* tract are large unploughed wastes, utilized in dry seasons as grazing grounds. Several important but unmetalled roads meet at Sambhal town.

The total area of Sambhal *tahsíl* in 1881-82 was 468·74 square miles, of which 443·13 square miles were assessed for Government revenue, namely, 360·34 square miles cultivated, 55·69 square miles cultivable, and 27·10 square miles uncultivable. Population (1881) 248,107, namely, males 130,441, and females 117,666; average density of population, 530 persons per square mile. Classified according to religion, Hindus numbered 173,850; Muhammadans, 73,808; Christians, 273; and Jains, 180. Of the 465 towns and villages comprising the *tahsíl*, 323 had less than five hundred inhabitants; 111 between five hundred and a thousand; 28 between two and three thousand; and 3 upwards of five thousand inhabitants. Total Government land revenue (1881-82), £35,291, or including local rates and cesses levied on land, £39,832. Total rental paid by cultivators, including cesses, £81,181. Sambhal *tahsíl* contained in 1885, 1 civil and 2 criminal courts;

number of police circles (*thānas*), 3, strength of regular police, 79 men, village watch or rural police (*chaukidars*), 424

Sambhal — Town and municipality in Moradābād District, North Western Provinces, and head quarters of Sambhal *tahsil*, situated in lat $28^{\circ} 35' 5''$ N, and long $78^{\circ} 36' 45''$ E, on the Aligarh road, 23 miles south west of Moradābād town, and 4 miles west of the Sot river, in the midst of a cultivated and well wooded plain. The modern town covers the summit of an extensive mound, composed of remains and *debris* of the ancient city. Two heaps of ruins, known as Bhaleswar and Bikteswar, mark the old bastions of the city wall. The town formed the head-quarters of the local Government from the earliest period of Muhammadan supremacy, and was the capital of a *sarkar* under Akbar. Population (1881) 21,373, namely, males 10,659, and females 10,714, number of houses, 4710. Classified according to religion, Muhammadans number 13,965, Hindus, 7333, Jains, 38, and Christians, 37. Municipal income (1883-84) £1588, of which £1471 was derived from taxation, average incidence of taxation, 10d per head of the population (35,196) within municipal limits.

Sambhal is a prettily situated town, with the houses mostly built of brick. Only in the town and suburbs are there any metalled roads, but unmetalled ones connect it with Moradābād, Bilān, Amroha, Chandausi, Bahjoi, and Hasanpur. The public buildings include the *tahsil* or sub collectorate offices, *munsifs* or subordinate judges' court, police station, post office, dispensary, American mission church and schools, several municipal schools, distillery, and a *sardis* or native inn. Refined sugar is the chief manufacture, and also the principal article of trade. Wheat and other grains and *ghī* are also exported, and there is some export of hides. Cotton cloth is manufactured, but chiefly for local wants.

Sambhar — Great salt lake in the States of Jaipur (Jepore) and Jodhpur, Rājputāna. The lake lies between $26^{\circ} 52'$ and $27^{\circ} 2'$ lat, and between $74^{\circ} 57'$ and $75^{\circ} 16'$ E long, on the border of the States, 40 miles north west of Ajmere, and with a range of hills which mark the general north westward run of the range as it begins to lose continuity and to subside. The lake is a round slopes towards the lake, which thus forms a great lake with an outlet, containing a shallow sheet of water. The surrounding country is arid and sterile, being composed of rocks abounding in salt, and belonging to the Permian system, and it is supposed that the salt of the lake is derived from the washings of these rocks. The bottom consists of a tenacious black mud, resting on a layer of sand. When full, the lake forms a sheet of water measuring 2½ miles in length, from 3 to 10 miles in breadth, and from 1 to 2 miles in depth.

After the rains, in August and September, the waters of the lake begin to evaporate, and this process goes on almost uninterruptedly from October to June. In very hot and dry summers, the wet bed is little more than a mile in length and less than half a mile across. The lake's longest stretch is nearly east and west; and the deeper portion, which never dries up, and which is locally called 'the treasury,' is situated near the centre of the lake, almost opposite a bold rocky promontory (Máta-ki-devi) which juts out from the southern shore.

In the dry season, the view of the lake is very striking. Standing on the low sandy ridges which confine the basin on the south, one may see what looks like a great sheet of snow, with pools of water here and there, and a network of narrow paths marking the near side of it. What appears to be frozen snow is a white crisp efflorescence of salt. The salt is both held in solution in the water of the lake, and also pervades in minute crystals the whole substance of black mud that forms so large a part of its bed.

This valuable property has often been fiercely contested. The lake was worked by the Imperial administration of Akbar and his successors up to the time of Ahmad Sháh, when it fell back into the hands of the Rájput Chiefs of Jaipur and Jodhpur. The eastern shore, and part of the southern shore, are now the joint possession of Jaipur and Jodhpur; the rest belongs to Jaipur. During the ten years 1835 to 1844, the Government of India, in order to repay itself a portion of the expenses incurred in repelling the predatory incursions of the Rájputs into British territory, took the salt-making into its own hands; but with this exception, the lake has been owned and worked jointly by the Jaipur and Jodhpur Governments from the 17th century to 1870, when the British Government became lessees under separate treaties concluded with the two chiefs.

As soon as the salt is formed, native labourers of both sexes wade out to it through the mud, and placing their hands under the salt crust, lift it off in good-sized cakes into baskets. A man brings to shore in this way about half a ton of salt a day. The salt is also made in shallow pans, into which the brine is baled; and in walled enclosures, the beds of which are sunk below the level of the lake. Nearly the whole of the salt extracted is white or slightly discoloured. Some portions are blue and red, the varieties being said to be due to the presence of microscopic algæ. The Sámbar lake supplies nearly all the chief salt marts of the Punjab, the North-Western Provinces, and Central India. The town of Sámbar within the joint jurisdiction of Jaipur and Jodhpur States, and Nawa and Gudha in Jodhpur State on the opposite side of the lake, have recently been connected by a branch line with the Rájputána-Málwá Railway. According to travellers in the early part of this century, the dimensions of the lake were larger

than they are at present, and reached as much as 50 miles in length by 10 in breadth during periods of heavy rain

The average yearly out turn for the 15 years ending 1883-84, since the Government of India leased the lake, has been 2,800 000 *maunds* (about 100 000 tons) The average cost of storage and extraction, about 6 *pies* (three farthings) a *maund* (82½ lbs) From the beginning of the lease to 1883-84, the quantity of salt manufactured was 42,039,480 *maunds* (about 1,500 000 tons), the total sales amounted to 31,998,365 *maunds*, yielding a revenue of £1,393,739, total charges, including treaty payments, £1,210,983, net credit balance, £182,756 In 1883-84, the total quantity of salt manufactured at Sambhar lake was 7,111,353 *maunds* Gross realizations, including duty, £880,606, the direct charges amounted to £58,395, and payments made under treaties, £75,495, total, £133 890, leaving a surplus of £746,716 The labour employed in 1883-84 was—labourers, 421,925, carts, 38,757, cattle, 33,987

Sámbar—Town within the joint jurisdiction of Jaipur and Jodhpur States, on the bank of the Sámbar lake, Rájputána, situated 39 miles south west of Jaipur city Population (1881) 5574 Hindus number 4831, and Muhammadans 743 A station on the Sámbar branch of the Rájputána Málwá Railway Dispensary and post office

Sambhuganj—Village in Maimansingh District, Bengal, 3 miles east of Nasrábád Population (1881) 938 One of the busiest marts in the District for country produce of all kinds large exports of jute In 1876-77, the registered exports from Sambhuganj included 72,000 *maunds* of jute (mostly sent direct to Calcutta), 31,000 *maunds* of rice, and 9500 *maunds* of mustard seed No later trade statistics are available

Sameswari (*Somesuari, or Samsang*)—River in the Gáro Hills, Assam Rising near the station of Turá, it flows first in an easterly direction along the north of the Turá range, and then turns south through a picturesque gorge and finds its way into the plains in the Bengal District of Maimansingh It finally empties itself into the Kanks river in *pargana* Susáng Both in size and utility, the Sameswari is the most important river in the Gáro Hills It is navigable up-stream as high as Siju, about 20 miles within the hills Here its channel is interrupted by a bed of granite rocks and rapids In several other portions of its course it again becomes navigable for canoes Valuable outcrops of coal have been discovered and surveyed in the Sameswari valley, but none has yet been worked Limestone of good quality abounds on the river banks, and there are some curious caverns in the limestone formation The largest of these caves lies near Siju, and has been explored for a whole day without reaching the source of a small stream which issues from the cave Above Siju, the Sameswari flows through

a tract of sandstone, in which extensive coal-beds have been discovered on both sides of the river; but up to 1884 they had not been worked otherwise than experimentally. In its upper course are several magnificent gorges, with rocky cliffs, clothed in tropical vegetation. The water swarms with fish, including the excellent *máhsir*; and the Gáros are enthusiastic fishermen.

Sami.—Town in Rádhanpur State, Bombay Presidency.—See SHAMI.

Samla.—Petty State in the Jháláwár division of Káthiáwár, Bombay Presidency; consisting of 2 villages, with 4 separate tribute-payers or shareholders. Area, 13 square miles. Population (1881) of the State, 1330; and of Samla village, 757. Estimated revenue, £762; of which £96 is paid as tribute to the British Government, and £10, 8s. to the Nawáb of Junágarh.

Sámnagar.—Town in the Twenty-four Parganá District, Bengal.—See SYAMNAGAR.

Samod.—Town in Jaipur State, Rájputána. A large and flourishing town, the principal place of Samod *samíndári*. It is defended by a fort of some strength on the summit of a hill, at the base of which the town stands. Samod *samíndári* is held by one of the principal *thákurs* of Jaipur State, and yields an annual revenue of £11,000.

Sampaji Ghát.—One of the passes connecting South Kánara District, Madras Presidency, with Coorg. Good road; practicable for wheeled carriages.

Sámpgáon.—Sub-division of Belgáum District, Bombay Presidency. Area, 425 square miles; villages, 123. Population (1872) 131,504; (1881) 119,843, namely, males 59,565, and females 60,278. Hindus number 106,552; Muhammadans, 10,027; and 'others,' 3264. Sámpgáon has great variety of soil and surface. From the hilly west, the country gradually sinks eastwards into a great black cotton plain. In the south-west, ranges of quartz and ironstone, about 150 feet high, and a quarter to half a mile apart, run nearly north and south. The Malprabha river crosses the middle of the Sub-division from west to east. Of a total area of 424 square miles, 22 square miles are occupied by the lands of alienated villages. The rest contains 217,179 acres of cultivable land, of which 52,998 acres are alienated lands in Government villages; 4223 acres, uncultivable land; 1277 acres, grass; 16,627 acres, forests; and 12,927 acres, village sites, roads, etc. In 1881-82, out of 158,320 acres held for tillage, 18,598 acres were under grass. Of the remaining 139,722 acres, 17,726 acres were twice cropped. Cereals and millets occupied 115,281 acres; pulses, 18,637 acres; oil-seeds, 3504 acres; fibres, 16,452 acres; and miscellaneous crops, 3574 acres. In 1883-84 the Sub-division contained—criminal courts, 2; police circles (*thánás*), 6; regular police, 49 men; village watch (*chaukidárs*), 489. Land revenue, £23,913.

Sámpgáon—Town in Belgaum District, Bombay Presidency, and head-quarters of Sámpgaon *taluk*, situated about 18 miles south east of Belgaum town, in lat $15^{\circ} 36' N$, long $74^{\circ} 50' E$. Population (1881) 3629. Besieged and captured in 1683 by Akbar's son, Prince Muhammad Muazzam. Towards the end of the seventeenth century, the founder of the Kittur Desai family settled at Sámpgáon, which lapsed to Government after the Kittur outbreak in 1824. Sámpgaon has a few looms, weekly market on Sundays, when cattle, cloth, cotton, and grain are sold. Post office, library, two schools, one for girls, and an old mosque.

Sámpla—East central *tahsil* of Rohtak District, Punjab. Area, 417 square miles, towns and villages, 123, houses, 19,855, families, 30,516. Total population (1881) 142,177, namely, males 76,004, and females 66,173. Average density of population, 341 persons per square mile. Classified according to religion, the population consists of—Hindus, 129,508, Muhammadans, 12,394, Jains, 263, Sikhs, 11, and 'others,' 1. Of the 123 towns and villages, 33 contain less than five hundred inhabitants, 37 between five hundred and a thousand, 52 between one and five thousand, and 1 between five and ten thousand inhabitants. The average area under tillage for the five years ending 1881–82 is returned at 306 square miles, or 195,909 acres, the area under the principal crops being as follows—*jodr*, 47,134 acres, *bajra*, 41,043 acres, gram, 32,265 acres, wheat, 25,036 acres, barley, 17,076 acres, other food grains, 1352 acres, cotton, 14,279 acres, sugar cane, 6078 acres, the remainder consisting of a little vegetables, indigo, and tobacco. Revenue of the *tahsil*, £25,898. The local administrative staff consists of a *tahsildár* and an honorary magistrate, presiding over 1 civil and 2 criminal courts. Number of police circles, 3, strength of regular police, 69 men, village watch or rural police, 217.

Sámpla—Village in Rohtak District, Punjab, and head-quarters of Sámppla *tahsil*, situated in lat $28^{\circ} 47' N$, and long $76^{\circ} 49' E$, on the Rohtak and Delhi road, half way between Rohtak town and Bahádurgarh. *Tahsili*, police station, post office, village school, and *sarai*.

Samra (Semra)—Town in Ihtimadpur *tahsil*, Agra District, North Western Provinces, situated in lat $27^{\circ} 19' 26' N$, long $78^{\circ} 7' 10' E$, 14 miles north west from Ihtimadpur town. Population (1881) 4797. Bi weekly market, and village school.

Samrála—Eastern *tahsil* of Ludhiána District, Punjab. Area, 288 square miles. Population (1881) 152,509, namely, males 84,838, and females 67,671, average density of population, 530 persons per square mile. Classified according to religion, there are—Hindus, 89,154, Muhammadans, 46,223, Sikhs, 16,893, and 'others,' 239. Revenue of the *tahsil*, £27,577. The local administrative staff consists of a

tahsildár and a *munsif*, presiding over 1 criminal and 2 civil courts. Number of police circles (*thánds*), 3; strength of regular police, 58 men; village watch or rural police, (*chaukidárs*), 244. Samrála, the head-quarters of the *tahsíl*, is a small village, and was only chosen as such on account of its central position.

Samsa Parvat.—Peak of the Western Gháts bordering on South Kánara District, Madras Presidency, 6300 feet high. Lat. $13^{\circ} 8' N.$, long. $75^{\circ} 18' E.$ The hill is used as a sanitarium by the European residents of South Kánara; there are two bungalows, but no village; easy access by road (56 miles) from Mangalore. The climate, except from June to September, during the south-west monsoon, is delightful; and for sportsmen there is abundance of game. Wood, water, and grass are also plentiful. There is no plateau, properly speaking, but undulating ground along the line of the mountain for some miles. English fruits, flowers, and vegetables grow well, and in most respects the climate and soil resemble those of COONOR (Kunur).

Sámthar (*Samphthar*, *Sumpter*).—Native State in Bundelkhand, under the political superintendence of the Bundelkhand Agency, Central India; lying between $25^{\circ} 42'$ and $25^{\circ} 57' N.$ lat., and between $78^{\circ} 51'$ and $79^{\circ} 11' E.$ long. Area, 174 square miles. Population (1881) 38,633, namely, males 20,403, and females 18,230; occupying 7131 houses, in 1 town and 87 villages. Hindus number 36,195; Muhammadans, 2284; Jains, 56; Christians, 5; and aboriginal tribes (Moghias), 93. Estimated revenue, £40,000. Sámthar is bounded on the north and west by Gwalior; on the south-west, south, and south-east by the British District of Jhánsi; and on the east by Jaláun District. The State of Sámthar was separated from Datiya only one generation previous to the British occupation of Bundelkhand. When the British first entered the Province, Rájá Ranjít Singh requested to be taken into the friendship and under the protection of the British Government; but nothing definite was done till 1817, when a treaty was concluded with him. The chief is entitled to a salute of 11 guns. He has received the right of adoption. The military forces of the State are 300 cavalry and 2000 infantry, with 35 guns and 150 gunners.

Sámthar.—Chief town of Sámthar State, Bundelkhand, Central India. Lat. $25^{\circ} 51' N.$, long. $78^{\circ} 55' E.$ Population (1881) 7891, namely, Hindus, 6905; Muhammadans, 980; and 'others,' 6.

Sámulkota (*Chámarlákota*).—Town in Cocanáda *táluk*, Godávári District, Madras Presidency.—See CHAMARLAKOTA.

Sanála.—Petty State in the Gohelwar division of Káthiáwár, Bombay Presidency; consisting of 1 village, with 2 separate tribute-payers or shareholders. Area, 51 square miles. Population (1881) 500. Estimated revenue, £270; £30, 14s. is paid as tribute to the Gáekwár of Baroda, and 30s. to the Nawáb of Junágarh.

Sánand—Sub-division of Ahmadábád District, Bombay Presidency Area, 360 square miles Population (1872) 73,229, (1881) 76,964, namely, males 39,249, and females 37,715, occupying 20,194 houses, in 1 town and 84 villages Hindus number 68,811, Muhammadans, 4690, and 'others,' 3463 Except an undulating strip of land on the west, Sánand is in the centre a rich plain of light soil with well wooded fields, and in the south and west a barer stretch of black soil The people live in prosperous villages, with several fine ponds Water supply generally good Of a total area of 360 square miles, 162 square miles belong to alienated and *tilukdári* villages The remainder contains 126,547 acres of occupied land, of which 38,696 acres are alienated land in Government villages, 69,525 acres cultivable waste, 39,703 acres uncultivable waste, and 17,319 acres village sites, roads, etc In 1860-61, the year of settlement, 5674 holdings were recorded, with an average area of $12\frac{1}{2}$ acres, paying an average Government assessment of £1, 9s. 0 $\frac{1}{2}$ d In 1877-78, 74,517 acres were under actual cultivation, of which 657 acres were twice cropped Cereals and millets occupied 62,144 acres, pulses, 2771 acres, oil seeds, 1264 acres, fibres, 8163 acres, and miscellaneous crops, 832 acres In 1883 the Sub-division contained—criminal courts, 2, police circle (*thánda*), 1, regular police, 54 men, village watch (*chaukidárs*), 292 Land revenue, £17,628

Sánand—Chief town of the Sanand Sub-division of Ahmadábád District, Bombay, situated 16 miles west of Ahmadábád city, in lat 22° 59' N, and long 72° 25' 30" E Population (1881) 6984 Hindus numbered 5463, Muhammadans, 299, Jains, 112, Christian, 1, and 'others,' 9 Sánand is a station on the Bombay, Baroda, and Central India Railway, 18 miles from Ahmadábád Post-office, dispensary, and *dharmshála*

Sanavárapeta—Town in Ellore *tiluk*, Godávári District, Madras Presidency Population (1881) 3100 Hindus numbered 2773, and Muhammadans 427 Number of houses, 597

Sanáwan—Northern *tahsil* of Muzaffargarh District, Punjab, consisting of a high central upland, almost barren, known as the *thal*, together with two strips of lowland along the banks of the Indus and the Chenab Area, 1327 square miles, number of towns and villages, 127, houses, 15,413, families, 17,177 Population (1881) 80,851, namely, males 43,656, and females 37,195 Average density of population, 61 persons per square mile Classified according to religion, Muhammadans numbered 71,584, Hindus, 9555, and Sikhs, 712 Of the 127 towns and villages, 76 contain less than five hundred, 29 between five hundred and a thousand, and 22 between one and five thousand inhabitants The average area under tillage for the five years ending 1881-82 is returned at 158 $\frac{1}{2}$ square miles, or 101,438 acres,

the area under the principal crops being—wheat, 51,796 acres; *joar*, 6960 acres; *bájra*, 6504 acres; gram, 2795 acres; *moth*, 2052 acres; barley, 1829 acres; rice, 633 acres; cotton, 8334 acres; indigo, 3981 acres; tobacco, 259 acres; sugar-cane, 105 acres; and vegetables, 382 acres. Revenue of the *tahsil*, £14,099. The local administrative staff consists of a *tahsildár* and an honorary magistrate, presiding over 1 civil and 2 criminal courts. Number of police circles (*thánás*), 2; strength of regular police, 51 men; village watch or rural police (*chaukidárs*), 105.

Sanáwar.—Plot of land in Simla District, Punjab. Made over by the British Government in 1852 as the site of the Lawrence Military Asylum. The buildings stand in lat. $30^{\circ} 54' 35''$ N., and long. $77^{\circ} 2' 10''$ E., on a wooded hill facing Kasauli, which is 3 miles distant. They consist of boys and girls' schools, and the residences of the Principal, with a staff of teachers, and a church. The institution, which is undenominational, accommodates from 400 to 500 children. In September 1883, there were 424 boys and girls on the rolls, including 64 in the orphanage.

Sánchi.—Village in the Native State of BHOPAL, Central India; situated on the left bank of the Betwa river, about $5\frac{1}{2}$ miles south-west of Bhílsa, and 20 miles north-east of Bhopál city. Sánchi is famous as the site of some of the most extensive and remarkable Buddhist remains in India, the centre of the great group described by General Cunningham under the name of '*The Bhílsa Topes*.'

The present village of Sánchi is situated on a low ridge of sandstone, the general direction of which is from north to south, the whole summit of the hill being covered with ruins. The hill is flat-topped and isolated, with a steep cliff to the eastward, and to the westward an easy slope, covered with jungle at the foot, and near the top broken into steps by horizontal ledges of rock.

The principal buildings which now remain occupy only the middle part of the level summit, and a narrow belt leading down the hill to the westward. They consist of one great *stupa* or tope, with its railing and other adjuncts; about ten smaller *stupas*, some now showing nothing more than the foundations; a stone bowl, $4\frac{1}{2}$ feet in diameter and $2\frac{1}{2}$ feet deep, supposed to have once contained Buddha's holy nettle, and other objects of antiquarian interest. The summit of the hill, on which these remains are found, has a gentle slope in the same direction as the dip of the strata; and the level of the court of the great *stupa* is about 12 or 15 feet below that of a ruined *vihára* and temple on the eastern edge of the precipice. The hill, which is about 300 feet in height, is formed of a light red sandstone, hard and compact in texture, but subject to split. This stone has been used for all the topes and other buildings where mere hardness and durability

were required, but for the colonnades and sculptured gateways, a fine grained white sandstone was brought from the Udayagiri Hill, 3½ miles to the northward. The village is now very small, but the numerous ruins scattered over the hill between Sanchi and Kánakhhera show that there once was a large town on this site. Plaster casts of the gateways, etc., of the topes have been sent to England.

Fergusson (*History of Indian and Eastern Architecture*, 1876, page 61) thus writes of this group of remains —

‘The principal of these, known as the Great Tope at Sanchi, has been frequently described, the smaller ones are known from General Cunningham’s descriptions only, but altogether they have excited so much attention that they are perhaps better known than any group in India. We are not, however, perhaps justified in assuming, from the greater extent of this group as now existing, that it possessed the same pre-eminence in Buddhist times. If we could now see the topes that once adorned any of the great Buddhist sites in the Doab or Behar, the Bhilsa group might sink into insignificance. It may only be that, situated in a remote and thinly peopled part of India, they have not been exposed to the destructive energy of opposing sects of the Hindu religion, and the bigoted Moslem has not wanted their materials for the erection of his mosques. They consequently remain to us, while it may be that nobler and more extensive groups of monuments have been swept from the face of the earth.

‘Notwithstanding all that has been written about them, we know very little that is certain regarding their object and their history. Our usual guides the Chinese Pilgrims, fail us here. Fa Hian never was within some hundreds of miles of the place, and if Hsien Tsiang ever was there, it was after leaving Ballabhi (Valabhi), when his journal becomes so wild and curt that it is difficult, sometimes impossible, to follow him. He has, at all events, left no description by which we can now identify the place, and nothing to tell us for what purpose the Great Tope or any of the smaller ones were erected. The *Mahāvanso*, it is true, helps us a little in our difficulties. It is there narrated that Asoka when on his way to Ujjain of which place he had been nominated governor, tarried some time at Chétayagiri, or, as it is else where called, Vessanagara the modern Bīsnagar, close to Sanchi. He there married Devi, the daughter of the chief, and by her had twin sons, Ujjenio and Mahindo, and afterwards a daughter, Sanghamitta. The two last named entered the priesthood, and played a most important part in the introduction of Buddhism into Ceylon. Before setting out on this mission, Mahindo visited his royal mother at Chétayagiri, and was lodged in “a superb *vihara*,” which had been erected by herself. In all this there is no mention of the Great Tope, which may have existed before that time, but till some building is

found in India which can be proved to have existed before that age, it will be safe to assume that this is one of the 84,000 topes said to have been erected by Asoka. Had Sanchi been one of the eight cities which obtained relics of Buddha at the funeral pyre, the case might have been different; but it has been dug into, and found to be a *stupa*, and not a *daghoba*. It consequently was erected to mark some sacred spot or to commemorate some event, and we have no reason to believe that this was done anywhere before Asoka's time.

'On the other hand, two smaller topes on the same platform contained relics of an undoubted historical character. That called No. 2 Tope contained those of ten Buddhist teachers who took part in the third great convocation held under Asoka, and some of whom were sent on missions to foreign countries, to disseminate the doctrines then settled; and No. 3 Tope contained two caskets. One of these enclosed relics of Maha Moggalana, the other of Sariputra, friends and companions of Buddha himself, and usually called his right and left hand disciples. It does not of course follow that this *daghoba* is as old as the time of Buddha; on the contrary, some centuries must elapse before a bone or rag belonging to any mortal becomes so precious that a dome is erected to enshrine it. The great probability seems to be that these relics were deposited there by Asoka himself, in close proximity to the sacred spot which the Great Tope was erected to commemorate. The tope containing relics of his contemporaries must of course be much more modern, probably contemporary with the gateways, which are subsequent to the Christian era.'

San-daw (*Tshan-daw*).—A small pagoda situated amid the hills on the left bank of Sandoway town, Sandoway District, Arakan Division, Lower Burma. Built in 784 A.D. by King Nyo-kin, to enshrine a hair of Gautama. The inhabitants of Sandoway town spend one day at this temple in March, June, and October of each year, spending the other days during which their feasts last at the pagodas of An-daw and Nan-daw.

Sándi.—*Parganá* in Bilgrám *tahsíl*, Hardoi District, Oudh. Bounded on the north and west by *parganá*s Báwan, Barwán, and Katiári; on the south-west and south by the Ganges and *parganá* Bilgrám; and on the east by *parganá* Bangar. The *parganá* is intersected by the Garra river from north to south, and the Rámangá flows irregularly along or near its western and south-western border. It is divided into two distinct portions by an irregular sandy ridge, which, running from north to south immediately to the east of Sándi town, marks the bank of an ancient channel of the Ganges, long since abandoned by the river in its gradual westward recession. All the villages on and to the east of this ridge are poor, uneven, and sandy. Irrigation is scanty and difficult. On the other hand, all the country to the west of the ridge, or about four-fifths of the

total area of the *parganá*, is a distinctly alluvial tract, levelled and enriched by the floods of three Himálayan rivers, the Garra, Rámgangá, and Ganges, and by minor streams such as the Sendha. All this tract is *taráí*, that is to say, it has been scooped by fluvial action out of the adjacent *bangar* or original plateau, and in it the water level is always so near the surface, that in the dry months percolation largely supplies the want of irrigation, while in the rainy season it is more or less completely flooded. It constitutes, in fact, the flood basin of the three rivers named above. In heavy floods such as those of 1871, a sea of waters spreads from Sándi to Fatehgarh, 20 miles west. The rivers bring down a rich alluvial deposit locally called *seo*, which fertilizes the submerged fields and makes manuring unnecessary. The silt brought down by the Rámgangá in heavy floods is sometimes spread 2 feet thick over the fields. Area, 168 square miles, of which 107 square miles are cultivated. Chief products—wheat, barley, rice, *bajra*, gram, *joár*, and *arhar*. Population (1881) 72,830, namely, males 39,749, and females 33,081. Of the 141 villages in the *pargana*, 80½ are held by Rájputs, 26 by Muhammadans, 11½ by Bráhmans, 5½ by Lodhs, 4 by Káyasths, 1½ by Ahírs, and 12 by Government. *Táldukdárí* tenure prevails in 30½ villages, *zamindárí* in 61½, and *pattidárí* in 49. Government land revenue, £12,056, equal to an average of 3s 6d per cultivated acre, or 2s 3d per acre of total area.

Sándi—Town and municipality in Hardoi District, Oudh, and head quarters of Sandi *parganá*, situated on the left bank of the Garra river, on the old route from Sháhjahánpur via Sháhábád to Lucknow. Lat $27^{\circ} 17' 15''$ N, long $79^{\circ} 59' 45''$ E. A considerable town, with a population (1881) of 9810, namely, Hindus, 6780, Muhammadans, 3022, and Christians, 8. Municipal income (1883-84), £471, of which £366 was derived from taxation, average incidence of taxation, 9d per head. Sandi has a local reputation for the manufacture of a description of cotton carpets (*kalín*). Numerous handsome mosques and tombs of Muhammadan sults. A fine *sarái* or travellers' rest house is situated in the market in the Nawábganj quarter of the town.

Sandila—*Tahsil* or Sub-division of Hardoi District, Oudh, lying between $26^{\circ} 53'$ and $27^{\circ} 21' 4''$ lat., and between $80^{\circ} 18'$ and $80^{\circ} 52' 1''$ long. Bounded on the north by Hardoi and Miráikh, on the east by Mahmudábád, on the south by Malihábád and Mohan, and on the west by Bilsgrám *tahsils*. Area, 557 square miles, of which 317 are cultivated. Population (1881) 250,406, namely, Hindus 225,496, and Muhammadans 24,910. Number of males, 132,372, females, 118,034, number of villages, 415, average density, 449 persons per square mile. This *tahsil* comprises the four *parganas* of Sandila, Kalyanmaul, Balámau, and Gundwa. In 1883 it contained 4 civil and 6 criminal courts, including

a bench of Honorary Magistrates; number of police circles (*thánás*), 4; strength of regular and town police, 110 men; village watch or rural police (*chaukidárs*), 681.

Sandila.—*Parganá* of Hardoi District, Oudh. Bounded on the north by Gopámau; on the east by Gundwa and Kalyánmal; on the south and south-west by Mohan, Aurás, Safipur, and Bangarmau; and on the west by Bálamau and Mallanwán *parganá*s. A poorly wooded tract, with a large area of barren and sandy soil. Area, 329 square miles, of which 170 square miles are cultivated. Chief products—barley, wheat, *bájra*, gram, *arhar*, *mash*, and *joár*. At the time of the survey, barley occupied a fourth of the cultivated area; wheat a fifth; *bájra* and gram together, rather more than a fifth; while another fifth was under *arhar*, *mash*, *joár*, and rice. Other crops—cotton, sugar-cane, poppy, tobacco, and indigo. Population (1881) 151,440, namely, Hindus 130,910, and Muhammadans 20,530. Of the 213 villages comprising the *parganá*, 82 are held by Rájputs, 81 by Muhammadans, 41 by Káyasths, 5 by Bráhmans, 2 by Kurmís, and 1 each by Kalwárs and Lodhs. *Tálukdári* tenure obtains in 114 villages, 70 are *samíndári*, 26 imperfect *pattidári*, and 3 *bháyáchára*. Government land revenue, £18,299; equal to an average of 3s. 4d. per cultivated acre, or 1s. 9d. per acre of total area. The principal landholding families are Sayyid Musalmáns.

Sandila.—Town and municipality in Hardoi District, Oudh, and head-quarters of Sandila *tahsil* and *parganá*; situated 32 miles north-west of Lucknow, and 34 miles south-east of Hardoi town. Lat. 27° 4' 15" N., long. 80° 33' 20" E. The fourth largest town in Oudh, and the second largest in Hardoi District. Population (1881) 14,865, namely, males 7366, and females 7499. Muhammadans number 7487; Hindus, 7373; and Christians, 5. Municipal income (1883-84), £745, of which £724 was derived from taxation; average incidence of taxation, 11½d. per head of the population. The town contains the usual Sub-divisional civil and criminal courts, police station, dispensary, and Anglo-vernacular school. No buildings of special interest or antiquity. The *bára kambha* or hall of twelve pillars, a stone building, was erected about 150 years ago. Markets are held twice a week, at which *pán* and *ghí* are sold for export in considerable quantities. Station on the Oudh and Rohilkhand Railway. During the Mutiny, two severe actions were fought at Sandila on the 6th and 7th October 1858.

Sandoway (*Than-dwat*).—British District in the Arakan Division, Lower Burma. Area, 3667 square miles. Population (1881) 64,010 souls. Bounded on the north by the Ma-í river, separating it from Kyauk-pyu District; on the east by the Arakan Mountains; on the south by the Gwa river; and on the west by the Bay of Bengal. Its

extreme length is 136 miles, its breadth in the north 48, and in the south 24 miles. The administrative head quarters are at SANDOWAY TOWN.

Physical Aspects—Sandoway District is a mountainous country, the Arakan range sending out spurs which reach to the coast. These in their turn give off numerous sub spurs, running for the most part parallel to the main chain. The surface configuration of the District is so disrupted by the influence of igneous action that not more than one eighteenth of the area can be called plain, and except in this plain, and on the hillsides, where clearings are made for *taungya* or nomadic cultivation, the District is covered with dense forest. From the mouth of the Sandoway river northwards the coast is indented with navigable and intercommunicating tidal creeks by means of which communication can be kept up without going out to sea. Southwards, it presents a rugged and rocky barrier to the ocean, and has few available harbours. The rivers draining the District are but mountain torrents to within a few miles of the coast. The principal of these are—the Maí and the Tanlwe, falling into the arm of the sea which divides Ramri island from the mainland; the Taung-gup (Toung-goop), which enters the Bay of Bengal by several mouths between lat $18^{\circ} 44'$ and $18^{\circ} 50' N$, the Sandoway, a tidal river, navigable by the largest boats as far as Sandoway town, the Gwa, which falls into the sea in about lat $17^{\circ} 36' N$, forming a good anchorage for steamers and vessels drawing from 9 to 10 feet of water, though the entrance is rendered difficult by rocks and a sandy bar.

The main range of the Arakan Yomas has in the north a direction south-east by south, but it gradually curves towards the west, and, at the source of the Gwa runs nearly due north and south. In the north, some of the peaks attain an elevation of little less than 5000 feet, which falls to 3200 feet at Shauk bin, where the Taung-gup road crosses the range. South of lat $18^{\circ} 21' 26'' N$, the height rapidly diminishes, and at the sources of the Gwa is only about 890 feet. The chief pass is that from Taung-gup to Pa-dlung on the Irrawaddy (Irrawaddy) in Prome District, a route followed by the main body of the Burmese in their invasion of Arakan in 1784, but found impracticable for troops or beasts of burden in 1825-26. Since then, the road has been considerably widened and rendered fit for the passage of an armed force. It is now mostly used by traders from Pegu, and the telegraph line to Calcutta is carried along it. Another pass connects Gwa with Le myet hna in Bassein.

The three most important timber trees found in the District are—*Pyngado* (*Nylira dolabriformis*), used in house building and for railway sleepers, *in* (*Dipterocarpus tuberculatus*), and *ka gnyin* (*Dipterocarpus alatus*), from which are extracted resin and oil respectively. *BH 13*

(*Lagerstroemia Flos-Reginæ*), *thin-gau* (*Hopea odorata*), *ka-gnyaung* (*Dipterocarpus turbinatus*), and many other trees abound. The low ground within tidal limits is covered with dense mangrove jungle. The area of reserved forest in 1883-84 was 307 square miles.

Owing to the wild and inaccessible character of the greater portion of Sandoway District, its geological structure has received very cursory examination. The existence of cretaceous rocks was first established in 1872. Mr. Theobald says that they extend down from Kyauk-pyu District, in lat. $29^{\circ} 30' N.$, certainly as far as Kyein-ta-lí in Sandoway, a distance of 94 miles. Limestone occurs about 4 miles south-south-west of Ma-lí, where it is quarried and burned for local use. The rock is argillaceous, very homogeneous in grain, and occasionally seamed with calcite. Other outcrops, also belonging to the cretaceous age, are found in various parts of the District. It is very probable that on examination, the formations in the plains would give evidence of frequent alterations of marine with fresh-water sediments. They certainly indicate nothing of the consolidation of older systems. Limestone, intermixed with the tertiary clays and sands of the lower lands, is abundant and very pure; yielding on analysis carbonate of lime (with traces of iron), 93.6 per cent.; insoluble clay, 6.4. Veins of steatite and white fibrous quartz also occur in the District.

History.—According to the palm-leaf chronicles, there reigned in Baranathi (Benares), at a time when the duration of human life was 90 millions of years, a descendant of the first Buddha of the present epoch, who had sixteen sons; to the eldest of whom, Tha-mú-tí-de-wa, was allotted the country now forming Sandoway District. For him the spirits or Nats built a city, Dwa-ra-wad-dí, near the modern Sandoway. Many ages later, Sek-kya-wad-dí, the embryo Gautama Buddha, was King of Baranathi; and to his son, Kan-myin, he gave all the lands inhabited by the Burmese, Shan, and Malay races. Kan-myin came to Dwa-ra-wad-dí; dispossessed the descendant of Tha-mú-tí-de-wa; and was succeeded by kings of his own line, who ruled for a period represented by a unit followed by 140 ciphers. During the reign of Na-rein-da, the last of these monarchs, the country was attacked by the grandsons of a king who ruled in Mo-gaung.

The legend runs thus:—Arriving at the mouth of the Than-dwe (Sandoway) river, they failed in their attempts to find the city, owing to the devices of its guardian Bi-lú-ma, or, as some say, to its miraculous power of soaring above the earth in times of danger. At length the guardian, being propitiated, withdrew her protection; and the ten brothers then bound the city to the earth with an iron chain, and divided their conquest in ten shares, making Than-dwe ('iron-bound') their capital. But the eight younger brothers were slain in combat with the people, who appear to have risen against them, and the two elder fled.

Henceforth Sandoway appears only as a province of the Arakan kingdom, ravaged alternately by the Burmese and Talaings until the conquest of Arakan by the Burmese in 1784. It was then formed into a governorship, and its *zuni* was one of the commanders of the Burmese army which invaded Bengal at the commencement of the first Anglo-Burmese war. The country was ceded to the British by the treaty of Yandabu in 1826, and on the withdrawal of General Morrison's army, one regiment of Native infantry was left at Sandoway. A few years later, the military head quarters were transferred to Kyaukpju, and subsequently the small detachment of two companies was also withdrawn.

Antiquities—On the hills close to Sandoway are three small white washed pagodas, the An daw, Nan-daw, and Sin daw. The An daw is said to have been erected in 761 A.D. by King Min tsek kyup, to cover a tooth of Gautama. The building is 242 feet in circumference and 63 feet high. The Nan daw stands on a hill 480 feet above the level of the plain, and is 38 feet high, it is said to have been built in 763 A.D. by Min bra, to enshrine a rib of Gautama. The Sin daw is assigned to Min nyo khin (784 A.D.), and covers a hair of Gautama brought from Ceylon. Three times a year pilgrims resort to these pagodas, remaining one day at each temple on each occasion. Two stones inscribed in Sanskrit of the 8th century have been found near the Sandoway river. Silver coins struck by ancient kings of Arakan are occasionally met with, some of which have the dates and names in Burmese characters, whilst others bear Persian or Nagari inscriptions. Celts or stone implements are abundant.

Population—Mountainous and forest-clad, Sandoway District seems to have been always sparsely inhabited, but the increase of population since the British occupation has been proportionately larger than in other parts of Arakan. In 1828, the number of inhabitants was 19,538, by 1852, it had risen to 42,886, in 1872 to 54,725, and in 1881, to 64,010, namely, males 32,706, and females 31,304. Number of villages, 469, occupied houses, 11,639, unoccupied houses 773, average density of population, 17.66 persons per square mile. Classified according to age, there were—under 15 years, boys 14,058, and girls 13,486, total children, 27,544, or 43 per cent of the population. 15 years and upwards, males 18,648, and females 17,818, total adults, 36,466, or 57 per cent of the population.

Buddhists number 56,458, Nat worshippers, or persons of non-Buddhist indigenous religion, 4888, Muhammadans, 2509, Hindus, 124, and Christians, 31. Taken by language—persons speaking Burmese (including Arakanese) numbered 58,061, Chin, 5045, Karen, 107, Shan, 59, Bengali, 399, Hindustani, 263, and a very few speaking English, Greek, Chinese, Tamil, Telugu, and Manipuri.

The Muhammadans are of two classes. The Me-du, who ascribe their origin to members of a colony from near Ava, who originally came as soldiers with the invading Burman army, and who, about 70 or more years ago, were joined by many of their co-religionists who left Burma during a famine. The Kaman, who claim to have come originally from Delhi, and to be descended from the followers of the unfortunate Sháh Shujá, who was put to death by the King of Arakan, with whom he had sought refuge from his brother Aurangzeb. Neither of these classes differ much from their Buddhist neighbours, except in religion and education, of which they have less. The Hindus are mainly convicts transported from India many years ago, when Sandoway was a convict station. Chin, a race of mountaineers, have long inhabited the north and east, and of late years have spread into the plains. See article THAYET-MYO.

There is (1881) no town in the District with more than 2000 inhabitants, and by far the greater number of villages, namely, 381, have fewer than 200; 80 only having from 200 to 500; 6 from 500 to 1000; and 1 from 1000 to 2000 inhabitants. These are nearly all situated between the sea-coast and the slopes of the Arakan Yomas. The chief places in the District are—SANDOWAY, the administrative head-quarters, situated on the Sandoway river, and containing the usual public buildings; population (1881) 1901: TAUNG-GUP, on the Taung-gup river, and head-quarters of a township; population 1778: GWA, a trading village, with a population of 1072; KYEIN-TA-LI, a small village at the mouth of the river of the same name.

Agriculture.—Of the total area of the District, namely, 3667 square miles, only 60 square miles were returned in 1883–84 as cultivable, and about 75 as under actual cultivation. In 1881, the total agricultural population numbered 53,662, or 83·83 per cent. of the District population. Total amount of Government assessment, including local rates and cesses on land, £6441, or an average of 2s. 9½d. per cultivated acre. The chief crops are rice, sesamum, tobacco, cotton, pepper, sugar-cane, *dhani* palms, and yams. In 1883–84, the area under the various crops was as follows:—Rice, 36,754 acres; oil-seeds, 981; sugar-cane, 1044; cotton, 336; vegetables, 292; *dhani* palms, 2355; tobacco, 1874; plantains, 664; mixed fruit-trees, 606; chillies, 320; *taungya*, or hill gardens, 3986; miscellaneous crops, 896. Land suited for rice yields on an average 940 lbs. per acre; cotton, 480 lbs.; oil-seeds, 400 lbs.; sugar, 1040 lbs.; tobacco, 400 lbs.; and chillies, 240 lbs. Sesamum and cotton are grown principally with rice in *taungya* or hill gardens. The cultivation of tobacco is extending; the best is grown on the alluvial soil deposited during the south-west monsoon by the torrents of the Yoma range in their short course to the sea. The Cuba plant was introduced by Captain (now Sir A. P.) Phayre and Captain (now

Lieutenant General) Fytche, and thrives well, but is considered by the natives inferior in flavour to their own tobacco which is said to have been originally brought from China. Madder is produced near the Gwá, and the cultivation is very profitable, it is exported to Bassein.

As an almost universal rule, the land in the plains is held by small proprietors directly from the State, the average size of the holdings is 5 acres. In 1883-84, the average rent of land suited for rice was 7s an acre, oil seeds, sugar, cotton, tobacco, and chillies, 3s 3d. Land is not often mortgaged, but very high interest is charged for loans. If a large amount is required, the land is generally made over to the mortgagee for several years on the payment of a lump sum, for which no other interest is charged. Labourers engaged for ploughing receive 2 rupees, or 4s, per acre and their food, and when hired for transplanting or reaping, a bushel of grain per diem. When land is leased the rent is almost invariably paid in kind, and averages one third of the yield. In 1883-84 the average prices per *maund* of 80 lbs were—cotton 11s, rice, 5s, sugar, 8s, salt 2s 3d, tobacco £1, 8s, oil seeds, 8s, chillies 24s, plough bullocks £3, 10s each, sheep and goats, £1 each, buffaloes £4, 10s. The wages of skilled labour were from 1s to 1s 6d, and of unskilled labour, 9d a day. In 1883-84, the agricultural stock and implements consisted of—Cows and bullocks, 11,777, buffaloes, 25,147, pigs, 2355, sheep and goats, 484, horses and ponies, 31, elephants, 7, ploughs 14,592, carts, 790, boats, 1692.

Manufactures, etc.—The most important manufacture is thatch from the leaves of the *dhani* (Nipa) palm, which is in great demand in Akyab and Kyaukpadaung as well as locally. Cotton cloth and silk dresses are woven by the women in almost every house. The silk used is obtained from the southern township, where silkworms are bred and from the valley of the Irawadi. There is a large export trade with Akyab, Kyaukpadaung, and Bassein in rice, tobacco, sesamum, plantains, salt, salt fish, *nga pu* or fish paste, and boats. The imports consist of piece-goods, cotton twist, betel nuts, crockery, and hardware. In 1883-84 the total length of water communication in Sandoway District was 130 miles, of roads, 20½ miles.

Administration—Under Burmese rule, the regular revenue was derived from transit dues, a poll tax, and a tax on land. Five baskets (each holding 40 lbs) of rice in the husk were taken for each pair of buffaloes used, and half a basket was claimed by the keeper of the royal granary as 'wastage'. But there was no fixed rate, and the governors often exacted more. In 1828, it was calculated that every head of a family paid £1, 15s a year to the Government, whilst the annual cost of living for four persons was only £4, 4s. In 1851, the revenue amounted to £8362, in 1871, to £11,744, including local funds. In 1877-78, the imperial revenue was £14,423, of which £5685 was land revenue,

the local revenue was £580. The incidence of taxation of all kinds was 3s. 0½d. per head. In 1883-84, the gross revenue was £13,978, of which £6749 was land revenue. In Burmese times, the country was administered by a *wun* or governor, under whom were the *sit-ke*, *myo-uk thugyi*, and other subordinates. It appears from the records at Sandoway that the *thugyi* generally levied their demands thus:—From married people, well off, with families, bond servants, cattle, etc., £1, 14s.; married people not so well off, £1, 10s.; married people dependent upon their own labour, or too old for work, and newly married people with means, 18s.; newly married people with little or no substance, 7s. *Púngyís* (priests), the maimed and infirm, Government servants, and bachelors, were exempt from taxation.

For some time after the British occupation, the country was in a disturbed state. It has now settled down into a peaceful District, administered by a Deputy Commissioner with extensive judicial powers, who is the chief revenue authority under the Commissioner of the Division. Under him are the extra-Assistant Commissioners. The regular police consisted in 1883-84 of 196 officers and men, or about 1 policeman to every 18 square miles or every 327 inhabitants. There is a jail at Sandoway town; the daily average of prisoners in 1883 was 15. The total cost was £419. The hospital and civil dispensary, also at the head-quarters town, gave relief in 1883 to 83 in-door and 5889 out-door patients. Little education has, till lately, been given except by the Buddhist monks. The Census of 1881 showed 2371 boys and 83 girls as under instruction, besides 9051 males and 105 females able to read and write, but not under instruction. The Muhammadans were still more backward; in towns the children are better instructed, and in some cases learn both Arabic and Hindustaní. A middle-class school was opened in 1876, and had 44 pupils on the rolls at the end of the year, and 116 in 1883-84. Total number of schools in 1883-84 under public management, indigenous and private, 20; number of scholars, 683.

Climate.—From November to February the dews are exceedingly heavy, and the nights very chilly, the terrestrial radiation thermometer often recording only 38° F. From February to May, dense fogs rise during the evenings, and the wind blows from the west. Towards the middle of May, storms of thunder and lightning are of frequent occurrence. The average rainfall registered for the twenty years ending 1881 was 212·02 inches. Total rainfall in 1883, 223·18 inches. The maximum temperature was 103° F., and the minimum 61° F. The town of Sandoway is considered by some to be the healthiest place in Arakan. The prevalent diseases of the District are agues and fevers. [For further information regarding Sandoway, see the *British Burma Gazetteer*, compiled by authority, vol. ii. pp. 606-626; the *British*

Burma Census Report for 1881, and the several Administration and Departmental Reports of the Government of Burma]

Sandoway—Chief town and head quarters of Sandoway District, Arakan Division Lower Burma, situated in lat $18^{\circ} 27' 35''$ N, and long $94^{\circ} 24' 36''$ E, on the Sandoway river, about 15 miles from its mouth, but only $4\frac{1}{2}$ miles from the sea in a direct line. The town lies in a basin about 12 miles long by 1 broad, which is cultivated with rice, and surrounded by hills the only outlets being those through which the river flows. The larger portion of the town, which is laid out regularly, lies on the left bank of the river, whilst on the right side is a long straggling suburb, buried in trees, and presenting the appearance of an independent village. It contains the court houses, police station, market, jail, hospital, dispensary, and circuit house.

Sandoway is a very ancient town and is often mentioned in Arakanese history as the capital of a kingdom, or more probably a petty chieftainship. Its original name was Dwa ra wa di, but according to a current legend it was called Than dwe (by which appellation it is now known to the Burmese and Arakanese, Sandoway being an English corruption), from its having been miraculously fastened to the earth by iron chains.

After the capture of Arakan town in 1824 a force was sent southwards to attack Ramri and Sandoway. General MacBean reached Sandoway on the 30th of April, and occupied the town without resistance. After the cessation of the war, it remained for some years the head-quarters of the troops garrisoning Arakan. The garrison has now been altogether withdrawn. When the British first took the town the number of inhabitants was found to be 4500. In 1877-78, the population was returned at 1617, and in 1881, 1901.

Sandoway carries on a small coasting trade in rice, vegetables, etc., and a land traffic in silk and other piece goods with Prome and Bassein over the Arakan Mountains valued at £2000 per annum. Owing to the numerous creeks intersecting the coast, boats can get as far as Akjeb without entering the open sea. In the neighbourhood of Sandoway are the three pagodas of An daw, Wan-daw, and San daw, to which pilgrims resort three times a year, spending one day on each occasion at each shrine.

Sandoway—River in Sandoway District, Arakan Division, Lower Burma. It rises in the Arakan Hills, and, flowing west north west, falls into the sea in about lat $18^{\circ} 31'$. About 15 miles up the river is Sandoway town, which can be reached by large boats. The anchorage inside the mouth is from 5 to 6 fathoms, the tide is felt for a short distance above Sandoway town. About 50 miles from the entrance is a sulphuretted hydrogen spring in the bed of the river, the water of which attains a heat of 110° F.

Sandoway Myoma.—Township in Sandoway District, Lower Burma, sometimes called the central township. Bounded on the west by the Bay of Bengal. It comprises 14 revenue circles; chief town, SANDOWAY, on the Sandoway river. In 1881, the cultivated area was 20,667 acres; products—rice, tobacco, sesamum, cotton, pepper, sugarcane, cocoa-nuts, hemp, and miscellaneous garden stuff. Exports—agricultural produce; imports—European cotton and woollen goods, silk goods from Prome and Bassein, and earth-oil and lacquered ware from the latter District. Good communication by boat.

Sandru.—Pass in Bashahr (Bussahir) State, Punjab, across the Himálayan range in Kunáwar. Lat. $31^{\circ} 24' N.$, long. $78^{\circ} 2' E.$ (Thornton). Said to be open during only two months of the year. Elevation above sea-level, about 16,000 feet.

Sandúr (*Sundoor*, *Sandhur*?).—Native State within the British District of Bellary, Madras Presidency, lying between $14^{\circ} 58'$ and $15^{\circ} 12' N.$ lat., and between $76^{\circ} 28'$ and $76^{\circ} 43' E.$ long. Area, 164 square miles, of which a large proportion is hill jungle. The State is bounded on the south by the Kúdligi *táluk*, and on all other sides, save a small portion bordering on Mysore State, by the Hospet *táluk* of Bellary District. The tract is elliptical in shape, stretching from north-west to south-east, and is almost entirely shut in by hills, which isolate it from the neighbouring country. Population of the State (1881) 10,532. The annual revenue from all sources somewhat exceeds £4500.

Physical Aspects.—One chain of hills on the western limits of the State is known as the Sandúr or RAMANDRUG range (*q.v.*); and from the north, the Timmappa Hills run down to form its eastern boundary. These are crossed by three principal passes. On the east, the Yettinhatti or Bhimagandi *ghát* connects the State with Bellary; on the south-west, through the Oblagandi gorge, runs an excellent cart-road for through traffic. The Rámangandi valley between the two main converging ranges is the northern entrance, and has a good road to Hospet. The principal elevations are the Rámandrug, Kumáraswámi, and Kombatharavu plateaux. All these attain an elevation of about 3000 feet. The sides of the hills are in most places forest-clad, but indiscriminate felling and charcoal-burning have done much to keep down the more valuable timbers.

Several streams water the State. These, for the most part, find an outlet in the Sandúr river or Nári Nálá through the Yettinhatti gorge, and feed the Daroji tank in Hospet. On the hills, tigers, leopards, hogs, porcupines, bears, *sámbar* deer, and jungle sheep are found. The prevailing rock is a chloritic slate, often highly impregnated with oxide of iron, and crested in many places with mural ridges of ferruginous quartz rock, tinted with a variety of colours, from a steel-grey to a deep

liver brown. This rock often forms whole hillocks, always, however, overlying the slate. On the hills generally, iron ore is obtained. It is often of a rich quality, easily got at, and usually of a friable description. On Rámandrug various coloured clays are procurable without difficulty. The prevailing soil in the valley is a rich heavy loam, interspersed here and there with patches of black cotton soil. In various parts, lime is obtained near the surface, chiefly in nodular form. The ascent to the Kumdraswami pagoda passes over an extensive bed of lava conglomerate, and the same feature characterizes part of the Ramandrug range.

History — The founder of the Sandúr family was a Maráthá named Malaji Ráo Ghorpae, an officer in the Bijápur army, whose son Biráji entered the service of Sivaji the Great. The State had been previously held by a Bidar Poligár, but Biráji's son Sidaji took Sandur from the Bedars, and his conquest was confirmed to him and his heirs by Sambhaji, the successor of Sivaji. Sidaji died in 1715, and was succeeded in Sandur by his second son, Gopál Rao, whose fate is involved in obscurity. All that is known is that Sandur was taken by Haidar Ali some time after his capture of Gooty (Guti) in 1779, that Haidar began, and Tipu completed, the fort, and that Gopál Rao's son, Siva Rao, was killed in battle in 1785, in a vain attempt to recover his patrimony.

In 1790, Siva Rao's brother, Venkat Rao, acting on behalf of his nephew Sidaji, expelled Tipu's garrison, but did not attempt to occupy Sandur till the fall of Seringapatam. The Peshwa then claimed the State as his own, and presented it to Yaswant Rao Ghorpae, a distinguished officer of Sindhiá's army, who belonged to the same family as the former holders. Yaswant Rao did not enter into possession, and the widow of Sidaji, who died in 1796, adopted Siva Rao, a son of Khandi Rao, the younger brother of Yaswant Rao. The Peshwa made an unsuccessful attempt upon Sandur in 1815, and at his request in 1817, the British Government, in conformity with the provisions of the treaty of Bassein, sent a force under Sir Thomas Munro to reduce it. In October of that year, the fort and State were surrendered. On Sir Thomas Munro's recommendation, Siva Rao received as compensation a *jagir* of £1000.

In 1818, however, after the downfall of the Peshwa's Government, Siva Rao was restored to his State, and in 1826 he received a *sarai* from Government confirming the lands of Sandúr to him and his heirs free of any pecuniary demands. Siva Rao was succeeded in 1840 by a nephew named Venkat Rao, who died in 1861. His eldest son, Siva Shan Mukhar Rao, being then a minor, did not receive the *sarai* till 1863. On the 24th January 1876, Lord Northbrook, then Governor General, conferred on him the title of Raja, as a hereditary distinction.

to be assumed by his successors on formal recognition of their succession. Siva Shan Mukha Ráo died in May 1878, and was succeeded by his half-brother Rám Chendra Vittala Ráo, the present Rájá, to whom the *sanad* was granted in February 1879. The Rájá has the entire management of the revenue and police of his State, and the duty of administering civil justice. In the administration of criminal justice, he is required to refer all cases calling for capital punishment for the orders of the Madras Government. The Collector of Bellary acts as Government Agent. The chief holds a *sanad* conferring rights of adoption, granted by the British Government.

In the office of the Agent of the Rájá at Sandúr is a copper-plate document evidencing the grant of land in *inám* to village carpenters, and the building of villages by a 'Narpati' king.

Population.—The population of Sandúr State in 1865 was 12,962. At the Census of 1871 it was returned as 14,994; and the Madras Administration Report for 1877-78 gives the number as 14,999. It is probable that this estimate was considerably in excess of the actual population, as the Census was taken a few days previous to the Kumáraswámi festival, when there was a considerable influx of strangers. The Census of 1881 gives the population as 10,532. The decrease of nearly 30 per cent. since 1871 is due to the loss caused by death and emigration during the famine of 1876-78, and the subsequent removal of the military depôt from Rámandrug. According to the Census of 1881, males numbered 5298, and females 5234, occupying 2173 houses in 23 villages. Hindus numbered 9000; Muhammadans, 1521; and Christians, 11. In caste and race, the people are identical with those of the surrounding District of Bellary. On the plateaux there is a hill tribe of hunters, called Bedars, divided into two clans. They are a healthy and industrious people; and although possessing peculiar customs, they are probably Dravidian Hindus, and in no way connected with the aboriginal tribes, such as Malayális, etc.

Places of Interest.—The two places of most interest in the State are the important sanatorium of RAMANMALAI, situated 3150 feet above the sea, and used chiefly as a convalescent depôt for troops; and the temple of Kumáraswámi, of which Newbold gives the following description:—'It is situated near the basin of a ravine, not far from the summit of the south-west part of the range of hills that enclose the valley; and after an ascent of 4 miles. The temple is neither large nor magnificent, but has an air of antiquity, of which its whitewashed exterior and gilded cupola cannot entirely divest it. The *gopuram* faces the east; on the left of the entrance is the shrine of the goddess Párvati, consort of Siva; to the west is the image of her son Kumáraswámi, the presiding genius of the place; and to the right stands the shrine of the destroyer Siva. In front is a square pool called "Aguste

Tirtha" In front of the *gopuram* is a small octangular column of hewn stone, at the foot of which lie three trunkless stone heads. The largest is that of the giant Tarakasam, slain by Kumáraswámi. The great festival occurs triennially, and at this the number of pilgrims has latterly amounted to 25,000 or 30,000, the temple revenue averages from 15,000 to 20,000 rupees (say £1500 to £2000) annually. A *Shasanam* in old Kanarese is still preserved, which grants the endowment of the temple. It was given in S 615 (713 A.D.) by a king of the Marala dynasty, named Bijala Nájak. The climate of Kumáraswámi is described as very agreeable, although, owing to its easterly position, it is not so cool as that of Rámandrug.

Revenue—The revenue of the State is at present about £3700, of which £1800 is derived from land. The land revenue includes grants of land to dependants and service lands, other lands to the annual value of £1300 are alienated. It has been the policy of the present Rájá to increase the security of the land tenures, and render them permanent. The peasants may cut wood for all agricultural purposes free of payment, nor are they liable to be charged for firewood which they themselves carry home. The poorer classes were formerly permitted to cut firewood and grass in the jungles, and to sell it in the *bazár* free of tax, but under recent regulations each head load of firewood brought for sale is subject to a tax of 3 *pies* (or $\frac{3}{16}$ d). In 1882, an arrangement was entered into between the Rájá and the Government, according to which 40,000 acres of forest land were leased to the latter for 25 years at 4 *annas* (6d) per acre per annum, reserving to Government the option of renewing the lease on the same terms at the end of that period, and every succeeding period of 25 years.

The average annual rainfall of Sandúr is about 36 inches. The chief village is Sandúr, population (1881) 4096, occupying 793 houses.

Sandur (*Sundoor*, or more properly *Rámandrug*)—Hills in Bellary District, Madras. A range of hills about 15 miles long, running from south east to north west, ending abruptly near Hospet. This range forms the greater part of the western boundary of the Native State of SANDUR, dividing it from the Hospet *taluk*. Rámandrug, 3150 feet above the sea, is the principal peak, and was selected as far back as 1846 for the sanitarium of RAMANMALAI. The range consists of gneiss much weathered. The upper part of Rámandrug is clay ironstone, and the slopes consist of a variety of schistose rocks containing manganese and antimony. Tigers are found in these hills, and much useful wood comes from them.

Sandwip (*Sundeeep*)—Island in the Bay of Bengal, situated off the coast of Chittagong and Noakháli, and forming part of the latter District. Lat. $22^{\circ} 24'$ to $22^{\circ} 37' N$, long $91^{\circ} 22'$ to $91^{\circ} 35' E$. The largest of many *chars* formed by the MEGHNA as it enters the sea. For long, in process

of diluvion went on in the south of Sandwíp, but the soil re-formed and reappeared in 1865 as the Kálí *char*, many miles long, lying parallel with the south face of the island, at a distance of 2 or 3 miles. This *char* already acts as a bar to protect Sandwíp from further diluvion, and will eventually, in all probability, become attached to it by the silting up of the intermediate channel.

Sandwíp early attracted the notice of travellers. Cæsar Frederick, the Venetian (1565), described the inhabitants as 'Moors;' and stated that the island was one of the most fertile places in the country, densely populated, and well cultivated. He mentions the extraordinary cheapness of provisions; and adds that 200 ships were laden yearly with salt, and that such was the abundance of materials for shipbuilding, that the Sultan of Constantinople found it cheaper to have his vessels built here than at Alexandria. Purchas (*circa* 1620) states that most of the inhabitants near the shore were Muhammadans; and there are several mosques on Sandwíp Island two hundred years old. Sir Thomas Herbert (*circa* 1625) bears testimony to the fertility of the island, which he describes as one of the fairest and most fruitful spots in all India. The cocoa-nut palm flourishes in Sandwíp, and the nuts are exported to Chittagong and Akyab. Sugar-cane is also cultivated to a small extent.

The island of Sandwíp figured conspicuously in the contests of the 17th century between the Arakanese, Muhammadans, and Portuguese (see CHITTAGONG DISTRICT), and during that period numerous forts were erected. In one of these, the Muhammadan troops took refuge in March 1609, when the Portuguese landed on the island. But the fort was besieged and captured, and the defenders put to the sword. In 1616, Sandwíp was taken from the Portuguese by the Arakanese. In 1665, Sháístá Khán, the Muhammadan Nawáb of Bengal, determined to reconquer the island. An interesting account of his expedition, by the French traveller Bernier, was translated in the *Calcutta Review* for 1871, and is quoted in *The Statistical Account of Bengal*, vol. vi. pp. 243-246.

Until 1822, the island formed part of Chittagong, but in that year it was made over to the newly formed District of Noákhálí. It had, from the time when it came under British administration (1760), formed a constant source of disquiet. It afforded an asylum for the refuse of the river Districts from Dacca southwards, and had a mixed population of Hindus, Muhammadans, and Maghs, who formed agricultural colonies, fishing settlements, piratical villages, and robber communities. The subordinate tenants kept up a bitter quarrel with the landholder-in-chief, and every class seemed to have a grudge against the rest, and some complaint to make to Government. But the firm administration of the British officials gradually produced its

effect. A Commissioner was appointed to measure and partition the island. His appearance, however, was at first only the signal for new disorders. On the one hand, he complained of 'obstructions and difficulties' thrown in the way of executing his duty, on the other hand, the *idulddars* forwarded a bitter petition and lament. An enterprising native gentleman proposed, in May 1785, to relieve the officials of further difficulty by taking Sandwip in farm. But the Government was resolved to have the work thoroughly done, and rejected his offer. Accordingly, the troublesome island was placed under the direct management of the Collector, who was ordered to conduct a land settlement.

The administration of justice in Sandwip was formerly under the authority of an officer called a *faujddar*, resident in the island. But from a Report (dated September 1779) by Mr Duncan, specially deputed to Sandwip, it appears that when Government ceased to maintain a fortress on the island, the *faujddar* was no longer retained, and justice was administered by an inferior officer with the title of *daroga*. This official had not, however, uncontrolled jurisdiction. From the year 1760, if not from an earlier date, he was entirely under the authority of the *ndib ahad ddr*. It was the duty of the *daroga* and his assistants to prepare cases for hearing, and on fixed days in each week the *ndib ahad-ddr* would sit in his court of justice, attended by the *darogás*, *kánungos*, and *zaminddrs*, to dispose of all cases brought before him. 'This court,' writes Mr Duncan, 'took cognizance of all matters, civil and criminal—its jurisdiction being only restrained as to matters of revenue, the cognizance of which rested with the *ahad ddr* in his separate capacity. In matters of debt, the court retained the fourth part of the sum in litigation, and enacted discretionary fines for theft, gang robbery (*ddkúti*), fornication, assaults, and the like.'

Among the miscellaneous inquiries conducted by Mr Duncan in 1779, was one relating to complaints of slaves, or persons reported to be slaves, against their masters. 'This unfortunate race of man kind,' says Mr Duncan, 'bears in Sandwip a larger proportion to the other inhabitants than perhaps in any other District in the Province, there is hardly a householder, however indigent, who has not at least one slave, and the majority have many in their families. Their number also very soon increases by marriage, in which they are encouraged by their masters, the custom of the country being such that a free woman, on marrying a male slave, reduces herself and her family to be the perpetual slaves of her husband's master, who continues ever after to retain them in the same bondage.' One man alone was said to possess more than 1500 slaves. The principal cause assigned by Mr Duncan for the great extent to which slavery prevailed in Sandwip, was 'the extreme cheapness and abundance of grain in

the island, so that as often as there is any scarcity in Dacca District, it attracts people to Sandwip, where it has been common for many of them to sell themselves and their posterity for maintenance.' Although Mr. Duncan in 1779 set at liberty only 15 slaves and their families, yet none of his proceedings created more general apprehension than his taking cognizance of this particular grievance, because all the principal people were immediately interested.

From its low-lying position, Sandwip is peculiarly exposed to inundation from storm-waves, and suffered severely in loss of life and property by the cyclones of 1864 and 1876. The calamity of the latter year was the severest on record. The following account of the inundation is quoted from a report by Mr. Pellew, the Collector of Noákhálí:—'The people in the villages on the south-western coast stated that the inundation commenced with a wave at least 6 feet high, which burst over the land from the south-east. Very shortly afterwards, another wave, 6 feet higher, came from the south-west. These waves came suddenly, just like the bore, mounting up and curling over. The second wave is described as lifting the roofs of the houses, and whirling the contents—human beings, furniture, etc.—violently outside. The mat walls, with their wooden posts, were swept away, the latter being either broken off short or wrested out of the ground. All this was done suddenly; people described it as occurring in one second of time. Behind each wave the water did not fall again, but remained, so that after the second wave there was 12 feet of water over the land.

'In the centre of the island the water came up less suddenly. The Government Pleader at Harishpur was taking refuge from the storm in his new office. Suddenly an alarm was raised that the water was coming. He got on the wooden dais, but the water immediately covered this. He then went up to his neck in water, along a raised path, to the bank of his tank, which is about 12 feet high. He told me that the rising of the water did not take longer than two minutes from first to last, and that he was only just in time. The bank of the tank was not more than 10 yards from his office.'

In many villages whole families were swept away, and in some of the *chars* the entire population was destroyed. 'In the village of Nayámasti,' writes Mr. Pellew, 'one man was the sole survivor of thirteen; four men were the survivors of a household of twenty-five. The women have perished in immense numbers. Most of the men who remain are wifeless. In Kangáli Char, the Sub-Inspector of Police found nothing but two wild buffaloes alive, and the corpses of men, cows, and buffaloes. In Char Maulavi, out of 177 people, 137 died.'

For the first few days after this cyclone of 1876, there were several

attempts at plundering, and demoralization prevailed among the low Muhammadan population. Men, in gangs and singly, armed with cudgels, bills, and hatchets, were, the Collector reported, wandering about the inundated tracts, and breaking open and looting all they could lay their hands upon, whether under the care of owners or not. This lawlessness was, however, rapidly suppressed, and the people soon returned to the sites of their former houses, and busied themselves in drying their grain and in saving what they could of their property. Throughout the devastated tracts, 'the demerit of those who really bore the brunt of the storm was,' Sir Richard Temple states, 'marked by that enduring fortitude under suffering which distinguishes the native character.'

The number of deaths was officially estimated at 40 000, out of a total population of 87,016. Cholera set in soon after the cyclone had passed over. Although a large medical staff was immediately despatched to the District, the epidemic continued to rage to such an extent, that when Mr Pellew visited the Sandwip islands, the mortality from the plague threatened in some places to exceed that from the storm itself. The returns for thirty three police beats in South Sandwip, with a population of 10,855 souls, gave the deaths by drowning as 1063, whereas those from cholera in the same tract had by December 1876 amounted to 764. The pollution of the tanks and watercourses, both by the salt water inundation and by the corpses of men and the carcasses of cattle, added to the other evils resulting from the cyclone, while the stench from the dead tainting the air throughout the inundated tract aggravated the plague of cholera. Nearly all the scavenger animals—jackals, dogs, and even vultures—perished by the storm and the wave, and for weeks after the inundation, the land was covered with the dead bodies of men and cattle, preserved by the salt water from rapid decomposition. The total population of Sandwip Island in 1881 was returned at 72,467, showing a decrease since 1872 of 14,549, or 16 72 per cent.

Sangakhera—Village in Hoshangabad *tahsil*, Hoshangabad District, Central Provinces. Population (1881) 2957, namely, Hindus, 2592, Muhammadans, 118, and non Hindu aborigines, 247.

Sangala—Ruins in Jhang District, Punjab, standing on a small rocky hill, upon the border of Gujranwala District, now known as Sanglawala Tiba, and identified by General Cunningham with the Sākala of the Brāhmans, the Sagal of Buddhism, and the Sāngala of Alexander's historians. The hill rises to a height of 215 feet above the surrounding plain on its north side, and slopes southward till it ends in an abrupt bank only 32 feet in height, crowned in early times by a brick wall, traces of which still exist. The whole intervening area is strewn with large antique bricks, great quantities of which have

been removed during recent years. An extensive swamp covers the approach on the south and east, the least defensible quarters, with a general depth of 3 feet in the rains, but dry during the summer. This must have been a large lake in the days of Alexander, which has since silted up by detritus from the hill above. On the north-east side of the hill, General Cunningham found the remains of two considerable buildings, with bricks of enormous size. Close by, stands an old well, lately cleared out by wandering tribes. On the north-west side, about 1000 feet distant, rises a low ridge of rock, known as Munda-ka-pura, 30 feet in height, also covered by brick remains.

The earliest notice of the locality occurs in the *Mahābhārata*, where Sākala figures as the capital of the Mādras or Jātakas, and the Bāhikas, situated upon the Apagā rivulet, west of the Irāvati or Rāvi, and approached from the east by pleasant paths through the Pīlu forest. The neighbourhood bears the name of Mādra-des, or country of the Mādras, to the present day. The Apagā rivulet has been identified by General Cunningham with the Ayak *nadī*, a small stream which has its rise in the Jāmmu hills north-east of Siālkot, but which is now quite dry in the neighbourhood of Sāngala.

In Buddhist legends, the city reappears as Sāgal, whither seven kings made their way to carry off Prabhāvatī, the wife of King Kusa. That monarch, however, met them outside the gates, mounted upon an elephant, and shouted with so loud a voice that his words were heard over the whole world, and the seven kings fled away in terror. Arrian, Curtius, and Diodorus all notice Sāngala, 'a great city, defended not only by a wall, but by a swamp,' which was deep enough to drown several of the inhabitants who attempted to swim across. Alexander seems to have turned out of his direct line of march to punish the Kathæans of Sāngala, who had withheld their allegiance. He stormed the outpost of Munda-ka-pura, crowded with fugitives from other cities, and then, breaching the walls by means of a mine, captured the town by assault. Hiuen Tsiang, the Chinese Buddhist pilgrim, who visited Sākala in 630 A.D., found the fortifications in ruins, but traced their foundations for a circuit of $3\frac{1}{2}$ miles. In the midst of the remains, a small portion of the ancient city, 1 mile in circuit, was still inhabited, and contained a Buddhist monastery with 100 monks, and two *stupas*, one of them founded by the famous Emperor Asoka. The accurate details of the Chinese traveller have been principally instrumental in settling the identity of Sānglawāla Tiba with the historical site.

Sangam.—Anicut and village in Nellore District, Madras Presidency; situated on the Penner river, 38 miles from the sea and 20 miles above the anicut at Nellore town. The object of the anicut is to extend irrigation along the northern bank of the Penner, commanding an area of 220 square miles. This tract of country already contains many

tanks, and is partially irrigated by cuts from the Penner. The construction of the anicut will render certain the existing irrigation, and will largely increase it. Present irrigation, 44,053 acres, estimated increase, 49,947 acres, total, 94,000 acres. From the anicut, a main channel, leading from a head sluice on the north bank of the river, will supply two large existing reservoirs, namely the Kanigiri and Duvur tanks. From the former, the irrigation channels will be taken off.

When finished the anicut will be 4290 feet in length, or nearly three times the length of the Penner anicut at Nellore. Its crest will be 7 feet above the deep bed of the river, or 105 feet above mean sea level. The head sluice (which was finished in 1884) has 21 vents of 6 feet span, and is designed to carry 4800 cubic feet of water per second (when the water in the river is flush with the anicut crest). The water will be distributed in the following proportion to the reservoirs — Kanigiri tank, cubic feet per second, 4576.5, Duvur tank, cubic feet per second 223.5. The present capacity of the Kanigiri tank is to be greatly enlarged. The total capacity of the two reservoirs will ultimately be — Kanigiri tank, 6419 millions of cubic feet, Duvur tank, 1043 millions of cubic feet, total, 7462 millions of cubic feet. When finished, the Kanigiri tank will be the largest reservoir in the Madras Presidency.

It is estimated that the works will be completed in 1889-90. The estimate of the work amounts to £356,905, and was sanctioned by the Secretary of State in February 1881. It is anticipated that, on completion of the works, the annual revenue will amount to £23,800. The estimate of annual working expenses is £5026, and the net revenue should therefore be £18,774 or 5.26 per cent. on the total capital.

Sangam village is situated on the north bank of the Penner river, 20 miles above Nellore town. Population (1881) 1212, occupying 250 houses.

Sangameshwar — Sub-division of Ratnagiri District Bombay Presidency. Area, 557 square miles. Population (1881) 104,640, namely, males 50,379 and females 54,261, occupying 20,434 houses in 179 villages. Hindus number 99,249, Muhammadans 4778, and 'others,' 613. The chief river is the Shastri, which cuts the Sub-division nearly in half. Fur amount of alluvial soil in the river valleys, yielding average crops of rice and pulse. Almost all the rest of the Sub-division is crumbled trap. The area of actual cultivation in 1877-78 was 20,423 acres, cereals and millets occupied 19,136 acres, pulses, 736 acres, oil seeds, 467 acres, fibres, 28 acres, and miscellaneous crops, 56 acres. In 1883 the Sub-division contained 1 civil and 2 criminal courts, police circles (*thands*), 7, regular police, 59 men. Land revenue (1878), £12,620. Head-quarters, since 1878, at Deorukh.

(Devrukh); population (1876) 2660; not separately returned in the Census Report of 1881.

Sangameshwar.—Old head-quarters of Sangameshwar *tāluk*, Ratnāgiri District, Bombay Presidency; situated on the Shāstri river, about 20 miles from the coast. Lat. $17^{\circ} 9' N.$, and long. $73^{\circ} 36' E.$ Population (1877) 2475; not separately returned in the Census Report of 1881. The river, which 35 years ago was navigable for the largest vessels to the Sangameshwar quay, is now impassable six miles lower down. Trade in grain, piece-goods, and salt fish. During the famine of 1877–78, 1440 tons of grain were forwarded from Bombay through Sangameshwar to the Deccan. Early in 1878, 55 houses were burnt; and a few weeks later (March 16th) a disastrous conflagration completely destroyed the Sub-divisional offices and 75 private houses. On the destruction of the public offices, the head-quarters of Sangameshwar Sub-division were moved to the more central and convenient village of Deorukh (Devrukh).

Sangamner.—Sub-division of Ahmadnagar District, Bombay Presidency. Area, 708 square miles; greatest length, 40 miles; greatest breadth, 30 miles. Population (1872) 68,765; (1881) 68,357, namely, males 34,770, and females 33,587, occupying 11,767 houses, in 1 town and 151 villages. Hindus number 63,488; Muhammadans, 3728; and 'others,' 1141. The Sub-division is divided into three distinct portions by the two mountain ranges which traverse it in a parallel direction. The chief rivers are the Prāvara and the Mula. The Prāvara flows in the valley between the two mountain ranges. With the exception of irrigation from the Ojhar canal, garden cultivation is carried on chiefly by means of wells. A large dam of solid masonry, 830 feet long with a maximum height of 29 feet, was built in 1873 across the rocky bed of the Prāvara close to the village of Ojhar-Khurd. Total cost of the dam, together with the head-works, about £6000. The canal which leads the water from the work is on the north side of the river; total area irrigated from the 17 miles which lie in the Sangamner Sub-division, 2227 acres in 1881. Irrigation rates vary from 2s. to 16s. per acre. The area under actual cultivation in 1881–82 was 204,020 acres; cereals and millets occupied 197,190 acres, of which 157,823 acres were under spiked millet (*Pennisetum typhoideum*); pulses, 4764 acres; oil-seeds, 662 acres; fibres, 11 acres; and miscellaneous crops, 1393 acres. The manufactures are cotton and silk cloth, turbans, woollen blankets, bangles, and saltpetre. Of the 2100 looms in the Sub-division, 2000 are in the town of Sangamner. In 1883 the Sub-division contained 2 civil and 2 criminal courts; police circle (*thānd*), 1; regular police, 44 men; village watch (*chaukidārs*), 189. Land revenue, £7120.

Sangamner.—Chief town of the Sangamner Sub-division of

Ahmadnagar District, Bombay Presidency, situated 49 miles north west of Ahmadnagar city, in lat $19^{\circ} 34' 30''$ N, and long $74^{\circ} 16' 10''$ E. Population (1881) 8796. Hindus numbered 7079, Muhammadans, 1603, Jains, 104, Christians, 7, and 'others,' 3. Besides the ordinary Sub divisional revenue and police offices, Sangamner has an Assistant Collector's bungalow, post office, dispensary, and four schools, markets on Wednesday and Saturday. Municipality, established in 1860, had in 1883-84 an income of £705, incidence of taxation per head of population, 1s 4d. Brisk trade, number of looms 2000.

Sanganer—Town in Jipur State, Rájputána, situated on the bank of the Amán Sháh river, 7 miles south west of Jaipur city, and 3 miles from the Sanganer station on the Rájputána Málwá State Railway. Its principal features of interest are temples and Jain edifices, one of which is said to be over a thousand years old. Celebrated for dyeing and printing of cotton stuffs.

Sangarh—Northern *tahsil* of Dera Gházi Khán District, Punjab, consisting of a narrow strip of land between the Sulaimán mountains and the Indus. Area, 628 square miles, towns and villages, 136, houses, 8389. Population (1881) 51,779, namely, males 27,730, and females 24,049, average density of population, 82 persons per square mile. Muhammadans number 46,205, Hindus, 5452, and Sikhs, 122. Of the 136 towns and villages in the *tahsil*, 102 contain less than two hundred inhabitants, 20 from five hundred to 1 thousand, and 14 from one thousand to five thousand. There is no town of Sangarh, nor any place with a population exceeding five thousand inhabitants. The *tahsil* takes its name from a little mountain torrent, the Sangarh, and the head quarters are at the village of Taunsa. Principal crops—wheat, *býra*, *jeár*, and cotton. Revenue of the *tahsil*, £4977. The administrative staff consists of a *tahsildár* and an honorary magistrate, who preside over 2 civil and 2 criminal courts, strength of regular police, 28 men, village watch or rural police (*chaukídárs*), 38.

Sángarhi—Town in Sakoli *tahsil* Bhandára District, Central Provinces, situated in lat $20^{\circ} 58'$ N, long 80° E, 24 miles south-east of Bhandára town, and 3 miles south of the Seoni Lake (*vide* SEONI). Population (1881) 3172, namely, Hindus, 2637, Muhammadans, 178, Jains, 7, and non Hindu aborigines, 350. Manufactures of cotton cloth, which is largely exported, and silk spinning. SÁNGARHI derives its name from the ruined Afghan fort which commands it. The town stands on a gravelly soil, but is unhealthy, owing to the brackishness of the water supply from most of the wells. Flourishing Government school.

Sanghi—Town in Rohtak *tahsil*, Rohtak District, Punjab, situated in lat $29^{\circ} 1'$ N, long $76^{\circ} 37'$ E, about 9 miles from Rohtak town, and

1 mile from the right bank of the Rohtak branch of the Western Jumna Canal. Population (1881) 5194, namely, Hindus, 4621; Muhammadans, 545; Jains, 25; and 'others,' 3. Number of houses, 844. Rather an agricultural village than a town, with a school and post-office.

Sángli.—Native State in the Political Agency of the Southern Maráthá Country, Bombay Presidency; consisting of six separate divisions—a group of villages near the valley of the Kistna; a second group between the Kolhápúr territory on the west and Jámkhándi State; a third group in Sholápur District, near the junction of the Mán and Bhíma rivers; a fourth in Dhárwár District; a fifth just north of the town of Belgáum; and the last to the south of the river Malprabha and to the north-east of Kittúr in Belgáum. The State contains a total area of 896 square miles, of which about 91 square miles are under forest. Population (1872) 223,663; (1881) 196,832, namely, males 98,037, and females 98,795, occupying 31,183 houses, in 5 towns and 235 villages. Hindus number 172,257; Muhammadans, 13,082; and 'others,' 11,493.

The portion of the State of SÁNGLI watered by the Kistna is flat, and the soil particularly rich. The remaining divisions are plains surrounded by undulating lands, and occasionally intersected by ridges of hills. The prevailing soil is black. Irrigation is carried on from rivers, wells, and tanks. The climate is the same as that of the Deccan generally, the air being very dry, especially when east winds prevail. The most common diseases are cholera, small-pox, and fever. The chief products are millet, rice, wheat, gram, and cotton; and the manufactures coarse cotton cloth, and native articles of apparel.

The chief of SÁNGLI is a member of the Patwardhan family, whose founder Haribhat, a Konkan Bráhmaṇ, rose to military command under the first Peshwá, and received grants of land on condition of military service. In 1772, Miraj descended to Chintáman Ráo, grandson of Govind Ráo Hari, the original grantee. Chintáman Ráo being a child of six years, the State was managed during his minority by his uncle, Gangádhara Ráo. When the minor came of age, he quarrelled with his uncle, who attempted to keep him out of his rights. Eventually the estate was divided between them, the uncle retaining Miraj, and Chintáman Ráo taking SÁNGLI. The revenue of SÁNGLI was £63,518, and of Miraj, £47,980; the estates being respectively subject to a service of 1920 and 1219 horse. Chintáman Ráo, the father of the present chief of SÁNGLI, became a feudatory of the British Government on the downfall of the Peshwá in 1818-19. In 1846, the East India Company presented him with a sword in testimony of their respect for his high character, and in acknowledgment of his fidelity and attachment to the British Government. Chintáman Ráo died in 1851. The

chief of Sāngli does not now pay any contribution on account of military service, having ceded lands of the annual value of £13,500 in lieu thereof. The family hold a title authorizing adoption.

The present chief is Dhundi Rao Chintāman, a Hindu of the Brāhmaṇ caste. He ranks as a 'first-class' Sardār in the Southern Marāṭhā Country, and has power to try capital offences without the express permission of the Political Agent. This power, however, applies to his own subjects only. In consequence of misgovernment by the chief, an English officer was in 1873 appointed as Joint Administrator. The share of the chief in the administration consists in signing such papers as are placed before him. Every improvement has proceeded from the Joint Administrator. The chief enjoys an estimated gross revenue of £98,135, and maintains a police force of 473 men, of these, 43 are mounted, 24 are employed in the State band, and 110 are armed. There were in 1883-84, 60 schools, of which 4 were girls' schools and 4 Anglo vernacular, number of pupils, 3611. Indigenous schools numbered 36. There are in the State 5 municipalities, the largest has an income of £1238, and the smallest of £117. In the eight jails of the State, 732 persons were confined in 1883-84.

Sāngli—Chief town of Sangli State, Bombay Presidency, situated in lat 16° 51' 35" N, and long 74° 36' 20" E, on the river Kistna, a little north of the confluence of the Wārna, and north-east of Kolhāpur. Population (1872) 12,961, (1881) 13,272, namely, males 6755, and females 6517. Hindus numbered 10,786, Muhammadans, 1660, Jains, 820, and Christians, 6. The income of the municipality in 1883-84 was £1238. The fort, in which is the chief's palace and most of the public offices, was built about 80 years ago. Dispensary and ten schools, including one for girls.

Sangod—Town in Kōṭh State, Rājputana. Population (1881) 5006, namely, Hindus, 4261, Muhammadans, 582, and 'others,' 163.

Sāngola—Sub-division of Sholāpur District, Bombay Presidency, situated in the south-west corner of the District. Lat 17° N to 17° 40' N, and long 74° 59' to 75° 32' E. Area, 649 square miles. Population (1872) 67,960, (1881) 62,849, namely, males 31,797, and females 31,052, occupying 8196 houses, in 1 town and 75 villages. Hindus number 60,540, Muhammadans, 2197, and 'others,' 112. Sāngola is a level plain with a few treeless hillocks fringing its southern border. It is mostly bare of trees. Villages are three or four miles apart. The chief river is the Mān, which drains the Sub-division from west to north-east for about 35 miles. Most of the soil is stony and barren, and much of it fit only for grazing. In 1882-83, including alienated lands, the total number of holdings was 5259, with an average area of about 54 acres. In 1881-82, the area under actual cultivation was 215,894 acres, of which 8019 were twice cropped. Cereals and millets

occupied 187,840 acres; pulses, 16,982; oil-seeds, 9801 acres; fibres, 5599 acres; and miscellaneous crops, 3691 acres. In 1883 the Sub-division contained 1 civil and 2 criminal courts; police circles (*thánás*), 3; regular police, 37 men; village watch (*chaukidárs*), 115. Land revenue, £8454.

Sángola.—Chief town of the Sàngola Sub-division of Sholápur District, Bombay Presidency; situated 19 miles south-west of Pandharpur, in lat. $17^{\circ} 26' 30''$ N., and long. $75^{\circ} 14' 15''$ E. Population (1881) 4726, namely, Hindus, 4294; Muhammadans, 403; and Jains, 29. Besides the revenue and police officers of the Sub-division, Sàngola has a post-office, two schools, and a fort. The fort, which is now occupied by the Sub-divisional offices, is said to have been built by a Bijápur king; and so prosperous was the town which grew up round it, that until it was plundered by Holkar's Patháns in 1802, it was locally called the Golden Sàngola (*Sonyáche Sàngola*). The town has never recovered the sack of 1802. Municipality, established in 1855, had an income in 1883-84 of £146; incidence of taxation per head of population, 7d.

Sangrámpur.—Town in Champáran District, Bengal; situated in lat. $26^{\circ} 28' 38''$ N., and long. $84^{\circ} 44'$ E., on the river Gandak. Population (1872) 6181. Not separately returned in the Census Report of 1881.

Sangri.—One of the Simla Hill States, Punjab. Area, 16 square miles. Sangri is situated south of the river Sutlej (Satlaj), and formerly belonged to the Rájás of Kúlu, whose main possessions lay north of that river. Population (1881) 2593, all Hindus, residing in 435 houses; number of families, 550. When the Gúrkhas were expelled by the British in 1815, the estate was restored to the Rájá of Kúlu. His territories north of the Sutlej were, however, conquered by the Sikhs, and the Rájá took refuge in Sangri, where he died childless in 1841. On the country falling under British power after the first Sikh war, his nephew was recognised, in 1847, as chief of Sangri. The present (1884) Tika of Sangri is Hira Singh, a Rajput. Estimated gross revenue, £100. The chief products are opium and grain.

Sangu.—Sub-division of the Chittagong Hill Tracts, Bengal, formed in March 1867. It comprises the tract of country between the rivers Sangu and Mátámuri, along the north-eastern frontier of Bengal. Owing to the manner in which the Census of 1881 was taken in this backward District, no separate details of population, etc. are available. In 1883 the Sub-division contained 1 civil and 1 criminal court, with a regular police force of 32 men, and a semi-military frontier police numbering 135.

Sangu.—River of Chittagong, Bengal; rises in the range of hills dividing Arakan from the Chittagong Hill Tracts, near the hill of Kudáng. After a circuitous course of about 125 miles, generally

northerly, over a rocky bed, it reaches Bandarban, from which town it takes a tortuous westerly direction through Chittagong District, and finally empties itself into the Bay of Bengal, in lat $22^{\circ} 6' N$, and long $91^{\circ} 53' E$, about 10 miles south of the Karnaphuli. The Sangu is tidal as far as Bandarban, its bed here is sandy. Though shallow in ordinary times, during the rains this river becomes deep, dangerous, and rapid. In its upper reaches, the Sangu is called by the hillmen the Rigray Khyaung, midway, before entering the plains, it is known as the Sabak Khyaung. It is navigable by large cargo boats for a distance of 30 miles throughout the year. The principal tributary is the Dolu.

Sanivarsante — *Kasba* or administrative head-quarters of Yelusa virashime taluk, in the territory of Coorg. Lies on the Merkara Kodlipet road. Distance from Merkara, 38 miles. Population (1881) 390. The name of the village is derived from a weekly fair held on Saturday. Manufacture of coarse cloth.

Sanján — Small village in Thána (Tanna) District, Bombay Presidency, and a station on the Bombay, Baroda, and Central India Railway. Believed to have been formerly a large town, and the place where the Pársis first landed in India. Known to the Portuguese, and long after their time, as 'St John'.

Sanjeli — Petty State of Rewá Kántha, Bombay Presidency. Area, $33\frac{1}{2}$ square miles, contains 12 villages. Population (1881) 3751. Estimated revenue, £700. No tribute is paid. The chief is named Thákur Partáb Sinhyi. The land is fertile, but the people are Bhils and poor husbandmen.

Sankaridrug (*Sanka giri Durgam*) — Village in Trichengod taluk, Salem District, Madras. Lat $11^{\circ} 28' 52'' N$, long $77^{\circ} 55' 40'' E$. Population (1881) 1302, dwelling in 280 houses. Sub magistrate's court, railway station, Roman Catholic chapel, and telegraph office.

The village is situated at the foot of the Durgam or Drúg, a square mass of gneiss rising 1000 feet above the plain, and 2345 feet above sea level, completely terraced with fortifications, while half way up, like a pearl set in emeralds, a white mosque nestles amongst the rich foliage which still covers part of the hill. On the summit is a small plateau, with a good supply of water stored in the rock. Viewed from below, the hill is a source of interest to the geologist, from the very fine specimens of granite veins piercing the gneiss, which have been exposed in the course of ages.

The Drúg was a place of great strength, and was not attempted by Colonel Wood in 1768, when he captured all the surrounding forts. The fortifications on the summit show traces of European engineering.

Sankarkati — Village in Khulna District, Bengal. Noted for its

numerously attended fair held during the *Durgá-pújá*, *Dol*, and *Rath Jātrā* festivals. Bi-weekly market.

Sankarnainárkoil.—*Táluk* or Sub-division of Tinneveli District, Madras Presidency. Area, 712 square miles. Population (1881) 181,064, namely, males 89,566, and females 91,498, occupying 37,817 houses, in 3 towns and 110 villages. Hindus number 172,633; Muhammadans, 2666; Christians, 5761; and 'others,' 4. The *táluk* lies at the foot of the *gháts*, and contains both red and black soils. The red-soil country is broken into valleys and ridges by numerous small torrents and streams descending from the mountains. Its principal wealth lies in its irrigated lands. Rice, plantain-gardens, and betel-vines are the products grown under irrigation. One-fourth of the whole area is black cotton soil, being a portion of the great cotton plain which occupies the north and north-east portion of Tinneveli District. The greater portion of the cotton soil of the *táluk* is poor. In 1883 the *táluk* contained 2 criminal courts; police circles (*thánds*), 8; regular police, 52 men. Land revenue, £26,464.

Sankarnainárkoil.—Town in Tinneveli District, Madras Presidency; situated in lat. 9° 10' 10" N., and long. 77° 34' 35" E., 10 miles east of the road from Madura to Travancore. Population (1881) 8212, dwelling in 1542 houses. Hindus number 7679; Muhammadans, 455; and Christians, 78. A large, well-built town, with fine temples and tanks; and the head-quarters of Sankarnainárkoil *táluk*. Post-office.

Sankarpur.—Town in Chándá District, Central Provinces; situated in lat. 20° 38' N., and long 79° 34' E., 16 miles north-north-east of Chimár. Population (1881) 1758. Government school. Under the Maráthás, a cannon foundry was worked in Sankarpur, and some half-finished guns yet remain.

Sankeswar (more correctly *Shankheswar* or 'the *Shankh* god').—Town in Belgáum District, Bombay Presidency; situated in lat. 16° 15' N., and long. 74° 31' 30" E., 27 miles north by west of Belgáum town. Population (1881) 8109. Sankeswar has a large traffic carried on by about 50 traders, who export cotton and import dry cocoa-nuts, dates, spices, and curry stuff. The ordinary industry is the weaving of waist-cloths, women's robes, and blankets. Post-office, three schools, two of them private, an old temple, and a monastery.

Sankh.—River of Chutiá Nágpur, Bengal; rises in the west of Lohárdagá District, and after a tortuous course of 120 miles, first south-westerly and then south-easterly, joins the South Koel in Gangpur State. The united stream, under the name of the Bráhmañí, enters the sea in the north of Orissa. The confluence of the South Koel and the Sankh is the most picturesque spot in Gangpur. Local tradition

asserts it to be the scene of the amour of the Sage Parásurama with the fisherman's daughter Matsya Gandhá, the offspring of which was Vyása, the reputed compiler of the *Veda* and the *Mahabhárat* :

Sankhá — Village in Gházipur *tahsil*, Gházipur District, North Western Provinces, situated in lat. $25^{\circ} 47' N$, long $80^{\circ} 44' 34'' E$, 4 miles from Gházipur town. Population (1881) 2262, chiefly Rájputs. Bi weekly market. Annual fair in September, lasting two days.

Sankhatra — Town and municipality in Zaffarwál *tahsil*, Sidlkot (Sealkote) District, Punjab, situated in lat. $32^{\circ} 13' N$, long $74^{\circ} 58' E$, about 30 miles from Sidlkot town. Population (1881) 2381, namely, Muhammadans, 1242, Hindus, 1030, Juns, 82, and Sikhs, 27. Number of houses, 305. Municipal income (1883-84), £125, or an average of 1s 1d per head. Trade in sugar, the produce of neighbouring villages. School and post-office.

Sankheda — Town in Baroda State, Bombay Presidency — See SAKHERA.

Sankheda Mewás — Group of native estates in Rewá Kántha, Bombay Presidency — See SINDKHER MEWAS.

Sámkhund — Spring in Bhágalpur District, Bengal, so called from the monster *sankh* or shell Panchajanya, mentioned in the *Mahádbhárata*, the sound of which filled the breasts of the enemy with dismay. This shell is said to have rested beneath the waters of the spring and its impression on the bank—three feet in length by a foot and a half wide—is still shown.

Sankisa.—Village and ruins in Farukhábad District, North Western Provinces, identified by General Cunningham with the great city of the same name, which formed the capital of a considerable kingdom in the 5th century A D. Situated on the Kálí nadí river, 23 miles west of Fatehgarh town. Visited by Fa Hian about 415 A D, and by Hiuen Tsiang in 636 A D, when it was a celebrated place of Buddhist pilgrimage, as being the reputed spot where Buddha, accompanied by Indra and Brahma, descended again upon earth by three staircases of gold, silver, and crystal or precious stones after a residence of three months in the Triyastinshas' heaven, spent in preaching the law to his mother, Maya. The three staircases are believed to have sunk underground immediately after the descent, leaving only seven steps visible. King Asoka afterwards erected a pillar to commemorate the event, but no remains of it can now with certainty be discovered. Hiuen Tsiang mentions that the site and the memorial pillar were, in his time, enclosed within the walls of a great monastery.

The existing village is perched upon a mound of ruins, known as the *kilá* or fort, 41 feet in height, with a superficial extent of 1500 feet by 1000. A quarter of a mile southward is another mound, composed of solid brickwork, and surmounted by a temple to Lisari Devi. North

of the temple mound, at a distance of 400 feet, lies the capital of an ancient pillar, bearing an erect figure of an elephant, wanting the trunk and tail. The capital is described by General Cunningham as being of the well-known bell-shape, reeded perpendicularly with a honeysuckle abacus, as in the pillar at Allahábád; and it evidently belongs to the same period, the 3rd century B.C. Hence General Cunningham considers it identical with Asoka's monument, mentioned by the Chinese Pilgrims, although the latter was said to be crowned by the figure of a lion—a discrepancy which the learned archæologist explains away by supposing that the trunk was already broken off in the 5th century A.D., and that the animal could no longer be distinguished at a height of 50 feet above the ground.

South of the temple of Bisári Devi, again, at a distance of 200 feet, occurs a third small mound of ruins, apparently the remains of a *stupa*; while 600 feet due east is a fourth mound, 600 feet by 500, known as Nivi-ka-kot, which seems to contain the remains of some large enclosed building like a Buddhist monastery. The fort and the various mounds which surround the temple form a mass of ruins 3000 feet in length by 2000 in breadth, or nearly 2 miles in circuit; but this space appears only to enclose the citadel and the religious edifices which gathered round the three holy staircases by which Buddha descended upon the earth. The city itself, which surrounded the central holy enclosure, was girt by an earthen rampart upwards of $3\frac{1}{2}$ miles in circumference, and still distinctly traceable in the shape of an irregular dodecagon. Three openings which occur in the rampart are traditionally pointed out as the gates of the ancient city. South-east of the Sankisa ruins lies the tank of the Nága, known as Karewar, and identified with a 'dragon tank' described by Fa-Hian. The city was probably destroyed during the wars between Prithwi Ráj of Delhi and Jai Chand of Kanauj. Other interesting ruins occur in the neighbouring village of SARAI-AGHAT, $\frac{3}{4}$ mile distant north-west.

Sankos (or *Suvarnakos*; so called from its golden sands).—River of North-Eastern Bengal, flowing through the low tract of country between the Himálayas and the Brahmaputra, where no river preserves its identity amid the frequent fluvial changes that take place year by year. It can only be affirmed that the name is given, in different parts of its course, to a river that flows southward from the Bhután Hills, and ultimately joins the Brahmaputra, in lat. $25^{\circ} 52' N.$, and long. $89^{\circ} 52' E.$ The main channel of this river forms the boundary between the Eastern and Western Dwárs, thus separating Bengal from Assam. Its chief tributaries are the Káljání and Ráidhak on the right bank, and the Gadádhar on the left. The name of the GADADHAR is commonly applied to the united stream.

Sánkshi (*Sakse*).—Customs division in Kolába District, Bombay

Presidency Under Sánkshi are two ports—Antora, the port of Pen on the Pen creek, and Nagothna at the head of the Rewas creek or Amba river. Average annual value of sea borne trade for the five years ending 1883-84—imports, £42,690, exports, £87,172, total, £129 862. In 1883-84 the trade amounted to—imports, £42,041, exports, £87,498, total, £129 539.

Sánkshi (also known as *Badr ud din* or *Dargahcha Kila*, from a tomb or *dargah* of the saint *Badr ud-din* at its foot)—Fort in the Pen Sub-division of Kolába District, Bombay Presidency, situated on a hill about five miles north east of Pen town. The scene of repeated struggles between the Gujarát and Ahmadnagar princes and the Portuguese, passing into the possession of either power more than once. In 1827, Sánkshi was the scene of an encounter between a detachment of the 4th Rifles and a band of fanatical *dakáts*, in which three European soldiers were killed. The place was the head-quarters of a Sub-division until 1866, when they were removed to Pen.

Sann—Town in the Mánjhand *táluk* of Sehván Sub-division, Karáchi (Kurrachee) District, Sind, Bombay Presidency, situated in lat 26° N, and long 68° 8 E, close to the western bank of the Indus, at the mouth of a torrent that issues from the Laki Hills, on the main road from Kotri to Sehván, being 11 miles north of Mánjhand, and 11 south of Amri. Sann station, on the Sind, Punjab and Delhi Railway, is a little more than two miles from the town. To the south west of Sann is the ruined fort of Raní ká kot said to have been constructed by two of the Talpur Mirs early in the present century, at a cost of 12 *lákhs* of rupees (say £120,000). Originally the river flowed near the walls, but when its course changed, the fort was abandoned. Sann has no trade or manufactures of any consequence, but as it is situated on the trunk road, *kafilas* (caravans), with various commodities from Kandahár and Khelát, pass through it. Sann is the head-quarters of a *tappadár*, it also contains a post-office school *dharmsáls* and a small police post. Population (1872) 1798, namely, 1362 Muhammadans and 436 Hindus, not separately returned in the Census Report of 1881.

Sanosra—Petty State in the Jhaláwír division of Káthiáwar, Bombay Presidency, consisting of 3 villages, with 1 shareholder or tribute-payer. Area, 13 square miles. Population (1881) 1140. Estimated revenue, £403 of which £18, 12s is paid as tribute to the British Government and £5, 0s 2d. to the Nawáb of Junágarh.

Sansar Dhára.—Grotto and place of pilgrimage in Dehra Dun District, North Western Provinces. Lat 30° 21 N, long 78° 6 E. A waterfall gushes from a cleft in the rock, with a grotto behind it, in which stalactites are formed. The Hindus consider it sacred to Mahadeva, and visit it in considerable numbers. Distant from Mussooree (Masúri) about 12 miles.

Santál Parganá, The.—District in the Lieutenant-Governorship of Bengal, lying between $23^{\circ} 48'$ and $25^{\circ} 19'$ N. lat., and between $86^{\circ} 30'$ and $87^{\circ} 58'$ E. long. Area, 5456 square miles. Population, according to the Census of 1881, 1,568,093 souls. The Santál Parganá form the southern portion of the Bhálgapur Division. They are bounded on the north by the Districts of Bhálgapur and Purniah; on the east by Maldah, Murshidábád, and Bírbbhúm; on the south by Bardwán and Mánbbhúm; and on the west by Hazáribágh, Monghyr, and Bhálgapur. The administrative head-quarters are at DUMKA.

Physical Aspects.—Three distinct types of country are represented in the Santál Parganá. In the east of the District, a belt of hills stretches with a semicircular curve for about a hundred miles from the Ganges to the Núnbil river. West of this is a rolling tract of long ridges with intervening depressions, covering an area of about 2500 square miles. The third type is exemplified by a narrow, almost continuous, strip of alluvial land about 170 miles in length, lying for the most part along the loop-line of the East Indian Railway. The total area of this alluvial tract is about 650 square miles. The undulating upland tract, which includes the Sub-divisions of Deogarh and Jamtára and the southern portion of Goddá, is in many parts overgrown with jungle; and the gneiss, which forms the geological basis of the District generally, is here overlaid by the carboniferous shales and sandstones that form the Deogarh coal-field.

The RAJMAHAL HILLS, which abruptly rise from the valley of the Ganges, were, until very recently, regarded as a continuation of the Vindhyan range of Central India. It has been found, however, that not only are they physically quite detached from the Vindhyan hill system, but geologically there is nothing in common between the two. The Rájmahál Hills occupy an area of about 2000 square miles, of which 1366 square miles are in the Government estate of the Dáman-i-koh; they nowhere rise higher than 2000 feet above the sea, their average elevation being considerably less. Among the highest ridges are Morí and Sendgarsa, each about 2000 feet above the sea. The principal ranges of the Rájmahál Hills outside the Dáman-i-koh are the Núni, Sankara, Rámgarh, Kulanga, Sarbor, Sundardihi, Lakshmanpúr, and Sabchala. Singanmát, a peak in the Sankara range, is well known as a landmark for all the country round. Most of these hills are covered almost to their summits with dense jungle, and are difficult of access. There are, however, numerous passes through the successive ranges, over which good roads might without difficulty be made.

The Ganges forms the northern and a large part of the eastern boundary of the Santál Parganá, and all the rivers of the District eventually flow either into it or into the Bhágíráthí. The chief of these rivers are the Gumání, the Moral, the Bánsloi, the Bráhmańí, the Mor or

Morákhi with its tributary the Naubí, the Ajai, and the Bardkhar. None of them is navigable throughout the year.

Forests — Although the face of the country is to a large extent covered with jungle, there are no forests in the Santál Parganá which contain timber of much commercial value. Government obtains a small revenue by leasing out the right to cut timber for fire wood in the Dámnikoh, and trifling amounts are realized by the landholders in the form of royalties on every axe employed in cutting wood. The characteristic tree of the jungles of the District is the *sál*, large numbers of which are floated down the Mor during the rains, while still more are exported during the dry season on *sagurs* or block wheeled carts.

Jungle Products — The principal jungle products of the Santál Parganá are the following — Lac, found on the *palus, ber*, and *pípal* trees, and exported in small quantities from the Maharájpur station, but not locally manufactured. *Tasar* silk cocoons are gathered in large quantities by the Santals and Pahariás. *Dhund* or resin is obtained by girdling the *sál* tree. Beeswax, catechu, honey, *sábus* grass, *konju*, and *jombár*, two creepers used for making rope, and also a variety of edible products, are collected in the jungles. The use of jungle products as a means of subsistence is confined, for the most part, to Pahariás, Santáls, and Bhuiyás. Patches of grazing ground are to be found in all the hills and jungles, but cattle are not brought from other Districts for grazing.

Minerals — Coal and iron are found in almost all parts of the Santál Parganá. The various attempts that have been made to work coal mines, and to quarry building stone in the District are noticed in a subsequent paragraph. In 1850, some copper and silver ores were dug up by Captain Sherwill in the Sub District of Deoghar. Fourteen pounds of silver ore were treated in Calcutta by Mr H. Piddington, Curator of the Museum of Economic Geology, and yielded 154 grains of pure silver, showing it to be 'far above an average ore'. The copper ore was found to be very poor. Picturesque waterfalls are formed near the villages of Kuskurá, Simhpur, and Mahárajpur, and there are several mineral springs in the District.

Fera Naturæ — Tigers, leopards, bears, hyenas, deer, and wild hog, with a variety of small game, are common almost everywhere. Elephants and rhinoceros used to be seen, but have now almost died out. Wild ducks, pigeons, geese, snipe, partridges, and quail abound in the marshes of the alluvial part of the District.

History — The administrative history of the Santál Parganá is the history of the gradual withdrawal of the territory now comprised in the District from the operation of the general Regulations, that withdrawal being throughout dictated by a regard for the peculiar national

character of the two races of Paháriás and Santáls. The policy was in the first instance set on foot by Mr. Augustus Cleveland, Collector of Bhágálpur, in the rules which he proposed for the management of the Paháriás between 1780 and 1784. These rules, which are referred to in the article on BHÁGALPUR DISTRICT, were incorporated in Regulation I. of 1796, so that Cleveland has a fair claim to be considered the author of the Non-Regulation system. It followed, however, from confirming the Paháriás in possession of the hills, that disputes arose between them and the Hindu *zamíndárs* of the plains as to the right of grazing cattle and cutting timber along the lower slopes. That the hills had really or nominally belonged to the *zamíndárs*, there can be no doubt; but the troubles following the British accession, and shortly afterwards the great famine of 1769-70, had weakened or destroyed their control. Cleveland practically assumed possession of the hills on behalf of Government; they were excluded from the Permanent Settlement in 1793; and finally in 1823, the Government by Resolution declared its proprietary right in the hills, and ordered that the tract covered by this declaration should be demarcated. Accordingly, in 1825, two Government officials were deputed to demarcate with solid masonry pillars the present area of the Dáman-i-koh or 'skirts of the hills,' a work which was not completed till 1833. The great central valley still remained the property of the *zamíndár* of *parganá* Bhágálpur till 1839, when it too was resumed. The permission to Santáls to settle in the valleys and on the lower slopes of the Dáman-i-koh stimulated Santál immigration to an enormous extent; and it might be supposed that the natural consequence of that immigration would have been the admission of the Santáls to the exceptional privileges which the Paháriás already enjoyed. But this measure, although more than once proposed, was not approved by Government; and the next phase in the history of the District is the Santál rebellion of 1855-56.

The story of that rebellion, and the causes which led to it, would occupy more space than can here be given; but the reader will find an exhaustive account of it in Hunter's *Annals of Rural Bengal*, and a shorter sketch under article INDIA (*ante*, Vol. VI.). The Santáls, starting with the desire to revenge themselves on the Hindu money-lenders who had taken advantage of their simplicity and improvidence, found themselves arrayed in arms against the British Government. The insurrection was not repressed without bloodshed, but it led to the establishment of a form of administration congenial to the Santál immigrants; and a land settlement has recently been carried out on conditions favourable to the occupants of the soil.

Population.—No estimate of the population of the entire District exists previous to the Census of 1872. That enumeration disclosed a total of 1,259,287 persons; while the last Census in 1881 returned

a total of 1,586,093, or an apparent increase of 308,806, or 24.52 per cent, in 9 years. This increase, however, is to a very large extent only nominal, and is mainly attributable to the much greater accuracy of the enumeration in 1881. The results of the Census of 1881 may be summarized as follows — Area of District, 5456 square miles, towns 4, and villages 11,750, number of houses, 252,486, namely, 246,746 occupied, and 5740 unoccupied. Total population, 1,568,093, namely, males 785,330, and females 782,763. Average density of population, 287.4 persons per square mile, towns and villages per square mile, 206, persons per town or village, 139, houses per square mile, 46.28, persons per occupied house, 6.36. Classified according to sex and age, there were—under 15 years of age, boys 368,939, and girls 358,530, total children, 727,469, or 46.4 per cent of the population. 15 years and upwards, men 416,391, and women 424,233, total adults, 840,624, or 53.6 per cent. The abnormally large proportion of children is due to the fact that the aboriginal Santals are one of the most prolific races in Bengal.

Religion — Classified according to religion, the Census of 1881 returned the population as follows — Hindus, 847,590 or 53.4 per cent, Muhammadans, 108,899 or 6.8 per cent. Christians, 3057, Buddhists, 132, Sikhs, 54, Jains, 2, Jews, 6, and tribes professing aboriginal religions, 608,353 or 38.4 per cent, of whom 559,602 were Santals and 11,995 Kols, the remainder being made up of other tribes.

Among the higher Hindu castes, Bráhmans number 36,075, Rajputs, 28,124, Bábhans or cultivating Brahmans, 5406, Káyasths, 7820, and Baniyás, 28,124. The lower or Sudra castes of Hindus include the following — Ghátwál, not properly a caste, although returned as such in the Census Report, but a branch of the aboriginal race of Bhuiyás. They, however, take the name of Ghátwál as a caste designation to denote their occupation as guardians of the hill passes. They keep fowls and pigs, but the well-to-do members of the tribe claim to be Kshattriyas. The number of Ghátwáls returned as such in the Census Report of 1881 was 38,032. Goálá, the most numerous caste in the District, 88,544, Dom, 35,723, Chamár, 33,546, Lohár, 26,433, Telí, 24,986, Nápit, 21,714, Kumbhár, 21,484, Mál, 20,533, Sunrí, 19,059, Musahár, 18,588, Buirí, 18,515, Kahárs, 16,608, Koerí, 13,589, Mádál, 13,462, Kurmí, 13,177, Dhanuk, 12,162, Kalu, 10,929, Dosádh, 10,801, Kaibartta, 10,749, Hari, 8894, Tántí, 8864, Dhobí, 8052, Rajwar, 6215, Barhai, 5841, Baidi, 5104, Kaláír, 4673, Sonár, 4156, Málí, 3807, Tainbuh, 3186, Málíah, 2799, Káindu, 2772, Chárf, 2626, Sadgop, 2471, Pasi, 2420, Tatwál, 2401, Tiór, 2381, and Birui, 2218. Caste-rejecting Hindus were returned at 8103, of whom 6346 were Vaishnavs.

character of the two races of Paháriás and Santáls. The policy was in the first instance set on foot by Mr. Augustus Cleveland, Collector of Bhágálpur, in the rules which he proposed for the management of the Paháriás between 1780 and 1784. These rules, which are referred to in the article on BHAGALPUR DISTRICT, were incorporated in Regulation I. of 1796, so that Cleveland has a fair claim to be considered the author of the Non-Regulation system. It followed, however, from confirming the Paháriás in possession of the hills, that disputes arose between them and the Hindu *zamíndárs* of the plains as to the right of grazing cattle and cutting timber along the lower slopes. That the hills had really or nominally belonged to the *zamíndárs*, there can be no doubt; but the troubles following the British accession, and shortly afterwards the great famine of 1769-70, had weakened or destroyed their control. Cleveland practically assumed possession of the hills on behalf of Government; they were excluded from the Permanent Settlement in 1793; and finally in 1823, the Government by Resolution declared its proprietary right in the hills, and ordered that the tract covered by this declaration should be demarcated. Accordingly, in 1825, two Government officials were deputed to demarcate with solid masonry pillars the present area of the Dáman-i-koh or 'skirts of the hills,' a work which was not completed till 1833. The great central valley still remained the property of the *zamíndár* of *parganá* Bhágálpur till 1839, when it too was resumed. The permission to Santáls to settle in the valleys and on the lower slopes of the Dáman-i-koh stimulated Santál immigration to an enormous extent; and it might be supposed that the natural consequence of that immigration would have been the admission of the Santáls to the exceptional privileges which the Paháriás already enjoyed. But this measure, although more than once proposed, was not approved by Government; and the next phase in the history of the District is the Santál rebellion of 1855-56.

The story of that rebellion, and the causes which led to it, would occupy more space than can here be given; but the reader will find an exhaustive account of it in Hunter's *Annals of Rural Bengal*, and a shorter sketch under article INDIA (*ante*, Vol. VI.). The Santáls, starting with the desire to revenge themselves on the Hindu money-lenders who had taken advantage of their simplicity and improvidence, found themselves arrayed in arms against the British Government. The insurrection was not repressed without bloodshed, but it led to the establishment of a form of administration congenial to the Santál immigrants; and a land settlement has recently been carried out on conditions favourable to the occupants of the soil.

Population.—No estimate of the population of the entire District exists previous to the Census of 1872. That enumeration disclosed a total of 1,259,287 persons; while the last Census in 1881 returned

a total of 1,586,093, or an apparent increase of 308,806, or 24.52 per cent, in 9 years. This increase, however, is to a very large extent only nominal, and is mainly attributable to the much greater accuracy of the enumeration in 1881. The results of the Census of 1881 may be summarized as follows — Area of District, 5456 square miles, towns 4, and villages 11,250, number of houses, 252,486, namely, 246,746 occupied, and 5740 unoccupied. Total population, 1,568,093, namely, males 785,330, and females 782,763. Average density of population, 287.4 persons per square mile, towns and villages per square mile, 2.06, persons per town or village, 139, houses per square mile, 46.28, persons per occupied house, 6.36. Classified according to sex and age, there were—under 15 years of age, boys 368,939, and girls 358,530, total children, 727,469, or 46.4 per cent of the population. 15 years and upwards, men 416,391, and women 424,233, total adults, 840,624, or 53.6 per cent. The abnormally large proportion of children is due to the fact that the aboriginal Santals are one of the most prolific races in Bengal.

Religion — Classified according to religion, the Census of 1881 returned the population as follows — Hindus, 847,590 or 53.4 per cent, Muhammadans, 108,899 or 6.8 per cent, Christians, 3057, Buddhists, 132, Sikhs, 54, Jains, 2, Jews, 6, and tribes professing aboriginal religions, 608,353 or 38.4 per cent, of whom 559,602 were Santals and 11,995 Kols, the remainder being made up of other tribes.

Among the higher Hindu castes, Bráhmans number 36,075, Rájputs, 28,124, Bábhrans or cultivating Brahmans, 5406, Kájasths, 7820, and Baniyás, 28,124. The lower or Súdra castes of Hindus include the following — Ghátwál, not properly a caste, although returned as such in the Census Report, but a branch of the aboriginal race of Baniyás. They, however, take the name of Ghátwál as a caste designation to denote their occupation as guardians of the hill passes. They keep fowls and pigs, but the well-to-do members of the tribe claim to be Kshattriyas. The number of Ghátwáls returned as such in the Census Report of 1881 was 38,032. Goálá, the most numerous caste in the District, 88,544, Dom, 35,723, Chamár, 33,546, Lohár, 26,433, Telí, 24,986, Nápit, 21,714, Kumbhár, 21,484, Mál, 20,533, Sunrí, 19,059, Musahár, 18,588, Baurí, 18,515, Kárhárs, 16,608, Koerí, 13,589, Madáik, 13,462, Kurmí, 13,177, Dhanuk, 12,162, Káru, 10,929, Dosádh, 10,801, Kaibartta, 10,749, Han, 8894, Tántí, 8864, Dhobí, 8052, Rajwar, 6215, Burhau, 5841, Bagdú, 5104, Kalkár, 4673, Sonár, 4156, Málí, 3807, Fainbuh, 3186, Mallah, 2799, Kandu, 2772, Chísí, 2626, Sadgop, 2471, Písí, 2420, Tatwá, 2401, Tior, 2381, and Biruf, 2218. Casteless Hindus were returned at 8193, of whom 6346 were Vaishnavs.

The Muhammadans in 1881 numbered 108,899, or 6·33 per cent. of the population, classified according to sect into—Sunnís, 96,736; Shiás, 2607; and unspecified, 9556. The Musalmán population of Deogarh Sub-division is said to have been introduced early in the 18th century by the Muhammadan Rájá of Nagar in Bírghúm District, of whose *samindari* or principality it formed a part. In Dumká Sub-division, the Muhammadans mostly belong to the low weaving castes, whose adherence to the religion of Islám is little more than nominal. A few Wahábi revivalists are found in Rájmahál Sub-division, where the landholders are Muhammadans, and memories of Musalmán domination still survive. Taking the Santál Parganá as a whole, the Muhammadans do not hold a high social position, and are a far less wealthy and less influential body than the Hindus.

Of the aboriginal population, 608,353 are returned as still professing their primitive faiths. Of these, 559,602 are returned as Santáls, 11,995 as Kols, and 36,756 as belonging to other aboriginal tribes. Besides these, the Census returns show 108,355 aborigines among Hindus, consisting of—Bhuiyás, 61,640; Santáls, 9148; Bhumijs, 3880; Khárwárs, 2862; Kols, 2094; Gonds, 571; and other tribes, 28,160. The Paháriás are not returned separately in the Census of 1881, and are probably included with the general body of Santáls. Total Hindu and non-Hindu aboriginal population, 716,708. This, however, does not include aborigines converted to the faith of Islám or to Christianity; and the list of Hindu castes includes several undoubted aboriginal and semi-aboriginal tribes; e.g. the Ghátwáls, Baurís, Bindis, etc. An account of the Santáls forms the subject of the following article in this volume.

The Christian population of the Santál Parganá amounted at the time of the Census of 1881 to 3057 souls, namely, Europeans, Americans, and Africans, 182; Eurasians, 108; natives of India, 2718; and 'others,' 49. Nearly all the converts belong to the aboriginal races who are engaged in agriculture; and Christianity has produced little effect upon the general Hindu population, or on the more civilised inhabitants of the towns. The Church Missionary Society has stations in the District at Hiránpur, Táljhari, Godda, Bhagaia, and Baháwa; as also has the Santál Home Mission, with its head-quarters at Dumká. A private mission carries on work in Jamtára. Within the past few years, attempts have been made, through the Rev. L. O. Skrefsrud, the head of the Santál Home Mission, to improve the condition of the converts by establishing Christian colonies of Santál agriculturists in Assam, where unlimited spare land is available. Between 1880 and 1885, nine such colonies were established, with a total population of between 600 and 700 men, women, and children. These colonies were situated in the Gumá dwár, near Berresen, in charge of

the Settlement, reported in September 1885, that the colony had successfully passed the initial stage of experiment, that a considerable area of land had been reclaimed from jungle and brought under cultivation, that, free from the pressure of Bengali landlords and usurers, and with a splendid soil yielding rich crops, the colonists, with three or four individual exceptions, had all become well to-do, and many of them rich according to Santal ideas. The whole of the debt due to Government, incurred in the shape of advances made to start the undertaking, has been paid off by the settlers.

Ethnical Division of the People—The distribution of the races in the Santal Parganas is traceable rather to the controlling action of Government, than to the geographical position or physical conformation of the District. The colony of Pahariás which occupies the Rájmahál hills is like an advanced outpost, cut off from the main body of the aboriginal races farther west by the great Aryan line of communication between Bengal and Behar. Although the crests of the ranges are barren enough to deter any other race from contesting their possession with the Pahariás, yet there is little doubt that but for the ring fence erected by Government between 1825 and 1833, all the lands of the lower levels would have been occupied by Bengali or Hindustáni immigrants. Since the enclosure of the Dámaní koh, however, a continual stream of Santal immigrants has been pouring into the District from Hazáribágh and Mámbhum, and occupying the valleys and lower slopes of the hills which the Pahariás do not cultivate. The remaining inhabitants of the District are either Bengali immigrants from the south east, or Hindustánis from the north west, but the Census returns afford no means of estimating the relative strength of the two nationalities in the Santal Parganas. With reference to the three tracts of hilly, undulating and alluvial country into which the District is divided, it may be laid down with approximate correctness that the hilly country is inhabited mainly by Santáls, Pahariás, and other aboriginal tribes, the undulating region by semi aboriginal races, with a smaller proportion of aborigines and a fair sprinkling of Aryan settlers, and the alluvial strip of country almost entirely by Aryans.

Town and Rural Population—The population is almost entirely rural, and the only places with upwards of five thousand inhabitants are DEOGAHI, population (1881) 8005, and SAHIBGANJ, the great commercial mart on the Ganges, population 6512. The only other places with any pretensions to be called towns are DUMKA, the administrative headquarters of the District, 2075, and RAJMAHAL, 3839. Of the 11,250 villages, as many as 8998 contain less than two hundred inhabitants, 1881 between two hundred and five hundred, 335 between five hundred and a thousand, 33 between one thousand and two thousand, and 3 between two thousand and three thousand inhabitants.

As regards occupation, the Census Report returns the male population under the following six classes:—(1) Professional class, including civil and military, 7134; (2) domestic class, 14,625; (3) commercial class, including traders and carriers, 15,323; (4) agricultural and pastoral class, including gardeners, 325,718; (5) manufacturing and industrial class, including all artisans, 27,593; and (6) indefinite and unspecified class, comprising general labourers and male children, 394,937.

Agriculture.—Rice forms the staple food-grain of the District. *Jārān* or *ūman* rice, the winter crop of the year, is of two kinds—*būo*, which is sown broadcast; and *ropū dhūn*, which is transplanted; of these, forty varieties are named. In the alluvial strip of country which runs along the eastern boundary of the District, rice is largely cultivated; and the lower slopes of the ridges in the undulating tract, as well as the swampy ground between those ridges, are also sown with rice. Level terraces are cut out of the hillsides, which thus present the appearance of a series of steps varying from one to five feet in height. These rice terraces are flooded as soon as possible after the rains set in, small banks being left round the edge of each plot to hold the water. Among the other crops of the District are millets, wheat, barley, maize, various pulses and oil-seeds, jute, flax, sugar-cane (of which four varieties are distinguished), cotton, and indigo. There are two seasons for sowing indigo: the spring sowings are put into the ground in March, and reaped in June; and the autumn or October sowings are also cut in the following June.

No accurate statistics are available showing the area under different crops; and it is evident from what has been said regarding the physical aspects of the District, and the mode of rice cultivation in the undulating tract, that there would be considerable difficulty in estimating the aggregate area under rice. The food crops grown in the District are, (1) rice, (2) *janirā* or maize, and (3) other grains, such as millet and pulses. Of this food supply locally produced, rice forms eleven-sixteenths; *janirā* three-sixteenths. There are large stretches of spare land all over the District, and cultivation is being gradually extended to them.

No scientific system of rotation has as yet been developed, but a sort of rotation is followed on high lands only recently brought under cultivation, which are sown for three successive years with oil-seeds or pulses. On homestead lands around the cultivator's house, which can be thoroughly manured, it is a common practice to alternate Indian corn with mustard. Manure, consisting of cow-dung, wood-ashes, and mud from the bottom of tanks, is commonly used for sugar-cane, and for such high land crops as Indian corn, tobacco, and mustard, when they are in the neighbourhood of the house, and can conveniently be

attended to. Rice is not manured at all. Irrigation is effected for the most part by *bāndhs* or small embankments thrown across the upper and narrower ends of the trough like hollows which make up the surface of the country. Each embankment thus holds up the natural drainage and forms a small reservoir at a high level. Land below the *bāndh* growing a rice crop can be irrigated by leading the water round the edges of the embankment, or by cutting the embankment itself, while the wheat, barley, sugar cane, and poppy crops of the adjacent high lands can be watered by a lift. Wells are not used for irrigation.

There is no tendency towards the formation of a distinct landless labouring class. Such a class formerly existed in the *lamis* or bondsmen, the nature of whose servitude is described in the article on Hazaribāgh District (vol v pp 376, 377). This system, however, was put an end to in the Santāl Parganās by the late Sir George Yule, when Commissioner of the Bhāgalpur Division, who ordered the cancellation of all *lami* bonds, and sent the *lamias* to work upon the railway then under construction. The agricultural day labourers, while finding their regular employment in working for others, are not, as a class absolutely landless, and generally have small patches of cultivation of their own. Of such labourers there are two kinds, known as *krishāns* and *bhagīrs*. The *krishān* either uses his own agricultural implements and takes one half of the produce, or uses his employer's implements and gets only one third. In any case, the employer pays the rent and provides the seed. The *bhagīr* works on less advantageous terms, as he not only contributes his personal labour and the use of his own agricultural implements, but also finds the seed, and only receives one half of the produce.

In consequence of the enhanced demand for labour on the railway and public works, wages have risen materially of late years. Prices of food grains and of all agricultural produce have also risen. Common rice in 1883-84 sold at the rate of 19½ *seers* per rupee, or 5s 9d per cwt, and wheat at 14½ *seers* per rupee, or 7s 9d per cwt. These prices are rather above the average, owing to the year being one of deficient rainfall.

Natural Calamities — Blight of a serious kind is not known in the Santāl Parganās. Owing to the completeness of the natural drainage, floods are almost impossible over a large area, on the rare occasions on which the crops in the alluvial tract have been injured by flood, the loss thus caused was more than compensated by the increased yield of the high lands. Drought caused considerable distress in the Santāl Parganās in 1866, and again in 1874. In the former year the price of rice rose in July to 7½ *seers* and in August to 6½ *seers* for the rupee, in the latter year the highest price was 10 *seers*. The fact of rice rising to 10 or 14 *seers*, or paddy to 20 or 25 *seers*,

would indicate the approach of famine, and relief measures would become necessary. It has been remarked that abundant crops of wild fruit are usually concomitants of famine years; and this was the case both in 1866 and in 1874. The *mahuá* tree, which is very common in the Santál highlands, yielded in 1874 a bounteous crop of edible blossoms and seeds; and the mango was also plentiful, and formed a sensible addition to the food supply of the people, who live much on wild fruits and herbs. In 1866, the people in this District, as in other parts of Behar, were forced by want to eat the mangoes while still unripe, and thousands of deaths by cholera were the result. In 1874, relief was afforded on such a scale that the fruit was allowed to ripen before being plucked, and there was no outbreak of disease.

Commerce and Trade, etc.—The trade of the District is carried on by means of permanent markets. The chief exports are rice, Indian corn, oil-seeds, *tasar*-silk cocoons, lac, small-sized timber, hill bamboos, and stone. The imports include European piece-goods, salt, and brass or bell-metal utensils for household use. The principal mart, both for railway and river trade, is SAHIBGANJ, on the Ganges. This place is most favourably situated on the deep channel of the river, which flows at all seasons close under the town; and the railway station is quite near. RAJMAHAL, on the loop-line of the East Indian Railway, is another important mart. Both Sáhíbganj and Rájmahál mainly depend upon their through traffic. They are, in fact, depôts, where the agricultural produce of the trans-Gangetic Districts of Maldah, Purniah, and Bhágalpur is collected for transmission by rail to Calcutta. The manufactures of the District are insignificant. Iron is roughly smelted; coarse cloth is woven, silk-spinning is carried on, a few bell-metal utensils are made, and indigo is manufactured on a small scale. There are altogether about 500 miles of road in the Santál Parganás; and the District is traversed on the east by the loop-line, and on the west by the chord-line of the East Indian Railway—the total length of both lines, including a portion of the small branch connecting Madhupur with the Karharbári collieries, being about 130 miles. Coal is found in the District, but of such inferior quality that all attempts made to work it have failed. Stone is quarried by an English firm under leases from Government and the *zamíndárs*, and exported down the Ganges to Calcutta for use as road-metal.

Administration.—In 1860–61, the total revenue of the Santál Parganás amounted to £22,680, and the expenditure to £16,845. In 1870–71 the revenue was £38,901, and the expenditure £14,391. In 1883–84 the five main items of Government revenue aggregated £45,437, made up as follows:—Land revenue, £22,556; excise, £11,758; stamps, £9662; registration, £740; municipal taxes, £721. Cost of civil administration, £16,438. Number of criminal,

Pákaur, (5) Jamtára, and (6) Godda. There are 32 fiscal divisions (*parganás*) in the District. The gross municipal income of Deogarh and Sáhíbganj (the only municipalities in the Santál Parganás) amounted in 1883 to £1216, of which £721 was derived from taxation; average incidence of taxation, 1s. per head of the population (14,296) within municipal limits.

Medical Aspects.—The climate of the Santál Parganás varies in the different tracts which have been referred to in describing the physical features of the District. The alluvial strip of land has the damp heat and moist soil characteristic of Bengal; while the undulating and hilly portions are swept by the hot westerly winds of Behar, and resemble in their rapid drainage and dry subsoil the lower plateau of Chutiá Nágpur. In this undulating tract the winter months are very cool, but the hot season is correspondingly trying. The average annual rainfall is 60·23 inches. Rainfall in 1883–84, 47·84 inches, or 12·39 inches below the average. No thermometrical returns are available. The prevailing endemic diseases of the District are fevers of the ordinary type, bowel complaints, and skin diseases. The hill tracts of Rájmahál are very malarious. Epidemics of cholera and small-pox break out from time to time, but have been for the most part confined to the town of Deogarh. There are 5 charitable dispensaries in the Santál Parganás, which afforded medical relief in 1883 to 7569 in-door and out-door patients. [For further information regarding the Santál Parganás, see *The Statistical Account of Bengal*, by W. W. Hunter, vol. xiv. pp. 265 to 384 (Trübner, 1877); also the *Bengal Census Report* for 1881; and the several Administration and Departmental Reports of the Government of Bengal.]

Santáls, The.—An aboriginal Kolarian tribe, inhabiting a tract of country forming a strip of Bengal; about 350 miles in length, extending from the Ganges at Bhágálpur to the Baitarani river in Orissa. The Imperial Census Report of 1881 does not return the number of Santáls to be found throughout India; but, with the exception of a small body of about 7000, who have emigrated to Assam as coolies on the tea estates, or as labourers, and a few isolated cases of individuals scattered elsewhere, the whole Santál population inhabits the strip of Bengal above cited. The Census Report of Bengal for 1881 returns the total Santál population of the Province, excluding Christian converts, or any who may have embraced the faith of Islám, at 1,087,202, comprising Hindus 203,264, and non-Hindus 883,938. A little more than one-half, namely, 546,694, or 50·3 per cent. (of whom only 9148 are Hindus), are found in the single District of the Santál Parganás, which, however, as explained below, and in the District article, is not the original home of the race, but that in which they have settled during the present century. The following table, compiled from the Bengal Census

Report of 1881, shows the distribution of the Santals in the different Bengal Districts in 1881, classified into Hindus and non Hindus —

SANTALS IN BENGAL IN 1881

DISTRICTS	Non Hindu	Hindus	TOTAL
Santal Parganas	537 245	9 148	546 694
Midnapur	42 700	86 403	129 103
Bankura	112 062	565	112 627
Hazaribagh	84 559	20 034	104 593
Singbhum	56 598		56 598
Birbhum	648	51 924	52 600
Bhagalpur	14 172	726	14 898
Bardhaman	13 384	42	13 426
Monghyr	6 418	5 606	12 224
Balasar	6 938		6 938
Orissa Tributary States	4 206	339	4 545
Other Bengal Districts,	633	922	1 555
	4 074	27 325	31 399
Grand Total	883 938	203 264	1 087 202

The following paragraphs quoted in a slightly condensed form from Colonel E. T. Dalton's *Descriptive Ethnology of Bengal* describe generally the history of the Santals so far as ascertained their physical appearance habits and mode of life —

History — The Santal Parganas or Santalia said to contain upwards of 100,000 Santals [546 694 in 1881] may now be regarded as the nucleus of the Santal race, though it does not appear to have been one of their original seats. Dr Buchanan Hamilton in describing the hill tribes of Bhagalpur and its vicinity, makes no mention of Santals. The aboriginal tribes he fell in with are called Malais the Rajmahal hill men proper and their kindred who are a Dravidian people. It is singular that no old colonies of Santals or other Kolarian tribes are found between the Himalayas and the Ganges. The Santal Settlements that now border on that river or skirt the Rajmahal hills are readily traced back to more southern Districts and their own traditions hardly support the theory of their northern origin. Indeed when we find that the Kolarian races have left their trail in Assam that it may be followed throughout the Siam States and Burma to the Pegu District, and is faintly discerned in the adjoining islands that it may be taken up at Point Palmyra and clearly traced along both banks of the Damodar river till it reaches the hills and table land of Chutia Nagpur, — it is scarcely reasonable to assume that they have all come direct from the Himalayas. The Damodar, rising in Palamau, divides the Hazaribagh and Chutia Nagpur plateau and draining the northern face of the one, and the southern face of the other, discharges itself

into the Húglí near the mouth of the latter river. It is the terrestrial object most venerated by the Santáls; and the country that is most closely associated with their name, which they apparently regard as their fatherland, is between that river and the Kasáí. There is no doubt, however, that Santáls colonized parts of Hazáribágh District and of Bírbbhúm at a very remote period, and it is chiefly by migrations from these colonies that the modern Santália has been formed.

'In 1832, a considerable impetus was given to the northward movement, in the action taken by Government to secure to the Rájmahál highlanders their possessions in the hills that form the turning-point of the Ganges at Sáhíbganj. To prevent the encroachments of the lowland *zamíndárs* of Bhágálpur, which were constantly exciting reprisals from the highlanders, a tract of country measuring nearly 300 miles in circumference was separated and marked off by large masonry pillars. Of the land within these pillars the Government was declared to be direct proprietor, and the hill people were informed that their rights in it would be respected so long as they conducted themselves peaceably. But the hill-men only cared for the highlands; and the tract included within the pillars, called the Dáman-i-koh or skirts of the hills, and the valleys running into the hills, were available for other settlers, and were speedily taken up by Santáls. In a few years the Santál population had increased from 3000 to 83,000 souls, when the colony received a check by the Santál insurrection of 1854.

'For a history of this rebellion, and the causes that led to it, the reader may be referred to the *Annals of Rural Bengal*. The Santáls, starting with the desire to revenge themselves on the money-lenders who had taken advantage of their simplicity and improvidence, found themselves arrayed in arms against the British Government. It was not without bloodshed that the insurrection was suppressed; but it led to their being re-established under a more genial administration in what are now called the Santál Parganás. In the Dáman-i-koh, their own form of self-government is to some extent restored to them. The villages are farmed to the head-men, called *mánjhis*, who are also the sole guardians of the peace, a system that had been already introduced with success into the Kolhán of Singhbbhúm.

Migratory Habits.—'In marked contrast to the Kolarians of the Munda and Ho Divisions, the Santáls, as a rule, care little for permanently locating themselves. A country denuded of the primeval forest which affords them the hunting-grounds they delight in and the virgin soil they prefer, does not attract them; and when, through their own labour, the spread of cultivation has affected this denudation, they select a new site, however prosperous they may have been on the old, and retire into the backwoods, where their harmonious flutes sound

to the sun god, Singh Bonga, for the prosperity of the family, especially of the children, "that they may not be cut off by disease, or fall into sin" The sacrifice is offered at sunrise, on an open space cleaned and purified for the occasion. A very important distinction is observed by all the Kolarians in the motives of the sacrifices to the supreme deity, and of those by which the minor gods are propitiated. To Singh Bonga the sacrifice is to secure a continuance of his mercies, and for preservation. The other deities are resorted to when disease or misfortune visits the family, the sacrifice being to propitiate the spirit who is supposed to be afflicting or punishing them.

'Ancestors are worshipped, or rather their memory is honoured, at the time of the *Sohrai* festival, and offerings are made at home by each head of a family. In the meantime the *naijá* propitiates the local devils or *bhuts*. In many villages the Santals join with the Hindus in celebrating the *Durgá Púja*, the great festival in honour of Devi, and the *Holi*, in honour of Krishna. Their own priests take no part in the ceremonial observances at those Hindu feasts, which are left to the Bráhmans.

'The person or persons who have to offer sacrifices at the Santal feasts prepare themselves for the duty by fasting and prayer, and by placing themselves for some time in a position of apparent mental absorption. The beating of drums appears at last to arouse them, and they commence violently shaking their heads and long hair, till they work themselves into a real or apparent state of involuntary or spasmodic action, which is the indication of their being possessed. They may then give oracular answers to interrogatories regarding the future, or declare the will of the spirit invoked or about to be propitiated. When the demoniacal possession appears to have reached its culminating point, the possessed men seize and decapitate the victims, and pour the blood into vessels ready placed for its reception. Among the Santals in Chutiá Nágpur, Singh Bonga, or the sun, is the supreme god, the creator and preserver. The other deities are Jahir Era, Monika, and Mirang Burú, who are all malignant and destructive. In the eastern Districts the tiger is worshipped, but in Rámgarh only those who have suffered loss through that animal's ferocity condescend to adore him. If a Santal is carried off by a tiger, the head of the family deems it necessary to propitiate the Bagh Bhut, the tiger, and to be sworn on a tiger skin in the most solemn of oaths.

'Santals who, under the example and precept of Bengali Hindus, have abjured some practices considered impure by the latter, are called Sat Santals, that is, pure Santals, but there is a national antagonism between the Santals and the Hindus that prevents any close fraternization or communion between the races. The Santals are not over

characteristics which the tribes linguistically allied to them do not possess."

Tribal Divisions.—‘The Santáls, like the Israelites, are divided into twelve tribes:—(1) Sírán; (2) Murma; (3) Marll; (4) Kisku; (5) Desera; (6) Handsa; (7) Túdi; (8) Baski; (9) Hemrow; (10) Karwár; (11) Chorai; (12) Except No. 11, the above agree with the nomenclature of tribal divisions of Santál tribes in Mr. Mann’s work; numbers 1, 2, 3, 4, 6, 7, and 11 with the names of the seven sons of the first parents as given in the *Annals of Rural Bengal*. Numbers 2, 3, 6, 9, and 11 are found in the list of the tribes of the Singhbhúm Larka Kols or Hos. This is remarkable, as the legends of origin handed down among the Larkas have little in common with the traditions of the Santáls. Though the former also assign twelve sons to the first parents, these were the primogenitors, not of the various *kilis* or tribes of Hos, but of different families of mankind, including Hindus and Santáls, the latter being the offspring of the youngest pair, who, when told to separate from the family, selected pig as their staple food. The names given above include only one to which a meaning is attached, viz. Murma, which signifies the *nilgái* (Portax vel Antelope pictus); and the Murmas may not kill the animal whose name they adopt, nor touch its flesh.

Village Polity, Festivals, and Religion.—‘The polity of the Santáls is very patriarchal. In each village there is (1) a *jag-mánjhí*, whose most important duty is apparently to look after the morals of the boys and girls; (2) a *parámánik*, whose business it is to attend to the farming arrangements, and to apportion the lands. He disallows any monopoly of peculiarly fertile rice lands; all must take their share of good and bad. He has to look after the interest of new settlers, and to provide for guests, levying contributions for that purpose on the villagers. All the offices are hereditary; when a new settlement is formed, the office-bearers are elected, after that the next of kin succeeds. (3) There is a village priest who is called *naiyá* (*nayaka*, vulgo *layá*). This is a word of Sanskrit derivation, and as the Santáls have no name in their own language for such an office, it is probably not an original institution. He has lands assigned to him; but out of the profits of his estate he has to feast the people twice in the year at the festival of the *Sarkíl*, held towards the end of March, when the *sál* tree blossoms, and at the *Moi Muri* festival, held in the month of Aswin (September–October), for a blessing on the crops. At the *Sohrai* feast, the harvest home, in December, the *jag-mánjhí* entertains the people, and the cattle are anointed with oil and daubed with vermilion, and a share of rice-beer (*hándia*) is given to each animal. Every third year in most houses, but in some every fourth or fifth year, the head of the family offers a goat

to the sun-god Singh Bonga, for the prosperity of the family, especially of the children, "that they may not be cut off by disease, or fall into sin." The sacrifice is offered at sunrise, on an open space cleaned and purified for the occasion. A very important distinction is observed by all the Kolarians in the motives of the sacrifices to the supreme deity, and of those by which the minor gods are propitiated. To Singh Bonga the sacrifice is to secure a continuance of his mercies, and for preservation. The other deities are resorted to when disease or misfortune visits the family, the sacrifice being to propitiate the spirit who is supposed to be afflicting or punishing them.

Ancestors are worshipped, or rather their memory is honoured, at the time of the *Sohrai* festival, and offerings are made at home by each head of a family. In the meantime the *naijá* propitiates the local devils or *bhuts*. In many villages the Santals join with the Hindus in celebrating the *Durgá Puja*, the great festival in honour of Devi, and the *Holi*, in honour of Krishna. Their own priests take no part in the ceremonial observances at those Hindu feasts, which are left to the Brahmins.

The person or persons who have to offer sacrifices at the Santal feasts prepare themselves for the duty by fasting and prayer, and by placing themselves for some time in a position of apparent mental absorption. The beating of drums appears at last to rouse them, and they commence violently shaking their heads and long hair, till they work themselves into a real or apparent state of involuntary or spasmodic action, which is the indication of their being possessed. They may then give oracular answers to interrogatories regarding the future, or declare the will of the spirit invoked or about to be propitiated. When the demonical possession appears to have reached its culminating point, the possessed men seize and decapitate the victims, and pour the blood into vessels ready placed for its reception. Among the Santals in Chutiá Nágpur Singh Bonga, or the sun, is the supreme god, the creator and preserver. The other deities are Jahur Lra, Monika, and Mirang Buru who are all malignant and destructive. In the eastern Districts the tiger is worshipped, but in Rámgarh only those who have suffered loss through that animal's ferocity condescend to adore him. If a Santal is carried off by a tiger, the head of the family deems it necessary to propitiate the Bagh Bhút, the tiger, and to be sworn on a tiger skin is the most solemn of oaths.

Santals who, under the example and precept of Bengali Hindus, have abjured some practices considered impure by the latter, are called Sat Santals that is pure Santals, but there is a national antagonism between the Santals and the Hindus that any close
nization or communion between the is are

particular about food, but nothing will induce them to eat rice cooked by a Hindu, or even by a Bráhmán. Unfortunately, during the famine of 1866 this was not known to us. The cooks who prepared the food distributed at the relief centres were all Bráhmáns, and it was supposed that this would suit all classes; but the Santáls kept aloof, and died rather than eat from hands so hateful to them. They have no tradition to account for this bitter feeling. The animosity remains, though its cause is forgotten.

Social Customs.—‘The Santál parents have to undergo purification five days after child-birth; a kind of gruel is prepared, and after a libation to Singh Bonga or Marang Búrú, it is served out to the mother and the other members of the family. An eldest son is always named after his grandfather, other children after other relations. The Santáls have adopted as a rite the tonsure of children, and do not appear to recognise the necessity for any other ceremonial observance till their marriage when adult. Child marriage is not practised.

‘There is no separate dormitory for the boys and girls in a Santál village. Accommodation is decorously provided for them in the house of the parents, but the utmost liberty is given to the youth of both sexes. The old people, though affecting great regard for the honour of the girls, display great confidence in their virtue. Unrestrained, they resort to markets, to festivals, and village dances in groups; and if, late in the evening, they return under escort of the young men who have been their partners in the dance or have played to them, no harm is thought of it.

Music.—‘The peculiar emblem of the Santáls should be the flute; they are distinguished from all people in contact with them by their proficiency on that instrument. Made of bamboo, not less than one inch in diameter, and about 2 feet in length, their flutes are equal in size to the largest of our concert flutes, and have deep rich tones. This faculty of playing the flute and a general knowledge of singing and dancing were, they say, imparted to them by their first parents; and it was also by their first parents that they were taught the mysteries of brewing rice-beer, and they therefore consider there can be no great harm in freely indulging in it.

Dances.—‘There is always reserved an open space in front of the *jag-mánjhí*'s house as a dancing place. To this the young men frequently resort after the evening meal. The sound of their flutes and drums soon attract the maidens, who smooth and adjust their long hair, and, adding to it a flower or two, blithely join them. It is singular that, in this national amusement of the Santáls, we have handed down to us a most vivid living representation of one prominent scene in the sports of Krishna in Braja and Brindában. There is

nothing in modern Hinduism that it all illustrates, the animated scenes so graphically delineated in the *Purānas*, but the description of the *Rāsa* dance in chapter xiii, book 1, of the *Viṣṇu Purāṇa* might be taken literally as an account of the Santāl *Jumhur*. We have in both the maidens decked with flowers and ornamented with tinkling bracelets, the young men with garlands of flowers and peacocks' feathers, holding their hands and closely compressed, so that the breast of the girl touches the back of the man next to her, going round in a great circle, limbs all moving as if they belonged to one creature, feet falling in perfect cadence, the dancers in the ring singing responsive to the musicians in the centre, who, fluting, drumming, and dancing too, are the motive power of the whole, and form an axis of the circular movement. Thus, as the pivot for the dances, sometimes sported Krishna and his favourite companions, "making sweet melody with voices and flutes," but more frequently they took their places in the ring, "each feeling the soft pressure of two maidens in the great circling dance." We are told that Krishna, when he thought the lovely light of autumn propitious for the *Rāsa* dance, commenced singing sweet low strains in various measures, such as the Gopīs (milkmaids) loved, and they, as soon as they heard the melody, quitted their homes and joined him. Just so, on a moonlight night, the Santāl youth invite the Santāl maidens. Professor Wilson, in his note on the passages of the *Viṣṇu Purāṇa* referred to above, observes that the *Rāsa jātra* is celebrated in various parts of India in the month of Kārtik (October), but that a circular dance of men and women does not form any prominent feature at these entertainments, and he doubts if it ever is performed. In the late autumn months the Kols and Uraṇs have numerous *jātras*, at which these circular dances are performed by thousands.

Marriage Ceremonies — 'With such freedom of intercourse, it follows that marriages are generally love matches, and, on the whole, happy ones, but it is considered more respectable if the arrangements are made by the parents or guardians, without any acknowledged reference to the young people. The price to be paid for the girl, averaging five rupees, with presents of cloths to her parents, having been determined on, a day is fixed for a preliminary feast, and afterwards for the marriage itself, and a knotted string which shows the number of days that intervene, is kept as a memorandum. Each morning one of these knots is removed by the impatient lover, and, when the last is loosened, the bridegroom and his friends with noisy music, set out for the abode of the bride. As they approach the village, the *jangam* comes out to meet them attended by women with water to wash the feet of the guests, who are then escorted to the house of the bride, and the two mingling together merrily sing, dance, and feast

in front of the bride's chamber. At the last quarter of the night, the bridegroom makes his appearance, riding on the hips of one of his comrades, and soon after the bride is brought out by a brother or brother-in-law in a basket. Then comes the inevitable *sindra dán*. The groom daubs his lady-love on the crown and brow very copiously with vermilion (*sindur*), and the assembled guests applaud with cries of *hari bol*. The bride and bridegroom, having fasted all day, now eat together, and this is supposed to be the first time that the girl has sat with a man at her food. It is creditable to the Kolarians that this custom has been retained through ages, notwithstanding the derision with which it is viewed by all Hindus. On the following day, before the party breaks up, the young people are thus admonished by one of the sages:—"Oh boy! oh girl! you are from this day forth to comfort each other in sickness or sorrow. Hitherto you have only played and worked (as directed), now the responsibility of the household duties is upon you; practise hospitality, and when a kinsman arrives wash his feet and respectfully salute him." No priest officiates at a Santál marriage. The social meal that the boy and girl eat together is the most important part of the ceremony. By this act the girl ceases to belong to her father's tribe, and becomes a member of her husband's family. Santáls seldom have more than one wife, and she is treated with most exemplary kindness and consideration. Should the husband be for any reason, as her barrenness, induced to seek a second partner during her lifetime, the first wife is never deposed from her position as head of the household; the second wife must obey her and serve her.

Hunting Expeditions.—'A Santál in prosperous seasons leads a pleasant life. He is either busy with his cultivation, or playing his flute, or dancing with the girls, or engaged in the chase. He throws himself with ardour into the latter pursuit, and in hunting down beasts of prey he evinces great skill and powers of endurance and indomitable pluck. The Santáls have every year a great hunting festival, in which thousands take part. These expeditions are organized with as much care and forethought as if the hosts engaged in them were about to undertake a military campaign. They take place in the hot season, when the beasts have least cover to conceal themselves in. When the array of hunters reaches the ground on which operations are to commence, they form a line of beaters several miles in length, every man armed with a bow and arrows and a battle-axe, and accompanied by dogs, who, though ugly creatures to look at, appear, like their masters, to be endowed with a true hunting instinct. When they emerge from the woods on open spaces, the game of all kinds that are driven before them suddenly appear. Birds take wing and are beaten down with sticks or shot with arrows; quadrupeds, great and

small, are similarly treated, and in this way deer, pig, jungle fowl, peafowl, hare, etc., are bagged, but tigers and bears on these occasions of open warfare are generally avoided. These hunting excursions last for four or five days, and at the end of each day the Santals feast merrily on the contents of their bags, and thoroughly enjoy themselves. The rule in regard to possession of an animal killed is that it belongs to him who first wounded it, no matter by whom the *coup de grace* may have been inflicted.

'The Santals employed in the police force are very highly spoken of by an officer who long commanded them. They may not be expert detectives in tortuous cases, but in following up *dakáits*, and attacking them when found, they are far superior to the ordinary Bengali constables, and many instances of their activity and pluck have been related to me. Living as they generally do on the edges of forests, their constitutions are proof against malaria, and they may be employed on outpost duty in localities that are deadly to most people. They have been thus utilized on the Grand Trunk Road in places where the jungle comes down to the road.

Dress — 'The Santals dress better than most of their cognates. This also, it appears, is derived from the instruction of their first parents, who appointed the size of the garments that were to be worn respectively by male and female but omitted to teach their offspring how they were to be made. They have no weavers among their own people. The women wear ample *sáris*, a large thick cloth, not less than six yards in length, with a gray red border. One-half of this forms the lower garment, secured at the waist, but not so as to impede the free action of the limbs, the other half is passed over the left shoulder, leaving the right shoulder, arm, and part of the breast free, and allowed to hang down in front. It is not, as with Hindu maidens, used also as a veil. The heads of young girls are generally uncovered, displaying a mass of black, rather coarse, but sometimes wavy hair, gathered into a large knob at one side of the back of the head, ornamented with flowers or with tufts of coloured silk.

'"Their arms, ankles, and throats, writes Colonel Sherwill, "are each laden with heavy brass or bell metal ornaments. I had a quantity of these ornaments weighed, and found that the bracelets fluctuated from two to four pounds, and the entire weight sustained by one of these belles was ascertained to be no less than thirty four pounds of brass or bell metal. The average may be estimated at about twelve pounds."

'In *Funerel Ceremonies* the Santal varies from the practice of the Ho and Mundá tribes. The body is borne away on a *chápá* or cot by kinsmen, and when it reaches a cross road, some parched rice and cotton seed are scattered about, as a charm against the

malignant spirits that might throw obstacles in the way of the ceremony. It is then taken to a funeral pile near some reservoir or stream, and placed on it. The son or brother is the first to apply fire to the body, by placing a piece of burning wood on the face of the corpse; and soon all that is left are ashes and a few charred fragments of bones of the skull, which are carefully preserved. Towards evening, it is customary for a man to take his seat near the ashes with a winnowing fan, in which he tosses rice till a frenzy appears to seize him, and he becomes inspired and says wonderful things. After the incremation, the immediate relatives of the deceased have to undergo a quarantine, as impure, for five days. On the sixth they shave themselves and bathe, and sacrifice a cock. In due course, the bones that have been saved are taken by the nearest of kin to the Dámodar. He enters the stream bearing the sacred relics on his head in a basket; and selecting a place where the current is strong, he dips, and commits the contents of his basket to the water, to be borne away to the great ocean as the resting-place of the race. All inquirers on the subject appear to have arrived at the conclusion that the Santáls have no belief in a future state. The pilgrimage to the Dámodar with the remains is simply an act of reverence and affection, unconnected with any idea that there is a place where those who have left this world may meet again. It is to be observed that when the Santáls in disposing of their dead differ from the Mundas, they approximate to the Bráhmanical custom. It is, in fact, a rough outline of the Bráhman ritual, and only wants filling in. The halting at cross-roads and the scattering of rice, the application of fire first to the head by a relation, the collecting of the charred bones, especially those of the head, are all included in the ceremonies enjoined on Bráhmans and orthodox Hindus. The Bráhman, like the Santál, carefully preserves the bones in an earthen vessel; he is ordered to bury them in a safe place till a convenient season arrives for his journey to the sacred river—in his case, the Ganges—where he consigns the vessel with its contents to the waters.'

Sántalpur-with-Chádchat.—Native State in the Political Superintendency of Pálanpur, Gujarát, Bombay Presidency. The two Subdivisions of Sántalpur and Chádchat together form an estate ruled by a number of petty chieftains. Bounded on the north by the Morwára and Suigám estates, on the east by the States of Wáráhi and Rádhanpur, and on the south and west by the Rann of Cutch. The two estates measure together about 37 miles in length, and 17 miles in breadth. Area, 440 square milés. Population (1881) 20,466; estimated yearly revenue, £3500. The country is flat and open. *Ghasiá* or self-produced salt is found in large quantities. There are no rivers, but

many ponds exist, which in normal seasons retain water till March, when the inhabitants have to depend upon wells for their supply. Fever is common. The holders of this State are Járeja Rájputs, kinsmen of the Ráo of Cutch, by whom the country was conquered about 400 years ago. The ruling family hold no *sanad* authorizing adoption, in matters of succession they follow the rule of primo geniture. One school with 49 pupils in 1882-83—See also CHAND CHAT

Santapilly (*Sentapilli*)—Village and lighthouse in Vizagapatam District, Madras Presidency—See CHANTAPILLI

Sántipur—The most populous town in Nadia District, Bengal; situated on the river Hugli, in lat $23^{\circ} 14' 24''$ N, and long $88^{\circ} 29' 6''$ E. Population (1881) 29,687, namely, males 13,708, and females 15,979. Hindus number 20,701, Muhammadans, 8945, and 'others,' 41. Municipal income (1883-84), £2288, of which £1855 was derived from taxation, average incidence of taxation, is 2½d per head. Sántipur is famous for its cloth manufactures, which were at first spread throughout the whole District, but afterwards became centralized in this town, owing to its being the site of a commercial residency and the centre of large factories under the East India Company. Considerable local trade. The *Rasjatra* festival, in honour of Krishna, is celebrated at Sántipur on the day of the full moon in Kártik (October or November). The fair is visited by about 25,000 persons, and continues for three days, on the last of which there is a procession along the high road. Sántipur is also a celebrated bathing place.

San ywe (*Tsan rwe*)—The southern township of Tharawadi District, Pegu Division, Lower Burma. In the east, the country is mountainous and forest-clad, producing teak and other valuable timber, in the west, it is low and liable to inundation. The township is traversed from north to south by the Hlaing river, which receives drainage from the Pegu Yoma range, and communicates with the Irawadi on the west. Population (1881) 70,430. Land revenue, £10,876. Head-quarters at San ywe village, containing a court house and police station, population (1881) 615.

Sáoli.—Town in Chánda District, Central Provinces: situated in lat $20^{\circ} 5'$ N, and long $79^{\circ} 50'$ E, 7 miles east of Múl. Population (1881) 3680, namely, Hindus, 3508, Muhammadans, 28, Jains, 9, and non Hindu aborigines, 135. Manufacture of cotton cloth, and trade in cotton, cotton cloth, grain, groceries, and *gur*. Sáoli has a weekly market, and contains a Government school.

Sáoligarh—State forest, yielding teak and *sál*, in the north and north west of Betúl District, Central Provinces. Comprises several blocks of hills between the Moran river on the east and north, and Rájabardi on the west. Area, 130 square miles.

Sáoner (*Sonár*).—Thriving town in Nágpur District, Central Provinces; situated in lat. $21^{\circ} 23' N.$, and long. $78^{\circ} 58' E.$, 24 miles north-west of Nágpur city, near the main road to Chhindwára, with which place a good branch road connects the town. Population (1881) 5023, chiefly agricultural. Hindus number 4739; Muhammadans, 232; Jains, 7; and non-Hindu aboriginal tribes, 45. Municipal income (1882-83), £159; average incidence of taxation, $7\frac{1}{2}d.$ per head. The Kolár river flows through the town, which stands in a fertile and well-cultivated plain. It has a circular market-place, with large masonry platforms, from which two broad metalled roads lead south-west and west through the most populous quarters, and are connected by a third street of similar character. Chief manufactures—cotton cloth, which is largely exported, and an inferior snuff, made by the Musalmán population. A large cattle fair is held weekly. Sáoner has a travellers' bungalow (rest-house), handsome *sarái* (native inn), police station, and school, in which English is taught. The fort in the centre of the town, now ruined, must once have been large and strong. Tradition relates that it was built by Gauli chiefs before the days of the Gond; but for many generations Sáoner has belonged to the Gond family of Swasthánik.

Sáorgaon.—Village in Kátol *tahsil*, Nágpur District, Central Provinces. Population (1881) 3241, namely, Hindus, 3039; Muhammadans, 172; Jains, 9; and non-Hindu aborigines, 21.

Saptagrám.—Ruined town in Húglí District, Bengal.—See SATGAON.

Sar.—Lake in Puri District, Bengal. A back-water of the BHARGAVI river, situated to the north-east of Puri town; its length from east to west is 4 miles, and its breadth from north to south 2 miles. Lat. (centre) $19^{\circ} 51' 30'' N.$, long. $85^{\circ} 55' E.$ This lake has no outlet to the sea, and is separated from it by sandy ridges, which are entirely destitute of inhabitants. The Sar is not used to any extent for fisheries; its water, however, is employed for irrigation when the rainfall proves deficient.

Sará.—*Parganá* in Hardoi District, Oudh; bounded on the north by Alamnagar, on the east by Mansúrnagar, on the south-east and south by Gopámau and Báwan, and on the west by Sháhábád. A *parganá* with a fertile soil, and a large area occupied with *jhils* and marshes. Area, 90 square miles, of which 49 are cultivated. The main products are wheat and barley, which occupy nearly one-half the total cultivated area. Population (1881) 34,527, namely, 33,140 Hindus and 1387 Muhammadans. Of the 85 villages in the *parganá*, 59 are owned by Chamár Gaurs. Only 1 of these villages is held in *tálukdári* tenure, 40 in *zamindári*, 43 in imperfect *pattidári*, and 3 in *bháyáchára* tenure. Government land revenue, £5612;

equal to an average of 3s. 7d per cultivated acre, or 2s per acre of total area

Sárágaj (or *Langla*)—Hill range in the south of Sylhet District, Assam, running northwards as a spur from the State of Hill Tipperah. Estimated area, 81 square miles, height above sea level, 1100 feet

Saragur (*Sargur*)—Municipal village in Mysore District, Mysore State, situated in lat. $12^{\circ} 0' 10''$ N, and long $76^{\circ} 25'$ E, on the right bank of the Kabbani river, 36 miles south west of Mysore city. Since 1870 the head quarters of the Heggaddevankot taluk. Population (1871) 1626, not separately returned in the Census Report of 1881. Owes its administrative importance to its healthy position, the neighbourhood being free from jungle

Saráhán—Town in Bashahr (Bussahir) State, Punjab, situated in lat $31^{\circ} 30'$ N, and long $77^{\circ} 50'$ E, in a wooded amphitheatre, 3 miles from the left bank of the Sutlej (Satlej), and backed up by the snow clad summits of a spur of the Himálayas. Thornton describes it as the summer residence of the Bashahr Rájá. Tasteful houses in Tibetan style, with pent roofs, balconies, and intricate carved wood work. Handsome temple dedicated to the goddess Káli. Northern limit of the Brahmans, none of whom reside to the north of the town. Elevation above sea level, 7246 feet

Sarái Aghat—Town and ruins in Etah District North Western Provinces. Distant from Etah town 43 miles south east, from SANKISA three quarters of a mile north west. Lies on either side of a ravine of the Káli Nadi. Population (1881) 2880. *Bázár* of well built houses, leading to a central market place. Police outpost station, village school. Trade in cotton, grain, and indigo seed. Founded towards the close of the 17th century by three Afghán leaders, who came from Farukh Ábád District, and built the Sarai Abdur Rasul and a mosque. West of the village stands a lofty and extensive mound, 40 feet in height and about half a mile in diameter, the northern portion being built over with brick houses. It bears the name of Aghat, derived from Muni Agastya, the mythical regenerator of the Deccan. The houses on the top have been built of bricks from the mound, part of which has been honeycombed by excavations in search of building materials. Images of Buddha, together with gold, silver, and copper coins of all ages, frequently occur. In 1843 about £2000 worth were found among the ruins. Aghat probably formed part of the ancient city of SANKISA.

Sarái Akil—Town in Chail taluk, Allahábad District, North Western Provinces, situated in lat $25^{\circ} 22' 43''$ N, and long $81^{\circ} 33' 15''$ E, 20 miles west-south west of Allahábad city. Population (1881) 2823. The town is noted for its colony of Thatheras, whose brass work and metal ornaments have more than a local reputation. Bi-weekly markets on Tuesdays and Saturdays. Post-office, police station,

and village school. A small house-tax is levied for police and conservancy purposes, realizing £58 in 1881-82.

Sarāikālā.—Political estate in Singhbhūm District, Bengal, lying between $22^{\circ} 33'$ and $22^{\circ} 54' 30''$ N. lat., and between $85^{\circ} 53'$ and $86^{\circ} 13'$ E. long. Area, 457 square miles. Population (1872) 66,347, inhabiting 568 villages or townships (*mauzás*), and 13,675 houses. Not separately returned in the Census Report of 1881.

Sarāikālā.—Village in Sarāikālā estate, Singhbhūm District, Bengal. Lat. $22^{\circ} 41' 52''$ N., long. $85^{\circ} 58' 28''$ E. Weekly market for local produce and articles of trade. Bengali school.

Sarāi Kheta.—Village in Khutahán *tahsíl*, Jaunpur District, North-Western Provinces, and station on the Oudh and Rohilkhand Railway; situated in lat. $25^{\circ} 58' 16''$ N., and long. $82^{\circ} 43' 21''$ E., 6 miles east of Khutahán town. Population (1881) 2921. Bi-weekly market, and large *sarāi* (native inn). Post-office.

Sarāi Mír.—Town in Azamgarh District, North-Western Provinces. Population (1881) 5238, namely, Hindus 2993, and Muhammadans 2245. A small municipal revenue is raised for police and sanitary purposes.

Sarāi Sáleh.—Town in Haripur *tahsíl*, Hazára District, Punjab. Population (1881) 3533. Stands in the Haripur plain, of which it forms the ancient commercial centre. Considerable local traffic. Prosperous colony of weavers. Manufacture of brass and copper vessels. Large cultivation and export of turmeric. Goldsmiths from this place have been in the habit for generations of visiting Afghánistán and Central Asia in pursuit of their trade.

Sarāi Sidhu.—Northern *tahsíl* of Múltán (Mooltan) District, Punjab; consisting of a lowland strip on either bank of the Beas (*Biás*) river, together with an extensive tract of barren upland. Area, 1752 square miles, with 299 towns and villages, and 11,361 houses. Number of families, 16,147. Population (1881) 80,012, namely, males 44,535, and females 35,477. Average density of population, 46 persons per square mile. Classified according to religion, the population consists of—Muhammadans, 66,796; Hindus, 13,084; Sikhs, 126; and Christians, 6. Of the 299 towns and villages, 252 contain less than five hundred inhabitants; 35 between five hundred and a thousand; and 12 between one thousand and five thousand inhabitants. Of a total average cultivated area of 99 square miles, or 63,561 acres, for the five years ending 1881-82, wheat occupied 40,639 acres; *joár*, 4275 acres; gram, 2806 acres; barley, 2386 acres; and cotton, 2025 acres. Revenue of the *tahsíl*, £10,184. The local administration is in the hands of a *tahsildár*, who presides over 1 civil and 1 criminal court; number of police circles (*thánás*), 3; strength of regular police, 77 men; village watch or rural police (*chāukidárs*), 89.

Sarai Sidhu.—Town in Multan (Mooltan) District, Punjab Lat $30^{\circ} 35' 30''$ N, long $72^{\circ} 1'$ E

Saran—District in the Lieutenant Governorship of Bengal, lying between $25^{\circ} 40'$ and $26^{\circ} 38'$ N lat, and between $83^{\circ} 58'$ and $85^{\circ} 14'$ E long Area, 2622 square miles Population (1881) 2,280,382 souls Saran forms one of the north western Districts of the Patná Division It is bounded on the north by the District of Gorakhpur in the North Western Provinces, on the east by the Bengal Districts of Champáran and Muzaffarpur, the boundary line being formed by the river Gandak, on the south by the Ganges, which separates it from Sháhábád and Patná Districts, on the south west by the District of Azimgarh in the North Western Provinces, the Gogra forming the boundary line, and on the west again by Gorakhpur District The administrative head quarters are at CHAPRA, which is also the most populous town of the District

Jurisdiction—Saran formerly constituted one District with Champáran The revenue areas of the two Districts were not finally separated until 1866, but the magisterial jurisdictions were first divided in 1837 The Judge of Saran still holds sessions at Motihári in Champáran The Sub division of Sewán was opened in 1848, and a second Sub division at Gopálganj was sanctioned in 1875

Physical Aspects—Saran forms a vast alluvial plain, bounded on three sides by the great rivers Ganges, Gandak, and Gogra (Ghagra), and intersected by numerous *nadis* or water-channels, which flow in a south-easterly direction and carry off the drainage of the District The rivers run on a higher level than the adjacent country, which is therefore liable to inundation when they overtop their banks Beneath these high banks lie the basins in which the surface drainage primarily collects, to be discharged into the running channels at a lower stage in their course The District has the shape of an isosceles triangle The base, which is very irregular, lies to the north west, one of the sides is formed by the Gandak, and the other by the Gogra and the Ganges, while the apex is at the south east corner, where the Gandak and the Ganges join at Sonpur From this spot, the levels slope very gently up towards the western parts of the District Kochai Kot, in the north west corner, is 222 feet above mean sea level, while Sonpur is only 168 feet The whole District is beautifully wooded, and mango groves are very numerous The lower levels are but sparingly used for rice cultivation, high rice lands predominate, and on these indigo, opium, wheat, barley, and several kinds of pulse are also grown The soil is in many places saliferous, and saltpetre is extracted by the Núnjás, a poor and hardy caste There are no hills in Saran

The only rivers which are navigable all the year round are the three

great streams already mentioned—the GANGES, GANDAK, and GOGRA. Among the smaller *nadís*, many of which dry up altogether in the hot weather, are the Sundí or Dáhá, the Jharáhi, the Gandakí, the Gangrí, the Dhanái, and the Khatsá, all of which ultimately fall into the Gogra or Ganges. Alluvion and diluvion are constantly taking place along the banks of the large rivers. One bank of the river, on which the current strikes, is generally high and abrupt, while the other is shelving; but these characteristics may be reversed in a short space of time. The high bank is gradually eaten away, and the current then turns to the opposite side, where a similar process is repeated. Large sandbanks form in the bed of the river one year and are swept away the next, sometimes making changes in jurisdiction necessary. Thus, in 1872, an alteration in the deep stream of the Ganges transferred seven alluvial estates (*diárás*) from Sárán to Azímgarrh District in the North-Western Provinces. The drainage of the District is from north-west to south-east, and is carried off by the many small *nadís* into the larger streams. When the rainfall is unusually heavy, these *nadís* are unable to contain all the water, and large tracts of cultivated ground are inundated. The consequences are specially disastrous when the mouths of the *nadís* are stopped by high floods in the great rivers into which they flow.

There is very little jungle in Sárán, and hardly any forest-products. The lac insect is found on the *pípal* tree, and it is estimated that about 200 *maunds* of the dye are annually exported. Shells are largely gathered for burning into lime. The minerals found in Sárán District are Glauber's salt (*gulbar sora*); and nodular limestone of excellent quality, which is locally used for metalling the roads, and is exported in large quantities to Patná. Large game is not met with, although both tigers and leopards are said to have been at one time very common in the District. Wolves and wild hog are still numerous. Among the game birds found are quail, wild duck, snipe, plover, partridge, ortolans, and green pigeons. Snakes are very numerous. Crocodiles are common in the large rivers, and the rivers and marshes abound in fish.

Population.—Several early estimates were made of the population of Sárán. In 1800, a calculation based on an enumeration of the houses gave 1,104,000 as the number of inhabitants; but this included the present District of Champáran, which was not separated from Sárán until 1837. Estimates based on similar enumerations were made in 1843, 1847, 1854, 1855, and 1860, the earliest giving a population of 1,376,215, and the latest 1,271,729. The first accurate Census was that taken in 1872, which disclosed a total population of 2,063,860. The last enumeration in 1881 returned the population of Sárán District at 2,280,382, showing an increase of 216,522, or 10·49 per cent., in the nine years since 1872.

The results arrived at by the Census of 1881 may be summarized as

follows —Area of District, 2622 square miles, with 7 towns and 4372 villages. Number of houses, 376,787, namely, occupied 326,699, and unoccupied 50,088. Total population, 2,280,382, namely, males 1,083,765, and females 1,196,817, proportion of males, 47·4 per cent. The slight excess of females is due to emigration of males from the more thickly populated tracts, to seek labour elsewhere. As regards density, Sárán is the most thickly populated District within the Lieutenant Governorship of Bengal (except the suburban District of Howrah), with an average pressure on the soil of 870 persons per square mile, as against 860 per square mile in Muzaffarpur, and 845 per square mile in Patná, both neighbouring Districts. Sárán is one of the most purely agricultural Districts in Bengal, with a very fertile soil, and in tracts like the police circles (*thanas*) of Mashrák, Digwára, and Mánjhí, with no towns or large trade centres, the density reaches the enormous average of 1240, 1134, and 1047 per square mile respectively. The most sparsely populated *tháná* is Baragón, with an average of 689 per square mile. The number of villages over the whole District area averages 1·67 per square mile, persons per town or village, 521, houses per square mile, 143·7, inmates per house, 6·9. Classified according to sex and age, the population consists of—under 15 years of age, boys 461,553, and girls 442,538, total children, 904,091, or 40 per cent of the District population. 15 years and upwards, males 622,012, and females 754,279, total adults, 1,376,291, or 60 per cent.

Religion —Classified according to religion, the Census Report of 1881 returns the Hindus at 2,010,958, or 88·2 per cent of the population, Muhammadans, 269,142, or 11·8 per cent, and Christians, 282. High caste Hindus are strongly represented, numbering 579,800, or 25·3 per cent of the total Hindu population, namely, Brahmans, 173,362, Rajputs, 243,972, Bábhans, or *samindari* Brahmans, 84,733, Káyasths, 51,067, and Baniyás, 26,666. The Sudra or lower Hindu castes include the following —Goálá, the herdsman caste, and the most numerous in the District, 256,513, Koerí, 150,354, Kandu, 120,310, Kurmi, 112,570, Chamár, 111,144, Dosádh, 79,593, Nuniyá, 68,720, Tell, 63,087, Lohár, 42,057, Káhar, 35,537, Nápit, 31,844, Kumbhar, 24,594, Kalwar, 23,979, Málh, 22,599, Sonár, 21,472, Bind, 19,127, Dhanuk, 17,801, Dhobí, 17,103, Barhá, 16,936, Tatwá, 10,826, Barui, 10,386, Gareri, 9881, Dom, 9506, Mah, 6909, Musahar, 6465, and Pási, 5562. Caste rejecting Hindus are returned at 3476, of whom 2320 are Vaishnavs. Aboriginal tribes number 20,953 including 11,428 Gonds (?), but all are returned as professing Hinduism. The Muhammadan population, classified according to sect, consists of—Sunnís, 231,533, Shíás, 4072, and unspecified, 33,537. Of the 282 Christians, 138 are Europeans by race, 10 Eurasians, and 134 natives of India. By sect, 71 belong to the Church of England, 43 are Roman Catholics, 31 Protestants

without distinction of sect, and 34 are Lutherans; other sects and unstated, 103. A branch of the Lutheran Evangelical Mission has been stationed in Chapra town since 1840. The majority of the native Christians are very poor, nearly all being cultivators, domestic servants, or labourers.

Town and Rural Population.—The Census Report returns 7 towns as containing upwards of five thousand inhabitants, namely, CHAPRA, population (1881) 51,670; SEWAN, 13,319; REVELGANJ, 12,493; Panapur Chagwan, 6425; Ránsipur Tengrahi, 6197; Mánjhi, 6068; and Parsa, 5735. The total urban population thus disclosed is 101,907, or 4·4 per cent. of the District population. Only the three first-named places, however, are towns in any sense of the word, and they constitute the only municipalities within the District. The other places are merely large villages or collections of hamlets, in the midst of which are conducted all the operations of agricultural life. The income of the three municipalities in 1883–84 amounted to £5302, of which £3556 was derived from taxation; average incidence of taxation, 11d. per head of the population (76,942) within municipal limits.

Of the 4372 villages, 1209 contain less than two hundred inhabitants; 1696 between two and five hundred; 989 between five hundred and a thousand; 392 between one and two thousand; 65 between two and three thousand; and 21 between three and five thousand inhabitants.

As regards occupation, the Census divides the male population into the following six classes:—(1) Professional and official class, 14,915; (2) domestic servants, inn and lodging-house keepers, etc., 27,432; (3) commercial class, including merchants, traders, carriers, etc., 26,640; (4) agricultural and pastoral class, including gardeners, 479,076; (5) manufacturing and industrial class, including all artisans, 62,040; and (6) indefinite and non-productive class, comprising general labourers and all male children, 473,462.

The Material Condition of the People can hardly be good in a densely crowded agricultural District like Sárán. The District is unusually fertile, and almost every available acre highly cultivated. The larger husbandmen, and classes who hold at privileged rates of rent, are enabled to live in comfort in ordinary good seasons. But, considering the rise of rents in late years, it is doubtful whether the great body of cultivators, in spite of the general rise in prices of grain, are better off than formerly. In many parts of the District, too, the increasing number of indigo factories, and the demand for land on this account, are said to have further unfavourably affected their condition. The wealthier classes live in brick houses; the country shopkeepers and husbandmen in mud huts. The better class of houses in the town of Chapra have a verandah, often ornamented with carvings in wood. The house of an ordinary cultivator consists of three or four rooms,

with an outer and an inner verandah, and sometimes a covered place in the centre, where the family sit and receive visitors. The huts of the poorest classes are of a very primitive character, and consist merely of walls of common thatching grass, with a thin roof of the same materials, supported by a few bamboos. *Golds* or granaries for keeping rice are common. The estimated living expenses for a household of six members belonging to a well-to-do shopkeeper is estimated at about £1, 7s per month, and for a similar family of the ordinary cultivating class, at a little below £1 a month, at the ordinary market prices. The husbandman, however, himself produces nearly all his food requirements, and he very seldom has to purchase anything beyond cloth and salt in the *bādar*.

Agriculture—Rice is, perhaps, the most important crop grown in Saran, though the area under rice is largely exceeded by the collective area under such inferior grains as *makar*, *kodo*, and *marud*. It consists of two great harvests—the *bhadai* or autumn harvest, and the *aghani* or winter harvest, the latter being by far the larger of the two. The *bhadai* is generally sown broadcast on high ground in June, and reaped in September. Its chief varieties are, (1) *sathi*, (2) *sarha*, (3) *kathi* or *munga*, and (4) *larhani*. *Aghani* rice is sown on low ground. In June, after rain has fallen, a nursery is selected, and ploughed three or four times before the seed is sown. It is afterwards transplanted, and is harvested in December or January. The 33 principal varieties of this rice are as follows—(1) *Bhoinsloti*, (2) *lanugi*, (3) *khahi*, (4) *jigar*, (5) *senegra*, (6) *jasaria*, (7) *thanomi*, (8) *stro*, (9) *sera*, (10) *salla*, (11) *shakhni*, (12) *kalunji*, (13) *satal*, (14) *sela*, (15) *linji*, (16) *batarini*, (17) *kajri*, (18) *lildana*, (19) *umath*, (20) *rathgoli*, (21) *dachni*, (22) *bellaur*, (23) *baharni*, (24) *bdnsmati*, (25) *simjira*, (26) *jugar*, (27) *lpera*, (28) *rds*, (29) *paharid*, (30) *singhar*, (31) *syamsu dar*, (32) *karanga*, and (33) *gajpatta*.

The other cereals cultivated are wheat, barley, and Indian corn. Green crops comprise *matar* or peas, *lhesari*, gram, *arhar*, *rug*, *urid*, beans, sweet potatoes, mustard seed, etc. Cotton, hemp, and flax are also grown. *Pān* or betel leaf is generally cultivated on high land situated near a well or tank, in the vicinity of the homestead. Special crops comprise tobacco, sugar-cane, indigo, and opium, the latter being cultivated only under Government licence. The total area under indigo in (1884) estimated at 48,750 acres yielding an average outturn of 10,250 cwt, valued at £315,000. The total area under poppy is about 48,700 acres, with a yield of 733,360 lbs. Manure is used whenever it can be procured, and irrigation is largely practised for the cold weather crops.

The poorer class of cultivators are, as a rule, deeply in debt. Rents are high, the following being returned as the average rates throughout

the District :—Transplanted rice, 9s. 6 $\frac{3}{4}$ d. per acre ; broadcast rice, 6s. 9d. ; Indian corn, wheat, *marud*, *arhar*, and cotton, 11s. 3d. ; *kodo*, barley, and pulse, 9s. 5 $\frac{1}{2}$ d. ; poppy, 15s. 8d. ; indigo, 10s. 4 $\frac{1}{2}$ d. ; and sugar-cane, 9s. 11d. It is very common to find Bráhmans, Bábhans, Rájputs, and other high castes holding the best lands in a village at rates varying from 50 to 75 per cent. below what a low-caste man pays for inferior land. Rents are now almost invariably paid in money, instead of in kind, as was formerly common. As a general rule, the cultivators claim to hold under a right of occupancy, but such tenures are rarely transferable, except with permission of the landlord. Tenants holding their lands without liability to enhancement do not number more than 5 per cent. of the whole. Wages have increased about 30 per cent. of late years. The rates for ordinary day-labourers vary from 3d. to 4 $\frac{1}{4}$ d. per day, according as they are employed in the country or the town ; women and boys receive from 2d. to 3d. per day. Bricklayers and blacksmiths get from 6d. to 7 $\frac{1}{2}$ d. a day ; sawyers, 6d. ; and carpenters, from 4 $\frac{1}{2}$ d. to 7 $\frac{1}{2}$ d. a day. Prices of food-grains have risen in like proportion. In 1882–83, which may be taken as an ordinary year, 40 lbs. of common rice could be obtained for the rupee ; while in 1883–84, a year of deficient rainfall, the price rose to 31 $\frac{1}{4}$ lbs. for the rupee. In 1877–78, when scarcity prevailed owing to an ill-distributed rainfall and excessive exportation to Southern India, only 27 lbs. of rice were to be got for the same money. Old records show that in 1790 the price was 150 lbs. for the rupee.

Natural Calamities.—The District is subject to blight, flood, and drought. The most common kind of blight is called *hindá*, a mildew which attacks wheat and barley. Insects do considerable damage ; and also hailstorms in the cold weather. Sárán District, being bounded on two sides by large rivers, which flow on ridges and carry enormous volumes of water, is peculiarly exposed to inundation. The northern side of the District is now, however, completely protected by the Gandak embankment. Towards the south, along the banks of the Ganges and Gogra, protective works are still required, as large tracts are inundated nearly every year. The old records are full of complaints about these inundations, which in many cases rendered a remission of revenue necessary. The most noteworthy floods of late years occurred in 1871 and 1874. Droughts have occurred several times, the worst known having taken place in 1866 and 1874, both of which were caused by the failure of the local rainfall. During the scarcity of 1874, relief works on an extensive scale were undertaken by Government, and in the first fortnight of June a daily average of 229,885 persons were employed in road-making. Advances of grain were made to the extent of 324,831 *maunds*. Prices were kept down, however, by Government importations, and the highest rate reached for common

rice in 1874 was 12s 1½d per cwt, as against £1, 1s 10d. per cwt in 1866. To remedy this liability to drought, a scheme of irrigation was commenced in 1878, by which the waters of the Gandak are now led through the centre of the District. The total cost amounted to £70,000, on which sum a few planters and *zamindárs* have guaranteed interest at the rate of 4 per cent. The total irrigated area is estimated at 163,800 acres.

Means of Communication, Trade, etc.—The District possesses a total length of 926 miles of made road, and the Bengal North Western Railway (opened in 1884) runs east and west through the District, with stations at Sonpur, Chapra, Sewán, and Mairwa. The principal manufactures are indigo, sugar, brass work, pottery, saltpetre, and cloth. The chief exports from Sárán are oil seeds, indigo, saltpetre, sugar, and grain of all sorts, except rice, the principal articles of import are rice, salt, and European piece goods. The great trading mart of the District is Revelganj. In 1876-77, the total registered river traffic of Sárán District, including both imports and exports, amounted to just two millions sterling. A great portion of this total is merely through traffic, which comes down from Oudh and the North Western Provinces, and changes boat at Revelganj and Semuria, on its way to Patná or Calcutta. Revelganj is perhaps the largest mart for oil seeds (chiefly linseed) in all India. In 1876-77, the total registered import of oil seeds into the District was valued at £265,000, the total export was £370,000, thus leaving a balance of more than £100,000 for the local produce. As regards food grains, however, the figures show decisively that Sárán is unable to supply its own dense population. In 1876-77, the imports of food-grains of all kinds were valued at £326,000, as compared with exports valued at only £118,000. The other principal items of export were indigo (£179,000), and saltpetre and other saline substances (£67,000). Salt was imported to the value of £143,000. Owing to an alteration in the system of collecting trade statistics, later figures than those for 1876-77 are not available.

Administration—In 1794, the net revenue of the District (which then included Champáran) amounted to £195,254, with a civil expenditure of £27,496, in 1850-51, the revenue (still including Champáran) was £230,567, with an expenditure of £24,131, in 1870-71 (after the separation of Champáran), the net revenue of Sárán alone was £185,072, with an expenditure of £43,826. In 1883-84, the six main items of Government revenue aggregated £203,734, made up as follows—Land revenue, £122,612, excise, £34,362, stamps, £26,086, registration, £2492, road cess, £14,625, municipal taxes, £3557. Cost of officials and police of all kinds, £24,532. The total number of estates in Sárán District in 1883-84 was 4207, with 45,593 registered proprietors or coparceners, average

payment from each estate, £27, 2s. 10d., or from each individual proprietor, £2, 13s. 9d.

For administrative, police, and fiscal purposes, Sáran District is divided into three Sub-divisions and ten police circles (*thánás*), as follows:—(1) Head-quarters Sub-division, with the five *thánás* of Chaprá, Mánjhí, Parsa, Mashrak, and Dighwara; (2) Gopálganj Sub-division, with the two *thánás* of Gopálganj and Barágáon; and (3) Sewán Sub-division, with the three *thánás* of Sewán, Darauli, and Basantpur. Seven judges and 9 stipendiary magistrates. The regular and town police force in 1883 consisted of 539 officers and men, maintained at a cost of £9443, being an average of 1 policeman to every 4·8 square miles and to every 4230 of the population. Besides, the village watch or rural police numbered 5327 men, maintained, either by the *zamíndárs* or by service lands held rent-free, at an estimated total cost of £10,326 a year. Each village watchman has charge of 66 houses on an average, and receives an average pay in money or lands of £1, 18s. a year. There are 2 jails in the District, at Chaprá and Sewán towns, with a daily average prison population in 1883 of 262; the total admissions being 2134. The principal criminal classes are the Dosádhs, Goálás or Ahírs, and Maghya Doms.

Education has rapidly progressed since the introduction of Sir George Campbell's educational reforms in 1872. In 1870-71 there were only 9 Government or aided schools in the District, attended by 585 pupils. At the close of the year 1873-74 the inspected schools numbered 326, with 7066 pupils. In 1883-84 there were upwards of 1525 inspected schools, attended by about 18,000 pupils. The *zillá* school at Chaprá town had 388 pupils on the 31st March 1884. The Census Report of 1881 returned 19,452 boys and 631 girls as under instruction, besides 31,732 males and 1024 females able to read and write, but not under instruction.

Medical Aspects.—The seasons in Sáran are very similar to those of Tírhút, but perhaps a little hotter. The hot weather begins about the end of March; and in a fortnight afterwards, hot westerly winds begin to blow during the day. At night, the wind comes generally from the east, and the temperature is comparatively cool, being lowered by occasional thunderstorms. The rains set in about the middle of June, and continue, with intermissions, till about the end of September or the middle of October. September is by far the most trying month of the year; the air is damp and steamy, while the sun's rays are extremely strong. The cold weather begins about the middle of October, and continues till the beginning of March. Average annual rainfall at Chaprá town, 39·43 inches. No thermometrical returns are available. The prevailing diseases are cholera, small-pox, fever, and dysentery. The civil surgeon states that it is doubtful if cholera

is ever really absent from the District, and it commits great ravages towards the end of the hot and beginning of the rainy season. Small pox comes next in intensity, but the people are beginning to avail themselves of vaccination. Both these diseases are said to be now on the decrease, owing to the improved habits of the people and the high state of cultivation. The people who live in the neighbourhood of low rice lands suffer a good deal from fever. Dysentery, the result of bad water and insufficient clothing, is sometimes very severe. Six Government charitable dispensaries afforded medical relief in 1883 at Chaprá, Sewán, Hatwá, Bhorí, Gopálganj, and Revelganj to 60,243 patients. Cattle disease exists in the form of *guts* or rinderpest, and *kurhd* or foot and mouth disease. [For further information regarding Sírán, see *The Statistical Account of Bengal*, by W. W. Hunter, vol. xi pp. 225-371 (London, Trubner & Co., 1877), the *Bengal Census Report* for 1881, and the several Administration and Departmental Reports of the Bengal Government.]

Sáran — Head quarters Sub division of Sárán District, Bengal
—See CHAPRA

Sáranda — Hill range in the extreme south west corner of Singhbhum District, bordering on Gangpur State, Bengal. Consists of a grand mass of mountains, rising to the height of 2738 feet, known as 'Sáranda of the seven hundred hills.' The population inhabiting this region is scattered over a few poor hamlets nestling in deep valleys, and belongs for the most part to one of the least reclaimed tribes of Kols.

Sáranda.—One of the *purs* or groups of villages of the Kolhan, in Singhbhum District, Bengal. According to the Census of 1881, the *púr* contains 88 villages, assessed at a Government revenue of £58. Lat. $22^{\circ} 15'$ to $22^{\circ} 30'$ N., long. $85^{\circ} 2'$ to $85^{\circ} 28'$ E.

Sarangarh.—Native State attached to Sambalpur District, Central Provinces, formerly one of the *Athra Girhjá* or 'Eighteen Forts,' lying between $21^{\circ} 21'$ and $21^{\circ} 45'$ N. lat. and between $82^{\circ} 59'$ and $83^{\circ} 31'$ E. long. Bounded on the north by the Chandrapur chiefship, and Ráigarh State, on the east by Sambalpur District, on the south by the Phulhar chiefship, and on the west by Biláspur District. Population (1881) 71,274 (of whom 63,231 were Hindus), residing in 44 villages and 25,406 houses. Area, 540 square miles, of which 320 were cultivated in 1877, while of the portion lying waste 80 square miles were returned as cultivable. Density of population 132 persons per square mile.

The country is generally level, but in the south and east rise two considerable ranges of hills. The Mahánadi flows through the north of the State and affords water communication for a length of 50 miles, the only other river worth mention in the Láh. Though no large

forests remain, patches of *sáj*, *dhaúrd*, *tendú*, etc. are met with here and there. Bison, formerly numerous, have now abandoned the State; but tigers, bears, and leopards still range the hills and jungle. The soil is for the most part light and friable, with a strong admixture of sand. Rice forms the staple crop; but pulses, oil-seeds, sugar-cane, cotton, and a little wheat are also produced. The only manufactures are *tasar*-silk and coarse cotton cloth; and though iron-ore abounds, no mines are worked.

The chief is a Gond, and traces his origin through 54 generations up to Jagdeva Sá, a son of Narendra Sá, Rájá of Lánjí in Bhandará about 91 A.D. In return for military assistance, Narsingh Deva, Rájá of Ratanpur, presented Jagdeva Sá with a *khilat* or personal mark of distinction, and conferred on him the title of *diwán*, together with 84 villages in the Sárangarh tract. Forty-two generations later, when Kalyán Sá was *diwán*, Raghuji Bhonsla of Nágpur was stopped on his way to Cuttack by the Phuljhar people, who held the Singhora Pass against him. Raghuji applied to Banojí, Rájá of Ratanpur, who directed Kalyán Sá to clear the pass. For this service, Kalyán Sá received the title of Rájá, with the right to carry a standard. The title was confirmed by Rájá Chhatra Sá of Sambalpur, when Sárangarh became a dependency of his kingdom; and by their military assistance from time to time to the Sambalpur princes, succeeding Rájás of Sárangarh gained further grants of villages and *pargands*, and gradually made Sárangarh a State of some importance. The only remarkable building in the State is the temple of Samleswar Deva, erected in 1748 by Aditya Sá Díwán. Sangráam Singh, the late Rájá, established a good school at his chief town, and there are also indigenous schools in other parts. During the minority of the present Rájá, Bhawáni Pratáp Singh, the State has been under British management. The young chief, who was educated at the Rájkumar College at Jabalpur, attained his majority in 1885. The tribute is £135; revenue (1883-84), £3850. The climate is unhealthy, and fever prevails widely from September to November.

Sárangarh.—Chief town of Sárangarh State, Central Provinces, and residence of the Rájá. Population (1881) 4220, namely, Hindus, 3638; Kabíranthis, 35; Muhammadans, 230; and non-Hindu aborigines, 317.

Sarangpur.—Town in Dewás State, Central India Agency; situated on the right bank of the Káli Sind river, on the trunk road between Gúna and Indore, 92 miles from the former, and 80 miles from the latter. Population (1881) 13,543, namely, males 6610, and females 6933. Hindus number 8776; Muhammadans, 4737; and 'others,' 30.

Saraspur (*Sarishpur* or *Siddheswar*).—Hill range in the south of

Assam, forming the boundary between Cachar District on the east and Sylhet on the west. The height varies from 600 feet to 2000 feet above sea level. At Badarpur, at the northern extremity of the range, is an ancient temple dedicated to Siva, who is worshipped under the name of Siddheswar (Lord of the Pure). An annual fair takes place here, which is numerously attended.

Saraswati (Sarsuti)—Sacred river of the Punjab famous in the early Brāhmanical annals. Rises in lat $30^{\circ} 23' N$, long $77^{\circ} 19' E$, just beyond the British border, in the low hills of Sirmur (Sarmor) State, emerges upon the plain at Zadh Budri in Ambāla (Umballa) a place esteemed sacred by all Hindus, flows in a general south westerly direction, and loses itself more than once in the sands, but reappears again with little diminished volume, passes by the holy town of Ihanesar and the numerous shrines of the Kurukshetra, a tract celebrated as a centre of pilgrimages, and as the scene of the battle fields of the *Mahābhārata* enters Karnal District and Patiala State, where it finally joins the Ghaggar (lat $29^{\circ} 51' N$, long $76^{\circ} 5' E$).

In ancient times, the united stream below the point of junction appears to have borne the name of Sarsuti, and undiminished by irrigation near the hills, to have flowed across the Rājputānā plains, debouching into the Indus below its confluence with the Punjab rivers. The deserted bed can still be traced as far as Mirgarh in Bihāwalpur, but the water now penetrates no farther than Dhatner in Rājputānā, where its trickling streams finally disappear by evaporation. The numerous dams across the hill torrents at the foot of the mountains probably account for the drying up of the ancient channel.

The name of Saraswati, 'the river of pools' sufficiently describes the character of the stream in its upper portion where it dries up partially in the early months of the year, becoming a mere succession of separate ponds. To each of these is attached a legend and a shrine, visited by thousands of pilgrims every year. According to Hindu legend the disappearance of the Saraswati in the sands is accounted for as follows—Saraswati was the daughter of Mahideva but her father one day, in a drunken fit, approaching her with the intention of violating her modesty, the Hindu Arcthusa fled, and dived underground when ever she saw her pursuer gaining upon her and the river which sprang up in her track, still disappears underground at the self same spots. By devout Hindus the Saraswati is supposed to flow in a subterranean course till it joins the Ganges and the Jumna (Jamuna) at ALLAHABAD, where the moisture on the walls of the crypt in the temple of the Undying Banyan tree forms a conclusive proof of its existence in the eyes of the faithful. The real direction of the Saraswati basin, however, lies towards the Indus below Mithankot. Some of the earliest Aryan settlements in India were on the banks of the Saraswati, and the

surrounding country has from almost Vedic times been held in high veneration. The Hindus identify the river with Saraswatī, the Sanskrit Goddess of Speech and Learning. [See Muir's *Orig. Sanskrit Texts*, vol. i., many passages (ed. 1868); General Cunningham's *Anc. Geog. Ind.* pp. 331–33 (ed. 1871); Prof. Dowson's *Dict. Hindu Mythol.* p. 284 (ed. 1879); and article INDIA, *ante*, Vol. VI.]

Saraswatī.—Silted up channel in Húglí District, Bengal. Formerly the main stream of the Ganges, and navigable by large vessels as far as SÁTGAON, the royal port of Bengal, from the earliest historical times up to the 16th century. At one time, this was a broad river flowing between high banks, at places 600 feet apart. It carried the main body of what is now the Húglí, and enjoyed religious honours as the true continuation of the Ganges. According to Sanskrit legend, the sanctifying waters of the Saraswatī enter the Jumna at Allahábád, and leave the Ganges at Tribení Ghát, 36 miles above Calcutta, in lat. 22° 59' N., and long. 88° 26' 45" E. By the beginning of the 16th century, the Saraswatī mouth had so far silted up, that the Portuguese abandoned SÁTGAON, and established a new port of their own a few miles lower down the Húglí at Gholghát, which grew up into Húglí town. At the present day, the Saraswatī at Tribení is a mere tidal ditch. The site of SÁTGAON is left high and dry, but remains of old ships have been frequently discovered buried many feet in the ground. The course of the dead river can still be traced to the south-west of Tribení by a series of pools and marshes, until after throwing off a branch into the Damodár near Amptá, the main stream regains its character of a navigable channel near SÁNKREL in Howrah District, where it re-enters the Húglí a short distance below the Calcutta Botanical Gardens.

Saraswatī.—River of Western India, rising in Mount Abu, Rájputána. Flowing through the Pálanpur and Rádhanpur States of the Mahi Kántha Agency, and through the Patan Sub-division of Baroda State, the Saraswatī, after a south-westerly course of over 100 miles, enters the Rann of Cutch to the east of the State of that name. In the vicinity of Sidhpur and Patan towns, by which the river passes, the Saraswatī is said to have a subterranean course of several miles, reappearing before it enters the Rádhanpur territory. The river is fordable almost everywhere; its banks and bed are generally sandy; it is nowhere navigable. The only importance of the Saraswatī consists in its sanctity. It is visited by Hindus, especially those who have lost their mothers; Sidhpur on this river being considered the appropriate place to perform rites in honour of a deceased mother, as Gayá in Behar is assigned for ceremonies in honour of a deceased father.

Sārathā.—Port on the Sārathā river, in Balasor District, Orissa. Lat. 21° 34' 45" N., long. 87° 8' 16" E. Frequented by native rice

sloops, the river being navigable as far as Nalitagarh, 8 miles from the sea. The sister port of Sārathī is CHHANUYA.

Sarath Deogarh.—Sub division and town in the Santāl Parganas, Bengal.—See DEOGARH.

Sarauli.—Village in Khakreru *tahsil*, Fatehpur District, North-Western Provinces, situated in lat. $25^{\circ} 40' 21''$ N, long. $81^{\circ} 0' 19''$ E, $4\frac{1}{2}$ miles from Khakreru town, and 22 miles from Fatehpur. Population (1881) 3228; prevailing caste, Lodhās.

Sarayan.—River of Oudh. Rising in Kheri District in lat. $27^{\circ} 46'$ N, and long. $80^{\circ} 32'$ E, after a course of 49 miles in a south easterly direction it enters Sitapur District, where it receives the Jamwāri on its left bank, in lat. $27^{\circ} 32'$ N, and long. $80^{\circ} 47'$ E. Thence it flows for about 3 miles in a north westerly course, and, resuming its previous direction, joins the GUNTI in lat. $27^{\circ} 9'$ N, and long. $80^{\circ} 55'$ E. Total length, about 95 miles. It causes destructive floods in some years, as it drains a considerable area of country with its numerous affluents.

Sārda.—River of North-Western India and Oudh. Rising in the loftier ranges of the Himālayas, which separate Kumāun from Tibet, at an altitude of 18,000 feet, it debouches from the hills at Barmdeo, 148 miles from its source, in lat. $29^{\circ} 6'$ N, and long. $80^{\circ} 13'$ E, at an altitude of 847 feet above sea level. The river is here 450 feet broad, with a minimum discharge of 5600 cubic feet per second. Shortly after leaving Barmdeo, it divides into several channels, which reunite 9 miles farther down at Banbāsa, but again separate, and finally join at Mundrī Ghāt, 168 miles from its source, where the last rapids occur, and the stream becomes an ordinary river of the plains. Eleven miles lower down, it touches British territory in Khairigarh *fargand*, Oudh, and 11 miles farther on, or 190 miles from its source, it joins the CHAUKA near Mothia Ghāt. From this point the united stream takes the name of the Chaukī, till it falls into the GOGRA on its right bank, in lat. $27^{\circ} 9'$ N, and long. $81^{\circ} 30'$ E.

Sardār Shahr (*Sirdār Shir*).—Town in Bikaner (Bickaneer) State, Rājputāna, situated about 75 miles north-east of Bikaner town. Population (1881) 5841. Hindus number 2748, Muhammadans, 851; and 'others,' 2242.

Sardhāna.—*Tahsil* of Meerut (Merath) District, North-Western Provinces, lying on either side of the Hindan river, and watered by the Ganges and Eastern Jumna Canals; comprising the *fargands* of Sardhāna and Birmāwar. Area, 251 square miles, of which 184 square miles were cultivated. Population (1881) 159,422, namely, males 85,855, and females 73,567. Hindus number 117,803; Muhammadans, 33,770; Jains, 7267; and Christians, 582. Number of towns and villages, 123, of which 40 contain less than five hundred inhabitants; 29 from five hundred to a thousand; 51 from one to five thousand;

and 3 upwards of five thousand inhabitants. Land revenue, £30,043; total Government revenue, £33,051; rental paid by cultivators, £55,455. In 1883 the *tahsíl* contained 1 criminal court, with 3 police circles (*thánás*); strength of regular police, 36 men; rural police or village watch (*chaukídars*), 276.

Sardhána.—Town in Meerut (Merath) District, North-Western Provinces, and former capital of the notorious Begam Samru; situated in lat. $29^{\circ} 9' 6''$ N., and long. $77^{\circ} 39' 26''$ E., on a low site near the Ganges Canal, 12 miles north-west of Meerut city. A station on the Sind, Punjab, and Delhi Railway. Population (1881) 13,313, namely, males 6858, and females 6455. Hindus number 5898; Muhammadans, 5764; Jains, 1070; and Christians, 581.

The town has a poor and decayed appearance, being in a decadent condition since the death of the Begam Samru. Northward lies Lashkarganj, founded by the Begam as a camp, and the old fort; next succeeds a wide parade-ground; and southward stands the town itself. Local tradition assigns the foundation of Sardhána to one Rájá Sarkat at a period anterior to the Muhammadan conquest. Its modern history is interesting from its connection with the two European adventurers Walter Reinhardt and George Thomas.

The following sketch is condensed from an account given in the official Gazetteer of Meerut. Walter Reinhardt, better known by the name of Samru or Sombre, was a butcher by profession, and a native of Luxemburg. He came to India as a soldier in the French army, and deserting that service, took employment with the British, where he attained to the rank of sergeant. Deserting again, he rejoined the French service at Chandarnagar, and on the surrender of that settlement accompanied M. Law in his wanderings throughout India from 1757 to 1760. In the latter year, Law's party joined the army of Sháh Alam in Bengal, and remained with the emperor until his defeat in 1760 at Gayá by Colonel Carnac, in his attempt to reconquer Bengal from the Nawáb. Samru next entered the service of Mir Kásim, by whom he was employed to murder the English prisoners at Patna (PATNA DISTRICT, *q.v.*) in October 1763. He succeeded in escaping into Oudh, and afterwards entered the service of several native chiefs, until in 1777 he entered the service of Mirza Najf-Khán, the general and minister of Sháh Alam II., and received the *parganá* of Sardhána in fief, as an assignment for the support of his battalions. He died here in the following year, and was succeeded by his widow, the Begam Samru, who continued to maintain the military force. This remarkable woman, the illegitimate daughter of a Musalmán of Arab descent, and the mistress of Reinhardt before becoming his wife, assumed the entire management of the estate, and the personal command of the troops, which numbered 5 battalions of

sepoys, about 300 European officers and gunners, with 50 pieces of cannon, and a body of irregular horse

In 1781 the Begam was baptized into the Roman Catholic Church, under the name of Johanna. Her troops rendered excellent service to the Delhi Emperor in the battle of Gokalgarh in 1788, where a charge of Sardhana troops, personally led by the Begam and the celebrated adventurer George Thomas, saved the fortunes of the day at a critical moment. In 1792, the Begam married Levasseult, a Frenchman in command of artillery. In 1795, her European officers became disaffected, and an illegitimate son of Reinhardt known as Zafaryab Khán, put himself at their head. The Begam and her husband were forced to fly. In the flight the Begam's palanquin was overtaken by the rebels, and she stabbed herself to prevent falling alive into their hands, whereupon Levasseult shot himself, in pursuance of a vow that if one of them was killed the other would commit suicide. The Begam's wound, however, was but a slight one, and she was brought back to Sardhana. Another account is that the Begam had become tired of her husband, and that her self-inflicted wound was only a device to get rid of him. However, all her power passed temporarily into the hands of Zafaryab Khán, and she was treated with great personal indignity, till she was restored to power some months later by her old general George Thomas. Henceforth the Begam remained in undisturbed possession of her estates till her death in 1836.

After the battle of Delhi, and the British conquest of the Upper Doab in 1803, the Begam submitted to the new rulers, and ever after remained distinguished for her loyalty. Her possessions were numerous, and included several considerable towns, such as Sardhana, Baraut, Barnawa, and Dankaur, lying in the immediate neighbourhood of great marts like Meerut, Delhi, Kharja, and Bagpat. Her income from her estates in Meerut District alone amounted to £56,721 per annum. She kept up a considerable army, and had places of residence at Kharja, Jalsipur, Meerut, and Delhi besides her palace at Sardhana. She endowed with large sums the Catholic churches of Madras, Calcutta, Agra, and Bombay, the Sardhana Cathedral, the Sardhana poorhouse, St. John's Roman Catholic College, and the Meerut Catholic Chapel. She also made over a *lakh* of Sonat rupees to the Bishop of Calcutta for charitable purposes, and subscribed liberally to Hindu and Musalman institutions.

Zafaryab Khán, the son of Samru, died in 1802 and left one daughter, whom the Begam married to Mr. Dyce, an officer in her service. David Ouchterlony Dyce Sombre, the issue of this marriage, died in Paris, July 1851, and the Sardhana estates passed to his widow, the Hon. Mary Anne Forester, daughter of Viscount St. Vincent.

The Begam's residence, on the east of the town, is a fine modern

house, with a grand flight of steps at the entrance and extensive grounds. It is well furnished, and contains some good pictures. The Roman Catholic Cathedral, built in 1822, stands south of the town, and is an imposing building, surrounded by an ornamental wall. St. John's College, for training priests, occupies a low masonry house, once the Begam's private residence. Four Jain temples. Schools. *Tahsili*, police station, post-office. Old fort at Lashkarganj in ruins. Sardhána is now essentially an agricultural town, with little trade and no manufactures.

Two excellent papers on the Sardhána estate, and a biography of George Thomas, in the *Calcutta Review* for January and April 1880, by Mr. H. G. Keene, B.C.S., differ in some unimportant points from the history of the estate as given above.

Sareni.—*Parganá* in Dálmau *tahsil*, Rái Bareli District, Oudh; bounded on the north by Khiron, on the east by Dálmau, on the south by the Ganges, and on the west by Daundia Khera. Area, 114 square miles, or 72,968 acres, of which 41,679 acres are cultivated. Population (1881) 63,823, namely, Hindus 61,236, and Muhammadans 2587. Of the 169 villages in the *parganá*, 143 are held under *talukdári* tenure, Bais Rájputs being the chief proprietary body; 23 villages are *samíndári*; and 3 are *pattidári*. Government land revenue, £8924.

Sargúja.—The largest of the Native States of Chutiá Nágpur, Bengal; lies between $22^{\circ} 37' 30''$ and $24^{\circ} 6' 30''$ N. lat., and between $82^{\circ} 32' 5''$ and $84^{\circ} 7'$ E. long. Area, 6055 square miles. Population (1881) 270,311 souls. Bounded on the north by Mírzápur, a District of the North-Western Provinces, and the State of Rewá; on the east by Lohárdagá District; on the south by Jashpur and Udaipur States, and the District of Biláspur in the Central Provinces; and on the west by Koreá State.

Physical Aspects.—Sargúja may be described in general terms as a secluded basin, walled in on the north-east and south by massive hill-barriers, and protected from approach on the west by the forest-clad tract of Koreá. The eastern portion of the State consists of an undulating table-land about 2500 feet above the sea, continuous with, but slightly higher than, the adjoining plateau of Chutiá Nágpur proper. From this, again, isolated hill ranges, and *páts* or plateaux, capped with a horizontal stratum of trap rock, rise to an elevation of 3500 and 4000 feet, forming on the north the boundary of Palámau, and blending in the south with the northern Jashpur Hills. The two most prominent physical features of Sargúja are the Máinpát, a magnificent table-land 18 miles long, from 6 to 8 miles broad, and 3781 feet above sea-level; and the Jamírápát, a long winding ridge about 2 miles wide. The Máinpát is well wooded and watered throughout, and supplies extensive grazing fields during the summer months; the pasturage dues

SARGUJA

of this tract alone are estimated at £250 per annum. The chief peaks in the State are Mailán, 4024 feet, Jám, 3827, and Partagharsa, 3804. The principal rivers are the Kanhar, Rehr, and Máhán, which flow northwards into the Son (Soane), and the Sankh, a tributary of the Bráhmání. None of these streams is navigable. Coal is found in Central Sargúja, in the Bisrámpur field. There is a group of hot springs at Tatápaní, in the north of the State, their maximum temperature is 184°F . *Sál* timber abounds everywhere.

History — The early history of Sarguja is extremely obscure. Authentic records date from 1758, when a Maráthí army in progress to the Ganges overran the State, and compelled its chief to acknowledge himself a tributary of the Berar Government. In consequence of the chief having aided a rebellion in Palámau against the British at the end of the last century, an expedition entered Sarguja under the command of Colonel Jones. Order was restored and a treaty was concluded between the British Government and the Maharájá of Chutíá Nágpur, which, however, proved inoperative. As soon as the British force retired, fresh disputes broke out between the ruling chief and his relations, and in 1813 Major Roughsedge, the Political Agent, went to Sarguja and endeavoured to settle the affairs of the State. The young Rájá being imbecile, a *dewan* was appointed to carry on the government, but this officer was soon afterwards killed, and an attempt to seize the Rájá and his two Ranis was only frustrated by the gallantry of a small guard of British Sepoys who had been left in Sargúja for their protection. Until 1818, the State continued to be the scene of constant lawlessness, but in that year it was ceded to the British Government under a provisional agreement concluded with Vídhyá Bhonsla (Apá Sahib), and order was soon restored. In 1826 the chief received the title of Maharájá. The present chief, Maharájá Raghunáth Saran Singh, attained his majority in July 1882; the State having previously been under the direct management of the Commissioner of Chutia Nágpur.

Population in 1881 numbered 270,311 on an area of 6055 square miles, inhabiting 1286 villages and 51,122 houses. Males numbered 137,389, and females 132,922. Average density of population, 44 persons per square mile, villages per square mile, 0.21, persons per village, 210, houses per square mile, 8.44, persons per house, 5. Classified according to religion, Hindus numbered 268,027, Muhammadans 2284. The bulk of the population are of aboriginal descent, but the Census of 1881 does not give any ethnical classification. In 1872, however, the Dravidian aborigines, consisting principally of Gonds and Urdons, were returned as forming 40 per cent., and the Koláman tribes 21.5 per cent., of the total population. The residence of the Maharájá is at Bisrámpur, but Pratáp

virtually the capital of the State. It contains a court-house, jail, and school. Only two villages in Sargúja have a population of from 1000 to 2000 souls. The chief objects of interest are RAMGARH HILL, the remains of several temples, the deserted fortress of Júbá, and numerous images. [For a full account of these antiquities and of the aboriginal tribes of Sargúja, see *Statistical Account of Bengal*, vol. xvii. pp. 231-240.]

Agriculture, etc.—The staple crops are cereals, oil-seeds, and cotton. On an average, rents vary from 1s. 1½d. to 1s. 6d. per acre. Cesses, however, are levied, which equal, and sometimes exceed, the actual rent; and every cultivator is bound to work for his landlord fifteen days in the year, exclusive of the time spent in going to his work. This system of forced labour is at present the chief drawback to cultivation in Sargúja. The passes into the State are impracticable for wheeled traffic. The manufactures are pottery, coarse cloth, and rough ironwork. Weekly markets are held at Pratáppur, Bistrámpur, and Jhilmilí. Exports—food-grains, oil-seeds, *ghí*, lac, resin, and cocoons of *tasar* silk; imports—brass and pewter vessels, ornaments, piece-goods, and salt.

Administration.—The finances of the State have much improved while under direct administration; and in 1881, the year before the Mahárájá attained his majority, the revenue amounted to £4094, and the expenditure (including a tribute of £264) to £2109. Police duties are performed by the feudal sub-proprietors, styled *nákkaddrs*, each being responsible for the public peace within his borders. Sargúja is divided into 11 police circles, three of which are kept up by the State.

Sargúr.—Town in Mysore District, Mysore State.—See SARAGUR.

Sarh Sálimpur (or *Narwal*).—Easternmost *tahsíl* of Cawnpur District, North-Western Provinces; consisting of a fertile plain, lying along the south bank of the Ganges, and traversed by the East Indian Railway. Area, 214 square miles, of which 123 square miles are cultivated. Population (1881) 101,830, namely, Hindus 97,547, and Muhammadans 4283. Number of towns and villages, 176, of which 110 contain less than five hundred inhabitants; 34 between five hundred and a thousand; 31 between one and five thousand; and 1 upwards of five thousand inhabitants. Land revenue (1881-82), £22,955; total Government revenue, £26,196; rental paid by cultivators, £39,448. In 1885, the *tahsíl* contained 1 criminal court, with 4 police circles (*thánás*); strength of regular police, 37 men; rural police or village watch (*chaukidárs*), 367.

Sarila.—Petty State of Bundelkhand under the political superintendence of the Bundelkhand Agency and the Central India Agency. It lies within *parganá* Jalálpur of Hamárpur District, and is surrounded

on all sides by British territory. Area, 35 square miles. Population (1881) 5014, namely, Hindus 4655, and Muhammadans 359. Estimated revenue, £3000. On the division of his estates by Pahár Singh, son of Jagatráj, Rájá of Jaitpur, Mán Singh, his second son, obtained Sarila. His successor, Tej Singh, was expelled by Alí Bahádúr, but eventually recovered a portion of his territories through the assistance of Himmát Bahadur. At the time of the British occupation of Bundelkhánd he was found in possession of the fort and village of Sarila. In consideration of his voluntary submission and influence in the District, he was granted 11 villages by *sanad* in 1807. The military force of the State consists of 4 guns, 40 cavalry, and 200 infantry and police.

Sarishpur (or *Siddheswar*)—Hill range in the south of Assam, forming the boundary between Cachar District on the east and Sylhet on the west.—*See* SARASPUR.

Sarjápúr—Municipal village in Bangalore District, Mysore State. Lat $12^{\circ} 52' N$, long $77^{\circ} 49' 5'' E$. Population (1871) 2629. Municipal revenue (1881-82), £53. Considerable manufacture of cotton cloth, carpets, and tape. Muslins of fine quality are no longer made. A place of note in the time of Húdár's dynasty, but most of the Muhammadans are now in decayed circumstances. Weekly fair on Fridays.

Sarju—River in the North Western Provinces.—*See* GOGRA.

Sarkandí—Village in Gházípur *tahsil*, Fatehpur District, situated in lat. $25^{\circ} 44' 32'' N$, and long $80^{\circ} 57' 4'' E$, on the banks of the Jumna, 6 miles from Gházípur town. Population (1881) 2409, prevailing caste Bráhmans.

Sarkar Agrahára Vellalur—Town in Coimbatore *taluk*, Coimbatore District, Madras Presidency. Population (1881) 5259, namely, Hindus, 5243, Muhammadans, 7, and Christians, 9. Number of houses, 1247.

Sarmastipur—Trading village in Darbhanga District, Bengal.—*See* SOMASTIPUR.

Sarmor (or *A'dhan*)—One of the Punjab Hill States.—*See* SIRMUR.

Sárnáth (probably a corruption of *Sárangganáth*, 'Lord of Deer,' referring to a legend of Buddha)—Buddhist ruins in Benares District, North Western Provinces, distant $3\frac{1}{2}$ miles north of BENARES city, Sikya Muni first preached his doctrines here, and some of the ruins probably date from his time (543 B.C.) The remains form a mound of brick and stone *debris* about half a mile long by a quarter of a mile broad, out of which still emerge the remains of two great *stupas*, and a third is in the vicinity. The most remarkable, specially known as the Dhamek, is a solid dome 93 feet in diameter, and 110 feet above the

plain. The plinth, 43 feet high, is of solid stone cramped with iron, and richly sculptured on the exterior. The upper part consists of dilapidated brickwork. The second *stupa* was excavated for bricks in 1794. The third, now called Chaukandi, is 800 yards south of Dhamek, and consists of a lofty ruined mound of brickwork, 74 feet in height, crowned by an octagonal building, commemorating the Emperor Humáyún's visit in 1531. The remains of many other buildings have been excavated in the vicinity. The Dhamek tower probably stands on the site of, if it be not identical with, that erected by Asoka to mark the spot where Buddha first preached his doctrine. The name is a corrupt form of Dharma, 'The Law.' Both Dhamek and Chaukandi *stupas* appear to be mentioned by Hiuen Tsiang. See General Cunningham's *Anc. Geog. Ind.* pp. 437, 438 (ed. 1871).

Saromannagar.—*Parganá* in Hardoi District, Oudh. Bounded on the north by Sháhábád; on the east by Báwan; on the south-east and south by the Sukheta river, separating it from Barwán; and on the west by the Garra river, separating it from Páli *parganá*. Area, 35 square miles, of which 21 are cultivated. Population (1881) 13,096, namely, males 7249, and females 5847. Government land revenue, £2172, equal to an average of 3s. 1½d. per acre of cultivated area, or 1s. 11d. per acre of total area. Of the 42 villages in the *parganá*, 20 are held by Sombansís, and 15 by Chamár Gaurs. Thirty villages are held in imperfect *pattidári* and 12 in *zamindári* tenure. The country was originally occupied by Thatheras, who were driven out of many of their villages by Gaur Rájputs in the middle of the 12th century; and their total expulsion by the Sombansís occurred shortly afterwards. The *parganá* was first constituted in 1803 by Rájá Bhawání Parshád of Muhamdi, out of villages previously belonging to the neighbouring *parganá*s of Páli and Sára.

Saromannagar.—Town in Hardoi District, and head-quarters of Saromannagar *parganá*; situated 6 miles south of Sháhábád, and 15 miles north-west of Hardoi town. Population (1881) 1033, namely, Hindus 936, and Muhammadans 97. Village school. Bi-weekly market.

Sársa.—Town in Anand Sub-division, Kaira District, Bombay Presidency; situated 28 miles east by south of Kaira town, in lat. 22° 33' N., and long. 73° 7' E. Population (1872) 5218; not separately returned in the Census Report of 1881. The centre of the cotton trade of the District.

Sarsaganj.—Trading village in Máinpuri District, North-Western Provinces; situated in lat. 27° 3' N., and long. 78° 43' 50" E., on the Etáwah road, 6 miles north of the Bhadan station of the East Indian Railway, and 27 miles south-west of Máinpuri town. Population (1881) 5814, namely, Hindus, 4902; Muhammadans, 767; and 'others,' 145.

The village of Sarsa (population 2126) is a collection of mere agricultural hamlets, containing a large fortified brick house, belonging to a family of Kirār Thākurs, but the real importance of the place centres in the neighbouring *bāzār* of Sarsaganj, the principal trading market of the District, and the only one which carries on business with surrounding towns. Fine market place, known as Raikes ganj, bi weekly fair, large trade in cotton. Wealthy merchants, chiefly Jains, several Jain temples, very handsome little mosque of peculiar architecture. Large cattle market. Police station, post office, village school. A small house tax is levied for police and conservancy purposes.

Sarsawa—Ancient town in Sahrānpur District, North Western Provinces. Distant from Sahrānpur town 10 miles west, upon the Ambala (Umballā) road. Population (1881) 3978. Small trade to and from the Punjab. Chiefly remarkable for its historical associations, being identified by General Cunningham with Sharwa or Shīrāshārīr, the city of Rājā Chand, sacked by Mahmūd of Ghazni in 1019 A.D. The Rājā fled to the hills after the fall of his fort, but Mahmud followed up the fugitives, defeated them in the midst of a forest, and captured an enormous booty in gold, silver, precious stones and slaves. Police station, post-office, village school.

Sarsuti—River in the North Western Provinces, Punjab—See SARASWATI.

Sāru—The loftiest hill in Chutia Nāgpur, Bengal, situated in Lohardāgī District, west of Rānchī town, 3615 feet in height. Lat $23^{\circ} 30' N$, long $84^{\circ} 30' 45'' E$.

Sarvasiddhi—*Taluk* or Sub-division of Vizagapatam District, Madras Presidency. Area, 311 square miles. Population (1881) 131,754, namely, males 65,395, and females 66,359 occupying 27,868 houses in 150 villages. Hindus number 129,018, Muhammadans, 2709, Christians, 19, and 'others,' 8. The *taluk* in olden times formed a *zamindari*, which was purchased by Government for £75 in 1831. It is near the coast, and contains some of the best wet crop land in Vizagapatam District, but it is liable to sudden and injurious runs. In 1883 the *taluk* contained—criminal courts, 2, police circles (*thirsis*) 6, regular police, 54 men. Land revenue, £14,375. Head-quarters Yelamanchili.

Sarvepalli—Town in Gudur *Taluk*, Nellore District, Madras Presidency. Lat $14^{\circ} 17' 30'' N$, long $80^{\circ} 0' 40'' E$. Population (1881) 4929, namely, Hindus, 4624, Muhammadans, 300, and Christians, 5. Number of houses, 965. Sarvepalli contains the ruins of an old Rohilla fort. Its irrigation tank is one of the finest in the District, and is filled from the Penner (Ponnaiyār) anicut.

Barwān—Village in Unao District, Oudh, situated in lat $26^{\circ} 36' N$, and long $85^{\circ} 56' E$, 6 miles north-east of Purwā, and 26 miles east

of Unao town. Population (1881) 2014, namely, Hindus 1913, and Musalmáns 101. A very ancient village, with a noted Sivaite temple. Concerning this temple, Mr. C. A. Elliott narrates the following tradition in his *Chronicles of Unao*, pp. 5, 6:—‘To worship at this temple, and to shoot and hunt in the wild forest country around, came Rájá Dasaratha from Ajodhya, the father of Rámchandra, the 57th Rájá of Ajodhya. He was encamped at Sarwára on the edge of a tank. By night came Sarwán, a holy Rishi from Chaunsa (near Ajodhya), by caste a Baniyá. He was going on pilgrimage, and was carrying his blind father and mother in a pair of baskets, slung over his shoulders. Reaching the tank, he put his burden down and stopped to drink. Rájá Dasaratha heard a rustling noise, and thinking it was some wild beast, took up his bow and shot an arrow, which struck Sarwán, and he died. Then his blind parents in their misery lifted up their voices and cursed the man who had done the thing. They prayed that as he had slain the son who was the light of their hearts, so he might have trouble and sorrow from his own children, and might die of grief even as they were dying. Having so said, they gave up the ghost; and from that day to this no Kshattriya has lived in the town which is founded on the spot, and is called Sarwán. Many have tried it, but evil has overtaken them in one way or another. The tank remains to this day, and by it lies under a tree the body of Sarwán, a figure of stone; and as he died with his thirst unquenched, so if water is poured into the navel of the figure, the hole can never be filled up, but is inexhaustible in its demand.’

Sarwár.—Town in Kishangarh State, Rájputána; situated about 25 miles south-east of Nasirábád. Population (1881) 5361, namely, Hindus, 4107; Muhammadans, 785; and ‘others,’ 469.

Sarya.—Indigo factory in Muzaffarpur District, Bengal; situated 18 miles south-west of Muzaffarpur town, on the banks of the Bayá river, which is here crossed by the Chaprá road on a fine three-arched bridge. A short distance from Saryá is a monolith called Bhím Singh’s *láthí* or club, supporting a lion carved in stone. It consists of a plain cylinder about 24 feet high, on the top of which is a pedestal with the lion. The cylinder is in one piece, the height of the whole being about 30 feet. Its depth below ground is unknown, but it must be very great, as some persons once dug down several feet, and failed to reach the foundation. The stone is covered with names, many of them English, some of which date from 1793. It stands in the courtyard of a Bráhmaṇ’s house, but no religious meetings take place here. Close at hand is a well or deep excavation; and the Bráhmaṇ who owns the land on which the monolith stands affirms that a large amount of treasure is believed to lie concealed beneath, and that this excavation was made to try and recover it. The indigo factory and attached lands

cultivate about 4600 *lighds*, giving an average annual out turn of about 530 *maunds* of dye

Sásni (*Sísani*)—Town in Aligarh District, North Western Provinces Lat $27^{\circ} 42' 12''$ N, long $78^{\circ} 8' 5''$ E. Distant from Aligarh town 14 miles south on the Agra road, from Hâthras 7 miles north. Population (1881) 4851. Steadily declining in importance. Remains of ancient fort, which held out under its chief against Lord Lake in 1803, when it was captured not without considerable loss. Monuments in memory of the officers killed in the attack. Indigo factories, built from the materials of the fort. Police station, post-office encamping ground for troops. A small house-tax is levied for police and conservancy purposes.

Sâsserâm—Sub-division of Shâhâbâd District, Bengal, lying between $24^{\circ} 31'$ and $25^{\circ} 22' 30''$ N lat and between $83^{\circ} 33'$ and $84^{\circ} 30'$ E. long. Area, 1493 square miles, villages, 1986 houses 77,618. Population (1881) 519,207, namely, males 253,757, and females 265,450. Hindus number 475,395, Muhammadans 43,748, Christians 44, and 'others,' 20. Average density, 348 persons per square mile, villages per square mile, 133, persons per village 261 houses per square mile, 57, persons per house, 67. This Sub-division consists of the 4 police circles of Sâsserâm Khargurh, Dhingûn and Dehri. In 1870-71 it contained 1 civil and 2 criminal courts a regular police force of 141, and 1 village watch of 1713 men.

Sâsserâm—Chief town of Sâsserâm Sub-division Shâhâbâd District, Bengal, situated on the Grand Trunk Road 61 miles south of Arrah, in lat $24^{\circ} 56' 59''$ N, and long $84^{\circ} 3' 7''$ E. Population of Sâsserâm village (1881) 2531 of the municipality 22,000. Municipal income (1883-84), £1499 of which £761 was derived from taxation, average incidence of taxation, 8½d per head. The name Sâsserâm or Sâhsrâm signifies one thousand toys because a certain Asur or infidel who lived here had 1 thousand arms, each holding a separate plaything. The town, now fast declining in importance is noted as containing the tomb of the Afghan Sher Shah, who conquered Humâvân and subsequently became Emperor of Delhi. His mausoleum is at the west end of the town, within a large tank, the excavated earth of which has been thrown into unshapely banks some distance off. The tomb itself consists of an octagonal hall surrounded by an arcade, which forms a gallery, the roof is supported by four Gothic arches. The ornaments are in the very worst taste. It is now being repaired at Government expense. (For full details respecting this monument see *Statistical Account of Bengal* vol. XII pp. 205-208). The remarkable mosque of Chândan Shahîd is situated on a lofty hill east of the town.

Sasu—River in the south of Lakhimpur District, Assam—See SISA.

Sāsvar (*Sasar*).—Chief town of the Purandhar Sub-division of Poona (Púna) District, Bombay Presidency; situated on the left bank of the river Kárha 16 miles south-east of Poona city, in lat. $18^{\circ} 20' 20''$ N., and long. $74^{\circ} 4' 20''$ E. Population within municipal limits (1881) 5684, namely, Hindus, 5411; Muhammadans, 249; and Jains, 24. Sāsvar was the original Deccan home of the Peshwá's family. Beyond the town, across the river Kárha, stands the palace of the old Peshwá, now used for the Collector's office. Near the junction of the Kárha and one of its minor tributaries is a walled building, the palace of the great Bráhman family Purandhare of Purandhar, whose fortunes for upwards of a century were closely connected with those of the Peshwás. This latter palace was formerly strongly fortified, and in 1818 was garrisoned and held out for ten days against a detachment of British troops. About 1840 the Mírs of Sind were confined in Sāsvar. Municipal income (1883-84), £336; incidence of taxation, 1s. $1\frac{1}{2}$ d. per head. Dispensary, post-office, and two schools.

Sata.—Channel of the Indus in Sind, Bombay Presidency. The most important eastern branch of the river, that to the west being known as the BAGHAR. The Sata sends off, on the left or eastern side, two branches, the Mal and the Manti, both of which are now only shallow streams. Before the great earthquake that occurred in Cutch (Kachchh) in 1819, vessels from seaward entered the Richal mouth, the only accessible entrance, and passed into the Hajámro through what was then the Khedewári creek, and thence into the Mal to Sháhbandar, an important naval station under the Kalhora princes. This passage was closed by the earthquake, and a new mouth opened, viz. the Kukaiwári, which in 1867 was found to be completely choked by sand. The Khedewári was described by Lieutenant Carless in 1837 as having a depth of from 16 to 18 feet, but since 1845 the Hajámro had taken its place as the main channel.

Sátána (or *Báglan*).—Sub-division of Násik District, Bombay Presidency. Area, 619 square miles. Population (1881) 64,875, namely, males 32,885, and females 31,990, occupying 9992 houses in 155 villages. Hindus number 48,972; Muhammadans, 1678; and 'others,' 14,225. The chief river is the Mosam. The route from the Deccan through Sátána to the Gujarát coast has been a line of traffic from remote times. Akbar, when he conquered Khándesh in 1599, attempted to capture Sátána, and besieged the chief Pratápsháh for seven years unsuccessfully, and was in the end obliged to compound with him. In 1637, Sátána was attacked by Aurangzeb. The chief submitted and was made commander of 3000 horse. Sátána formed part of Khándesh District till 1869, when it was transferred to Násik. In 1875, Sátána, with its two petty divisions of Jaikhedan and Abhona, was divided into two Sub-divisions, Sátána (or Báglan) and

Kalwan In 1880-81, 6658 holdings or *khatas* were recorded, with an average area of $26\frac{1}{2}$ acres, paying an average assessment of £2, 2s. 6d. The area under cultivation in 1880 was 145,763 acres. Cereals and millets occupied 106,578 acres, pulses, 22,882, oil-seeds, 15,475, fibres, 500, and miscellaneous crops, 1756 acres. In 1883 the Sub-division contained 1 civil and 2 criminal courts, police circles (*thdnas*), 2, regular police 63 men, village watch (*chauki firs*), 306.

Sátána.—Town in Sátána or Bégán Sub-division, Násik District, Bombay Presidency, situated about 30 miles west of Málégán. Population (1881) 3516. Dispensary, post-office, annual fair.

Sátánones — Petty State in the Gohelwár *prant* or division of Kathiawár, Bombay Presidency, consisting of 1 village, with 2 shareholders or tribute payers. Area, 67 square miles. Population (1881) 411. Estimated revenue, £95, of which £10, os. 6d. is paid as tribute to the Gáekwár of Baroda, and 12s. to the Nawab of Junagarh.

Satanwári —Fort in Bhopál State, Central India Agency, situated in lat $23^{\circ} 36' N$, and long $77^{\circ} 10' E$, 30 miles north west of Bhopál town, close to the Gwahor frontier. Satanwári appears, says Thornton, to have been granted with other possessions in 1818 by the British Government to the Nawáb of Bhopál, 'in order to mark its approbation of his conduct, and to enable him to maintain the stipulated contingent.'

Sátára.—British District in the Deccan or Central Division of the Bombay Presidency, lying between $16^{\circ} 51'$ and $18^{\circ} 10' 30'' N$ lat, and between $73^{\circ} 37'$ and $74^{\circ} 58' E$ long. Area, 4988 square miles. Population (1881) 1,062,350 souls. It is bounded on the north by the States of Bhor and Phaltán and the Níra river separating it from Poona, on the east by Sholdápur District and the estates of the Panth Pratinidhi and the chief of Ját, on the south by the river Várna, separating it from Kolhápur and Sángh States, and by a few villages of Belgám District, and on the west by the Sahyádrí range of hills, separating it from the Konkán or southern Districts of Kolábar and Ratnágiri. The administrative head quarters are at SATARA TOWN.

Physical Aspects —From Mahábaleshwar in the north west corner of the District, 4717 feet above the sea, start two hill ranges of equal height and nearly at right angles to each other—one the main range of the Sahyádris, running towards the south and forming the western boundary of the District, and the other the Mahadeo range of hills, which, going first in an easterly and then in a south-easterly direction, extends towards the eastern boundary, where it sinks gradually into the plain. These hills throw out numerous spurs over the District, forming the valleys of the several streams which make up the head waters of the Kistna, one of the largest rivers in Western India. Except near Mahábaleshwar, and in the valley of the Kona, the base of the

1328, Chamars, 16,105, Darjis (tailors), 9664, Dhangars, 41,547, Dhobis (washermen), 7640, Nápis (barbers), 14,251, Jangams, 3796, Kunbis (cultivators), 583,569, Kolis (cultivators), 4198, Kumbhars (potters), 12,321, Koshtis, 8632, Lingáyats (traders), 17,035, Lohárs (blacksmiths), 5193, Malís (gardeners), 24,784, Mángs (depressed caste), 20,919, Mhárs (depressed caste), 87,679, Sonárs (goldsmiths), 8231, Sutárs (carpenters), 11,043, Telís (oilmen), 9499, Banjáris, 2046, and 'others,' 71,076. The Muhammadin population consisted of—Patháns, 3780, Siyids, 4235, Shaikhs, 27,979, and 'others,' 718. According to sect,—Sunnís, 36,109, Shiás, 546, and 'others,' 57. The Christian population of Sátara District included—Europeans, 407, Eurasians, 19, and natives, 460. Adopting another system of classification, there were—Roman Catholics, 387, followers of the Church of England, 317, and followers of other Christian creeds, 182.

Of the Hindus, who form the great majority of the population, more than a half consist of Kunbis, who during the period of Maráthá ascendancy (1674–1817) furnished the bulk of the armies. The Málís, Siyis best soldiers, were drawn from the *ghátultha* (hill top) portion of the District. During the last half-century they have become quiet and orderly, living almost entirely by agriculture. Dark skinned and, as a rule, small they are active and capable of enduring much fatigue. Bráhmans, employed as priests or Government servants, are found in large numbers in the towns of Sátara and Wai. Besides these, Vanis, Dhangars, Ramosis, Mhárs, and Mángs are among the principal castes met with throughout the District.

With reference to occupation, the Census of 1881 divided the male population into the following six main groups—(1) Professional class, including State officials of every kind, and members of the learned professions, 18,118, (2) domestic servants, inn and lodging house keepers, 4872, (3) commercial class, including bankers, merchants, and carriers, 4086, (4) agricultural and pastoral class, including gardeners, 241,526, (5) industrial class, including all manufacturers and artisans, 46,257, and (6) indefinite and non-productive classes, comprising general labourers, male children, and persons of unspecified occupation, 217,666.

Of the 1343 towns and villages in Sátara in 1881, 289 contained less than two hundred inhabitants, 410 from two to five hundred, 331 from five hundred to one thousand, 224 from one to two thousand, 49 from two to three thousand, 28 from three to five thousand, 8 from five to ten thousand, 3 from ten to fifteen thousand, and 1 from twenty to fifty thousand. Municipal towns—Sátara (1881), 28,601, Wai, 11,676, Karid, 10,778, Lágion, 10,206, Ashi, 9548, Islampur, 8940, Rahimatpur, 6082, Mhaswad, 5581, Vata, 4477, Malcolampur, 3248, Mayni, 2997, Pusesali, 2569, Shingna, ur, 1167.

1338, Chamars, 16,105, Daryls (tailors), 9664, Dhanguars, 41,547
Kumbhs (washermen), 7640, Koshus, 8632, Lumbhars (tailors), 4198, Kumbhars
(blacksmiths), 5193, Malis (gardeners), 24784, Vahns (goldsmiths),
2046, and, others, 71076 (carpenters) 11043, Ills (oilmen) 9499, Brijlads,
According to sect.—Sunnis, 36109, Shais 546 and others, 57, 118
Lurasans, 19, and natives 460. Adopting another system of classifica-
tion, there were—Roman Catholics, 387 followers of the Church of
England 317, and followers of other Christian creeds 182
more than a half consist of the great majority of the population,
The Vaidas Savjis (1674-1817) furnished the bulk of the armies
(hill top) portion of the District were drawn from the *g'walia*
Dark skinned and as a rule small they are active and capable of
enduring much fatigue. Brahmins employed as priests or Government
serants, are found in large numbers in the towns of Saltra and Wafi
I sides these, 1 mis Dharat Khmosis Vihars and Wafars are among
the principal castes met with throughout the District.
With reference to occupation the Census of 1881 divided the male
population into the following six main groups—(1) Professional class,
including State officials of every kind and members of the learned
professions, 1818 (2) domestic servants including bankers, merchants, and
keepers, 4872 (3) commercial class including pastoral gardeners, and
21526, (4) agricultural and pastoral class, including gardeners, and
46,257, and (5) industrial and non-productive classes comprising
217666
Of the 1343 towns and villages in 1881, 259 contained less
than two hundred inhabitants, 410 from one to five hundred, 331 from
five hundred to one thousand, 224 from one to five hundred, 49 from five
hundred to one thousand, 28 from one to five hundred, and 150 in excess of
one thousand. 75,000, 11,344, 9548, 11,344, 9548, 11,344, 9548,
Kathmandu, 6082, Wihars, 10,206, 14,171, 9548, 11,344, 9548,
Wihars, 2097, Pukar, 1167

1328, Chamars, 16,105, Darjis (tailors), 9664, Dhangars, 41,547, Dhobis (washermen) 7640, Nápis (barbers), 14,251, Jangams, 3796, Kunbis (cultivators), 583,569, Kolis (cultivators), 4198, Kumbhars (potters), 12,321, Koshtis, 8632, Lingdyats (traders), 17,035, Lohárs (blacksmiths), 5193, Máls (gardeners), 24,784, Mángs (depressed caste), 20,919, Mhárs (depressed caste), 87,679, Sonárs (goldsmiths), 8231, Sutárs (carpenters), 11,043, Tels (oilmen), 9499, Banjárs, 2046, and 'others,' 71,076. The Muhammadan population consisted of—Patháns, 3780, Sayyids, 4235, Shaikhs 27,979, and 'others,' 718. According to sect,—Sunnis, 36,109, Shiás, 546, and 'others' 57. The Christian population of Sátara District included—Europeans, 407, Russians, 19, and natives, 460. Adopting another system of classification, there were—Roman Catholics, 387, followers of the Church of England, 317, and followers of other Christian creeds 182.

Of the Hindus, who form the great majority of the population, more than a half consist of Kunbis, who during the period of Maráthá ascendancy (1674-1817) furnished the bulk of the armies. The Mávlás Snávis best soldiers, were drawn from the *ghimlitha* (hill top) portion of the District. During the last half century they have become quiet and orderly, living almost entirely by agriculture. Dark-skinned and, as a rule, small, they are active and capable of enduring much fatigue. Bráhmans employed as priests or Government servants, are found in large numbers in the towns of Sátara and Wá. Besides these, Vanis, Dhangar, Rámosis Mhárs and Mángs are among the principal castes met with throughout the District.

With reference to occupation the Census of 1881 divided the male population into the following six main groups—(1) Professional class, including State officials of every kind, and members of the learned professions, 18,118, (2) domestic servants, inn and lodging house keepers, 4872, (3) commercial class, including bankers, merchants, and carriers, 4086, (4) agricultural and pastoral class, including gardeners, 241,526, (5) industrial class, including all manufacturers and artisans 46,257, and (6) indefinite and non-productive classes, comprising general labourers, male children, and persons of unspecified occupation, 217,666.

Of the 1343 towns and villages in Sátara in 1881, 289 contained less than two hundred inhabitants, 410 from two to five hundred, 331 from five hundred to one thousand, 224 from one to two thousand, 49 from two to three thousand, 28 from three to five thousand, 8 from five to ten thousand, 3 from ten to fifteen thousand, and 1 from twenty to fifty thousand. Municipal towns—Sátara (1881), 28,601, Wá 11,676, Karid, 10,778, Tádgaon, 10,206, Ashi, 9548, Is'ánpur, 5049, Rahmatpur, 6082, Mhaswad, 5581, Vá 4477, Malcolmpur, 3248, Mavni, 2997, Palsasli, 2369, Shingapur, 1167.

1328, Chamars, 16,105; Darjis (sailors), 9664; Dhangers, 41,547, Dhobis (washermen), 7640, Nâpis (barbers), 14,251, Jangams, 3796, Kumbis (cultivators), 583,569, Kols (cultivators), 4198, Kumbhars (potters), 12,321, Koshis, 8632, Langdats (traders), 17,035, Lohars (blacksmiths), 5193, Malls (gardeners), 24,784, Mlâgs (depressed caste), 20,919, Mhars (depressed caste), 87,679, Sonars (goldsmiths), 8231, Sutar (carpenters), 11,043, Lells (oilmen), 9499, Bhandars, 2046, and 'others,' 71,076. The Muhammadan population consisted of—Pathans, 3750, Sayids, 4235, Shaikhs, 27 979, and 'others,' 718. According to sect.—Sunns, 36,109, Shîfs, 546, and 'others,' 57. The Christian population of Saltara District included—Europeans, 407, Lurasians, 19, and natives, 460. Adopting another system of classification, there were—Roman Catholics, 387, followers of the Church of England, 317, and followers of other Christian creeds, 182.

Of the Hindus, who form the great majority of the population, more than a half consist of Kumbis, who during the period of Marâthâ ascendancy (1674-1817) furnished the bulk of the armies. The Mlâvis, Sanyas best soldiers, were drawn from the *ghâtîmîlâ* (hill top) portion of the District. During the last half-century they have become quiet and orderly, living almost entirely by agriculture. Dark-skinned and, as a rule, small, they are active and capable of enduring much fatigue. Brahmins, employed as priests or Government servants, are found in large numbers in the towns of Saltara and Vâl. Besides these, Vanis, Dhangers, Kâmois, Mhars, and Mlâgs are among the principal castes met with throughout the District.

With reference to occupation, the Census of 1881 divided the male population into the following six main groups—(1) Professional class, including State officials of every kind, and members of the learned professions, 18,118, (2) domestic servants, inn and lodging house keepers, 4872, (3) commercial class, including bankers, merchants, and carriers, 4086, (4) agricultural and pastoral class, including gardeners, 241,526, (5) industrial class, including all manufacturers and artisans, 46,257, and (6) indolent and non-productive classes, comprising general labourers, male children, and persons of unspecified occupation, 217,666.

Of the 1343 towns and villages in Saltara in 1881, 259 contained less than two hundred inhabitants, 410 from two to five hundred, 331 from five hundred to one thousand, 224 from one to two thousand, 49 from two to three thousand, 28 from three to five thousand, 8 from five to ten thousand, 3 from ten to fifteen thousand, and 1 from twenty to fifty thousand. Municipal towns—Saltara (1881), 28,601, Wai, 11,676, Kard, 10 775, Tâlgion, 10,206, Vâh, 2, 9545, Saltara, 5949, Kâthimâpur, 6082, Mharsad, 5581, Vâl, 4477, Mâkolâpur, 3245, Mym, 2997, Pâncsavi, 2509, Shingari, 1167.

The general decay of the Mughal Empire from 1700 to 1750 opened the way for the Marathā supremacy. The Peshwās, or Mayors of the Palace, date their power from Balaji, about 1718. In 1749, the sovereignty passed from the Satara Rājās to the Brāhman Peshwās, with their head-quarters in the adjoining District of Poona. The descendants of Sivaji became little more than pensioned prisoners, but they clung to the title of Rājā of Satara. The battle of Panipat in 1761 broke the power of the great Marathā confederacy. But the Peshwās still remained the most important native rulers in India till the rise of Haider Ali.

Repeated wars with the English ended in the final defeat of the Peshwā's army at Ashti in 1818. His territory was thereupon annexed; but the English, with a politic generosity, freed the titular Marathā Rājā (the descendant of Sivaji) from the Peshwā's control, and assigned to him the principality of Satara. Captain Grant Duff was appointed his tutor until he should gain some experience in rule. In April 1822, the Satara territory was formally handed over to the Rājā, and thenceforward was managed by him entirely. After a time, he became impatient of the control exercised by the British Government; and as he persisted in intriguing and holding communications with other princes, in contravention of his treaty, he was deposed in 1839, and sent as a State-prisoner to Benares, and his brother Shahji was placed on the throne. This prince, who did much for the improvement of his people, died in 1848 without male heirs; and after long deliberation, it was decided that the State should be resumed by the British Government. Liberal pensions were granted to the Rājā's three widows, and they were allowed to live in the palace at Satara. The survivor of these ladies died in 1874.

Population.—The Census returns of 1872 showed a total population of 1,116,050; that of 1881 a total of 1,062,350, residing in 14 towns and 1329 villages, and in 151,173 houses; unoccupied houses numbered 23,233. Area, 4988 square miles. Average density of population, 212.98 persons per square mile; villages per square mile, 0.27; houses per square mile, 34.9; persons per village, 791.03; and persons per house, 7.02. Classified according to sex, there were 532,525 males and 529,825 females; proportion of males, 50.1 per cent. Classified according to age, there were—under 15 years, boys 220,901, and girls 199,697; total children, 420,598, or 39.6 per cent; 15 years and upwards, males 311,624, and females 330,128; total adults, 641,752, or 60.4 per cent. of the population. Classified according to religion, Hindus numbered 1,008,918; Muhammadans, 36,712; Jains, 15,679; Parsis, 99; Christians, 886; Jews, 21; Sikhs, 29; and Buddhists, 6. The Hindus were divided into the following main castes, and social distinctions:—Brāhman (priestly caste), 48,362; Rājputs (warrior caste),

Agriculture.—Agriculture, the main occupation of the people, supported in 1881, 744,013 persons, or 70·0 per cent. of the population; 374,576 only were agricultural workers. Of the total area of the District (5378 square miles), 3385 square miles are cultivated, of which 73 square miles are non-revenue-paying. Total amount of Government assessment, including local rates and cesses on land, £166,323; average incidence of assessment, including local rates and cesses, 1s. 4½d. The average area of cultivable and uncultivated land per agricultural worker is 5·9 acres.

The bulk of the Sátara landholders are Maráthá Kunbís. But the best class of husbandmen are the Jains of the south and south-west of the District. In the east of the District, the landholders are said to be only moderately hard-working; and the richer soils in the west are said to suffer from being cropped several years in succession without fallow. At the same time, certain parts of the District show notable instances of skill and enterprise. Sátara suffered from the famine of 1876-78; and the indebtedness of the people to the money-lenders has demanded special steps to be taken to preserve their position as peasant proprietors, by the introduction of the Deccan Agriculturists Relief Act. The soils of the District belong to three main classes, red in the hills, and black and light coloured in the plains. The black soil, especially along the valley of the Kistna and its tributaries, is very fertile, yielding two crops a year.

According to the Revenue Survey, of the total area of Government land (2,442,503 acres), 1,802,156 acres, or 73·8 per cent., are cultivable; 141,291 acres are uncultivable; 4956 acres are under grass; and 387,715 acres are forest. Of the whole cultivable area, 1,378,659 acres were held for tillage in 1882-83, namely, 43,462 acres garden land, 14,895 acres rice land, and 1,320,302 acres under dry crops. In 1882-83 the number of holdings was 120,158, with an average area of 14½ acres.

Jóár (*Sorghum vulgare*) and *bájra* (*Penicillaria spicata*), the staple food of the people, occupy nearly half the cultivated area. Rice-fields are found only in the west, along river banks. In the south and east, cotton is grown, most of it of a local variety, but some brought from Hinganghát. Near Mahábaleshwar, several European vegetables, especially potatoes, grow freely, and to a great extent supply the Bombay market. In some of the hill villages, which have a heavy rainfall, *nachni* (*Eleusine corocana*) and *vari* (*Panicum miliare*) are raised on the *kumari* system, that is, by cutting down and burning brushwood and sowing the seeds in the ashes. This practice, formerly general, has, on account of the damage it does to the forests, been to a large extent prohibited.

In 1882-83, 1,113,911 acres were under cultivation, of which 39,757 were twice cropped. Grain crops, consisting chiefly of *jóár* and *bájra*,

occupied 898,206 acres, pulses, 159,211 acres, oil seeds, 42,001 acres, fibres, 22,581 acres, of which 19,015 were under cotton, orchards, 3952 acres, drugs and narcotics, 8035 acres, of which 7523 acres were under tobacco, and miscellaneous crops, 19 682 acres.

In 1882-83, the prices of produce per *maund* of 80 lbs. were—wheat, 6s 8½d, rice (common), 7s 4d, *birra*, 3s 8½d, *jeer*, 3s. 4½d, *dill*, 5s 3d, salt, 6s 5d, flour, 7s 6½d, *ghl*, £3, 1s. 9½d. The wages per diem of a skilled labourer were 6d to 2s, of an unskilled labourer, 1½d to 9d, the hire per diem of cart, 1s to 1s 6d, of bullocks, 6d to 1s.

In 1882-83, the agricultural stock consisted of—bullocks, 243 424, cows, 141,139, buffaloes, 110,479, horses, 12 797, sheep and goats, 396,994, ploughs, 48,981, carts, 17,387.

Irrigation—In 1883, Sâtara District had six large irrigation works. These are the Revâri canal on the Vâsna, the Yerla canal, the Gondoli canal on the Mân, the Mâyni reservoir on the Vâng, the Chikhli canal on the Nandni, and the Kistna canal. The Revâri canal is an old work restored, while the other five are new works. The Kistna canal, which has its source in the Sahyadri hills has an unfailing supply of water, while the others depend on the local rainfall. The total irrigable area is 47,145 acres, in 1882-83 5550 acres were watered. Besides these works, the Vhaswad lake is being built as a separate irrigation work on the lower Mân. In an average year the water supply from this lake would suffice for an area of 30 000 acres. The work may be said to protect an area of 90 000 acres one third of which may be watered every year. The country under command of this canal stands in great need of water, as its rainfall is very uncertain.

Natural Calamities—The uncertain and scanty rainfall makes eastern Sâtara one of the parts of the Bombay Presidency most liable to suffer from failure of crops. The earliest recorded is the famous famine known as Durga Devi, which, beginning in 1396 is said to have lasted twelve years, and to have spread over all India south of the Narbadâ river. Whole Districts were emptied of their people, and for upwards of thirty years, a very scanty revenue was obtained from the territory between the Godâvari and the Kistna rivers. In 1520 mainly owing to military disturbances, the crops in the Deccan were destroyed and a famine followed. In 1629-30, severe famine raged throughout the Deccan. The rains failed for two years, causing a great loss of life. According to local tradition, the famine of 1791-92 was the severest ever known. It seems to have come after a series of bad years, when the evils of scanty rainfall were aggravated by disturbances and war. The native governments granted large remissions of revenue, the export of grain was forbidden, and a sale price was fixed. Rice was brought from Bengal to Bombay.

The famine of 1802-03 ranks next in severity to that of 1791-92.

It was most felt in Khándesh, Ahmadnagar, Sholápur, Bijápur, and Dhárwár; but it also pressed severely on Belgáum, Sátára, Poona, Surat, and Cutch. This scarcity was mainly due to the ravages of Jaswant Ráo Holkar and his Pindáris, who destroyed the early crops as they were coming to maturity, and prevented the late crops being sown. This scarcity was followed by the failure of the late rains in 1803. The pressure was greatest in July and August 1804, and was so grievous that, according to tradition, men lived on human flesh. Grain is said to have been sold at a shilling the pound. In 1824-25, a failure of the early rains caused considerable and widespread scarcity. In 1862, a scanty fall of rain caused another scarcity.

The scanty and badly distributed rainfall of 1876 led to a failure of crops, and to distress amounting to famine over about one-half of the District. The east and south-east suffered most. In addition to this failure of the early rains, September and October passed with only a few showers, and but a small area of late crops was sown. With high prices, millet at seventeen instead of thirty-five pounds per rupee, and no demand for field work, the poorer classes fell into distress. The need for Government help began about the beginning of October. The long period of dry weather in July and August 1877 forced prices still higher, and caused much distress and suffering; but the plentiful and timely rainfall of September and October 1877 removed all cause of anxiety. By the close of November, the demand for special Government help had ceased. A special Census taken on the 19th May 1877, when famine pressure was general and severe, showed that of 46,235 labourers, 44,344 were on public and 1891 on civil works. As regards their occupation, 3062 were manufacturers or craftsmen, 24,611 were holders or under-holders of land, and 18,562 were labourers. The total cost of the famine was estimated at £118,137. In the eastern Sub-divisions the number of cattle fell from 994,272 in 1876-77 to 775,393 in 1877-78. In 1878, the tillage area fell short of that in 1876 by about 18,400 acres.

Commerce and Manufactures.—Besides *kamblis* (blankets) and coarse cotton cloth, the chief exports of the District are grain, tobacco, oil-seeds, chillies, molasses, and a little raw cotton. The imports are—European piece-goods, hardware, paper, dried fruits, refined sugar, and salt. Weekly or bi-weekly markets are held in large villages and towns. Of these, Mhaswad is famous for its blankets, and Belandi for its cattle. Cotton is spun by women of the Kunbí, Mhár, and Máng castes. The yarn thus prepared is made up by Hindu weavers of the Sáli or Koshtí caste, and by Muhammadans, into cloth, tape, and ropes. Blankets (*kamblis*), which command a large sale, are woven by men of the Sangar caste. Sátára brass dishes and Shirol lamps are well known throughout the Deccan. Notwithstanding the great number of carpenters, wheels

and axles for cart making have to be brought from Chiplun in Ratnágiri Paper is still manufactured to some extent.

Means of Communication—Of the several lines of road in Satara, extending over a total length of 956 miles, the Poona and Belgatim road, crossing the District from north to south and bridged and metalled throughout, is the most important. One branch of this line breaks off at Karád, and runs along the valley of the Koina to Chiplun, while two other branches from Surul and Sátara town, passing by Wai go in the direction of Mahábaleshwar and then towards Mahád, a Konkan seaport. The old Poona road by the Salpa Pass is now almost abandoned. Of the other lines that cross the District from east to west, the chief are the Pandharpur road and the two Tásáon lines, one from Sátara town and one from Karád. Along these and the Belgatim line, a large bullock cart traffic passes. Within the limits of the District, the Sahyádrí hills are crossed by thirteen roads or bullock tracks of which the principal are the Kamatgi, Pisarni, Kumbhárlí, Virándhri and Fitzgerald. Besides houses for the use of District officers when on tour, village offices, *chudis*, and temples, there are 243 *dharmshalas* or rest houses for the accommodation of travellers. The West Deccan line of the Southern Maráthá Railway, now under construction, will pass south and south-east through the centre of the District.

Administration—The total revenue raised in 1882-83 under all heads, imperial, local, and municipal amounted to £227,403 showing on a population of 1,067,350 an incidence of 4s. 3d. per head. The land tax forms the principal source of revenue, amounting to £154,790, or 72.6 per cent. of the total amount. The other chief items are stamps, excise, forest, and local funds. The District local funds created since 1863 for works of public utility and rural education, yielded £18,919. The 13 municipalities contain an aggregate population of 108,259 persons. Their aggregate receipts amounted in 1882-83 to £20,372, and the average incidence of taxation varied from 3d. to 10s. 5d. per head of population.

The administration of the District in revenue matter is exclusive of the Superintendent of Malcolmpet, entrusted to a Collector and 6 Assistant Collectors, four of whom are covenanted civilians. For the settlement of civil disputes there are 8 courts. Thirty-nine officers share the administration of criminal justice. The total strength of the regular police force consisted in 1882 of 177 officers and 776 constables, giving 1 policeman to every 1113 persons of the population. The total cost was £15,120, equal to £3.3s. per square mile of area and 3½d. per head of population. Besides the lock up at each *talukdar's* office, there is a District jail at Sátara and three subordinate jails at Karád, Khatáó, and Tásáon. The number of convicts in the Sátara jail on the 31st December 1882 was 84 of whom 24 were

females; the number of convicts admitted during the year being 297.

Compared with 114 schools and 1168 pupils in 1865, there were in 1877, 219 schools with a roll-call of 10,435 names. By 1882-83, the number of schools had reached 248, with 14,498 names, and an average attendance of 10,875. The first girls' school was opened in the town of Sátára in 1865. In 1882-83, the number of girls' schools was 5, with an average attendance of 260. The Census Report of 1881 returned 13,719 boys and 182 girls as under instruction, besides 27,678 males and 209 females as able to read and write, but not under instruction. Three vernacular papers, two of which have occasional English contributions, were published in Sátára District in 1882-83.

Medical Aspects.—According to the height and distance from the sea, the climate varies in different parts of the District. In the east, especially in the months of April and May, the heat is considerable. But near the Gháts it is much more moderate, being tempered by the sea-breeze. Again, while few parts of Western India have a heavier and more continuous rainfall than the western slope of the Sahyádrí hills, in some of the eastern Sub-divisions the supply is very scanty. The average annual rainfall at Mahábaleshwar is more than 252·8 inches, while in Sátára town it is only 40 inches, and in some places farther east it is less than 12. The west of the District draws almost its whole rain supply from the south-west monsoon, between June and October. Some of the eastern Sub-divisions, however, have a share in the north-east monsoon, and rain falls there in November and December. The May or 'mango showers,' as they are called, also influence the cultivator's prospects.

Seven dispensaries and 2 civil hospitals, one at Sátára and the other at Malcolmpet, afforded medical relief to 477 in-door and 41,499 out-door patients in 1882-83, and 32,422 persons were vaccinated. Vital statistics showed a death-rate of 22·6 per thousand in 1882-83. [For further information regarding Sátára District, see the *Gazetteer of Bombay Presidency*, published under Government orders, and compiled by Mr. J. M. Campbell, C.S., vol. xix., Sátára District (Government Central Press, Bombay, 1885). Also the *Bombay Census Report* for 1881; and the several Administration and Departmental Reports of the Bombay Government from 1880 to 1884.]

Sátára.—Chief town of Sátára District, Bombay Presidency; situated in lat. 17° 41' 25" N., and long. 74° 2' 10" E., 56 miles south of Poona, near the confluence of the Kistna and the Yena, in the highlands of the Deccan, where the country generally inclines towards the east. The strong fort of Sátára, midway between the Kistna and the Tornaghát, is perched on the summit of a small, steep, rocky hill. It takes its name from the seventeen (*sátára*) walls,

towers, and gates which it possessed, or is supposed to have possessed. At the close of the war with the Peshwá, in 1818, it fell, after a short resistance, into the hands of the British, who restored it with the adjacent territory to the representative of Sivaji's line, who, during the Peshwa's ascendancy, had lived there as a State prisoner under the title of the Rájá of Sátara. In 1848, on the death of the last Rájá the principality reverted to the British. The town of Sátara, lying at the foot of the hill fortress, consisted in 1820 of one long street of tiled houses, built partly of stone and partly of brick. After the breaking up of the Rájá's court, the population considerably decreased. But Sátara is still a large place, ranking as the twelfth city in the Bombay Presidency, with a population in 1881 of 28,601 in the town, and 427 in the military lines, total 29,028, namely, males 14,897, and females 14,136. Hindus numbered 24,525, Muhammadans, 3596, Jains, 284, Christians, 527, Pársis, 48 and 'others,' 48. Besides the courts of the Sub-divisional and District revenue officers it possesses a District Judge's Court and a High School. The Rájá's palace is plain and commonplace. Sátara has few large or ornamental buildings, but the town is clean and the streets broad. On account of its high position, 2370 feet above sea level, and its exposure to the sea breeze, the climate is unusually pleasant. The water supply is drawn by pipes from a reservoir on the hill of Enteshwar, and from three masonry ponds in the valley of Krishneshwar.

Sátara Jágirs, The — Group of Native States in the Bombay Presidency, under the Political Superintendence of the Collectors of Sátara and Sholápur, comprising—Akalkot, Aundh, Bhór Dáphlápúr, Jath, and Phaltán. Of these Bhór lies in the north west of Sátara District, Phaltán in the north, Aundh in the east, Jath in the extreme south east, Dáphlápúr also in the south east, and Akalkot in the south east of Sholápur. Total area 3821 square miles. Revenue, about £157,800. The Sátara *jágirs* were feudatory to the Rájá of Sátara, and became tributaries to the British Government on the lapse of that State in 1849. The *jágirdárs* retained all their former rights and privileges with the exception of the power of life and death, and of adjudicating upon serious criminal cases. Their administration is now conducted on the principles of British law. Criminal and civil justice is administered by the chiefs themselves, with the aid of subordinate courts. In civil suits, special appeals from the decisions of *jágirdárs* lie to the Political Agents. In criminal cases heinous offences requiring capital punishment or transportation for life are tried by the Political Agents, each assisted by two assessors, the preliminary proceedings being conducted by the *jágirdárs*. Criminal appeals from their decisions also lie to the Political Agents. The Collector of Sátara is in charge of the *jágirs*.

of AUNDH, BHOR, JATH, and PHALTAN, and of the little cluster of six villages (rent-roll of £1300; area, 40 square miles; population (1881) 6007; revenue, £900) belonging to the Bhai Sáhab of Daphlapur, who exercises the powers of a magistrate of the first class, and in civil suits those of a subordinate judge. AKALKOT is under the Collector of Sholápur. Population (1881) of the Sátára *jágírs*, 376,727, namely, males 190,497, and females 186,230, occupying 54,139 houses, in 3 towns and 838 villages. Hindus numbered 354,242; Muhammadans, 16,747; and 'others,' 5738.

Satásgarh (or '*Sixty Towers*').—Ruin in PANDUAH TOWN, Maldah District, Bengal.—See PANDUAH.

Sátgáon (or *Saptagrám*, 'The Seven Villages,' so called from seven sages who gave their names to the same number of villages).—Ruined town in Húglí District, Bengal. Lat. $22^{\circ} 38' 20''$ N., long. $88^{\circ} 25' 10''$ E. The mercantile capital of Bengal from the Puránic age until the foundation of HUGLI by the Portuguese. The decay of this port dates from the silting up of the channel of the SARASWATI, and nothing now remains to indicate its former grandeur except a ruined mosque; the modern village consists of a few miserable huts. Sátgáon is said to have been one of the resting-places of Bhágráthí. De Barros writes that it was 'less frequented than Chittagong, on account of the port not being so convenient for the entrance and departure of ships.' Purchas states it to be 'a fair citie for a citie of the Moores, and very plentiful, but sometimes subject to Patnaw.' In 1632, when Húglí was declared a royal port, all the public offices were withdrawn from Sátgáon, which rapidly fell into ruins. [For a full description of the ancient Sátgáon, see *Statistical Account of Bengal*, vol. iii. pp. 307–310.]

Sathamba.—Petty State in Mahi Kántha, Bombay Presidency. Population (1881) 5360. Estimated revenue, £825, of which £40, 2s. is paid as tribute to the Gáekwár of Baroda, £56, 2s. to Bálásinor, and £12, 14s. to Lunáwára. The chief, Thákur Ajáb Singh, is a Baria Kolí. The family holds no deed allowing adoption; in matters of succession it follows the rule of primogeniture. Area under cultivation, about 5000 acres. Staple crops, rice and *joár*. One school, with 74 pupils.

Sáthan.—Town in Sultánpur District, Oudh; pleasantly situated on high ground overlooking the Gúmti river, 40 miles north-west of Sultánpur town. Founded by Sáthan, a Bhar, and called after him. After the Mutiny of 1857, a certain Sháh Abdúl Latíf settled here as a 'missionary of pure religion,' and built a mosque, at which hundreds of the Sunní sect assemble every Friday. The '*ídgháh*' of Sáthan is a place of considerable resort for the faithful at the 'Id festival. Population (1881) 1566, namely, Hindus 818, and Muhammadans 748, principally Sayyids and Shaikhs.

Sátkhirá—Sub-division of Khulná District, Bengal, lying between $21^{\circ} 38'$ and $22^{\circ} 56' 45''$ N lat., and between $88^{\circ} 56' 30''$ and $89^{\circ} 4' 1''$ E. long. Area, 702 square miles, towns and villages, 1155, houses, 59,564. Population (1881) 434,766, namely, males 228,949, and females 205,817, proportion of males, 52.7 per cent. Average number of persons per square mile, 619, villages per square mile, 1.65, persons per village, 376, houses per square mile, 87, inmates per house, 7.3. This Sub-division consists of the 5 police circles of Sátkhírá, Kalaróá, Mágurá, Kálígánj, and Ásisuná. In 1884 it contained 2 civil and 4 criminal courts, a regular police of 92 men, and a rural force 810 strong.

Sátkhírá—Chief town of Sátkhírá Sub-division, Twenty-four Parganás District, Bengal, situated on the Betna river, in lat. $22^{\circ} 42' 35''$ N, and long. $89^{\circ} 7' 55''$ E. Population (1881) 8738, namely, Muhammadans 4391, and Hindus 4347. Municipal income (1883-84), £406, of which £376 was derived from taxation, average incidence of taxation, 10½d per head of the population. The town contains many Hindu temples, a large vernacular school or *pathshala*, entirely supported by the *samundár*, and a Government dispensary, in charge of a native sub-assistant surgeon. Once a rural village, Sátkhírá is now an important town, a canal having been cut to the Ichámati river, fair roads lead to the nearest marts of traffic, thus making it an emporium for the sale and shipment of the produce of the surrounding country. Large trade in sugar and rice.

Satlaj—One of the five rivers of the Punjab.—*See SATLEJ*.

Satlásna.—Native State in the Political Agency of Mahi Kántha, Bombay Presidency. Population (1881) 3281. The principal agricultural products are millet, wheat, Indian corn, and sugar-cane. The present (1882-83) chief is Thákur Hari Singh, a Hindu of the Parmár Koli tribe. He is thirty-four years of age, and manages his estate in person. He enjoys an estimated gross revenue of £450, and pays a tribute of £168 to the Gáekwar of Béroda, and £73 to the Rájá of Ldr. The family of the chief follow the rule of primogeniture in point of succession. There is 1 school in the State, with 43 pupils.

Satodar Wáori—Petty State in the Hállár *prant* or division of Káthiáwár, Bombay Presidency, consisting of 4 villages, with 4 shareholders or tribute-payers. Area, 13 square miles. Population (1881) 2447. Estimated revenue, £1200, of which £146, 12s. is paid as tribute to the British Government, and £46, 2s. to the Nawab of Junágarh.

Sátpáti—Port in Thína (Tanna) District, Bombay Presidency, situated about 6 miles north of Máhim. One of the ports of the Lárápur Customs Division. Average annual value of trade for five years ending

1881-82—imports £1831, and exports £6155. The trade in 1881-82 was—imports £2950, and exports £6882.

Sátpura.—Hill range or table-land, which begins at AMARKANTAK and extends westward across the Central Provinces, and beyond them nearly to the western coast. The name was formerly restricted to that portion of the range which divides the Narbadá (Nerbudda) and Tápti valleys; while sometimes the term Vindhya has been extended to include the Sátpuras, together with the parallel range on the northern side of the Narbadá, in one general appellation for the great chain which stretches across Central India and separates Hindustán proper from the Deccan. Geologically, however, the Vindhyan sandstones are entirely distinct from the Mahádeo and other groups which enter into the composition of the Sátpuras; and geographically, the line of demarcation between the two ranges is defined by the well-marked valley of a great river.

Taking Amarkantak as the eastern boundary, the Sátpuras stretch from east to west for about 600 miles, while their greatest breadth from north to south exceeds 100 miles. The range forms a rough triangle. From Amarkantak, 3328 feet above sea-level, an outer ridge runs south-west for about 100 miles to the Saletekli Hills in Bhandará District. This ridge, known as the MAIKAL range, constitutes the base of the triangle. Starting from this base, the Sátpura range shrinks, as it proceeds westward, from a broad table-land to two parallel dorsal ridges, bounding on either side the valley of the Tápti. Just east of Asirgarh occurs a break, through which the Great Indian Peninsula Railway from Bombay and Khándesh to Jabalpur is carried; and ASIRGARH marks the point where the Sátpuras leave the Central Provinces.

Following the range from east to west, the main features which it presents may be thus described. In Mandlá District, the slope is mainly northward towards the Narbadá. There are four principal upland valleys, each sending down a feeder to that river. The eastern valleys are higher than those to the west. Between the Kharmer and Burhner rivers, the country consists of a rugged mass of bare and lofty mountains hurled together by volcanic action. Their general formation is basaltic, intermixed with laterite, with which the higher peaks are capped. The Chaurádádar plateau, 3300 feet high, has an area of 6 square miles.

In Seoní District, the plateaux of Seoní and Lakhnádon are from 1800 to 2220 feet high. The slope of the country is from north to south; and in the lowest watershed, the Waingangá river rises. In Chhindwára, also, the country slopes southwards. The principal upland valleys are those of the Pench and Kolbirá. The general elevation is about 2200 feet, but the plateau of Motúr attains a height of 3500 feet. In Betúl, the slope to the south continues; and the Tápti rises

and flows in a deep and narrow gorge. In the south west corner of the District, the hill of Khamli rises 3700 feet high. To the north of Betul, spurs from the Sātpuras occupy a considerable portion of Hoshangabad. Dhupgarh (4454 feet) is the highest point, and the picturesque plateau of Pachmarhi, 3481 feet above sea level, covers an area of 12 square miles.

South of Hoshangabad, sandstone and metamorphic rocks emerge, and form a great portion of the hills of the Betul and Pachmarhi country. To the east, trap predominates. In Nimār District, the wild and barren range which parts the valleys of the Tāpti and the Narbadā has an average width of 15 miles. On its highest point stands the fortress of Asirgarh.

West of Asirgarh, the Sātpura hills form a broad belt of mountain land, stretching in a wall like line along the north bank of the Tāpti. They rise from the first range of hills, ridge behind ridge, to the central crest about 2000 feet high and then slope gently to the Narbadā. The Dombay Agra trunk road crosses the Sātpuras farther west. Among the peaks that rise from 3000 to 3800 feet above sea level, the grandest is TURANMAL, a long, rather narrow table land 3300 feet above the sea, and about 16 square miles in area. West of Turanmal, the mountain land presents, both towards the Tāpti and the Narbadā, a wall like appearance.

Sātpura.—State forest lying along the southern slopes of the Sātpura hills, in Seoni, Chhindwārā and Nāgpur Districts, Central Provinces. Area, about 1000 square miles. *Sit* forms the chief growth in the eastern, and teak in the western portion. The proximity of Kāmthi (Kamptee) and Nāgpur has caused the exhaustion of all but young timber, but what remains is now strictly preserved, and plantation experiments have been conducted at Sukāra and Sūājhar.

Satrikh—*Pargana* in Bara Banki District, Oudh, bounded on the north by Nāwābganj and Partabgarh, on the east by Siddhaur, on the south by Haidrabad, and on the west by Dewa. Area, 46 square miles, or 29,404 acres, of which 19,318 acres are cultivated. Population (1881) 27,570, namely, males 11,492, and females 11,078. Number of houses, 4238. Of the 42 villages comprising the *Pargana*, 17 are held in *Mikāfī*, 20 in *zanī* *darī*, and 5 in *darī* tenure. Government land revenue, £4796.

Satrikh—Town in Bara Banki District, Oudh and head-quarters of Satrikh *Pargana*, situated 5 miles south-east of Bara Banki town, in lat. 26° 51' 30" N., and long. 81° 14' 10" E. Population (1881) 4090, namely, Hindus 2458, and Muhammadans 1632. Number of houses, 943. The town was originally founded by a Hindu Pāji named Satrikh, but was captured by the Muhammadans under Sāfir Sabu a brother in law of Mahmūd of Ghazāl. Sāfir Sabu died here, and

an annual fair is held at his shrine, attended by about 18,000 persons.

Satrunjaya (*Shetrunja*).—Sacred hill near Pálitána, in the Gohelwar *prant* or division of Káthiáwár, Bombay Presidency.—See PALITANA TOWN.

Sattanapalli.—*Táluk* or Sub-division of Kistna District, Madras Presidency. Area, 714 square miles. Population (1881) 110,290, namely, males 55,695, and females 54,595, occupying 18,752 houses in 169 villages. Hindus number 94,862; Muhammadans, 9086; and Christians, 6342. A wide extent of black soil is found in the *táluk*, producing heavy crops of cotton. In the black soil, gneissic rock protrudes here and there. In this *táluk* are the fortresses of BELLAMKONDA and Dharanikota near AMRAVATI town. Sattanapalli contained in 1883—criminal courts, 2; police circles (*thánás*), 7; regular police, 53 men. Land revenue, £36,790. Head-quarters at Krossúr; population (1881) 1912, occupying 327 houses.

Sattankulam.—Town in Tenkarai *táluk*, Tinneveli District, Madras Presidency. Population (1881) 5116, occupying 1261 houses. Hindus number 3697; Muhammadans, 392; Christians, 1019; and 'others,' 8. Important agricultural town, with wealthy inhabitants engaged in money-lending.

Sátúr.—*Táluk* or Sub-division of Tinneveli District, Madras Presidency. Area, 548 square miles. Population (1881) 150,886, namely, males 73,382, and females 77,504, occupying 31,945 houses, in 2 towns and 212 villages. Hindus number 145,425; Muhammadans, 3052; Christians, 2409. The northern and eastern villages are part of the black cotton plain of Tinneveli District; the southern and south-western consist of red loam and sand. The latter or red soil portion is considerably larger in area than the former. Cotton is the staple produce; and *kambu* (*Pennisetum typhoideum*) and gram are also grown, as well as tobacco, chillies, and vegetables. About one-fifth of the *táluk* is *inám*, one-fourth *zamindari*, and the remainder Government. The South Indian Railway main line traverses the *táluk*. In 1883, Sátúr contained 2 criminal courts; police circles (*thánás*), 9; regular police, 76 men. Land revenue, £21,773.

Sátúr.—Village in Sátúr *táluk*, Tinneveli District, Madras Presidency; situated on the north bank of Vaipár river, and a station on the South Indian Railway main line, 55 miles north of Tinneveli town. Head-quarters of the *tahsildár* of Sátúr *táluk*; the sub-magistrate is stationed at VIRUDUPATTI. Population (1881) 2168, namely, Hindus, 1861; Muhammadans, 155; and Christians, 152. Number of houses, 428. Post-office.

Satyamangalam.—*Táluk* of Coimbatore District, Madras Presidency. Area, 1176 square miles. Population (1881) 151,313, namely,

males 73,762, and females 77,551, occupying 32,489 houses in 1 town and 184 villages. Hindus number 146,753, Muhammadans, 2724, Christians, 1831, and 'others,' 5. In 1883 the *taluk* contained 3 criminal courts, police circles (*thinnis*), 9, regular police, 99 men. Land revenue, £31,537.

Satyamangalam.—Town in Satyamangalam *taluk*, Coimbatore District, Madras Presidency. Lat $11^{\circ} 30' 20''$ N, long $77^{\circ} 17' 15''$ E. Population (1881) 3210, inhabiting 634 houses. Hindus number 2899, Muhammadans, 253, Christians, 55, and 'others,' 3. The fort is situated on the Bhavani river, and was built by the Nairs of Madura. It was taken by the Mysore generals in 1657. Owing to its situation, Satyamangalam was of considerable strategic importance in our wars with Haider Ali and Tipu. Colonel Wood took the place in 1768, but Haider recaptured it the following year. In 1790 Colonel Lloyd occupied Satyamangalam, and between the fort and Danavakhanottai fought a severe battle with Tipu in the same year, falling back upon Merdow's column, but effecting his retreat with such skill as almost to convert it into a victory. There are two *ghat* roads to the uplands from Satyamangalam—the Gazzahatti and the Hassanur roads. The latter is the most frequented route into Mysore.

Sanda—Sub-division and town, Khândesh District, Bombay Presidency.—See SANDA.

Saugor.—District, Sub-division, and Town, in the Central Provinces.—See SAGAR.

Saugor.—Island at the mouth of the Hugli river, Bengal.—See SAGAR.

Saundatti—Chief town of the Paragarh Sub-division of Belgium District, Bombay Presidency, situated 41 miles east by south of Belgium town, in lat $15^{\circ} 45' 50''$ N, and long $75^{\circ} 9' 40''$ E. Population (1881) 7133, namely, Hindus 6314, Muhammadans, 690, and Jains 129. About 2 miles due south of Saundatti are the ruins of an extensive hill fort called Paragarh, from which the whole Sub-division derives its name. Sub-judge's court, two schools, post-office, and dispensary. About $5\frac{1}{2}$ miles north west of Saundatti a large Hindu fair in honour of the goddess Yellamma is held twice a year about the full moon in April or May and in November or December. On each occasion, from 15,000 to 20,000 persons attend. Municipal income (1883-84), £296, incidence of taxation, 9½d per head. The water supply is poor. Weekly market on Wednesdays, when cloth, cotton oil, salt, and spices are sold.

Saunt Jot—Village in Khair *taluk*, Latchwar District, North Western Provinces, situated in lat $25^{\circ} 50' 46''$ N, and long $81^{\circ} 5' 9''$ E. Population (1881) 2216, prevailing caste, Chamars.

Saurath—Village in Darbhanga District, Bengal, 8 miles west of Madhubani. Famous for the large *sculp* (religious fair) which takes

place annually in June or July, when vast numbers of Bráhmans assemble to settle their children's marriages. Sauráth contains a temple of Mahádeo, built about 1845 by the Darbhanga Rájá; close to this building is a tank, shaded by a fine mango grove.

Saúsar.—Southern *tahsíl* or Sub-division of Chhindwára District, Central Provinces. Area 1088 square miles, with 407 towns and villages, and 22,668 houses. Population (1881) 110,809, namely, males 55,422, and females 55,387. Average density of the population, 102 persons per square mile. The male and female adult agriculturists number 46,029, or 41·54 per cent. of the total population; average area available for each adult cultivator, 9 acres. Of the total area of the *tahsíl*, 344 square miles are held revenue-free, leaving 744 square miles for Government assessment, of which 373 square miles are cultivated, 75 square miles cultivable, and 296 square miles uncultivable waste. Amount of Government land revenue, including local rates and cesses levied on land, £10,830, or an average of 10½d. per cultivated acre; rental paid by cultivators, £16,180, or an average of 1s. 4½d. per cultivated acre. In 1884 the *tahsíl* contained 1 criminal and 2 civil courts, with 2 police stations (*thánás*) and 5 outpost stations; strength of regular police, 83 men; *chaukidárs* or village watch, 392.

Saúsar.—Town and municipality in Chhindwára District, Central Provinces, and head-quarters of Saúsar *tahsíl*; situated in lat. 21° 40' N., and long. 78° 50' E., 34 miles south of Chhindwára town, on the main road to Nágpur. Population (1881) 4311, chiefly agriculturists, namely, Hindus, 3747; Kabírpánthis, 174; Muhammadans, 275; Jains, 7; and non-Hindu aborigines, 108. Municipal income (1882-83), £119, of which £82 was derived from taxation; average incidence of taxation, 4½d. per head. Saúsar has a Government school, and a small fort; the proprietor is the representative of the Gond dynasty of Deogarh. *Sardí*, or native rest-house.

Sáváli.—Town in Baroda State (Gáekwár's territory), Bombay Presidency. Population (1881) 6275. Sáváli is the trade centre of a wide circle of villages. In the immediate neighbourhood are wide tanks, shady trees, and fruitful fields; at no great distance is the wild Mehwasí country of ravines and jungles bordering the Mahi. At one of the corners of the beautiful Sáváli tank stand two temples which commemorate the names of Damáji and his father Piláji. The treacherous murder, the invasion of Abhi Singh, the hasty funeral of the founder of the Gáekwár house, mark a crisis in the history of the Maráthá conquest, and give something of historic dignity to the unpretending temple of Piláji. Custom-house, post and police offices, and dispensary.

Savandrúg.—Hill fort in Bangalore District, Mysore State, locally known as the Magadi Hill, 4024 feet above sea-level. Lat. 12° 55' N., long. 77° 21' E. It consists of an enormous mass of granite, standing

on a base ■ miles in circumference. The summit is divided by a chas- into two peaks—the *Kari* or black, and the *Jish* or white—each of which is abundantly supplied with water. The earliest fortifications are said to have been erected in 1543, by Sámanta Ráya, who gave the hill his own name of *Sámanta-durg*. The present appellation dates from the end of the 16th century, when Immadi Kempe Gowda of Bangalore established his stronghold here, in which his family maintained themselves until 1728. The fort was captured in that year by the Hindu Rájá of Mysore, from whom it passed into the hands of Haidar Ali. In 1791, Savandrug was stormed by a British army commanded by Lord Cornwallis. On December 10 a force under Colonel Stuart encamped within 3 miles of the place, and after great difficulties in bringing up the battering train, the bombardment was opened on the 20th, and in three days the breach was declared practicable. The assault was delivered on the following day under the eyes of Lord Cornwallis. The whole line of fortifications was carried within an hour, without the loss of a single life on the British side.

Savanur (Savanur)—Native State, situated within Dharwar District, Bombay Presidency, lying between 14° 56' 45" and 15° 1' 45" N. lat., and between 75° 21' 45" and 75° 25' 1" long. Area, 70 square miles. Population (1872) 17,288, (1881) 14,763, namely, males 7,347, and females 7,416, occupying 2646 houses, in 1 town and 23 villages. Hindus number 10,866, Muhammadans 3,839 and 'others,' 358. The principal products are cotton *sisir* (*Sorghum vulgare*), rice, *kulthi* (*Dolichos biflorus*), *mung* (*Phaseolus Mungo*), coconut, castor-oil *tur* (*Cyrinus indicus*) *pin* (*Piper Betle*), wheat, gram, plantains, and sugar cane. Of the total area of 44,660 acres, 40,055 are cultivable, area under actual cultivation in 1883-84, 31,707 acres. Coarse cloths, such as *saris*, *dhotis*, etc., are manufactured to a small extent, and one loom for weaving silk cloths (*pitambar*) is worked. Some trade in grain. The betel leaf grown in the Savanur gardens is celebrated for its superior quality. Within the State there is only one forest at Mulakari. Before Savanur came under Tipu Sultan (1785) there was a mint at which gold coins were struck called Savanur Huns, bearing the name of the reigning Nawab and valued at 6s. 8d.

The reigning family are Muhammadans of Afghan descent. Abdull Rauf Khan, the founder of the family, obtained in 1680 from the Emperor Aurangzeb the grant of the *jisir* of Bankapur, Torgal, and Azimnagar, with a command of 7000 horse. The family, though connected by marriage with Tipu Sultan, was entirely *shin* of its possessions by him, and the Nawab sought the protection of the Peshwa, from whom he received a pension of £4500 per annum. This was subsequently converted into a grant of territory, yielding an equal amount of revenue, through the intervention of General Wellesley.

The management of the State, which had since 1868 been under the care of the Collector of Dhárwár as Political Agent, was handed over in 1883 to Nawáb Abdúl Dalíl Khán, a young man of great promise, who had been carefully educated at Rájáram College, Kolhápúr. The young chief died in 1884. Strength of police, 66 men; cost of maintaining the force, £493. Criminal courts, 2; schools, 7. Average annual rainfall, 27·3 inches.

Savanúr.—Chief town of Savanúr State, Bombay Presidency. Lat. 14° 58' N., long. 75° 23' 5" E.; situated 40 miles south-east of Dhárwár. Population (1881) 7640, namely, Hindus, 4582; Muhammadans, 3031; and Jains, 27. The town is nearly circular, and covers an area of three-quarters of a square mile. It is enclosed by a ditch with eight gates, three of which are ruined. Between 1868 and 1876 the town was greatly improved, the roads widened and metalled, and many old wells and ponds repaired. Income of municipality in 1883–84, £629. Three schools with 218 pupils, of whom 60 were girls. Annual fair.

Savari (*Seberi*, *Severi*).—River in Madras Presidency. — See SABARI.

Sávda.—Sub-division of Khándesh District, Bombay Presidency. Area, 553 square miles. Population (1872) 124,519; (1881) 141,745, namely, males 71,720, and females 70,025, occupying 24,767 houses, in 4 towns and 178 villages. Hindus number 123,395; Muhammadans, 16,033; and 'others,' 2317. Sávda lies in the north-east of Khándesh District, and includes the petty divisions of Yával and Ráveri. The Sub-division is a well-wooded, unbroken plain, from which, along the north, the Sátপুরas rise in a wall-like line. Though highly cultivated and thickly peopled, it is not on the whole well provided with water, excepting in the villages along the Tápti and the Súki. Despite extreme heat from March to June, the climate is healthy. The prevailing soil is a black alluvial clay from four to five feet deep, resting on a subsoil of soft yellowish clay (*mán*). This black soil is best in the centre, and grows poorer towards the river on the south and the hills on the north. In 1854–55, the year of settlement, 12,970 holdings or *khdtás* were recorded with an average area of 16·3 acres, paying an average assessment of £1, 9s. 6d. In 1878–79, the area under actual cultivation was 217,874 acres. Cereals and millets occupied 125,846 acres; pulses, 11,902 acres; oil-seeds, 18,925 acres; fibres, 54,421 acres; and miscellaneous crops, 6780 acres. In 1883 the Sub-division contained 1 civil and 5 criminal courts; police circles (*thánás*), 3; regular police, 119 men; village watch (*chaukidárs*), 691. Land revenue, £30,844.

Sávda.—Chief town of the Sávda Sub-division of Khándesh District, Bombay Presidency, and a station on the Great Indian Peninsula Railway, 285 miles north-east of Bombay city; situated in lat. 21° 8' 30" N., and long. 75° 56' E. Population (1881) 8642, namely, Hindus,

7061, Muhammadans, 1324, Juns, 236, Christians, 6, Pársis, 2, and 'others,' 13. Sáva was finally ceded by the Nizám to the Peshwá in 1763, and was shortly afterwards bestowed on Sardár Raste, whose daughter was given in marriage to the Peshwá. In 1852, in connection with the introduction of the revenue survey, a serious disturbance occurred at Sáva. From 10,000 to 15,000 malcontents gathered, and were not dispersed till a detachment of troops arrived and seized 59 of the ringleaders. A municipality has recently been established and had an income in 1883-84 of £233, incidence of taxation, 5½d per head. Chief trade, cotton, gram, linseed, and wheat. Post-office, three schools. At the weekly market, valuable Nimar and Berar cattle are offered for sale.

Sávitri (Savatrí) — River of Bombay Presidency, rising on the western declivity of the Mahábaleshwar range, Sátara District, in lat. 18° 28' N, and long 73° 30' E. Descending the mountain side in a narrow rocky channel, it passes the towns of Mhar and Dásdion through Southern Kolába, and reaches Ratnágiri District at Mahápral. After a total course of about 50 miles, it falls into the Arabian Sea at Bínkot in lat 17° 58' N, and long 73° 31' E. The mouth of the Sávitri is formed by bluff hills, jutting out on either side of the creek into the sea. Fort Victoria or Bínkot crowns the southern headland. Bínkot is only a fair weather port. The passage is marked by buoys and beacons, but a rather formidable sand bar, with a depth of 2½ fathoms at low water, lies across the entrance to the anchorage. The river is navigable, for native craft drawing 7 feet of water, 36 miles to the town of Mhar in Kolába District, for vessels of 16 feet up to Mahápral in Ratnágiri, about 24 miles from the mouth. Between Bínkot and Mahápral there is no difficulty, large craft work up on a single tide. Between Mahápral and Mhar the river narrows, shoals and rocky ledges and reefs are numerous, and even for small craft navigation is both difficult and dangerous. Every year within these limits the creek is silting and becoming more difficult. After the first two or three miles, the scenery of the creek is particularly striking. The hills rising boldly from the water's edge to a considerable height are especially on the northern bank, clad with thick forests, which on some of the reaches surround the water on all sides, giving the creek the appearance of a mountain lake. Farther inland, the hills draw back giving place to broad belts of lowland, divided from the water by mangrove swamps. Before Mhar is reached, the banks have become flat and uninteresting.

Sáwantwári. — Native State in Bombay Presidency, under the charge of a Political Superintendent, situated about 200 miles north of Bombay city, between 15° 35' 30" and 16° 14' N lat, and between 73° 37' and 74° 23' E long. Area, about 900 square miles. Pop., about 1 (1872) 190,511, and (1881) 174,433. The State is bounded on the

north and west by the British District of Ratnágiri, on the east by the Sahyádrí Hills, and on the south by the Portuguese territory of Goa. The general aspect of the country is strikingly picturesque. From the sea-coast to the foot of the Sahyádrí hills, a distance varying from 20 to 25 miles, are densely wooded hills, and in the valleys, gardens and groves of cocoa-nut and areca-nut palms. The chief streams are the Kárlí on the north, and the Terekhol on the south, which open out into creeks. Both are navigable for small native craft; the Terekhol for about 15, and the Kárlí for about 14 miles. The climate is humid and relaxing, with a heavy rainfall, averaging for the 32 years ending 1879, 143 inches, varying from 222 inches in 1874 to 93 inches in 1855. April is the hottest month in the year; but in May (though the temperature is slightly higher) a strong sea-breeze, the precursor of the south-west monsoon, tempers the heat.

The State is rich in forests of teak, especially near the Sahyádrí Hills, blackwood, *ain* (*Terminalia tomentosa*), *kher* (*Acacia Catechu*), *jámbe* (*Xylia dolabriformis*). Nearer the sea, the more important trees are the jackwood, mango, and *bhirand* (*Garcinia indica*), whose fruit yields *kokam* oil. The principal fruits are mangoes and plantains, which are abundant and of excellent quality, citrons, limes, and jack fruit. Cocoa-nuts and cashew-nuts are very plentiful. The staple agricultural produce is rice; but the quantity grown is not sufficient for the wants of the people, and a good deal is imported. Excepting rice, none but the coarsest grains and pulses are raised. A species of oil-seed, *tíl* (*Sesamum indicum*), hemp, and black and red pepper, are also grown, but neither cotton nor tobacco. Both soil and climate are against the cultivation of wheat and other superior grains. For these, the people have to look to the country east of the Sahyádrí Hills, whence during the fair season, from October to June, large supplies come. Coffee has been grown with success, and it is believed that the spurs from the Sahyádrí range are suited to its cultivation on a large scale. Iron-ore of fair quality is found in the neighbourhood of the Rámghát, in the Sahyádrí range. The Akeri stone, a slate-coloured talc-schist, extremely hard, compact, and heavy, is unrivalled for building purposes. Laterite is quarried in many places. Talc of inferior quality is found at Kudáwal. The forests and wooded slopes of Sahyádrí hills contain large numbers of tigers, leopards, bison, *sámbar* deer, etc. In 1883-84, locusts visited the State for the sixth successive year, but in smaller numbers than on previous occasions. About 12 millions of locusts were destroyed.

Population.—Population (1881) 174,433, namely, males 86,061, and females 88,372, occupying 30,444 houses, in 1 town and 225 villages. Hindus number 166,080; Muhammadans, 3970; Christians, 4213; and 'others,' 170. The Christians are all Roman Catholics, and consist

of Indo Portuguese and natives who have embraced Christianity. The common language of the people is a dialect of Marathi, known as Kurauli. The sturdy and easily managed Marāthas and Mhars of the State are favourite recruits for the Bombay Native Infantry regiments. The inhabitants generally are poor, and are engaged chiefly in agriculture.

Manufactures—Salt of an inferior kind was formerly manufactured, but the salt pans have recently been abolished. The principal industries of the State consist of gold and silver embroidery work on both leather and cloth, fans, baskets and boxes of *Laske* grass, ornamented with gold thread and beetles' wings, lacquered toys, and playing cards, and elegant drawing room ornaments carved from the horn of the buffalo and bison. Recently a pottery establishment for the manufacture of tiles has been opened. The pottery is now becoming widely known, and it is expected that a ready sale will be found for the tiles not required by the State.

Means of Communication—There are no railways but an excellent trunk road has recently been constructed from the seaport of Vengurla, which, passing through the State, leads by an easy gradient over the Sahyādrī Hills to Belgaum and the Southern Marāthā Country. The other chief lines of communication with the Deccan are the Ramghāt, the Talakghāt, and the Phondāghāt.

Trade—Within the limits of the State there is not much local trade, but during the fair season a considerable quantity of cotton, hump, and grain from the rich Districts of the Southern Marāthā Country passes coastwards, especially to the port of Vengurla. Compared with the exports, the imports at Vengurla are small.

History—Early inscriptions show that from the 6th to the 8th centuries the Chālukyas ruled over Sāwantwārī. In the 10th century, the rulers were Yādavas. In the 13th century (1261) the Chālukyas were again in power. At the close of the 14th century (1391), Sāwantwārī was under an officer of the Vijayanagar dynasty. About the middle of the 15th century it formed part of a powerful Prānān dynasty. On the establishment of the Bijāpur power at the close of the 15th century, Sāwantwārī became part of the territory of these kings. About three hundred years ago (1554) one Māng Sāwant of the Bhonsla family revolted from Bijāpur, and making Hodwārā, a small village 9 miles from War, his headquarters, defied the troops sent against him, and maintained his independence during his life-time. After his death, his successors again became feudatories of the Bijāpur kings.

The chief who finally freed his country from the Mūlāmūlādār yoke was Khem Sāwant Bhorslī, who ruled from 1627 to 1640. He was succeeded by his son, Som Sāwant, who, after ruling for

eighteen months, was succeeded by his brother Lakham Sāwant. When the power of Sivajī seemed in the ascendant (1650), Lakham Sāwant tendered him allegiance, and was confirmed as *Sar Desai* of the whole South Konkan. Dying in 1665, Lakham was succeeded by his brother Phond Sāwant, who, after ruling for ten years, was succeeded by his son, Khem Sāwant II. This chief was a contemporary of Sāhu, the grandson and second successor of Sivajī, who assigned to him, conjointly with the chief of Kolāba, half the revenue of the Sālsi Mahal. It was during the time of Khem's successor (1709-1737) that the Sāwantwāri State first entered into relations with the British Government. A treaty was concluded between them against the notorious piratical chieftain, Kanojī Angria of Kolāba.

The chief who ruled from 1755 to 1803, under the name of Khem Sāwant the Great, married in 1763 the daughter of Jáyajī Sindhia; and consequently the title of Rāi Bahādur was conferred upon him by the Emperor of Delhi. The chieftain of Kolhāpur, envious of this honour, made a descent on Wāri, and captured several hill fortresses, which were, however, through Sindhia's influence, subsequently restored. The rule of Khem Sāwant, who, not content with wars on land, also took to piracy, was one long contest against Kolhāpur, the Peshwā, the Portuguese, and the British. Khem Sāwant died childless in 1803; and the contest for the succession was not decided till 1805, when Khem Sāwant's widow, Lakshmibāi, adopted a child, Rāmchandra Sāwant *alias* Bhāu Sāhib. This child lived for three years, and was then (1805) strangled in bed. Phond Sāwant, a minor, was chosen to fill his place. During these years of disorder the ports swarmed with pirates. So severely did British commerce suffer, that in 1812 Phond Sāwant was forced to enter into a treaty, ceding the port of Vengurla to the British, and engaging to give up all his vessels of war. Soon after the conclusion of this treaty, Phond Sāwant died, and was succeeded by his son, Khem Sāwant, a child of eight years. This chief, when he came of age, proved unable to manage his estate, and after several revolutions and much disturbance, at last in 1838 agreed to make over the administration to the British Government. After this, rebellion twice broke out (in 1839 and 1844), but the disturbances were soon suppressed, and the country has since remained quiet.

The present (1884-85) chief is Sar Desāi Raghunāth Rāo Sāwant Bhonsla, who is not yet considered fit to be entrusted with the duties of government. He has been educated at the Rājikumar College at Rājkot. He is entitled to a salute of 9 guns. He enjoys an estimated gross revenue of £32,500, and maintains a military force of 436 men, styled the Sāwantwāri Local Corps. The family of the chief

hold a title authorizing adoption, and in point of succession follow the rule of primogeniture. Strength of police, 155, cost in 1883-84 £2479. Daily average number of prisoners in jail, 51. Number of schools, 46, pupils, 2916.

Sāwantwārī (*Wārī* or *Sundar wārī*, 'the Beautiful Garden') — Chief town of Sāwantwārī Native State Bombay Presidency — *See* WAKI.

Sawar.—Town in Ajmere District, Ajmere Merwāra, Rājputāna. Lat $25^{\circ} 49' N$, long $75^{\circ} 21' E$. Distant 61 miles from Ajmere city. Chief town of Sawar *farānī*, and the residence of the *istīn rārār*. Good water supply. Post-office.

Sayāna.—Ancient town in Bulandshahr District North Western Provinces — *See* SIYANA.

Sāyāla.—Native State in the Jhālīwār *farānī* or division of Kathiawar, Bombay Presidency. Area, 222 square miles containing 37 villages. Population (1872) 16 528, (1881) 16 991. The climate is hot and dry, but healthy. Cotton is the chief produce the usual grains are also grown. Dyeing is the only industry of consequence. The nearest port is Dholera. Sāyāla ranks officially as a third class State in Kathiawar, and the ruler executed the usual engagements in 1807. The present chief (1882-83), Thakur Wakhra Singhji a Hindu of the Jhālī Rājput caste, is thirty-eight years old and administers his estate in person. He enjoys an estimated gross revenue of £7500 and pays a tribute of £1551 as jointly to the British Government and the Nawab of Junāgarh. The family of the chief follow the rule of primogeniture in point of succession, no *sanad* authorizing adoption is held. Military force (1882-83), 296 men. Five schools, with a total of 336 pupils.

Sāyāla.—Chief town of Sāyāla State Kathiawar Bombay Presidency, situated in lat $22^{\circ} 32' N$ and long $71^{\circ} 31' E$ 15 miles south west of Wadhwan on the bank of a large tank called Manasarowar, the excavation and building of which is popularly attributed to Sidhraj Jarsingh, the celebrated sovereign of Anhilwār. Population (1881) 6158. Sāyāla is famous for the temple of Kīrtichandra built by Lalji Bhargat, a Banias' saint who flourished in the beginning of the present century. Food is distributed daily to travellers, ascetics and others. School dispensary, and post-office.

Sayyidābad.—Eastern *tehsil* of Muttra (Mathura) District North Western Provinces, situated in the fertile Doab portion of the District — *See* SADANAB.

Sayyidnagar.—Old and decayed town in Jālūn District, North Western Provinces. Distant from Lucknow 17 miles to the west and on the ruins of the *Itāwā*. Population (1881) 3157. Large exports of cloth, dyed red and yellow, considerable manufacture and dyeing of cotton. Police station, school. A small house tax is levied for police and conservancy purposes.

Sayyidpur.—Town in Faridpur District, Bengal, formerly on the Barásia river, but now two or three miles distant from the bank, in lat. $23^{\circ} 25' 10''$ N., and long. $89^{\circ} 43'$ E. The town, which in 1876 contained an estimated population of 6324, mainly supported by river traffic, had in 1881 only 3269 inhabitants. There is still a considerable import trade in cotton, spices, iron, copper, brass, and bell-metal utensils; but the rising mart of Boalmári, $2\frac{1}{2}$ miles to the south and on the river bank, has attracted most of the business formerly carried on at Sayyidpur, which is now a decaying town. Fine *sitalpáti* mats are made in the neighbourhood. The town was formerly a municipality, now (1883) abolished.

Sayyidpur.—Western *tahsil* of Gházipur District, North-Western Provinces; situated in the angle formed by the junction of the Gumti with the Ganges. The *tahsil*, which consists chiefly of low alluvial soil, comprises the three *pargánás* of Sayyidpur-Bhitári, Bahariábád, and Khánpur. Area, according to the latest official statement (1881), 249 square miles, of which 150 square miles were cultivated, 7 square miles cultivable, and 92 square miles uncultivable waste. Population (1881) 169,720, namely, males 85,603, and females 84,117; average density of population, 668 persons per square mile. Classified according to religion—Hindus, 157,178; Muhammadans, 12,529; and Christians, 13. Of the 554 villages comprising the *tahsil*, 448 contain less than five hundred inhabitants; 77 between five hundred and one thousand; and 29 between one and five thousand. Total Government land revenue, £22,616, or including local rates and cesses levied on land, £24,725. Rental paid by cultivators (including cesses), £39,341. In 1884, Sayyidpur Sub-division contained 1 civil and 2 criminal courts, with 2 police circles (*thánás*); strength of regular police, 27 men; rural police or village watch (*chaukidárs*), 231.

Sayyidpur (*Sayyidpur-Bhitári*).—Village and ruins in Gházipur District, North-Western Provinces, and head-quarters of Sayyidpur *tahsil*; lying in lat. $25^{\circ} 32' 5''$ N., and long. $83^{\circ} 15' 40''$ E., on the north bank of the Ganges, 20 miles west of Gházipur town. Population (1881) 2905. Government charitable dispensary. Chiefly noticeable for its numerous remains of Hindu or Buddhist origin, including a flat-roofed, richly carved, massive stone building, besides several fragments and entire figures of ancient sculpture. At Bhitri, 5 miles north-east of the town, stands a sandstone monolith, 28 feet in height, of which 5 or 6 feet are buried beneath the ground. It bears an inscription recording the achievements of five kings of the Gupta dynasty. A ruined bridge of three arches, built by the Muhammadans out of stones from Hindu structures, spans the river Gángi. A small house-tax is raised for police and conservancy purposes.

Sayyidpur.—*Táluk* of Rohri Sub-division, now included in Ghotki

Atuk, Shikarpur District, Sind, Bombay Presidency Area, 168 square miles The Census Report of 1881 returned Sayyidpur separate from Ghotki Population, 19,049, namely, males 10,185, and females 8864 Hindus number 7552, Muhammadans, 15,747, Sikhs, 481, and non Hindu aborigines 269—For other information see GHOTKI

Sayyid Sarāwān—Village in Chail *tahsil*, Allahābād District, North Western Provinces, 15 miles west of Allahābād city, and 2 miles west of the Munaufi station on the East Indian Railway lat $25^{\circ} 28' 48''$ N, long $81^{\circ} 40' 34''$ E. Population (1881) 3066 The principal inhabitants are Shaikh *amindars* Good Anglo-vernacular school

Sayyidwala—Village and municipality in Gugaira *tahsil*, in Montgomery District, Punjab and head quarters of a police circle, situated in lat. $31^{\circ} 6'$ N, and long $73^{\circ} 31'$ E on the north bank of the Ravi, 20 miles north east of Gugaira Population (1881) 3389 namely, Muhammadans 1940, Hindus, 1356 and Sikhs 93 Number of houses, 654 Municipal income (1883-84), £183, average incidence, 1s 1d per head The town, which is of purely local importance, is connected by road with Chinot It is a collection of brick and mud built houses, surrounded by a wall with four gates, with a single well paved street for a *1/2* m, police station, school house, and municipal committee house

Sealkote—District, *tahsil*, and town in the Punjab—See SIALKOT

Seberu (*Seeri*)—River in Madras Presidency—See SAIVARI

Secunderābād—*Tahsil* and town in Bulandshahr District, North Western Provinces—See SIKANDARABAD

Secunderābād (*Sikandarābād*, or 'Alexander's Town')—British military cantonment in the Native State of Haidarābād or the Nizam's Dominions, situated 6 miles north east of Haidarābād city, in lat. $17^{\circ} 26' 30''$ N, and long $78^{\circ} 33'$ E, at an elevation of 1830 feet above sea level Population (1881) 74,124 Secunderābād cantonment, named after Nizam Sikandar Jah is the largest military station in India, and forms the head-quarters of the Haidarābād Subsidiary Force, which constitutes a Division of the Madras army The military force stationed here in September 1885 consisted of one regiment of European and another of Native Cavalry, one battery of Royal Horse Artillery, three batteries of Royal Artillery (field and garrison) two regiments of British and four of Native Infantry, with two companies of Sappers and Miners An Ordnance Establishment has charge of the Arsenal, and there is also a large Commissariat Staff This force is maintained by the British Government, under the terms of a treaty with the Nizam dated 21st May 1853, in lieu of certain contingent and auxiliary forces which had been previously raised by the Nizam to co-operate with the British army, but had proved inefficient The cost of the force is

defrayed out of the revenues of certain Districts ceded by the Nizám under the treaty of May 1853, revised by a second treaty in 1860. (*See HAIDARABAD STATE.*)

Up to the year 1850, the cantonment of Secunderábád consisted of a line of barracks and huts, extending to a distance of 3 miles from east to west, with the artillery in the front and on the left flank, and the infantry on the right. Since that date, however, the cantonment boundaries have been extended as far as BOLARAM, covering a total area of 19 square miles, including many interspersed villages. New double-storied barracks have been erected for the European soldiers; and the quarters for the Native troops, which are situated at some distance, are also comfortably built.

The country for miles around undulates into hummocks, with outcrops of underlying rock, crossed from east to west by greenstone dikes. East of the cantonment are two large outbursts of granite; in the north-east is a granite hill known as Múl Alf, and near it another called Kadam Rasúl, from a legend that it bears an impress of Muhammad's foot. Shady trees line the roads of the cantonment, and near the European barracks and Native lines are clusters of date and palmyra palms. Otherwise the face of the country is bare, with but little depth of soil in the elevated parts. Cultivation is carried on in the dips and valleys, in several of which tanks have been constructed. The water-supply from wells is not abundant. Immediately to the south-west of the cantonment is a large artificial reservoir or tank, known as the Husain Ságar, about 3 miles in circumference.

The parade-ground is of great extent, upon which a force of seven or eight thousand troops can be manœuvred with ease. To the right are the public rooms. Close by is the cemetery. A little to the left of the rooms is the mud fort or battery containing some heavy pieces of ordnance. A detachment of artillery is stationed in the fort. A short distance from Secunderábád is the cantonment of Trimalgiri, containing an entrenched camp capable of accommodating all the Europeans in the neighbourhood.

The Haidarábád Subsidiary Force is not the sole military body in the neighbourhood. Adjoining the Secunderábád cantonment to the north is the Boláram cantonment, one of the stations of the Haidarábád Contingent under the immediate authority of the Nizám. The force stationed here consists of one regiment of cavalry, one of infantry, and a battery of artillery. Again, about 5 miles south of Secunderábád cantonment, are the lines of the Haidarábád Reformed Troops, also belonging to the Nizám, comprising artillery, cavalry, and infantry, under the command of a European officer. Altogether, within a space of 10 miles from north to south, about 8000 disciplined soldiers are cantoned.

Begampett and Bruenpili are a short distance west of Secunderabad. The pioneers are stationed at the first place, and a Madras cavalry regiment at the latter. During the Mutiny of 1857, an unsuccessful attempt was made to tamper with the fidelity of the troops at Secunderabad. An attack on the British Residency was repulsed, and during the troubled times of 1857-58 much good service was rendered by both the Subsidiary Force and the Haidarabad Contingent.

In the rainy season especially towards its close, the climate of Secunderabad is unhealthy, both for Europeans and natives. The rainfall varies greatly, during the thirty nine years ending 1881 it averaged 27.7 inches. The prevalent diseases are fevers, dysentery, and rheumatism.

Sebsaugor — District, Sub division, and town in Assam — See SIPSAGAR

Segauli — Town in Champarni District, Bengal, situated 15 miles from Mithauri, on the Bettia road, in lat. $26^{\circ} 46' 41''$ N., and long $84^{\circ} 47' 51''$ E. A military station, ordinarily occupied by a regiment of Native cavalry. An embankment protects the cantonment from inundation by the Sikkhená river, which flows a little distance to the north. In 1857, the main body of the 12th Regiment of Irregular Horse stationed here broke into open mutiny and murdered their commanding officer, though a detachment did good service during the subsequent operations in Oudh — (See Sir J. W. Kaye's *Hist. of the Sepoy War*, vol. III. pp. 102-107.)

Seghur (Sigur) Ghát — Mountain pass in the Nilgiri Hills District Madras Presidency, running down the north face of the hills from Mutinid to near the village of Seghur. Lat. $11^{\circ} 29'$ to $11^{\circ} 31' 40''$ N., and long $76^{\circ} 43' 30''$ to $76^{\circ} 43' 35''$ E. The head of the pass is distant from Uthakmand nearly five miles. The descent from the crest is about seven miles in length, but a little more than eight miles to the old bungalow at Seghur. About half way down is the village of Kallatt with its picturesque waterfall (170 feet) not far below. The pass, being practicable for laden carts and other wheeled conveyances, was the most frequented of all the Nilgiri gháts. At one time it was the favourite approach to the hills by the visitors from the northern parts of the Presidency and Madras. 'By this pass, says Harrold, 'communication is kept up with Bangalore, Madras and all places to the northward, and the chief bulk of European supplies, heavy baggage, horse grain, rice, &c., comes to the settlement by it.' It also affords the means of transit for the timber used on the hills in the form of rafters, planks, &c., the road passing near the forests where the trees are cut.' The corrected spelling is Sagar.

Sehi — Village in Chhitta Ghat, Murá (Murá) District, North Western Provinces, situated in lat. $27^{\circ} 40' 2''$ N., and long $77^{\circ} 41' 13''$ E.,

8 miles south-east of Chhátá, and 16 miles north of Muttra city. Population (1881) 2211. Two annual fairs are held here. The village is the property of the high priest of the great temple at Brindában.

Sehorá.—Village in Tirorá *tahsíl*, Bhandará District, Central Provinces. Population (1881) 2539, namely, Hindus, 2268; Muhammadans, 196; Jains, 5; and non-Hindu aborigines, 70.

Sehore.—Town in Bhopál State, Central India Agency; situated on the right bank of the Saven, in lat. $23^{\circ} 11' 55''$ N., and long. $77^{\circ} 7' 14''$ E., on the route from Ságar (Saugor) to Asírgarh, 132 miles south-west of the former place, and 152 north-east of the latter; distant from Bhopál city 22 miles south-west, and 90 miles from Mhow and Indore; from the latter place a good road is being constructed *viâ* Dewás and Sonkach. Sehore is the head-quarters of the Bhopál Political Agency and of the Bhopál Battalion, a local corps under the orders of the Government of India. Population (1881) of the town, 5206, namely, Hindus, 3000; Muhammadans, 2045; and 'others,' 161. Of the cantonment, 10,389, namely, males 5666, and females 4723. Hindus number 8055; Muhammadans, 2288; and 'others,' 46. Manufacture of printed muslins. Good *bázár*.

Sehwán.—Sub-division of Karáchi (Kurrachee) District, Sind, Bombay Presidency; lying between $25^{\circ} 13'$ and $26^{\circ} 56'$ N. lat., and between $67^{\circ} 10'$ and $68^{\circ} 29'$ E. long. Area, 5759 square miles. Population (1872) 162,836; (1881) 176,917. Bounded north by Mehar, a Sub-division of Shikárpur; east by the Indus; south by the Jerruck (Jhirak) Sub-division of Karáchi (Kurrachee) District; and west by the Khirthar and Pab Mountains. The administrative head-quarters are at KOTRI TOWN.

The Sub-division of Sehwán differs from the rest of Sind in being more hilly. It contains the only large lake in the Province, viz. the MANCHHAR, which, when fed by the waters of the Indus during the months of flood, attains a length of 20 miles and a breadth of 10 miles, covering a total area estimated at 180 square miles. The chief hills are the LAKI range, an offshoot from the Kirthar mountains; and the Jatil Hills. There are 37 Government canals in Sehwán, the principal being the WESTERN NARA, the ARAL, the PHITO, and the KARO. The Sub-division contains several hot springs. Game and fish of all kinds are abundant. The Government forests cover an area of 24,474 acres, and yielded in 1873-74 a revenue of £3185. The population of Sehwán in 1881 numbered 176,917, namely, males 96,426, and females 80,491, occupying 32,897 houses, in 6 towns and 210 villages. Hindus number 19,292; Muhammadans, 151,266; Sikhs, 5779; Christians, 465; non-Hindu aborigines, 87; Pársis, 21; Brahmos, 4; Jews, 3. The principal antiquities are the forts of SEHWAN and Rání-ka-kot. (*See* SANN.)

Agriculture—The Dādu and Schwān *Mulks* contain perhaps the finest wheat lands in the whole of Sind. Much cultivation is carried on in the neighbourhood of the Manchhar Lake, after the subsidence of the annual inundation. The principal crops are wheat, *jir* (*Sorghum vulgare*), cotton, barley, pulse, oil seeds, and vegetables. The prevailing tenure is *zamindari* about one-twelfth of the whole area is held in *jagir*, or revenue free. In 1882-83 the area assessed to land revenue was 205,392 acres the area under actual cultivation being 189,200 acres. A large transit trade is carried on in wool, cotton, dried fruits, etc. (See KARACHI TOWN). The local traffic consists of fish, mits, cloths, oil, *ghi*, and grain. The principal manufactures comprise carpets, coarse cotton cloth, rugs and mats. The aggregate length of roads in the Sub-division is about 450 miles, and the Sind, Punjab, and Delhi (Indus Valley State) Railway passes through its entire length. The number of ferries is 20, nearly all of which are on the Indus.

Administration—The total revenue of Schwān Sub-division in 1881-82 amounted to £62,871, of which £58,244 was derived from imperial and £4627 from local sources. The land tax, *akiri* (excise), and stamp duties formed the main items. Two subordinate civil courts, at Schwān and Kotri. Criminal courts, 12 police circles (*thands*), 39. Total number of police, 360, or 1 constable to every 491 of the population. Number of municipalities, 6, namely, Kotri, Schwān, Johi, Hubak, Dādu, and Manjhand. Aggregate municipal income (1883-84), £3039, incidence of taxation varying from 15 $\frac{1}{2}$ d to 25 $\frac{1}{2}$ d. Subsidiary jails at Kohistan and Kotri. Number of Government schools (1873-74), 22, with 972 pupils.

Climate—Average annual rainfall for 17 years ending 1881 registered at Schwān, 751 inches. Prevalent diseases, fevers and cholera. Hospital at Kotri, dispensary at Schwān.

Schwān—*Talik* in Schwān Sub-division, Karachi (Kurrachee) District, Sind, Bombay Presidency. Area 923 square miles. Population (1872) 54,292, (1881) 54,327, namely, males 29,082, and females 25,245, occupying 10,648 houses, in 2 towns and 74 villages. Hindus number 6762, Muhammadans, 46,186, Sikhs, 1324, Christians, 38, non Hindu aborigines, 9, Parsis, 4, and Brahmins, 4. Area assessed to land revenue (1882-83), 75,598 acres, area under actual cultivation, 65,601 acres. The *Mulk* contained in 1883 1 civil and 2 criminal courts, police circles (*thands*), 9, regular police, 122 men. Revenue, £12,232.

Schwān—Chief town of Schwān *Mulk*, Karachi (Kurrachee) District, Sind, Bombay Presidency, situated in lat. 26° 26' N., and long. 67° 54' E., on the main road from Kotri to Sukkur and Larkana, 84 miles north north west of Kotri, and 95 miles south south west of

Selu (*Sailu*)—Town in Wardha *taluk*, Wardha District Central Provinces, situated in lat $20^{\circ} 50' N$, and long $78^{\circ} 46' E$, on the Hori river, 11 miles north-east of Wardha town, and close to the old high road from Nagpur to Bombay. Population (1881) 2918, namely, Hindus, 2715, Kafirpanthis 27, Muhammadans, 165 and non Hindu aborigines, 11. Selu was an old Gond settlement, but the fort was built by a chief named Kandel Sardar. It was the scene of a skirmish between Hazi Bhojla and the Pindaris. Chief manufacture, cotton cloth, in which as well as in raw cotton much business takes place at the market held every Tuesday. *Saru* (native inn), police outpost, and vernacular school.

Sendamangalam—Town in Salem District, Madras Presidency—*See SHENDAMANGALAM*

Sendgarsa—High tableland in the Santal Parganas District, Bengal, overlooking the great central valley of the Rajmahal hills. Height, about 2000 feet.

Sendurjana.—Town in Amritoti District Berar about 60 miles north-east of Ellichpur. Population (1881) 8501, namely Hindus, 7546, Muhammadans 782. Jains 166 and 'others' 7. A very fine well, which was built by a former *shikdar* and is said to have cost £2000, is about a mile distant. The principal trade of the large market held on Fridays is in turmeric, cotton and opium. Government school and police outpost.

Senhâti—Town in Khulna District Bengal 4 miles north of Khulna, contains the largest collection of houses in the District, and perhaps the most jungly place in it. Population above 2000 but not returned separately in the Census Report of 1881. The numerous tanks scattered over the town are filled with weeds and mud and the roads, with one exception wind through tangles of brushwood. Market place, called Nimai Râi's *hat*, with a temple to Kâlî. One or two sugar refineries the produce of which is exported chiefly to Calcutta. On the banks of the river Bhurab are two shrines—one dedicated to Sîrî, goddess of small pox, and the other to Jivânâtrîan god of fever.

Sentapilli (*Sentapilly*)—Village and lighthouse in Vizianagaram District, Madras Presidency—*See CHANTAPILLI*

Seodivadar—Petty State in the Gohelwâr *princ* of Division of Kathiawar Bombay Presidency consisting of a village with a share holder or tribute payer. Area, 1 square mile. Population (1881) 246. Estimated revenue £97, of which £54 is paid as tribute to the Gohelwar of Broda, and 16s. to the Nawab of Junagarh.

Seonâth (or *Seo*)—River rising in lat $20^{\circ} 20' N$ long $80^{\circ} 43' E$, in the Lakhnâw Chiefship in Chind's Dohar Central Provinces. After leaving a hilly tract, it flows through Nardona *taluk* and the richer parts of Khatwar District, then turning to the east, forms a

some distance the boundary between Raipur and Bilaspur; and finally joins the Mahanadi at Devíghát. Its chief affluents are the Agar, Hámp, Maniári, Arpa, Kárún, and Lilágar.

Seondará.—Village in Bilári *tahsil*, Moradábád District, North-Western Provinces; situated in lat. $28^{\circ} 33' 45''$ N., and long. $78^{\circ} 54' 30''$ E. Population (1881) 3724. Bi-weekly market held on Thursdays and Sundays. Police station, school, and *sarái* or native inn.

Seonhra.—Town in Datia State of Bundelkhand, Central India Agency.—See SEORHA.

Seoní (*Seonce*).—A British District in the Chief Commissionership of the Central Provinces, lying between $21^{\circ} 36'$ and $22^{\circ} 58'$ N. lat., and between $79^{\circ} 14'$ and $80^{\circ} 19'$ E. long. Bounded on the north by Jabalpur, on the east by Mandlá and Bálághát, on the south by Bálághát, Nágpur, and Bhandará, and on the west by Narsinghpur and Chhindwára. Area, 3247 square miles. Population (1881) 334,733 souls. The administrative head-quarters are at SEONI TOWN.

Physical Aspects.—The District of Seoní occupies a portion of the Sát-pura table-land, which separates the valley of the Narbadá (Nerbudda), on the north, from the great plain of Nágpur, on the south. The greater part of the District consists of the plateaux of Lakhnádon and Seoní on the north and west, together with the valleys between; and of the watershed and elevated basin of the Waingangá river on the east. Almost everywhere the scenery presents the varied aspect of an upland country. Geologically, northern Seoní constitutes a part of the wide field of overflowing trap which occupies the area between the Pachmarhí hills westward and the Maikal range beyond Mandlá to the east. In the south, the formation consists of crystalline rock. Towards the western boundary, the metamorphic rocks, chiefly gneiss and micaceous schist, form the southern face of the hills which bound the Seoní plateau. Northwards, they are lost sight of in the bed of laterite which overlies this part of the plateau, and covers the trap to within a short distance of Seoní town. A few miles east of Seoní, the crystalline rocks again come to the surface; and from this point eastward, the valley of the Sagar constitutes the line of demarcation between the crystalline rocks and the trap.

The District is hilly throughout, but the physical features of the geological formations present a marked contrast. In the north the trap hills either take the shape of ridges with straight outlines and flattened tops, or, rising more gradually, expand into wide undulating plateaux. The valleys are wide and bare, and contain the rich black soil formed by disintegrated trap, spread over a deep deposit of calcareous clay; while the intersecting streams, as they cut through the clay, expose broad masses of bare black basalt, alternating with marshy and stagnant pools. In the southern portion of the District, the hills are more

pointed, the valleys more confined, and the soil, even where it is rich contains a large admixture of sand. Seoni must at one time have abounded with timber. At present the northern hills have much teak, but of an inferior and stunted growth. Along the Wainganga a few patches of young teak are found, the vast bamboo forest of Sonáwani, in the south-east corner of the District, contains fine *Elea* and *tendu* while to the north some large *shy* grows upon the hills. The reserved forests consist of the great firewood reserve for Kāmthi and Nagpur, covering 315 square miles.

The chief river of the District is the Waingangi, which rises a few miles east of the Nagpur and Jabalpur road, near the Kurai Ghāt, and soon afterwards, turning to the south, forms the boundary between Seoni and Bilāghāt Districts. Its affluents are the Hiri and Sagar on the right bank, the Theli, Nijā, and Thānwar on the left. Besides these streams, the Timar and the Sher flow northwards to the Narbādī, and on the west, the Pench for some distance separates Seoni from Chhindwāra. The Nagpur and Jabalpur road crosses the Sher at Sonai Dongri, where a fine stone bridge spans the river. The general slope of the country is from east to west. The elevation of the Seoni and Lakhnādon plateaux varies from 1800 to 2200 feet above sea level.

Iron is found at several places in Seoni District, but is only worked at Jutāma near Pipwāni, as since the introduction of the system of Forest Conservancy, charcoal cannot be obtained at a sufficiently low rate. Gold is found in many of the smaller streams and their affluents, and is occasionally washed for by an aboriginal tribe called Mundias or locally in Seoni District, Songriās.

History—About the 5th century of our era, a dynasty of conquerors appears to have reigned on the Sitpura tableland. Some grants of territory inscribed on copper plates found in Seoni an inscription in the Zodiac cave at Ajintā and a few passages in the *Purānas*, dimly disclose a line of princes sprung from one Vindhya sakti. This mythical hero seems to be the eponymous monarch of the Vindhyan Hills, in which designation the *Purānas* include the Sitpura range. But the history proper of Seoni begins with the reign of Rājā Singrām Sā of Gurhā-Mandlā, who in 1530 extended his dominion over fifty-two chiefships three of which—Ghansor, Chauri, and Dongartāl—form the greater part of the present District. Nearly two centuries later, Narendrā Sā, the Rājā of Mandlā, conferred these tracts on Bakht Buland, the famous prince of Deorash in acknowledgment of his assistance in suppressing a revolt. Bakht Buland placed his kinsman Rājā Rām Singh in possession of the Seoni tableland, and the latter built a fort at Chhipard and established his headquarters in that town. Soon afterwards, Bakht Buland made a progress through the District, and planned to make the acquaintance of Taj

Khán, a Muhammadan adventurer. The bravery of Táj Khán in killing a bear single-handed first attracted the attention and won the favour of the Deogarh monarch ; and it was at the instigation, and in the name of Bakht Buland, that Táj Khán attacked and took Sângarhí in Bhandára District.

In 1743, Raghuji, the Maráthá Rájá of Nágpur, finally overthrew the dynasty of Deogarh ; but Muhammad Khán, who had succeeded his father, Táj Khán, at Sângarhí, refused to recognise the conqueror, and held out against the Maráthás for three years. Admiring his conduct, Raghuji offered him Seoní District if he would give up Sângarhí. Muhammad Khán consented ; and repaired to Chhapára, whence he governed Seoní, with the title of Díwán. One serious reverse chequered a fortunate and successful reign when, during the absence of Muhammad Khán at Nágpur, the Rájá of Mandlá attacked and captured Chhapára. The square tomb which still stands in the ruined fort covers the large pit in which all those slain in the assault were buried. The Díwán, however, speedily advanced from Nágpur with a large force, and recovered his capital ; and the Thánwar and Gangá rivers were again declared to be the boundaries between Seoní and the Mandlá kingdom.

Majíd Khán, the eldest son of Muhammad Khán, succeeded in 1761 ; and was followed in 1774 by his son Muhammad Amín Khán, who removed his head-quarters to Seoní, where he built the present family residence. After a prosperous reign of twenty-four years, he was succeeded by his eldest son, Muhammad Zamán Khán. The weakness of the new ruler proved disastrous both to the country and the dynasty. Chhapára, which, though no longer the capital, was still a large and flourishing city, with a population, it is said, of 40,000, was sacked and utterly ruined by the Pindáris ; and soon afterwards, perceiving the incompetence of the Díwán, and anxious to compensate by fresh acquisitions for their cession of Berar to the British in 1804, the Maráthás ejected Muhammad Zamán Khán. Raghuji then sold the government of the District for £30,000 per annum to Kharak Bhártí, a Gosáin. Eventually, with the downfall of the Nágpur power, Seoní came under British rule, and since then has remained undisturbed. The District contains but few architectural remains. At Umargarh, Bhainságarh, Partápgarh, and Kanhágarh, all situated on commanding spots along the southern margin of the Sátpuras, stand ruined forts attributed by tradition to the Bundelá Rájás. Of these, the Bhainságarh fort is in the least imperfect condition. Two old Gond forts also remain,—one in the Sonwára forest, near Ashta ; the other near Uglí, on a well-nigh inaccessible rock in the bed of the Hirí river. At Ghansor, 20 miles north-east of Seoní town, the ruins of about 40 temples seem to indicate the former existence of a large town. Some

of the plinths are still in their place, and are attributed to a caste of Hindus from the Deccan called Hemápanthis.

Population—A rough enumeration in 1866 returned the population of Seoni at 421,750, but on a much larger area than the present District. The Census of 1872 disclosed a population, in the District as at present constituted, of 300,558. The last Census in 1881 returned a total of 334,733 inhabitants, showing an increase of 34,175, or 11.37 per cent., in nine years, of which 9.6 per cent represents the natural increase of registered births over registered deaths, and the remainder the gain by immigration from neighbouring Districts.

The results of the Census of 1881 may be summarized as follows—Area of District, 3247 square miles, with 1 town and 1462 villages. Number of houses, 72,349, namely, 67,104 occupied, and 5245 unoccupied. Total population, 334,733, namely, males 167,925, and females 166,808. Average density of population, 103.1 persons per square mile. Villages per square mile, 0.45, persons per village, 229, houses per square mile, 20.67, persons per occupied house 5. Classified according to sex and age, the Census returns—under 15 years, males 72,384, and females 69,430. total children, 141,814, or 42.4 per cent. of the population. 15 years and upwards, males 95,541, and females 97,378, total adults, 192,919 or 57.6 per cent.

Religion—Hindus number 179,705, or 53.7 per cent. of the population, Muhammadans, 13,442, or 4 per cent., Jains 1408, Kabírpánthis, 598, Satnámis, 9, Sikhs, 25. Christians 99. Pársis, 3, and non Hindu aboriginal tribes, 139,441 or 41.7 per cent. The total number of aboriginal tribes, Hindu and non Hindu, was returned at 145,995, of whom 145,014 were Gonds.

Among the higher Hindu castes, Brahmans number 6160, Rájputs, 8958, Baniyas, 2600, and Káyasths, 1324. The lower or Súdri castes include the following—Ahír, the most numerous caste in the District, 26,674, Mehá, 17,919, Ponwár, 15,071, Mará, 9746, Katiyá, 7448, Kurmi, 7303, Ich, 6140, Gawá, 5161, Lolá, 4817, Dhimá, 4815, Lodhí, 4209, Kallá, 4065. Chamá, 3819, Ná, 3635, Kúár, 2746, Soná, 2525, Dhobí, 2512, Banjará, 2111, and Kichhí, 1806. The Muhammadan population are divided according to sect into—Sunnis, 12,612, Shias, 333. Wahábis, 36, and unspecified, 461. The Christian population comprises—Europeans, 15, Eurasians, 7, Indo Portuguese, 3, and Natives, 74.

Urban and Rural Population—Seoni town, with a population (1881) of 10,203, is the only place in the District with upwards of five thousand inhabitants, and is the sole municipality. Of the 1462 villages, 866 contain less than two hundred inhabitants, 495 between two and five hundred, 89 between five hundred and a thousand, and 12 between one thousand and three thousand. As regards occupation,

the Census divides the male population into the following six classes:— (1) Professional class, including civil and military, 7,300; (2) domestic class, 1009; (3) commercial class, including merchants, traders, carriers, etc., 1830; (4) agricultural and pastoral class, including gardeners, 83,536; (5) manufacturing and industrial class, including artisans, 17,378; (6) indefinite and non-productive class, comprising general labourers and male children, 60,452.

Agriculture.—Of the total area of 3047 square miles, only 1098 square miles were cultivated in 1883-84; and of the portion lying waste, 613 square miles were returned as cultivable, and 1536 square miles as uncultivable waste. The total area assessed for Government revenue is 2276 square miles, of which 984 square miles are cultivated, 596 square miles are cultivable, and 696 square miles are uncultivable waste. Wheat forms the chief crop of the District, and is grown year after year on the rich black soil of the plateaux in the north and west. In 1883-84, it occupied 265,913 acres; while 388,217 acres were devoted to other food-grains. The rice land of the District lies in the south. In 1883, rice was grown on 169,185 acres. Other products were—sugar-cane, 778 acres; cotton, 6594 acres; and other fibres, 2214 acres. The *Adz* grass, which yields an oil like the *ajépa* and the *bakni* (*Terminalia bellerica*), *Arnd* (*Terminalia chebula*), and *manji* (*Rubia munjeeta*), plants which supply valuable dyes, abound in the District. The average out-turn per acre in 1883 is returned as follows:—Wheat, 744 lbs.; inferior grains, 865 lbs.; rice, 555 lbs.; sugar, 1040 lbs.; cotton, 52 lbs.; oil-seeds, 147 lbs. The agricultural stock and implements in 1883-84 were thus returned—Cows, bullocks, and buffaloes, 279,735; horses, 297; ponies, 7032; donkeys, 306; sheep and goats, 22,183; pigs, 12,823; carts, 9611; and ploughs, 32,315.

Of the total male and female agricultural population in 1881, landed proprietors were returned as numbering 2894; tenants with occupancy rights, 21,767; tenants-at-will, 46,602; assistants in home cultivation, 13,879; and agricultural labourers, 50,710. Estate agents, farm-bailiffs, shepherds, herdsmen, etc., bring up the total agricultural population to 141,944, or 42·4 per cent. of the District population; average area of cultivated and cultivable land per head, 8 acres. The rent rates per acre in 1883 for the different qualities of land are returned as follows:—Land suited for wheat, 2s. 7½d.; inferior grains, 1s. 7½d.; rice, 2s. 3d.; cotton, 1s. 11½d.; sugar-cane, 4s. 3d.; cotton, 3s. 10½d. Total amount of Government assessment, including local rates and cesses levied on the land, £16,336, or 6¼d. per cultivated acre. Total rental paid by cultivators, £48,012, or 1s. 6d. per cultivated acre. The ordinary prices of produce per cwt. were as follows:—Wheat, 4s. 1d.; rice, 6s. 10d.; sugar (*gúr*), 12s. 3d.; cotton

(cleared), 45s 6d Wages averaged, for skilled labour, 1s., for unskilled labour, 3^d per diem

Commerce and Trade—The trade of the District is chiefly carried on by means of markets in the towns. The most important are those held at Burghat, Korai, and Piprawani, to which the grain of the rice producing tract in the south is brought for export to Nagpur and Kāmthi (Kamptee). Three annual fairs take place in the District—namely, at Mundāri, close to Seoni town at the source of the Waingangā, at Surdikhā at the junction of the Hurl and Waingangā, and at Chhapāri. The first two are primarily religious gatherings, but a large business is done in general merchandise, by traders from Seoni, Mandlā, Jabalpur, and Nagpur. The last is a cattle fair, at which some 70,000 head of cattle change hands annually. The imports and exports are both insignificant, but the through traffic between Nagpur and Bhandāra and the north causes some degree of business. The manufactures consist of coarse cloth, and some pottery of superior quality made at Kānhiwāri. At Khawāsa, in the midst of the forest, leather is beautifully tanned. The chief line of communication is the high road from Nagpur to Jabalpur, which enters the District near Khawāsa, and, passing by Seoni town, crosses the border into Jabalpur District near Dhūmā. It has travellers bungalows at Kurli, Chhapāri, and Dhūmā. A District road with American platform bridges runs from Seoni through Katangi, to join the Great Eastern Road. The other lines consist of mere bullock tracks, leading to various points in Bilāghat and Nagpur Districts. Seoni has no means of communication by water or by rail.

Administration—In 1861, Seoni was formed into a separate District of the British Government of the Central Provinces. It is administered by a Deputy Commissioner, with Assistants and *tehsildars*. Total revenue in 1876-77, £25,567, and in 1883-84 £35,419 of which £15,379 was derived from the land tax. Total cost of District officials and police of all kinds (1883-84), £7547. Number of civil and revenue judges of all sorts within the District, 6, magistrates, 5. Maximum distance from any village to the nearest court, 45 miles. Average distance, 24 miles. Number of regular and town police 317 men, costing £4621, being 1 policeman to about every 1034 square miles and to every 1066 inhabitants. The daily average number of convicts in jail in 1883 was 72, of whom 6 were females. The total cost of the jails in that year was £473. The number of Government-aided schools in the District under Government inspection was 39 attended by 2255 pupils. The Census Report of 1881 returned 1896 boys and 218 girls as under instruction, besides 3247 males and 126 females able to read and write, but not under instruction.

Medical Aspects—The people enjoy a respectable and healthy climate.

The average mean temperature at Seoní town for a period of ten years ending 1881 was returned at 74.4° F., the average monthly means being as follows:—January, 63.6° ; February, 68.6° ; March, 76.9° ; April, 84.1° ; May, 87.6° ; June, 82.7° ; July, 76.3° ; August, 75.6° ; September, 76.0° ; October, 72.6° ; November, 66.3° ; December, 62.9° . In May 1883, the maximum temperature registered was 111.2° , and the minimum 67.7° ; July, maximum 88.9° , minimum 68.0° ; December, maximum 80.8° , minimum 41.7° . The average annual rainfall for a period spread over 25 years is returned at 49.47 inches—namely, 3.76 inches from January to May; 42.83 inches from June to September; and 2.88 inches from October to December. In 1883, 59.9 inches of rain fell, or 10 inches beyond the average, the excess being solely in the monsoon months, June to September. The prevailing disease is fever, which proves most dangerous during the months succeeding the rains. In 1883, two charitable dispensaries, at Seoní and Lakhnádón, afforded medical relief to 17,865 in-door and out-door patients. The number of registered deaths in 1883 was 9183, equal to a death-rate of 28.43 per thousand, of which 22.62 per thousand were assigned to fever. The average death-rate for the previous five years is returned at 32.13 per thousand. [For further information regarding Seoní, see *The Central Provinces Gazetteer*, by Mr. (now Sir Charles) Grant, pp. 468–476 (Nágpur, 1870). Also the *Settlement Report of Seoní District*, by Captain W. B. Thomson, between 1854–1866, published in 1867; the *Central Provinces Census Report* for 1881; and the several annual Administration and Departmental Reports of the Central Provinces Government.]

Seoní.—South-western *tahsil* or Sub-division of Seoní District, Central Provinces, lying between $21^{\circ} 33'$ and $22^{\circ} 27'$ N. lat., and between $79^{\circ} 27'$ and $80^{\circ} 6'$ E. long. Area, 1664 square miles, with 1 town and 692 villages, and 38,500 houses. Population (1881) 196,017, namely, males 97,761, and females 98,256; average density of population, 117.8 persons per square mile. The adult agricultural population (male and female) numbers 85,390, or 43.56 per cent. of the total population of the Sub-division; average area of cultivated and cultivable land available for each adult agriculturist, 6 acres. Of the total area of the *tahsil* (1664 square miles), 489 square miles are held revenue-free. The Government assessed area amounts to 1175 square miles, of which 550 square miles are cultivated, 224 square miles are cultivable, and 401 square miles uncultivable waste. Total amount of Government assessment, including rates and cesses levied on the land, £9414, or an average of $6\frac{1}{2}$ d. per cultivated acre. Total rental paid by cultivators, £28,706, or an average of 1s. $7\frac{2}{3}$ d. per cultivated acre. In 1884, Seoní *tahsil* contained 4 civil and 3 criminal courts, with 5 police stations (*thánás*) and 8 outpost stations; strength of regular police, 132 men; rural police or village watch (*chaukidárs*), 736.

Seoni—Principal town and administrative head quarters of Seoni District, Central Provinces, situated in lat $22^{\circ} 5' 30''$ N, and long $79^{\circ} 35'$ E, on the road from Nagpur to Jabalpur, nearly half way between the two places. Population (1881) 10,203, namely, males 4917, and females 5256. Hindus number 6392, Muhammadans, 2803, Jain, 477, Kāfirpanthīs, 14, Satnāmīs, 9, Christians, 90, Pārsīs, 2, and non-Hindu aboriginal tribes, 416. Municipal income (1883-84), £1878, of which £1642 was derived from taxation, average incidence of taxation, 3s 2d per head. Founded in 1774 by Muhammad Amin Khān, who made it his head quarters instead of Chhapāri. Seoni

moderate

Seoni—Central *tahsil* or Sub division of Hoshangābād District, Central Provinces. Area, 491 square miles, with 1 town and 151 villages, and 12,085 houses. Population (1881) 53,865, namely, males 27,368, and females 26,497, average density of population, 109.7 persons per square mile. The adult agricultural population (male and female) numbers 16,476, or 30.59 per cent. of the total population of the Sub division, average area of cultivated and cultivable land available for each adult agriculturist, 11 acres. Of the total area of the *tahsil* (491 square miles) 169 square miles are held revenue free. The Government assessed area amounts to 322 square miles, of which 181 square miles are cultivated, 89 square miles are cultivable, and 52 square miles are uncultivable waste. Total amount of Government assessment, including local rates and cesses levied on the land, £6579, or an average of 15.1½ p per cultivated acre. Total rental paid by cultivators, £17,088, or an average of 25.10½ p per cultivated acre. In 1884 Seoni *tahsil* contained 2 civil courts, with 1 police station (*tharfi*) and 3 outpost stations (*chakris*), strength of regular police, 40 men, there are no rural police or village watch (*chakridars*).

Seoni—Town and municipality in Hoshangābād District, Central Provinces, situated in lat $22^{\circ} 28'$ N, and long $77^{\circ} 29'$ E, on the high road to Bombay. Population (1881) 6998, namely, Hindus, 5427, Muhammadans, 1235, Jains, 147, Kāfirpanthīs, 37, Christians, 4, and non-Hindu aboriginal tribes, 144. Municipal income (1882-83) £1818, of which £1342 was derived from taxation, average incidence of taxation, 3s 10d per head. Of the town or *tharfi* in the town of Akbar, no remains exist. The present town dates from the conquest of the country by Rājahūji Bhonsla about 1750, when a fort was built where an Amil resided. A detachment of British troops from Hoshangābād took the fort in 1818. Seoni is perhaps the chief manufacturing town in the whole Nagbād (Nerbudda) valley, being the centre of the iron

the cotton of Bhopál and Narsinghpur, as well as of Hoshangábád, is exported to Bombay. Grain is the other export. Imports—English cotton fabrics, spices, and metals. The Great Indian Peninsula Railway has a station at Seoní, and a *sardí* (native inn) has been built.

Seoníband.—Artificial lake in Bhandará District, Central Provinces; situated in lat. 21° N., and long. $80^{\circ} 2'$ E., 8 miles north-west of the Nawegáon tank; about 8 miles in circumference; average depth, 30 feet; length of embankment, 630 feet. Constructed before 1550 by Dádú Patel Kohrí, whose family held Seoní village for about 250 years. In the time of Raghují I., the village was granted to Báká Báí, whose descendants still own it.

Seopur (*Sheopur*).—Town in Gwalior State, Central India Agency; situated in lat. $25^{\circ} 39'$ N., and long. $76^{\circ} 41' 15''$ E., near the western boundary of the State. According to Thornton, it was formerly the capital of a small Rájput principality, but in the early part of the present century was subjugated by the forces of Daulat Ráo Sindhia. 'In 1816, when garrisoned by Sindhia's general, Baptiste, with 200 men, it was surprised and taken by escalade by the celebrated Rájput chief Jai Singh, who had only 60 men. The captor seized a large amount of treasure, and made the family of Baptiste prisoners.'

Seoráj.—Tract of country in Kángra District, Punjab; forming part of the Kúlu Sub-division, and lying between $31^{\circ} 20' 30''$ and $31^{\circ} 54' 30''$ N. lat., and between $77^{\circ} 14'$ and $77^{\circ} 43'$ E. long. Area, 575 square miles. This tract occupies the block of land between the Sainj and the Sutlej (Satlaj). The Jalori or Suket range, an offshoot of the Mid-Himálayan system, divides it into two portions, known as Outer and Inner Seoráj. The greater part of the surface is covered with forests of *deodar* and other trees; but the narrow river valleys present occasional patches of careful cultivation, interspersed with picturesque villages of wooden houses, often highly carved in a rough but effective style, and resembling Swiss *châlets*. Most of the cultivation, however, is conducted on the hill-sides. The custom of polyandry is prevalent.

Seorha.—Town in Datia State, Bundelkhand, Central India Agency; situated 36 miles east of Morár, and 40 miles north-east of Datia town. Population (1881) 7988, namely, Hindus, 6884; Muhammadans, 1102; and 'others,' 2.

Seorí Náráyan.—Eastern *tahsíl* or Sub-division of Biláspur District, Central Provinces. Area, 1415 square miles, with 788 villages and 71,078 houses. Population (1881) 276,590, namely, males 136,832, and females 139,758; average density of population, 195 persons per square mile. Of the total area of the *tahsíl*, 1415 square miles, 166 square miles are held revenue-free, while 348 square miles comprise the four *samíndáris* of Chápá, Katangi, Biláigarh, and Bhátgáon, which pay

only a nominal quit rent or *feshlash*. The lands subject to regular assessment cover an area of 899 square miles, of which 505 square miles are cultivated, 343 square miles are cultivable, and 51 square miles uncultivable waste. Total Government land revenue, including local rates and cesses levied on land, £6469, or an average of 4½d per cultivated acre. Rental paid by cultivators, £11,804, or an average of 8½d per cultivated acre. In 1884 the Sub-division contained 1 criminal and 1 civil court, with 3 police stations (*stints*) and 7 outpost stations (*stanks*), strength of regular police, 66 men, village watch or rural police (*chaulidars*), 706.

Seori Nārāyan — Town in Bilaspur District, Central Provinces, situated in lat. 21° 43' N., and long. 82° 39' E., 39 miles east of Bilaspur town, on the Mahanadi river. Population (1881) 2250, namely, Hindus, 2009, Khatris, 79, Muhammadans 127, non-Hindu aboriginal tribes 26, and 'others, 9. The temple to Nārāyan (whence the name) appears, from an inscription on a tablet to have been built about 841 A.D. It has no architectural merit. The town was once a favourite residence of the Katanpur Court. In the rains, the Mahanadi at this point forms a fine river, navigable by large boats from Sambalpur, and even at other times, its channel retains a considerable depth of water. An important religious fair is held every February.

Seota.—Town in Bilaspur District (Oudh) situated 32 miles east of Bilaspur town, between the Chauki and Gogra rivers. Founded by Alha, a Chandel Thakur, a *protégé* of Raja Jai Chand of Kanauj, who granted to Alha possession of all the surrounding tract known as Gānjār. The town contains a school, the ruins of a mosque, and an old *tilkhar's* fort. Good *tilkhar's* and annual fair. Population (1881) 3443.

Sera.—Ancient name for the Southern Division of Stravda, the present Madras Presidency.—*See CHITRA*.

Serājgunge—Sub-division and town of Pabna District, Bengal.—*See SIKAJGANG*.

Serampur (*Srirampur*)—Sub-division of Hooghly District, Bengal, lying between 22° 39' and 22° 55' N. lat., and between 88° and 88° 27' E. long. Area, 343 square miles, number of towns 5 and of villages 764, number of houses, 88,701, of which 7864 are unoccupied. Total population (1881) 351,955, namely, males 174,366, and females 177,589. Hindus number 292,174, Muhammadans, 59,098, Christians, 365, Buddhists, 288, Brahmans, 3, and Santals, 27. Average density of population, 1026 persons per square mile, villages per square mile, 2.24, persons per village, 457, houses per square mile, 259, persons per house, 4.3. This Sub-division comprises the 5 police circles of Serampur, Haridol, Krishnanagar, Singur, and Chardola. In 1884 it contained 3 civil and 9 criminal courts, strength of regular police, 293 men, rural police or village watch (*stint dars*) 1254.

Serampur (*Srīrámpur*).—Chief town and head-quarters of Serampur Sub-division, Huglí District, Bengal; situated on the west bank of the Huglí river, opposite Barrackpur, in lat. $22^{\circ} 45' 26''$ N., and long. $88^{\circ} 23' 10''$ E. Population (1881) 25,559, namely, males 13,137, and females 12,422. Hindus number 22,800; Muhammadans, 2461; and 'others,' 298. Serampur is a first-class municipality, with an income (1883-84) of £4210, of which £3353 was derived from taxation; average incidence of taxation, 1s. $5\frac{1}{4}$ d. per head of the population (27,520) within municipal limits. The municipality includes several neighbouring hamlets; 41 metalled and 36 unmetalled roads run through the town. Serampur was formerly a Danish settlement, and remained so until 1845, when all the Danish possessions in India were ceded by treaty to the East India Company on payment of £125,000. Station on the East Indian Railway, 13 miles distant from Calcutta (Howrah station). Serampur is historically famous as the scene of the labours of the Baptist missionaries, Carey, Marshman, and Ward; the mission still flourishes, and its founders have established a church, school, college, and noble library in connection with it; there is also a dispensary here. *The Friend of India*, a weekly paper formerly published at Serampur, but now at Calcutta, once rendered this town conspicuous in the history of Indian journalism. Chief manufactures, paper and mats.

Sergada.—*Zamíndári* estate in GanjáM District, Madras Presidency. Area, 25 square miles. Population (1881) 11,562, namely, males 5762, and females 5800, occupying 1992 houses in 35 villages. Hindus number 11,554, and Muhammadans 8, dwelling in the chief village of the estate. The estate yields fine crops of rice. Traversed by the Aska-Ichapur high-road. The annual *peshkash*, or fixed Government quit-rent, is £582; rental value to the *zamíndár*, £3479. Chief village, Sergadakota; population (1881) 2056, occupying 397 houses.

Seringapatam (*Srīrángapatnam*).—The old capital of the State of Mysore; situated on an island of the same name in the Káveri (Cauvery), 75 miles south-east by road from Bangalore, and 10 miles north-east of Mysore city. Lat. $12^{\circ} 25' 33''$ N., long. $76^{\circ} 43' 8''$ E. Population (1881), including the suburb of GANJAM, 11,734, namely, males 5579, and females 6155. Hindus number 9789; Muhammadans, 1768; and Christians, 177. Municipal revenue (1874-75), £1048; rate of taxation, 2s. per head. Since the rendition of Mysore State, later municipal statistics are not available.

History.—The name is derived from *Srī Ranga*, one of the forms of the god Vishnu, who is worshipped by the same title on two other islands lower down the Káveri, SIVASAMUDRAM and SRIRANGAM; but his temple here takes first rank of the three, as *Adi Ranga*. Local

legend relates that Gautama Buddha himself worshipped at this shrine. According to a Tamil MS., preserved in the Mackenzie collection, the site had become overgrown with jungle, and the temple was rebuilt in 894 A.D., during the reign of the last Chinga sovereign. In 1133, the Vishnuite apostle Ramanuja received a grant of the island, with the surrounding country, from a king of the Pallava dynasty. The fort is said to have been founded in 1454 by a descendant of one of the local officers or *hebbirs* appointed by Ramanuja. Seringapatam first appears in authentic history as the capital of the viceroys of the distant Hindu emperors of Vijayanagar, who took the title of Srirangarajal. Irumala, the last of these viceroys, surrendered in 1610 to Raju Wodeyar, the representative of the rising house of Mysore. Hence forth Seringapatam remained the seat of Government until the downfall of Tipu Sultan in 1799.

The existing fortifications were almost entirely constructed by Tipu who thrice sustained a siege from British armies. In 1791, Lord Cornwallis, the Governor General, commanding in person advanced up to the walls, but was compelled to retire through want of provisions. In the following year he won a decisive victory in the field, and had invested the city on all sides, when Tipu purchased peace by the cession of half his dominions. Finally, in 1799 the fort was stormed by General Harris, and Tipu fell in the breach. The siege was begun in April of that year with a powerful battering train, and the assault was delivered after a bombardment of nearly one month's duration. The spot selected for breaching was in the wall facing the River, for the defences were weakest on that side, and the river was at that season of the year easily fordable. After the capture the island of Srirangapatam was ceded to the British Government who leased it to the State of Mysore for an annual rent of £5000. At the rendition of Mysore State in 1881, it was made over free.

When the residence of the restored Raja was removed to Mysore city in 1800, Seringapatam immediately fell into decay. Dr Buchanan Hamilton, who visited the place in 1800 returned the population at 31,595 souls, as compared with 150,000 when Tipu Sultan was at the height of his power. An outbreak of epidemic fever accompanied this depopulation, and in 1811 the British military headquarters were removed to Bangalore. At the present day, the ruins of Seringapatam are almost deserted and the place bears such a bad name for malaria, that no European traveller dare sleep on the island. The natives attribute this climate of disease to the desertion of the sweet flag, a plant to which they ascribe extraordinary virtues as a febrifuge. The suburb of Gajpet, said to have been established by Tipu with the deserted military stores of Srirangapatam as a magazine, and crowded fairs are held there twice in the year.

General Description.—The island of Seringapatam is about 3 miles in length from east to west, and 1 mile in breadth. The fort stands at its upper or western end, immediately overhanging the river. The plan is that of an irregular pentagon, with an extreme diameter of $1\frac{1}{2}$ mile. The defences, which were laid out by Tipú himself, are imposing for their massiveness, though not constructed on scientific principles. They consist of wall piled upon wall, and cavalier behind cavalier, the chief characteristic being the deep ditches cut through the solid granite. The whole remains in almost precisely the same condition as it was left after the siege, even to the breaches, except that a luxuriant growth of trees has been allowed to spring up.

The spot where the English batteries were planted is now marked by two cannons stuck upright in the ground. Inside the fort are the ruins of Tipú's palace, now partly occupied as a storehouse for sandal-wood; the old temple of Rānga-nātha-swāmi; the Jamá Masjid, a tall mosque with two minarets, built by Tipú shortly before his death; and a few traces of the palace of the early Hindu rulers. Just outside the walls is the Dariya Daulat Bāgh, or 'garden of the wealth of the sea,' a building (now falling to decay) of graceful proportions, handsomely decorated with arabesque work in rich colours. It was erected by Tipú for a summer retreat, and contains the celebrated pictures representing the defeat of Baillie at CONJEVARAM in 1780, which, after being twice defaced, were finally restored by the express orders of Lord Dalhousie when Governor-General.

At the eastern or lower end of the island, near the suburb of Ganjām, is the Lál Bāgh or 'red garden,' containing the mausoleum built by Tipú Sultán for his father Haidar Alí, in which he himself lies, by his father's side. This is a square building, with dome and minarets, surrounded by a corridor which is supported by pillars of black hornblende. The double doors, inlaid with ivory, were the gift of Lord Dalhousie. The inscription on the tombstone of Tipú relates how he died a martyr to Islām, and at the same time indicates by the initial letters the date of his death. Each of the two tombs is covered with a crimson pall, and the expenses of the place are defrayed by Government. The island of Seringapatam yields valuable crops of rice and sugar-cane, which are watered from a canal originally constructed by Tipú, and brought across from the mainland by an aqueduct.

Seringham.—Town and famous temple in Trichinopoli District, Madras Presidency.—See SRIRANGAM.

Sesa.—River in the south of Lakhimpur District, Assam, which rises in a marsh near the village of Bājaltali, and, flowing south-west in a very circuitous course, empties itself into the Buri Dihing near its junction with the Brahmaputra. During the rainy season, the Sesa is navigable by canoes for a considerable distance.

Sesháchalam.—Hill range in Cuddapah (Kadapa) District, Madras Presidency, an offshoot of the Palkonda Hills, skirting the east and north-east of the District. Lat. $14^{\circ} 12'$ to $14^{\circ} 35' N$, long $78^{\circ} 1' 30''$ to $78^{\circ} 56'$ E. The hills are uniform in appearance, and rise from 1200 to 1800 feet above the level of the sea. There are no isolated peaks. The Sesháchalam Hills strike off in a westerly direction from the Palkonda range at a point about 15 miles south of the Penner (Ponnaiyár) river. In some parts they are clothed with rich forests, and the scenery is very beautiful.—*See also* PALKONDA.

Settipattalai (or *Tirupatti, Trijdi*)—Town in Cuddalore *Muk*, South Arcot District, Madras Presidency. Lat. $11^{\circ} 46' N$, long $79^{\circ} 36' 35'' E$, 15 miles west of Fort St David. Population (1881) 4566, namely, Hindus, 4273, Muhammadans, 284, and Christians, 9. Number of houses, 569. Except as the seat of a sub-magistrate, Settipattalai is now of no importance, but it was the scene of frequent fighting during the Karnatik wars of the last century. The French occupied it in 1850, Lawrence captured it in 1752. In the following year it was three times attacked by the French, the third time successfully. In 1760, it again fell into the hands of the English.

Settur—Town in Srivillipatur *Muk*, Tinnevely District, Madras Presidency. Lat. $9^{\circ} 26' N$, long $77^{\circ} 31' 20'' E$. Population (1881) 6443 occupying 1449 houses. Hindus number 6300, Muhammadans, 90, and Christians, 53. The *samirddar* is of the Maravar caste, and is descended from an old *pillai* family, who ruled Tinnevely as feudal chiefs dependent on the Madura kingdom. The estate is situated at the south west corner of Srivillipatur *Muk*. It is well irrigated from the mountains, a portion of which, including fine forests, is claimed by the *samirddar*. The area and population of the estate are not returned separately in the Census Report of 1881. The *samirddar* pays annually a *fixtash* or fixed revenue of £1254. The rental amounts to £3624.

Seven Pagodás—Town in Chengalpat (Chingelput) District, Madras Presidency.—*See* MAHARAJULU.

Severi (*Sekeri*)—River in Madras Presidency.—*See* SAKARI.

Sewan.—Sub-division of Siran District, Bengal. Area 553 square miles, with 1 town and 1460 villages. Number of houses, 121,204, of which 104,848 are occupied and 16,356 unoccupied. Total population (1881) 749,452, namely, males 359,734 and females 389,478, proportion of males, 48 per cent. Hindus number 647,271, Muhammadans 106,438, and 'others' 117. Number of inhabitants per square mile, 578, villages per square mile 171, persons per village, 513, houses per square mile, 142, inmates per house, 7. This sub-division consists of the 3 police circles of Sewan Darauli, and Bikanipar. It contained in 1884, 1 civil and 2 criminal

courts, a regular police force of 92 men, and 1805 village watchmen.

Sewan.—Town in Sāran District, Bengal.—See ALIGANJ SEWAN.

Sewan (*Siwan*).—Town in Kaithal *tahsíl*, Karnál District, Punjab; situated in lat. $29^{\circ} 42' N.$, and long. $76^{\circ} 25' E.$, about 6 miles west of Kaithal town. Population (1881) 5717, namely, Hindus, 3252; Muhammadans, 2454; and Sikhs, 11. Number of houses, 287. The town itself is an unpretentious collection of native houses, without any building of importance. Its lands include an enormous hollow in which rice is extensively grown with the aid of the floodwaters of the Saraswatí. On the stream is an old Mughal bridge and an abandoned village site of great size, where ancient bricks and Indo-Scythian coins are found in considerable numbers. This site is locally known as Teh Polar.

Sewáni.—Town in Hissár *tahsíl*, Hissár District, Punjab; distant from Hissár town 21 miles south. Population (1881) 3694, chiefly Muhammadan Rájputs, many of whom enjoy the title of Ráo. Thriving and prosperous town, said to have escaped unhurt from the periodical famines which ravage the dry surrounding tract.

Shabkadar (*Shankargarh*).—Town and fort in Doábá-Dáúdzai *tahsíl*, Pesháwar District, Punjab; situated in lat. $34^{\circ} 10' 30'' N.$, and long. $71^{\circ} 33' E.$, about 3 miles from the foot of the western hills, and 17 miles north-east of Pesháwar city. The village is the seat of one of the chief Gígíáni families in the Doábá, and contains a number of wealthy traders. The village sprung up around the fort of Shankargarh, built by the Sikhs on a mound about a mile north of the village. The fort is now strongly fortified, and garrisoned by a force under the command of a field officer. In the centre of the fort is a high bastion called the cavalier, which commands an extensive view of the surrounding country. The garrison consists of infantry and cavalry, who are relieved from Naushahra. The fort and village contains (1881) a total population of 1367, namely, Muhammadans, 667; Hindus, 663; Sikhs, 29; and Christians, 8. Municipal income (1881), £188. Dispensary and police station.

Sháhábád.—British District in the Lieutenant-Governorship of Bengal, lying between $24^{\circ} 31'$ and $25^{\circ} 43' N.$ lat., and between $83^{\circ} 23'$ and $84^{\circ} 55' E.$ long. Area, 4365 square miles. Population, according to the Census of 1881, 1,964,909 souls. Sháhábád forms the south-western portion of the Patná Division. It is bounded on the north by the District of Gházípur in the North-Western Provinces, and the Bengal District of Sāran; on the east by Patná and Gayá Districts; on the south by Lohárdagá; and on the west by the Districts of Mírzápur, Benares, and Gházípur, in the North-Western Provinces. On the north and east, the boundary is marked by the Ganges and Son (Soane)

rivers, which unite in the north-eastern corner of the District. Similarly, the Karamnāsa forms the boundary with the North Western Provinces on the west, from its source to its junction with the Ganges near Chausī, and the Son is the boundary with Lohardāgā on the south. The administrative head-quarters are at the town of ARRAN.

Physical Aspects — Shahābād naturally divides into two distinct regions, differing in climate, scenery, and productions. The northern portion, comprising about three fourths of the whole area presents the ordinary flat appearance common to the valley of the Ganges in the Province of Ilhar, but it has a briser aspect than the trans Gangetic Districts of Sāran, Darbhāngah, and Muzaffarpur. This tract is entirely under cultivation, and is dotted over with clumps of trees—mangoes, *mahud*, bamboos, palms, etc. The southern portion of the District is occupied by the Kāmūr hills, a branch of the great Vindhyan range. The area of these hills situated within Shahābād is 799 square miles. The boundaries of the hills though well defined, are very irregular, and often indented by deep gorges scoured out by the hill streams. The edges are generally very precipitous, and huge masses of rocks which have fallen from the top obstruct in many places the river channels below. The summit of the hills consists of a series of saucer shaped valleys, each a few miles in diameter, with a deposit of rich vegetable mould in the centre, on which the finest crops are produced. There are several *ghāts* or ascents to the top some of which are practicable for beasts of burden. Two of the most frequented of these passes are Sarkī and Khariyān—the first near the south western boundary, the second in a deep gorge north of Rohtās. Two passes on the north side are more accessible,—one, known as the Khālī *ghāt*, is 2 miles south of Sāsserām, the other is at Chhanpathar, at the extreme west of the District, where the Karamnāsa forms a waterfall. The slopes to the south are covered with bamboo while those on the north are overgrown with a mixed growth of stunted jungle. The general height of the plateau is 1500 feet above the level of the sea.

The SON and the GANGES may be called the chief rivers of Shahābād, although neither of them anywhere crosses the boundary. The District occupies the angle formed by the junction of these two rivers, and is watered by several minor streams, all of which rise among the Kāmūr hills and flow north towards the Ganges. The most noteworthy of these are the following.—The Karamnāsa, the accursed stream of Hindu mythology, rises on the eastern ridge of the Kāmūr plateau, and flows north west, crossing into Mirzāpur District near Kullāh. After a course of 15 miles in that District, it again touches Shahābād, which it separates from Benares, finally falling into the Ganges near Chausī. The Dhohā or Kio rises on the plateau, and flowing north, soon is a fine waterfall, and enters the plains at the Tarrachandī Pass, a

miles south-east of Sássetám. Here it bifurcates—one branch, the Kudra, turning to the west, and ultimately joining the Karamnása; while the other, preserving the name of Káo, flows north and falls into the Ganges near Gáighát. The Dargautí rises on the southern ridge of the plateau, and after flowing north for 9 miles, rushes over a precipice 300 feet high, into the deep glen of Kadhar Kho; eventually it joins the Karamnása, passing on its way the stalactite caves of Gupta and the hill-fortress of Shergarh. This river contains water all the year round; and during the rains, boats of $1\frac{1}{2}$ ton burthen can sail up stream 50 or 60 miles from its mouth. The chief tributaries of the Dargautí are the Súra, Korá, Gonhuá, and Kudra.

No system of forest conservancy prevails, and the forests have consequently been denuded of their best timber, more especially on the slopes of the hills. With the exception of the Government estate of Bánskati, these jungle tracts are the property of the hill *samíndárs*, who derive a revenue from them from the sale of wood, and a grazing tax. Large herds of cattle are annually driven up the hills in charge of Ahírs to graze on the upland pasturage. Each animal pays a tax of 4 *ánnás* (6d.) for the season. Stick-lac is collected by the Khárwárs in the jungles, worked up locally into bracelets, and is also used as a dye.

Minerals.—*Kankar*, or nodular limestone, is found in most parts of the plains, especially in the beds of rivers and along the banks of the Son. Where the nodules are large, it is used as a road metal; but where small, it is generally burnt for lime. The Káimur hills consist almost entirely of red sandstone, overlying fossiliferous limestone. The former is largely used in building, for which, on account of its durability, it is admirably adapted. As instances of this quality, it may be mentioned that the works erected of this stone by Sher Sháh and his family, now more than three centuries old, show not the slightest traces of decay; and there are inscriptions nine hundred years old, equally unaffected. Sandstone is largely quarried by the Irrigation Department, and by private individuals for sugar-mills, millstones, curry-stones, and potters' wheels. Limestone is found in large quantities at the bottom of the precipices which surround the table-land and its detached ridges, in the deep glens behind Shergarh, and in the bed of the Karamnása. The lime-burners pay a royalty to the *samíndárs* of Rs. 2 for every 100 *maunds* quarried. Alum, slate, and martial pyrites are also found, producing an impure sulphate of iron, but the deposits are nowhere worked.

Wild Animals.—In the hilly southern portion of the District, large game abounds. Tigers, bears, and leopards are common; five or six varieties of deer are found; and among the other animals met with are the wild boar, jackal, hyæna, and fox. The *nílgái* (blue cow), the Antelope *picta* of naturalists, is seen on the Káimur table-land. Of

SHAHABAD.

game birds, the barred headed goose (*Anser indicus*) is common black backed goose (*Sarkidornis melanotos*) and the grey goose (*Cinereus*) are also to be found. The former is very rare in Bengal, and the latter is seldom seen south of Central India, though it is a common visitor in the north. The other game birds of the District include many varieties of wild duck (the most remarkable being the sheldrake), several kinds of teal, turkeys, curlew, and peafowl, jungle fowl, snipe and golden and common plovers.

The Son Canals—The project of irrigating Shahabad District by a comprehensive scheme of canals which should also be navigable dates from 1855, when General Dickens proposed the construction of canals from Patna westwards to Chauri, a project subsequently extended to Monghyr in the one direction and to Mirzapur in the other. It was, however, finally decided in 1871 that the original scheme should not be extended, and it is still an open question whether the Main Western Canal shall be extended even as far as Chauri. The work was commenced in 1869 by the construction of an approach or weir at Dehri on Son, about half a mile south of the causeway which carries the Grand Trunk Road from Birnati to Dehri. This work is 1,000 feet long by 120 broad, and 8 feet above the normal level of the river bed. It constitutes the head work of the system. The Main Western Canal, starting from here, first carries up to the full mile where the APRAH CANAL branches off in a north westerly direction 451,000 feet of water per second to irrigate 1,00,000 acres of land which require simultaneous irrigation. The Arrah Canal takes off at the 1st mile, where the BAKA and CHANSA Canals take off in a north easterly direction, abstracting a further quantity of 1,00,000 feet per second. In aligning the Main Western Canal the next object was to escape a heavy cutting, 50 feet deep at Dehri, and to carry the water on the ridges of the country. It curves round and carries the water on the head works of the Arrah Canal then by means of a high aqueduct at Birnati. It then carries the water to this point is 21½ miles. The length of the canal from Dehri to the point where it enters the Grand Trunk Road 2 miles west of Sassee is 23½ miles. The distance from Dehri to the point where it enters the Grand Trunk Road is 25½ miles. The total length of the canal is 44½ miles. It has 7 distributaries and the Dumraon branch is 4½ miles long. The principal distributaries are the Dumraon branch, the Pauri and Chauri branches is 85 miles, and they connect with the railway lines between the Kāo and the Dumraon on the west, a tract which

greatly needs irrigation. As a rule, the canals run in such a way that they do not cross the natural drainage channels of the country; but where this is not so, siphons have been provided which allow the water to pass under the canal unhindered. Many of the works being still incomplete, it is not possible to give at present a trustworthy estimate of the total cost of the work. There can be little doubt that these canals have conferred upon Sháhábád entire immunity from future famines. As far as the Son readings have gone, they show that a minimum supply of 3000 cubic feet of water per second can be depended upon up to the 15th of January; and this would suffice to irrigate 480,000 acres. But many of the cold-weather crops will have been completely irrigated before this date, so that the amount of water required decreases equally with the volume of the stream. Thus, peas, which occupy a very large area, generally receive their last watering about Christmas, when the supply is 3500 cubic feet per second. Generally speaking, three waterings are required for the cold-weather crops—one early in November, one in December, and one in the middle of January. After February, the supply of water decreases very rapidly; and though in exceptional years of high flood, irrigation might be carried on up to March and April for sugar-cane and indigo, these crops can only be occasionally watered or drenched in an ordinary year.

Population.—Sháhábád was one of the Districts statistically surveyed in the beginning of the present century by Dr. Buchanan-Hamilton, who made the area 4087 square miles, and the population 1,419,520. According to a later estimate, based upon the Survey of 1844-46, the area was returned at 4404 square miles, and the population at 1,602,274. The Census of 1872 disclosed a total population of 1,723,974 persons upon the area of the District as at present constituted. The last Census in 1881 returned the population at 1,964,909, showing an increase of 240,935, or 13·97 per cent., between 1872 and 1881. This large increase in nine years is due entirely to natural causes, the District not having suffered from exceptional disease, and cultivation having been largely developed during these years, owing to the opening of irrigation canals.

The results of the Census of 1881 may be summarized as follows:—Area of District, 4365 square miles; number of towns 10, and villages 5631; number of houses, 312,762, namely, occupied 274,934, and unoccupied 37,828. Population 1,964,909, namely, males 950,250, and females 1,014,659; proportion of males, 48·4 per cent. Average density of population, 450 persons per square mile, ranging from 917 per square mile in Arrah *tháná*, and 777 per square mile in Belauti in the thickly populated tracts in the neighbourhood of the Ganges, to 188 per square mile in Bhabuá, and 225 per square mile in Sásserám in the west and south of the District, where there is much

hilly and uncultivated land. Number of towns and villages throughout the District, 129 per square mile, persons per town or village, 348, houses per square mile, 7165, inmates per occupied house, 715. Classified according to sex and age, the Census gives the following results—under 15 years of age, boys 394,940, and girls 370,788, total children, 765,728, or 38.9 per cent of the District population. 15 years and upwards, males 555,310, and females 643,871, total adults, 1,199,181, or 61.1 per cent.

Religion—The great majority of the people are Hindus by religion, that faith being professed by 1,817,881 persons, or 92.5 per cent of the total population, Muhammadans number 146,732, or 7.4 per cent, Christians, 276, and 'others,' 20. Among the higher castes of Hindus, Bráhmans numbered 213,308, Rájputs, 207,195, Bábhans, 59,075, Káyasths, 46,994, and Baniyás, 34,568. The lower or Sádri castes included the following—Góddá, cattle dealers, herdsmen, and dairy men, who form the most numerous caste in the District, 242,721, Koerí, the principal agricultural caste, 152,846, Chamárs, 119,010, Dosádh, 90,155, Kandu, 68,427, Kúrmí, 66,341, Káhar, 62,812, Ieli, 47,836, Lohár, 32,563, Nápit, 29,153, Bind, 24,582, Gareri, 23,817, Kumbhár, 23,814, Kalwár, 20,126, Nuniyá, 18,666, Sonír, 18,139, Dhobí, 16,741, Mallah, 14,943, Barhái, 14,741, Musahír, 12,912, Písí, 11,894, Tántí, 7016, Rájnar, 6802, Dom, 5732, Tambál, 5156, Máli, 5100, Madak, 4836, Sunrí, 4409, Keut or Kewat, 3389, Jatwá, 3372, Baruí, 2573, and Jugí, 2167. Caste rejecting Hindus numbered 3033, of whom 1542 were Vaishnavs. Hinduized aboriginal tribes were returned at 31,401, including Gond, 7089, Khárwár, 5959, Bhuiyá, 301, and 'others,' 18,052. The Muhammadans were divided according to sect into—Sunnís, 142,435, Shiás, 3106, and unspecified, 1191. The Christian community consisted of—Europeans, 166, Eurasians, 78, natives of India, 10, and 'others,' 22. By sect, 220 were Protestants or belonging to the Church of England, 40 were Roman Catholics, and 16 unspecified.

Urban and Rural Population—Sháhábád District contains eight towns with more than five thousand inhabitants, namely, AFRÁH, population (1881) 42,998, DUMRAON, 17,429, BILWAR, 16,498, JAGDISHER, 12,568, BHOGPUR, 9278, NASKIRGANJ, 6063, BHATLA, 5728, and DHANAU, 5600. Two other towns are returned as municipalities but with less than five thousand inhabitants, namely, CHIRWA, 3336, and SAKERRAM, 2531. The total urban population thus disclosed is 122,029, or 6.2 per cent of the District population. There are altogether nine municipalities in the District, with a total population of 126,163, municipal income (1883-84), £5464, of which £3888 was derived from taxation, average incidence, 7½d. per head of pop., within municipal limits. Of the 5631 villages, 2919 contained less

than two hundred inhabitants ; 1611 between two and five hundred ; 772 between five hundred and a thousand ; 254 between one and two thousand ; 53 between two and three thousand ; and 21 between three and five thousand. As regards occupation, the Census Report divides the male population into the following six classes :—(1) Professional class, including all Government servants, civil and military, 12,155 ; (2) domestic class, including inn and lodging-house keepers, 36,073 ; (3) commercial class, including merchants, bankers, traders, carriers, etc., 35,728 ; (4) agricultural and pastoral class, including gardeners, 307,604 ; (5) manufacturing and industrial class, including all artisans, 83,473 ; (6) indefinite and non-productive class, comprising general labourers and male children, 475,217.

Antiquities.—The principal place of interest in the District, from an antiquarian point of view, is the fort of Rohtás or ROHTASGARH, so called from Prince Rohitáswa, son of Harischandra, one of the kings of the Solar dynasty. The present buildings were erected by Mán Singh, soon after he was appointed Viceroy of Bengal and Behar in 1644. The remains of the fortress occupy a part of the Káimur table-land, measuring about 4 miles from east to west, and 5 miles from north to south. Other places of interest in Sháhábád are the ruins of Shergarh fort, named after Sher Sháh, its founder ; Chainpur fort, with several interesting monuments and tombs ; Darauti and Baidyanáth, with ruins attributed to the Suars or Sivrás ; Masár, the Mo-ho-so-lo of Hiuen Tsiang ; Chausá, the scene of the defeat of Humáyún in 1539 by Sher Sháh ; Tilothu, near which are a fine waterfall and a very ancient Cheru image ; and Pataná, once the capital of a Hindu Rájá of the Suar tribe. A description of these places will be found under their respective names. The sacred cave of Guptasar lies in the centre of the Káimur plateau, 7 miles from Shergarh.

The town of Arrah is invested with a special historical interest, as being the scene of a stirring episode in the Mutiny of 1857. A body of rebels, consisting of about 2000 Sepoys from Dinápur and four times as many armed villagers, under Kuár Singh, marched in the end of July on Arrah. They reached the town on the 27th of that month, and forthwith released all the prisoners in the jail, and plundered the treasury. The European women and children had already been sent away, but there remained in the town about a dozen Englishmen, official and non-official, and three or four other Christians of different races. The Commissioner of Patná, Mr. Tayler, had supplied a garrison of 50 Sikhs. This small force held out for a long eight days, until rescued by Major Vincent Eyre. The centre of defence had been wisely chosen. At this time the East Indian Railway was in course of construction, under the local superintendence of Mr. Vicars Boyle, who, fortunately, had some knowledge of

District, 2,200,000 acres are under cultivation. The area usually covered by autumn (*bhādai*) and winter (*aghañi*) food crops is about 1,500,000 acres; that occupied by spring or *rabi* food crops, 600,000 acres; and that under other than food staples, 100,000 acres. The area under poppy is about 22,000 acres (average out-turn, 27½ lbs. of opium per acre); that under tobacco, only 300 acres.

Sháhábád has, on the whole, a much drier soil than the trans-Gangetic Districts of Sárán, Muzaffarpur, and Darbhanga. Along the north of the District runs a fringe of low-lying *khádír* land, representing the bed of the Banás or old Ganges, which is inundated for about four months every year, when the main stream is in full flood. Cold-weather crops of the finest character are grown here, on a soil enriched by the silt brought down by every flood. Very little land has been rendered uncultivable owing to blown sand from the bed of the Son (Soane). The soil is light for a few miles west of that river during the greater part of its course, except at its mouth, where the influence of the Ganges makes itself felt. This light soil may be divided into two classes—one consisting of fine sand mixed with a loose mould; the other a very tenacious clay, intermixed with a good deal of coarse sand. Both soils, so long as they are kept moist, produce good crops; but without irrigation they grow nothing, except a few pulses sown in the rains. Throughout the District, a free mould forms a large portion of the soil; when quite free, it is known as *dorás*, *pairu*, and *dhash*; when mixed with a little clay, it is called *sigat*. This last soil is especially suited for rice. Clay or *bangar* lands are considered the best, on the whole, as they retain moisture very well, and produce cold-weather crops without irrigation. The soil in the saucer-shaped valleys on the Káimur plateau is a rich and purely vegetable mould, swept down from the hills above.

A holding of above 100 acres in extent is considered a very large farm, and anything below 3½ acres a very small one. A fair-sized comfortable holding for a husbandman cultivating his own lands would be about 13 acres. A small-sized holding of 5 acres, which is as much as a single pair of bullocks can cultivate, would not make a peasant so well off as a respectable retail shopkeeper; but it would enable him to live as well as a man receiving 16s. a month in money wages.

Sháhábád District contains a small but increasing class of day-labourers, called *banihargs*, who neither possess nor rent lands, but depend entirely on their wages. These men often hire themselves out as field-labourers, and are paid by a share (sometimes amounting to one-sixteenth) of the produce. In this case they are called *lajhiás*. They occasionally supply half the seed and half the number of cattle required. It is supposed that this class first sprang up when the railway was being constructed; and it has been largely fostered by the demand for labour on the Son Canal works.

Wages and prices are reported to have risen, but the figures for early years are not available. The Government irrigation scheme already described has considerably raised the price of labour, and masons, carpenters, and blacksmiths, who before the opening of the canal works earned from 4½d to 6d a day, now make from 6d to 9d. The cultivators pay their rent either in kind (*bhāli*) or in cash. The latter system prevails everywhere in the case of special crops, such as poppy, sugar cane, cotton, and potatoes and is universal for all crops in the north of the District. Under the *bhāli* system the proportion taken by the landlord varies according to the crop. Thus, for broadcast rice, the customary landlord's share is a little less than one half, while for transplanted rice and wheat, and generally where irrigation requires to be carried on from wells, the landlord's share is one third. Where money rents prevail, the following are returned as the outside rates—1 or early rice land, on which an after crop of pulses, vegetables, oil seeds, etc. is grown, 15s. 7d to 15s. 10d an acre, for late rice land, generally a single crop 3s. 2d to 15s. 10d an acre, other food grains such as wheat, peas, etc., and linseed, 2s. 4½d. to £1, 11s. 8d an acre.

Natural Calamities—Shāhibād is subject to blight, flood, and drought. Blights, although they occasionally cause considerable damage, never occur on such a scale as to affect the general harvest. The Ganges annually overflows its banks, but the principal inundations result from the rising of the Son on the elevated plateau of Central India. Destructive floods have only occurred during the last few years, since a portion of the high land that formerly protected the District was washed away. About one-sixth of the total area is subject to inundation. Droughts arising from deficient rainfall, and the want of an extensive and complete system of irrigation, frequently caused distress previous to the opening of the canal works described above, and four times in the course of five years—in 1865, 1866, 1867, and 1869—drought seriously affected the harvest. The Son Canals have now, as has been stated, secured for the District immunity from such a famine.

Commerce and Trade, &c.—The trade of the District is chiefly carried on by means of permanent markets in the towns, and at fairs. The most frequented of these fairs are held at Barhampur near Lashanāth railway station, Baxar, Zakhani, Dhusamā, Padamanian, Gadahel, Kastar Danwar, Dhimār, Masārah, and Gajasar. The principal exports are—rice, wheat, barley, pulses, gram, oats, linseed, carraway seed, paper, and spices, the chief imports—cleaned rice, betel nut, tobacco, sugar, molasses, salt, pepper, cotton, iron, brass, zinc, copper, lead, tin and betel leaf or *paṭ*. The two great highways of trade to and from the District are the Ganges and the Lāṭ. In 1871 a new railway runs through the District for a distance of 60 miles, from

Koelwár station on the Son to Chausá on the Karaninása, the intermediate stations being Arrah, Bihíyá, Raghunáthpur, Dumráon, and Baxár. The aggregate length of roads in the District, exclusive of village tracks, is about a thousand miles, maintained from the proceeds of a road cess of 1 per cent. on the land revenue of the District. The principal manufactures are sugar, paper, saltpetre, blankets, coarse cotton cloth, and brass utensils. The figures supplied for the first edition of this work returned 58 sugar refineries in the District in 1872-73 (of which 42 were at Nasriganj), and the amount manufactured at 965 tons, valued at £28,350. Statistics for a later year are not available. Paper is made at Sáhár and Harharganj, both on the Son; and blankets and carpets in the Sásserám and Bhabuá Sub-divisions.

Administration.—So far as can now be ascertained, it would appear that the net revenue of Sháhábád increased from £101,851 in 1790-91 to £167,277 in 1849-50, to £233,978 in 1870-71, and to £253,554 in 1883-84; while the net expenditure, in like manner, increased from £5627 in 1790-91 to £25,046 in 1849-50, and to £44,158 in 1870-71; while it fell to £37,937 in 1883-84. The land-tax forms the principal item of revenue here, as elsewhere in Bengal; and the amount collected increased from £97,508 in 1790 to £171,263 in 1883-84. The number of estates has more than doubled in the same time, being 2330 in 1790, and 5961 in 1883; while the number of proprietors has increased by nearly fifty-fold, namely, from 1289 in 1790 to 50,410 in 1883. In the former year, the average amount paid by each proprietor was £80, 14s., and in the latter year, £3, 8s.

For administrative purposes, the District is divided into 4 Sub-divisions, and 11 *thánás* or police circles, as follows:—(1) Arrah or headquarters Sub-division, with the three police circles of Arrah, Belauti, and Piru; (2) Baxár Sub-division, with the two police circles of Baxár and Dumráon; (3) Sásserám Sub-division, with the four police circles of Sásserám, Kharghar, Dhangáin, and Dehrí; and (4) Bhabuá Sub-division, with the two police circles of Bhabuá and Mohaniá. Number of civil judges (1883-84), 8; stipendiary magistrates, 12. In 1883 the regular and town police force numbered 611 officers and men of all ranks, maintained at a total cost of £10,024. There was also a rural police or village watch of 4854 men, costing in money or lands an estimated sum of £10,996. The total machinery, therefore, for the protection of person and property consisted of 5465 officers and men, giving 1 man to every 0.79 square mile of the area or to every 359 persons of the population. The estimated total cost was £21,020, equal to an average of £4, 16s. 4d. per square mile of area and nearly 2½d. per head of population. In 1883-84, 2562 persons were convicted of an offence of some sort, great or small. The District has 4 jails, which contained in 1883 an average daily number of 214 prisoners.

The number of Government and aided schools in Sháhábád in 1856-57 was 8, with 354 pupils, in 1870-71 there were only 13 such schools attended by 589 pupils. Since the latter year, however, owing to the encouragement of primary education by an extension of the grant in aid system, the number of Government and aided schools has largely increased. In 1871-72 there were 47 schools, with 1572 pupils, and in 1877-78 there were 282, attended by 7211 pupils. In 1883-84, by which time the grant in aid system had received full development, there were 1337 lower primary schools under Government inspection, attended by 20,883 pupils. The Arrah District school had 464 pupils in 1883-84. The Census of 1881 returned 13,960 boys and 385 girls as under instruction, besides 36,930 males and 1024 females able to read and write but not under instruction.

Medical Aspects—The climate of Sháhábád is fairly healthy. The prevailing endemic diseases are intermittent and remittent fevers, bowel complaints, and skin diseases. Cholera and small pox occur from time to time in an epidemic form. The total number of registered deaths in the District in 1883-84 was 36,930 showing a death rate of 21.28 per thousand. Seven charitable dispensaries afforded medical relief in 1883 to 690 in-door and 37,169 out-door patients. Average annual rainfall for 25 years ending 1881, 45.24 inches, distributed as follows—January to May, 4.08 inches, June to September, 38.15 inches, and October to December, 3.01 inches. In 1883-84 the rainfall was 32.19 inches, or 13.05 inches below the average, the deficiency being conspicuous in all three seasons. [For further information regarding Sháhábád, see *The Statistical Account of Berghal*, by W. W. Hunter, vol. xii pp. 157-294 (Trubner & Co., 1877), Dr Martin's Edition of the *Statistics of Behar and Shahabad*, collected by Dr Buchanan Hamilton (1807) under the orders of the Government of India. Also the *Berghal Census Reports* of 1872 and 1881, and the several annual Administration and Departmental Reports of the Government of Bengal.]

Sháhábád—*Tahsil* or Sub-division of Hardoi District, Oudh, lying between 27° 24' and 27° 47' N. lat., and between 79° 43' and 80° 21' E. long. Bounded on the north by Sháhjánpur District in the North Western Provinces, on the east by Muzaffar *tahsil*, on the south by Hardoi *tahsil*, and on the west by Farrukhábád District in the North Western Provinces. Area, 539 square miles, of which 310 are cultivated. Population (1881) 216,825, namely, Hindus, 189,000, Muhammadans, 27,823, and 'others,' 2. Males 116,752, and females 100,073, average density of population, 402 persons per square mile. Of the 520 towns and villages in the *tahsil*, 397 contain less than five hundred inhabitants, 92 between five hundred and a thousand, 29 between one and five thousand, and 2 upwards of five thousand.

Government land revenue, £8836. This Sub-division comprises the 8 *parganás* of Sháhábád, Alamnagar, Piháni, Mansurnagar, Sára (North), Saromannagar, Páli, and Pachhoha. In 1884 it contained 1 civil and 3 criminal courts; police circles (*thánás*), 3; regular and town police, 118 men; village watch or rural police (*chaukidárs*), 595.

Sháhábád.—*Parganá* of Hardoi District, Oudh. Bounded on the north by Sháhjahánpur District in the North-Western Provinces; on the east by Alamnagar and Sára, the Sukheta river forming the boundary line; on the south by Saromannagar; and on the west by Pachhoha and Páli, from which it is separated by the Garra river. Area, 131 square miles, of which 81 are cultivated. Chief products—wheat, barley, *bájra*, gram, *joár*, rice, *arhar*, and sugar-cane. At the time of the revenue survey, wheat occupied about one-third of the cultivated area; barley and *bájra* each about a tenth; and gram, *joár*, and rice together about a fourth. Population (1881) 67,182, namely, Hindus 55,867, and Muhammadans 11,315. Of the 143 villages that make up the *parganá*, 72 are held by Muhammadans, $25\frac{1}{2}$ by Bráhmans, $21\frac{1}{2}$ by Rájputs, 9 by Káyasths, 1 by Gosáins, 1 by Europeans, and 13 by the Government. The varieties of tenure are—*talukdári*, 26 villages; *zamindári*, 82; and *pattidári*, 35. Government land revenue, £9342, equal to an average of 3s. $7\frac{1}{2}$ d. per cultivated acre, or 2s. $2\frac{3}{4}$ d. per acre of total area. The Oudh and Rohilkhand Railway runs through the *parganá*, with a station near Sháhábád town.

The country was originally in the hands of the Thatheras, whose chief settlement seems to have been at and around Angni Khera, on the site of Sháhábád town. They are said to have been dispossessed in the 8th century A.D. by a band of Bráhmans, who were on a pilgrimage from Benares to Hardwár. The Bráhmans retained possession of Angni Khera and the surrounding country till the reign of Aurangzeb, when, having plundered a convoy of treasure on its way to Delhi, a retaliatory expedition was sent out under an Afghán chief, Diler Khán, who surprised the Bráhmans at a bathing festival, slew them, and took possession of their lands, which were confirmed to him by the Delhi Emperor. Diler Khán founded the town of Sháhábád on the old site of Angni Khera, which he filled with his Afghán kinsmen and troops, assigning them jungle grants in the neighbourhood. Diler Khán's family gradually extended their possessions, acquiring either by purchase, mortgage, fraud, or force, every village in the *parganá*, which they held as proprietors till some fifty or sixty years ago, when the family began to decay and the estate to fall to pieces. The old proprietors in some cases succeeded in recovering possession of their villages, mostly by purchase from the Nawáb's family. The descendants of Diler Khán, however, still hold possession of more than one-half of the *parganá*.

Sháhábád—Town and municipality in Hardoi District, and head quarters of Sháhábád *tahsil* and *pargana*, situated on the road from Lucknow to Sháhábád, 15 miles from the latter town, in lat. $27^{\circ} 38' 25''$ N, and long $79^{\circ} 59' 5''$ E. The most populous town in the District, and the fourth largest in Oudh. Population (1881) 19,510, namely, males 9210, and females 9300. Hindus number 10,784, and Muhammadans 7726. Municipal income (1883-84) £383, of which £312 was derived from taxation, average incidence of taxation, 4d per head.

The town is divided into wards or *ma'allis*, named for the most part after the companions in arms of the founder Diler Khán. It is connected with Sháhjahánpur, Páli, Sándi, Hardoi, and Piháni by unmetalled roads, it is also a station on the Oudh and Rohilkhand Railway. The Sub-divisional courts and police station are placed in the enclosure of the Jamá Masjid, a mosque built by Diler Khán. Vernacular school, dispensary, and *sarái* (travellers rest house). No trade or manufacture of importance. Several markets are held in the different wards.

Sháhábád town has decreased in importance during the past hundred years the inhabitants dating the decay from the decline of the Delhi Empire, and the rise of Oudh to independence. The present population is said to be only one third of what it was formerly. Lieffenthaler describes Sháhábád about 1770 A.D., as of considerable circuit, and nearly in the middle is a palace of brick strengthened with towers like a fortress (the Bari Deorhi constructed by Diler Khán), with a vestibule and spacious covered colonnade. Most of the houses are of brick, and there is a fine mosque built of the same material, and enclosed by a wall. The town extends a mile from north to south, its breadth is something less, but of its flourishing state little remains. When visited by Tennant in 1799 it was an expanse of ruins, 'that appeared in the form of hills and broken, crumbling to dust.' Heber found it in 1824 'a considerable town, or almost city, with the remains of fortifications and many large houses.'

The following account of Sháhábád in 1850 is quoted from Sir W. Sleeman's *Trip through Oudh*, vol. II, pp. 46, 47. It is interesting as giving the origin of the chronic ill feeling that exists between the Muhammadans and Hindus, which broke out into a riot at the *Makar-sim* festival of 1868.—'Sháhábád is a very ancient and large town, occupied chiefly by Pathán Muhammadans, who are a very tall, fierce and fanatical set of fellows. Subzuk Rá, a Hindu, and the most respectable merchant in the District, resided here and for some time consented to officiate as the deputy of poor old Háfiz Akbar for the management of the town, where his influence was great. He had lent a good deal of money to the heads of some of the Pathán families of the town, but finding few of them disposed to repay, he was last year obliged to refuse

Government land revenue, £8836. This Sub-division comprises the 8 *parganás* of Sháhábád, Alamnagar, Piháni, Mansurnagar, Sára (North), Saromannagar, Páli, and Pachhoha. In 1884 it contained 1 civil and 3 criminal courts; police circles (*thánás*), 3; regular and town police, 118 men; village watch or rural police (*chaukidárs*), 595.

Sháhábád.—*Parganá* of Hardoi District, Oudh. Bounded on the north by Sháhjahánpur District in the North-Western Provinces; on the east by Alamnagar and Sára, the Sukheta river forming the boundary line; on the south by Saromannagar; and on the west by Pachhoha and Páli, from which it is separated by the Garra river. Area, 131 square miles, of which 81 are cultivated. Chief products—wheat, barley, *bájra*, gram, *jodr*, rice, *arhar*, and sugar-cane. At the time of the revenue survey, wheat occupied about one-third of the cultivated area; barley and *bájra* each about a tenth; and gram, *jodr*, and rice together about a fourth. Population (1881) 67,182, namely, Hindus 55,867, and Muhammadans 11,315. Of the 143 villages that make up the *parganá*, 72 are held by Muhammadans, 25½ by Bráhmans, 21½ by Rájputs, 9 by Káyasths, 1 by Gosáins, 1 by Europeans, and 13 by the Government. The varieties of tenure are—*tálukdári*, 26 villages; *zamindári*, 82; and *pattidári*, 35. Government land revenue, £9342, equal to an average of 35. 7½d. per cultivated acre, or 2s. 2¾d. per acre of total area. The Oudh and Rohilkhand Railway runs through the *parganá*, with a station near Sháhábád town.

The country was originally in the hands of the Thatheras, whose chief settlement seems to have been at and around Angni Khera, on the site of Sháhábád town. They are said to have been dispossessed in the 8th century A.D. by a band of Bráhmans, who were on a pilgrimage from Benares to Hardwár. The Bráhmans retained possession of Angni Khera and the surrounding country till the reign of Aurangzeb, when, having plundered a convoy of treasure on its way to Delhi, a retaliatory expedition was sent out under an Afghán chief, Diler Khán, who surprised the Bráhmans at a bathing festival, slew them, and took possession of their lands, which were confirmed to him by the Delhi Emperor. Diler Khán founded the town of Sháhábád on the old site of Angni Khera, which he filled with his Afghán kinsmen and troops, assigning them jungle grants in the neighbourhood. Diler Khán's family gradually extended their possessions, acquiring either by purchase, mortgage, fraud, or force, every village in the *parganá*, which they held as proprietors till some fifty or sixty years ago, when the family began to decay and the estate to fall to pieces. The old proprietors in some cases succeeded in recovering possession of their villages, mostly by purchase from the Nawáb's family. The descendants of Diler Khán, however, still hold possession of more than one-half of the *parganá*.

Sháhábád—Town and municipality in Hardoi District, and head quarters of Sháhábád *tahsil* and *paraná*, situated on the road from Lucknow to Sháhábád, 15 miles from the latter town, in lat $27^{\circ} 38' 25''$ N, and long $79^{\circ} 59' 5''$ E. The most populous town in the District, and the fourth largest in Oudh. Population (1881) 18,510, namely, males 9210, and females 9300. Hindus number 10,784, and Muhammadans 7726. Municipal income (1883-84), £383, of which £312 was derived from taxation, average incidence of taxation, 4d per head.

The town is divided into wards or *mafallas*, named for the most part after the companions in arms of the founder, Diler Khán. It is connected with Sháhjahánpur, Páli, Sándi, Hardoi, and Piháni by unmetalled roads, it is also a station on the Oudh and Rohilkhand Railway. The Sub-divisional courts and police station are placed in the enclosure of the Jamá Masjid, a mosque built by Diler Khán. Vernacular school, dispensary, and *sardí* (travellers' rest house). No trade or manufacture of importance. Several markets are held in the different wards.

Sháhábád town has decreased in importance during the past hundred years the inhabitants dating the decay from the decline of the Delhi Empire, and the rise of Oudh to independence. The present population is said to be only one-third of what it was formerly. Tieffenthaler describes Sháhábád about 1770 A.D. as of considerable circuit, and nearly in the middle is a palace of brick strengthened with towers like a fortress (the Bar Dóorh constructed by Diler Khán), with a vestibule and spacious covered colonnade. Most of the houses are of brick, and there is a fine mosque built of the same material, and enclosed by a wall. The town extends a mile from north to south, its breadth is something less, but of its flourishing state little remains. When visited by Tennant in 1799, it was an expanse of ruins, 'that appeared in the form of hills, and broken, crumbling to dust.' Heber found it in 1824 'a considerable town, or almost city, with the remains of fortifications and many large houses.'

The following account of Sháhábád in 1850 is quoted from Sir W. Sleeman's *Trip through Oudh*, vol. II pp. 46, 47. It is interesting as giving the origin of the chronic ill feeling that exists between the Muhammadans and Hindus, which broke out into a riot at the *Muharrar* festival of 1868.—'Sháhábád is a very ancient and large town, occupied chiefly by Pathán Musalmáns, who are a very turbulent and fanatical set of fellows. Subzukh Rái a Hindu, and the most respectable merchant in the District, resided here, and for some time converted to efficient as the deputy of poor old Háiz Abdullá for the management of the town, where his influence was great. He had lent a good deal of money to the heads of some of the Pathán families of the town, but finding few of them disposed to repay, he was last year obliged to refuse

further loans. They determined to take advantage of the coming *Muharram* festival to revenge the affront, as men commonly do who live among such a fanatical community. The *tazias* are commonly taken up and carried in procession ten days after the new moon is first seen at any place where they are made; but in Oudh, all go by the day in which the moon is seen from the capital of Lucknow. As soon as she is seen at Lucknow, the king issues an order throughout his dominions for the *tazias* to be taken in procession ten days after. The moon was this year (1850), in November, first seen on the 30th of the month at Lucknow; but at Sháhábád, where the sky is generally clearer, she had been seen on the 29th. The men to whom Subsukh Rái had refused further loans determined to take advantage of this incident to wreak their vengeance; and when the deputy promulgated the king's order for the *tazias* to be taken in procession ten days after the 30th, they instigated all the Muhammadans of the town to insist upon taking them out ten days after the 29th, and persuaded them that the order had been fabricated or altered by the malice of their Hindu deputy to insult their religious feelings. The *tazias* were taken out accordingly; and having to pass the house of Subsukh Rái, when their excitement or spirit of religious fervour had reached the highest pitch, they there put them down, broke open the doors, entered in a crowd, and plundered it of all the property they could find, amounting to about 70,000 rupees. Subsukh Rái was obliged to get out with his family at a back door, and run for his life. He went to Sháhjahánpur, in our territory, and put himself under the protection of the Magistrate. Not content with all this, the Muhammadans built a small miniature mosque at the door with some loose bricks, so that no one could go either out or in without the risk of knocking it down, or so injuring this mock mosque as to rouse, or enable the evil-minded to rouse, the whole Muhammadan population against the offender. Poor Subsukh Rái has been utterly ruined, and ever since seeking in vain for redress. The Government is neither disposed nor able to afford it, and the poor boy who has now succeeded his learned father in the contract is helpless. The little mock mosque of uncemented bricks still stands as a monument of the insolence of the Muhammadan population, and the weakness and apathy of the Oudh Government.'

Sháhábád.—Town in Piplí *tahsíl*, Ambála (Umballa) District, Punjab; situated in lat. 30° 10' N., and long. 76° 55', on the Grand Trunk road, 16 miles south of Ambála town. Population (1881) 10,218, namely, males 5091, and females 5127. Muhammadans, 5961; Hindus, 3600; Sikhs, 652; and Jains, 5. Number of houses, 1049. Municipal income (1883-84), £520, or an average of 1s. 0½d. per head. Founded by one of the followers of Alá-ud-dín Ghorí about 1086 A.D. The town is well built of brick, and ornamented by several

District, Bombay Presidency; situated 48 miles north-west of Dhulia. Together with Kukdel, it contained in 1881 a population of 5441. Hindus numbered 3675; Muhammadans, 1192; Jains, 35; and 'others,' 539. Municipality, with an income in 1883-84 of £288; incidence of taxation, 11d. Dispensary; post-office.

Sháhápúr.—Sub-division of Thána District, Bombay Presidency. Area, 870 square miles. Population (1881) 107,729, namely, males 55,412, and females 52,317; occupying 18,630 houses in 273 villages. Hindus number 104,959; Muhammadans, 2486; and 'others,' 284. Sháhápúr includes the petty division of Mokháda, and was formerly known as Rolvan. It is a strip of country 50 miles long and 5 to 30 miles broad, stretching in the east of the District below the Sahyádris. The country is, for the most part, wild, broken by hills and covered with large forests. The open parts are in the south, where there are wide tracts of rice lands. The soil is mostly red and stony. In 1879-80, 8880 holdings were recorded with an average area of $26\frac{1}{2}$ acres each, paying an average Government assessment of £1, 7s. 11d. In 1880-81, the actual area under cultivation was 98,226 acres. Cereals and millets occupied 75,519 acres; pulses, 14,364 acres; oil-seeds, 8382 acres; fibres, 330 acres; and miscellaneous crops, 54 acres. In 1883 the Sub-division contained 4 criminal courts; police circles (*thánds*), 3; regular police, 85 men. Land revenue, £11,727.

Sháhápúr.—Chief town of Sháhápúr Sub-division, Thána District, Bombay Presidency; situated on the Agra road about 54 miles north-east of Bombay, and about $1\frac{3}{4}$ miles from the Great Indian Peninsula Railway. The town stands on the Bhádangi stream, a feeder of the Bhátsa river, and about 5 miles from the foot of Máhuli fort. Population (1881) 2124, namely, Hindus, 1923; Muhammadans, 192; Pársis, 5; and Christians, 4. Head-quarters of a *mámlatdar*; contains the usual public offices; school and dispensary. A fair, attended by upwards of 3000 people, is held on the great night of the *Maháshivrátri* festival in February; and a second and larger fair takes place about a fortnight afterwards at the *Holi* full-moon (March-April).

Sháhápúr.—Town in Sángli, one of the southern Maráthá States, Bombay Presidency. Lat. $15^{\circ} 50' 5''$ N., long. $74^{\circ} 33' 56''$ E. Population (1881) 10,732, namely, males 5415, and females 5317. Hindus number 9269; Muhammadans, 994; Jains, 378; and Christians, 91. Sháhápúr is the most important trading place in Sángli State. The Population is chiefly composed of bankers, traders, and weavers. Silk-dyeing is carried on to a great extent. The town is governed by a municipal body. Dispensary and school.

Sháhára.—Town and municipality in Khandwá *tahsíl*, Nimár District, Central Provinces. Population (1881) 2266, namely, Hindus

1923, and Muhammadans 343. Municipal income (1882-83) £57, average incidence of taxation, 6d per head.

Shāhbandar.—Sub-division of Karachi District, Sind Bombay Presidency, lying between 23° 35' and 25° N lat., and between 67° 20' and 68° 48' E. lon. Area, 3378 square miles. Population (1881) 117 362, namely, males 64 841, and females 52 521, occupying 22,651 houses, in 1 town and 360 villages. Hindus numbered 12,205, Muhammadans, 103 450, Sikhs, 972, non Hindu aborigines 729, and Christians, 6.

Shāhbandar consists mainly of a flat, alluvial plain, forming part of the delta of the Indus, and cut up by numerous creeks, the chief of which are the Kori channel (which is believed to have been formerly a mouth of the Eastern Nārā), and the Pinyāri or Sir river. Large tracts are covered with mangrove and tamarisk jungle. The south-western portion is annually inundated and the belt bordering the sea affords excellent grazing ground for large herds of buffaloes. Number of canals in Shāhbandar, 152, with an aggregate length of about 800 miles. Government forests, 13, with an area of 38,287 acres. Game and fish abound. The principal crops are rice occupying 76 per cent. of the total cultivated area, and *hijra* 13 per cent. The average yield per acre of cleaned rice on good land is about 560 lbs. Wheat, cotton, tobacco, and sugar-cane are also grown. In 1882-83 the area assessed to land revenue was 257 662 acres and the area under actual cultivation, 115 953 acres. The total area held in *shikr*, or revenue free, is estimated at 45 000 acres. The annual value of the imports, which are principally cloth, grain, drugs, oil *ghr*, sugar, tobacco, pepper, areca nut, and copper and brass vessels, is estimated at about £35 000, and the exports, mainly agricultural produce, at £70 000. The manufactures comprise salt, coarse blankets and leathern and iron goods. Furs, 13. Aggregate length of roads, 350 miles, number of ferries, 34.

In 1881-82, the total revenue of Shāhbandar Sub-division amounted to £29 646, of which £27,049 was derived from imperial and £2598 from local sources. The chief items are the land tax *shikr* or excise, and stamp duties. Total number of police, 136. Subordinate civil court at Mirpur Batoro. Criminal courts, 8. Police circles (*thirats*) 19. Municipal town, 1, namely Mirpur Batoro. Subordinate jails at Mirpur Batoro and Sujawal. Number of schools, 6, with a total of 224 pupils. Prevalent diseases, intermittent fever. Dispensary at Mirpur Batoro.

Shāhbandar—Taluk of the Shāhbandar Sub-division, Karachi District, Sind, Bombay Presidency. Area, 1388 sq. miles. Population (1881) 27 814, namely, males 14 377 and females 13 437, occupying 5593 houses, in 107 villages. Hindu population 2759,

Muhammadans, 24,694; Sikhs, 192; and non-Hindu aborigines, 189. In 1882-83, the area assessed to land revenue was 75,610 acres; and the area under actual cultivation, 33,568 acres. Revenue, £7518. The *táluk* contains 2 criminal courts; police circles (*thánás*), 4; regular police, 27 men.

Sháhbándar (*King's Port*).—Chief town of Sháhbándar *táluk*, Sháhbándar Sub-division, Karáchi District, Sind, Bombay Presidency; situated in lat. $24^{\circ} 10' N.$, and long. $67^{\circ} 56' E.$, in the delta of the Indus, 30 miles south-west of Mugalbhin, and 33 miles south of Sujáwál. Population (1881) less than 2000. Sháhbándar stood formerly on the east bank of the Malir, one of the mouths of the Indus, but it is at present 10 miles distant from the nearest point of the river. The great salt waste commences about a mile to the south-east of the town, and on its westward side are extensive jungles of long *bin* grass. It was to Sháhbándar that the English factory was removed from Aurangábád when the latter place was deserted by the Indus; and previous to the abandonment of the factory in 1775, it supported an establishment of 14 vessels for the navigation of the river. The disastrous flood which occurred about 1819 caused material changes in the lower part of the Indus, and hastened the decay of Sháhbándar, which is now an insignificant village. Carless states that the native rulers of Sind had a fleet of 15 ships stationed here. Vessels entered by the Richal, the only accessible mouth, and passing into the Hajámro through what is now the Khedewári creek, ascended that stream to about 10 miles above Ghorebári, where it joined the Malir. Sháhbándar is the head-quarters of a *múkhhtiárkár* and of a *táppádár*; police *tháná* or circle, with a force of 13 men.

Sháhbáznagar.—Large village in Sháhjahánpur *tahsíl*, Sháhjahánpur District, North-Western Provinces; situated in lat. $27^{\circ} 56' 5'' N.$, and long. $79^{\circ} 55' 6'' E.$, on the river Garra, 3 miles from Sháhjahánpur town, of which it may be said to form a suburb. Population (1881) 3259. The town is named after its founder, Sháhbáz Khán, who settled here and built a fort about the same time as the foundation of Sháhjahánpur town in the middle of the 17th century. His descendants remained in possession up to the time of the Mutiny, when the estate was confiscated for rebellion, and bestowed upon Maulvi Shaikh Khair-ud-dín, Deputy Collector at Bareilly.

Sháhbázipur.—Village in Kalyánpur *tahsíl*, Fatehpur District, North-Western Provinces; situated in lat. $25^{\circ} 55' 40'' N.$, long. $80^{\circ} 39' 35'' E.$, 7 miles from Bindki, and 13 miles from Fatehpur town. Population (1881) 1203, chiefly Kurmís and Baniyás. Police outpost station. Good market.

Sháhdádpur.—*Táluk* of the Upper Sind Frontier District, Sind, Bombay Presidency. This *táluk* was until recently a part of Lárkhána

Sub-division, and was formed out of parts of Sujáwíl Ráto Dero, and Kambar *tluk*. In 1883 the *tluk* contained 2 criminal courts, police circle (*tl iní*) 1, regular police, 19 men. Revenue, £8554.

Sháhdádpur.—*Tluk* of the Hala Sub-division, Haidarábád (Hyderábád) District, Sind, Bombay Presidency. Area, 733 square miles. Population (1881) 55,593, namely, males 30,293, and females 25,300, occupying 8316 houses in 1 town and 111 villages. Hindus number 6801, Muhammadans, 43,658, Sikhs, 2915, and non-Hindu aborigines, 2219. In 1882-83 the area assessed to land revenue was 53,969 acres, and the area under actual cultivation, 48,074 acres. In 1883 the *tluk* contained 3 criminal courts, police circles (*thárds*) 7, regular police, 31 men. Revenue, £13386.

Sháhdádpur—Chief town of Sháhdádpur *tluk*, Haidarábád District, Sind, Bombay Presidency, situated in lat. 25° 56' N., and long. 68° 40' E., on the Jámwah Canal, 15 miles north-east of Hala, and 40 miles north-east of Haidarábád city. Population (1881) 2068. Seat of a *mukhtárkar's* office, with the usual public buildings. Local trade in grain, oil seeds, sugar, and cloth valued at £6000; transit trade in *tyra*, wheat, rice, and cotton, valued at about £10,000. Chief manufacture, oil. Sháhdádpur is said to have been founded two centuries ago by one Mir Sháhdád.

Sháhdara.—Village in Lahore District, Punjab, situated in lat. 31° 40' N., and long. 74° 20' E., on the west bank of the Ravi, nearly opposite Lahore city, from which it is distant about 6 miles. Population (1881) 3847. Contains the mausoleum of the Emperor Jahángír and his wife Núr Jáhán and the tomb of Asif Khán brother of the empress, in a beautiful garden, a favourite resort of the residents of Lahore. The Sikhs committed great depredations upon all the buildings, carrying off much of the marble facings and enamelled work to decorate their own temple at Amritsar (Umrtsar). Sháhdara is the second station from Lahore on the Punjab Northern State Railway.

Sháhdara—Town and municipality in Ghazilúd *tluk*, Meerut (Meerut) District, North Western Provinces, situated in lat. 28° 40' 5" N., and long. 77° 20' 10" E., near the left bank of the Eastern Jumna Canal about 31 miles south-west of Meerut city, and a station on the Sind, Punjab, and Delhi Railway. The town was founded by the Emperor Shih Jáhán who gave it its present name of 'Royal Gate,' and designed it as an emporium for the supply of grain to his troops sacked by Siráj Mál Ját, of Páht, in and plundered by the soldiers of Ahmad Sháh Durrání just before the battle of Panipat. Population (1881) 6500, namely, Hindus, 4853, Muhammadans, 1505, Jains, 132, and Christians, 12. Manufacturing (1883-84) £210. Manufacture of sweetmeats. Large trade in shoes and leather, in pottery,

sugar refineries. Police station, post-office, and handsome new *sardī* or native inn.

Sháh Dheri.—Village and ruins in Ráwal Pindi District, Punjab.—*See* DERI SHAHAN.

Sháhganj.—Town in Khutáhan *tahsíl*, Jaunpur District, North-Western Provinces; situated in lat. $26^{\circ} 2' 42''$ N., long. $82^{\circ} 43' 36''$ E., on the metalled road to Faizábád, 8 miles north-east of Khutáhan town. The town owes its origin to the Nawáb Wazír of Oudh, Shuja-ud-daulá, who built a market-place, a *baradari*, and a *dargah* or tomb in honour of the famous Mecca saint, Sháh Hazrat Ali. Population (1881) 6317, namely, Hindus 4708, and Muhammadans 1609. At the commencement of British rule, Sháhganj was, and still remains, a thriving mart, second only to Jaunpur in commercial importance. Large centre of cotton trade, with markets on Tuesdays and Saturdays. School, post-office, police station, dispensary, and station on the Oudh and Rohilkhand Railway. A house-tax is levied for police and conservancy purposes, realizing £208 in 1882–83.

Sháhganj (or *Mukimpur*).—Town in Faizábád (Fyzábád) District, Oudh; situated about 10 miles from Faizábád town. Founded by a Mughal on the village land of Mukimpur; seized by Rájá Darshan Singh, whose fort and residence became celebrated during the Mutiny of 1857. Population (1881) 3191, namely, 2622 Hindus and 569 Muhammadans. Mosque, 2 temples, and vernacular school.

Sháhgarh.—Chief town of a tract bearing the same name in Bandá *tahsíl*, Sagar (Saugor) District, Central Provinces; situated in lat. $24^{\circ} 19'$ N., and long. 79° E., 40 miles north-east of Sagar town. Originally part of the Gond kingdom of Mándlá, it continued till 1857 to be the head-quarters of an independent chief of ancient lineage. Population (1881) 2155, namely, Hindus, 1747; Muhammadans, 241; Kabirpanthis, 43; Jains, 123; and 'other,' 1. Sháhgarh stands at the foot of a lofty hill range, with jungle on nearly every side. The small fort, now in ruins, on the east of the village, contained the Rájá's palace. At the villages of Báretá, Amarmau, Hirápúr, and Tigorá, all in the north of the tract, iron-ore is smelted and sent to Cawnpur. Markets are held every Tuesday and Saturday; Government boys' school, girls' school, and dispensary.

Sháhi.—Canal in Gurdáspur, Amritsar, and Lahore Districts, Punjab.—*See* HASLI.

Shahiwal.—Town in Sháhpur *tahsíl*, Sháhpur District, Punjab.—*See* SAHIWAL.

Sháhjahánpur.—A British District in the Lieutenant-Governorship of the North-Western Provinces, lying between $27^{\circ} 35'$ and $28^{\circ} 28' 15''$ N. lat., and between $79^{\circ} 23'$ and $80^{\circ} 25' 45''$ E. long. Area (1881), 1745 square miles. Population, 856,946 souls. Sháhjahánpur forms

the easternmost District of the Rohilkhand Division. It is bounded on the north west and north by Pilibhit and Bareilly (Bareli) Districts, on the east by the Oudh District of Kheri, on the south by Hardoi District, and by the Ganges, which separates it from Farukhabad District, and on the west by Buddaun and Bareilly Districts. The administrative head-quarters are at the city of SHAHJAHANPUR.

Physical Aspects—The District of Sháhjahánpur consists of a long narrow tract, running upward from the Ganges in the south west towards the Himálayas, reaching to within 3 miles of the Sarda river on the north-east, nearly at right angles to the river system of the Rohilkhand plain. Hence its natural features depend almost entirely upon the various streams which have cut themselves deep channels through the alluvial soil of the Gangetic basin. The north-eastern corner, beyond the Gúmá, presents an appearance not unlike that of the *first* or damp submontane belt. A large area still remains under forest, or lies otherwise waste. A scanty population inhabits this malarious tract, but water rises close to the surface, and the natural fertility of the soil is only marred by the feverish exhalations.

The next section, between the Gúmá and the Khanaut, passes from a rather wild and unhealthy northern region to a densely inhabited strip along the southern river, consisting of a productive loam, well cultivated with sugar-cane and other remunerative crops. The Khanaut falls into the Deoha or Garra just below Sháhjahánpur city, and the triangle enclosed between the confluent streams, though fertile in the immediate neighbourhood of their valleys, consists of a thinly peopled country, overgrown with thorn and *dhák* jungle.

The section between the Deoha and the Gardi comprises much marshy land, but south of the latter river, the country rises in a sandy ridge, till it reaches the valley of the Rámanga, through which the stream wanders in changing courses, destroying and re-forming its banks with great rapidity. Thence to the Ganges stretches a continuous lowland, consisting of marshy patches alternating with a stiff clay soil, and requiring irrigation in parts. This is supplied by the Set and other streams, which are utilized by being dammed up at particular places, and the water thus stored is distributed in channels, of en to great distances. Cultivation is here less easy and less remunerative. In the bed of the Ganges, at the extreme south of the District, are lowlands covered with high grass and brushwood.

The Rámanga and the Deoha or Garra discharge their waters in a most arbitrary manner, the Rámanga to an extent perhaps varying as much in the case of any river of equal volume. Each rises in a region of the land denuded by fresh alluvial deposits, and therefore the two local lines of rich soil crossing the District, the terrace of a valley deposited at an early date, and the late clay, occur, as the result of the

that lies between the valleys of the Rámangá and Deoha, the whole southern and central parts of the District. The northern part may be roughly divided into two tracts—(1) the moist *tardí*-like tract comprising Khutár *parganá* and the northern part of Pawáyan; and (2) the rich sugar-producing country about Pawáyan and Barágáon. There are in each tract minor variations, narrow ridges of light soil above the smaller rivers and streams, or small tracts of hard soil in depressions near the larger *jhils* or lakes.

The Rámangá forms the main waterway of the District, being navigable as far as Kola Ghát, near Jalálábád, whence considerable quantities of cereals and pulses are shipped in country boats by Cawnpur traders for the Ganges ports. A few swampy lakes (*jhils*) in the lower portions of the District afford irrigation for the spring crops in their neighbourhood. No large pasture-grounds exist anywhere, but cattle are sent in large herds from the northern *parganás* to graze in Nepál during the cold weather, returning at the commencement of the rains.

Khutár *parganá*, in the north of the District, contains a wide area of still unreclaimed jungle, consisting chiefly of *sál*, but not now containing any large trees. The jungles are, however, of great value, as furnishing large quantities of timber for house-building purposes. Two smaller tracts of the same description of jungle exist in Pawáyan *parganá*—one on the river Gúmti, and one on the Khanaut; but in the rest of the District, the jungle consists simply of dwarf *dhák* and thorn bushes, and is almost confined to the hardest and poorest soil in Nigohi, Jalálábád, and Jamaur *parganás*. The total of this unreclaimed area, consisting of forest, *dhák* jungle, open grass land, etc., amounted at the time of the land settlement to 226½ square miles, or 17 per cent. of the whole District area. The only mineral product of Sháhjahánpur is *kankar*, or nodular limestone, either burnt into lime, or used in its raw state for road metalling.

Feræ Naturæ.—Leopards are not uncommon in the jungle tracts in the north of the District; and a wandering tiger or lynx is occasionally shot. Spotted deer frequent the northern jungle, and *nilgái* and wild hog are found in small numbers in the patches of *dhák* scrub scattered about the District. The antelope is met with in small numbers almost everywhere, and in large herds on the highlands near the Gúmti, and in the valley of the Ganges. Smaller game comprises floriken, hare, black and grey partridge, quail, sand-grouse, and pea-fowl, found almost everywhere. The large ponds and marshes abound in water-fowl of all sorts; and several kinds of geese, ducks, teal, and snipe afford excellent sport for about four months during the cold season.

History.—Sháhjahánpur possesses little separate history of its own

before its annexation by the British in 1801. During the early Musalman times, it always formed part of Kather proper, or the country of the Katheriya Rajputs, nearly the whole of its *parganas* lying east of the Kimgangā, and it was then included under the government of Budhun. Shahjahanpur town was founded in the reign of Shāh Jahān In Nawāb Bahādur Khān, a Pathān, who named it in honour of the Emperor. About 1720, All Muhammad Khān who had risen into power at the head of his Rohillā clansmen, defeated the Governors of Bareilly (Bareh) and Morādābād and himself assumed the rule of those two Districts, together with Shahjahanpur. On his death in 1751, Hāfiz Kāhmat Khān, the guardian of his sons, became leader of the Rohillās, and defeated the imperial troops sent against him. Shāh jahānpur remained under the Bareilly authorities till 1774, when the Nawāb Wazīr of Oudh overran Rohilkhand with the aid of Warren Hastings. The Rohillās, however, had never gained complete control over the eastern portion of Shahjahanpur District, though their power was firmly established in the west. The Gaur or Katheriya Thākurs also retained their independence among the wild wastes of the north Shahjahanpur, indeed, lying on the border between Oudh and Rohilkhand formed a sort of debatable land between the two Provinces, but the sympathies and connections of the Shahjahanpur Pāndās lay always with Oudh rather than with the Rohillās. The Nawāb Wazīrs held Rohilkhand from 1774 till 1801, when it was ceded to the English by the treaty of Lucknow.

Henceforward, our rule was never disturbed until the Mutiny, although the District bordered upon the most turbulent part of Oudh. In 1857, however, Shahjahanpur became the scene of open rebellion. The news of the Meerut (Merath) outbreak arrived on the 15th of May, but all remained quiet till the 25th when the sepoys informed their officers that the mob intended to plunder the treasury. Precautions were taken against such an attempt but on the 31st while most of the officers civil and military, were at church, some of the sepoys forced their way into the building and attacked them. Three Europeans were shot down at once, the remainder closed the doors and aided by their servants, together with a hundred faithful sepoys held the church against the mutineers. The other officers then joined them and the whole party escaped, first to Panawan and afterwards to Morādābād. The mutineers burnt the station, plundered the treasury and made their way to the centre of local disaffection at Bareilly.

Rebel Government under Kadir Akbar Khān was proclaimed on the 1st of June. On the 18th, Ghulām Kadir Khān the brother of Nawāb of Shahjahanpur, passed through our lines way to Bareilly, where he was proclaimed Nāim of Shahjahanpur by Akbar Khān. On the 2nd the Nawāb returned to his seat for a while, but could not

Alí. He remained in power from June 1857 till January 1858, when our troops reoccupied Fatehgarh. The Nawáb of Fatehgarh and Firoz Sháh then fled to Sháhjahánpur, and on to Bareilly. After the fall of Lucknow, the Nána Sáhib also fled to Sháhjahánpur, but remained only ten days, and proceeded onward to Bareilly. In January, the Nawáb put to death Hámid Hassan Khán, Deputy Collector, and Muhammad Hassan, subordinate judge, for corresponding with the English. On the 30th of April 1858, the British force under Lord Clyde reached Sháhjahánpur. The rebels fled to Muhamdi, and the British went on to Bareilly on the 2nd of May, leaving only a small detachment to guard the station. The rebels then assembled once more, and besieged our troops for nine days; but Brigadier Jones' column relieved them on the 12th, and authority was then finally re-established.

Population.—The Census of 1853 returned the number of inhabitants at 986,096 persons. That of 1865 showed a total of 1,018,117, being an increase of 32,021 persons, or 3·2 per cent. The Census of 1872 gave the population as 951,006, showing a further decrease of 67,111 persons, or 6·6 per cent., since 1866; and of 35,090 persons, or 3·5 per cent., in the whole nineteen years. These returns yield, however, fallacious inferences, if compared with the area, which increased by 20 square miles in the first twelve years, and decreased by 605 square miles, or 35·1 per cent., in the seven years from 1865 to 1872, owing to the transfer of Puranpur *parganá* to Pilibhít District. The real rate of increase may best be seen from the figures representing the density of population, which amounted to 427 persons per square mile in 1853, 437 in 1865, and 549 in 1872. It must be borne in mind that the *parganá* transferred to Pilibhít between 1865 and 1872, lying close to the foot of the Himálayas in the pestilential *tardí*, had a much sparser population than any other portion of the District.

At the last Census in 1881, the population was returned at 856,946, showing a real decrease of 94,060, or 9·9 per cent., since 1872. This decrease is wholly due to the effects of the famine of 1877–78, in which Sháhjahánpur suffered terribly, the mortality from starvation, or diseases caused by privation, being estimated at not less than 150,000. For details of this famine, see the section of this article, *post*, on Natural Calamities.

The results of the Census of 1881 may be briefly summarized as follows:—Area of District, 1745·7 square miles; number of towns 6, and of villages 2020; houses, 123,640. Average density of population, 491 persons per square mile; towns or villages per square mile, 1·16; persons per town or village, 423; houses per square mile, 70·8; inmates per house, 6·9. Total population 856,946, namely, males 460,064, and females 396,882; proportion of males, 53·6 per

cent The excessive proportion of males is doubtless due to the former prevalence of female infanticide, but the Infanticide Act has been put in force in certain villages of the District, and is working well for the suppression of the practice In 1881, in five clans of Rājputs, Ahīrs, Ahars, Gujars, and Jāts, suspected of infanticide and proclaimed as such to the number of 129 886, the proportion of females was as low as 43·2 per cent That the Act is working satisfactorily is proved by the fact that of 30,461 children under ten years of age belonging to the above tribes, females numbered 14,259, or 46·7 per cent Classified according to sex and age, Shāhjahānpur contained in 1881—under 15 years of age, boys 173,119, and girls 143,393, total children, 316,512, or 36·9 per cent of the population 15 years and upwards, males 286,945, and females 253,489, total adults, 540,434, or 63·1 per cent.

Religion—As regards religious distinctions, the population is classified as follows—Hindus, 735,244, or 85·8 per cent of the District population, Muhammadans, 120,214, Christians, 1408, Sikhs, 78, and Parsis, 2 Of higher caste Hindus, Brāhmins number 59,366, Rājputs, 60,398, Gosains, 2616, Bhāts, 1680, Banijās, 22,864, and Kāyasths, 11,282 The lower or Sudra castes, who form the bulk of the population, include the following—Kūrmī, the principal agricultural class, and most numerous caste in the District, 103,958, Chamār, 85,491; Kachhī, 59,058, Ahīr, 65,216, Kāhīr, 34,965, Korī, 22,771, Tell, 21,943; Dhobī, 17,232, Pāsi, 17,186, Gadarī, 16,662, Bārhdā, 16,067; Bhurjī, 14,361, Nāī, 14,334, Dhanuk, 11,633, Lohār, 10,069, Kumbhār, 8993, Bhangī, 7228, Kalāīr, 6915, Sonār, 5185, Gūjar, 3163, Lonjī, 2877, Lodhī, 2413, Kathik, 2221, Tambulī, 1940, and Mālī, 1845

Of the Muhammadans, only 181 are recorded as Shī'īs by sect in the Census Report, the remainder being all Sunnīs Classified by race, as distinguished from religion, the Musalmāns consist of three classes—*Afghāns*, so called because their ancestors were the class to whom principally *ṣūks* or revenue free grants of lands were given by the Muhammadan rulers of the country They are subdivided into Sayyids and Shūkhs, and are reputed to be the descendants of Arabs The Pathāns or Afghāns, and the Mughals, are descended from immigrants into India from beyond the north west The Indian Muhammadans, or descendants of converts from Hinduism, include 677 Rājputs and Mewātīs by descent In the *ḥadd* of the Ganges, in Jāil'ūdī *ṭakīf*, a peculiar class of Musalmāns called *Pinkhās* are found in small isolated colonies These profess to be strict Muhammadans but imitate the lives of the *ḥadd* of the Ganges, and other animals and birds, and are called *ḥadd* and *ḥadd* They appear to be a fairly well-to-do community, and their families

show a stock of cattle, goats, and poultry much larger than that possessed by ordinary Hindu cultivators.

The Christian population consists of—Europeans, 942 ; Eurasians, 6 ; and natives, 460. The different sects include the Churches of England and Rome, Presbyterians, Baptists, Methodists, and Wesleyans. The American Baptist Mission has had a station at Sháhjahánpur since 1859, with several schools for boys and girls in the city, one teaching up to the university entrance standard. There is also a Christian village at Panápur, 10 miles east of the city, connected with a boys' orphanage under charge of the Mission, comprising about 900 acres of land laid out in small farms and cultivated by about 300 native Christians. The children of the orphanage are fed, clothed, educated, and instructed in various trades by the Mission, which receives a Government grant-in-aid of £25 a month. The Mission altogether maintains 26 day schools in the District, 18 for girls, and 8 for boys, attended in 1882 by 303 girls and 627 boys.

Urban and Rural Population.—Sháhjahánpur contains six towns with more than five thousand inhabitants, namely, SHAHJAHANPUR, population (1881) 74,830 ; TILHAR, 15,351 ; JALALABAD, 8025 ; KHUDAGANJ, 6925 ; MIRANPUR KATRA, 5949 ; and PAWAYAN, 5478. The urban population thus disclosed amounts to 116,558, or 13·6 per cent. of the District population, leaving 740,388, or 86·40 per cent., as forming the rural population. The only two municipal towns, however, are Sháhjahánpur and Tilhár. Total municipal income (1883-84), £7316, of which £5818 was derived from taxation in the shape of octroi duties ; average incidence of taxation, 1s. 3d. per head of the population (92,963) within municipal limits. The police and conservancy arrangements of the other towns is provided for by a small house-tax levied under the provisions of Act xx. of 1856. Of the 2020 minor villages, 829 contain less than two hundred inhabitants ; 754 between two hundred and five hundred ; 322 between five hundred and a thousand ; 97 between one thousand and two thousand ; 13 between two thousand and three thousand ; and five between three thousand and five thousand.

Material Condition of the People.—In the central portion of the District, the people are well off, and inhabit a richly cultivated plain, scarcely inferior to that of the Doáb. In the extreme north, however, agriculture is backward, waste tracts are numerous, and the people are poor and miserable like their neighbours in the *taráí*. In the south, also, where the swampy tract between the Rámangá and the Ganges alternates with stretches of stiff clay, the condition of the agricultural classes is much less prosperous. The best class of houses in towns rarely cost more than £200 ; the common huts of the peasantry, about £1. The latter consist merely of mud walls roofed with thatch.

As regards occupation, the Census Report of 1881 distributes the total male population among six great classes. The first or professional class numbers 7803, including 4372 engaged in the general government, 1228 in military defence, and 2203 in the learned professions or in literature. The second or domestic class numbers 1931, and comprises all males employed as private servants, washermen, water-carriers, barbers, sweepers, innkeepers, etc. The third or commercial class numbers 7588 and includes all persons who buy or sell, or keep or lend money or goods, such as bankers, money lender-brokers, shopkeepers, etc., 2338, and persons engaged in the carriage of men or goods, such as pack carriers, carters, etc. 5250. Of the fourth or agricultural class, besides the 225,509 males engaged in agriculture, the Census returns show 1270 persons engaged about animals, such as shepherds, etc., making a total of 226,779. The fifth or industrial class numbers 41,030, including all persons engaged in industrial arts and mechanics, such as dyers, masons, carpenters, perfumers, etc., 3016, those engaged in textile manufactures, such as weavers, tailors, cotton cleaners, etc., 18,456, preparers of articles of food or drink, such as grain parchers, confectioners, cooks, etc., 9840, and dealers in all animal, vegetable, or mineral substances, 9718. The sixth or indefinite class numbers 174,933 comprising all general labourers, 21,050, and persons of independent means, male children, and unspecified, 153,883.

Agriculture—The course of tillage follows the ordinary rule of the North Western Provinces, consisting of the *kharif* or autumn harvest—chief staples, cotton, rice, *khyra*, and *jir*, and the *rabi* or spring harvest, including wheat, barley, oats, vetch and peas. Sugarcane is grown in the low lying lands and Indian corn on ground capable of bearing two crops a year. Of the total District area of 17457 square miles 10896 square miles were returned in 1883-84 as under cultivation, 4637 square miles were available for cultivation, 1735 square miles were uncultivable waste, while 189 square miles were non-assessed or held revenue-free. The total crop area in 1883-84 (including lands bearing two harvests in the year) was returned at 730,819 acres, as follows—*Kharif*—wheat and barley 290,933 acres, pulses, 44,170 acres, oil seeds, 516 acres, miscellaneous, 12,194 acres. *Rabi*—rice, 96,241 acres, millets, 152,977 acres, cotton 2665 acres, clover, 1582 acres, miscellaneous, 84,578 acres. The crops sown in the previous year were—sugarcane, 38,509 acres, and vegetables 2454 acres.

There are no irrigation canals in Shahjahanpur, and there appear any need for them as the rainfall is copious, and the water level is from 12 to 15 feet below the surface. Irrigation is at present furnished by wells, tanks, *jaalis*, and the drawing up of the minor rivers and streams. In 1883-84 the area thus irrigated was

returned at 229,807 acres. Manure is employed where obtainable, but the poverty of the cultivators seldom permits them to let their land lie fallow. The land tenures belong to the standard types of the Province. The country, however, has been too recently occupied to have acquired such complicated holdings or undergone such minute sub-division as in the Lower Doab. The horned cattle of the District are small and weak, and good draught oxen can only be obtained by importation from beyond the Ganges. Government has made several attempts to improve the breed, but the people show no disposition to avail themselves of the facilities offered to them.

Land Tenures, Rent, etc.—At the time of the settlement of the District, out of a total of 3063 revenue-paying estates in Sháhjahánpur, 2191 were held under *samíndárí*, and 872 under *patidárí* tenure. The area alienated in perpetuity in rent-free grants of land, made by the *samíndár* proprietors, amounted to 11,712 acres, or a little over 1 per cent. of the total area. Cultivating tenures are divided into the two primary classes of proprietary and non-proprietary holdings. The fields cultivated by proprietors are called *sír* or homestead lands. The non-proprietary cultivators are either tenants with a right of occupancy, or tenants-at-will. Under the operation of the present rent-law, tenants-at-will are always on the way to acquiring the status of privileged tenants with rights of occupancy; the only qualification necessary being continuous cultivation of the same lands (other than *sír* lands) for twelve years. At the time of settlement, the proprietors held themselves 13·42 per cent. of the cultivated area as *sír* land; occupancy tenants, 61·31 per cent.; and tenants-at-will, 25·27 per cent. One reason for the large proportion of occupancy tenants is said to be the universal prevalence of money rents all over the District, except in the worst parts of Pawáyan and Khutár *pargands*.

The total male adult agricultural population in Sháhjahánpur District in 1881 was returned at 225,509, made up as follows:—Landed proprietors, 8468; estate servants and agents, 1047; tenant cultivators, 178,352; and agricultural labourers, 37,642. The population entirely dependent on the soil, however, numbered 622,593, or 72·65 per cent. of that of the whole District. Average area cultivated by each male adult agriculturist, 3·13 acres. Total Government assessment, including local rates and cesses levied upon the land, £139,760, or an average of 4s. per cultivated acre. Rental paid by cultivators, including cesses, £219,868, or an average of 6s. 2¾d. per cultivated acre. Custom, rather than competition, has regulated the rates of rent in this District, and the higher rates are still much the same as they were in 1818. The lower rates, however, were enhanced at the time of settlement by an average of 6½ per cent. The following is a statement of the maximum and minimum rates prevailing for each of the six

principal classes of land —Homes'ead (*gauh ini*) land, from 7s 6d to 16s an acre, first-class loam (*d'rat*), from 4s 6d. to 10s. an acre, second-class loam, from 3s. to 7s 6d an acre, clay (*matirde*) 3s 6d to 8s an acre, sand (*thur*), from 2s 3d to 5s. an acre, and hard clay (*dhitkar* and *khatpat*), from 2s. 3d to 5s. an acre. Rates of rent are determined quite as much by the respectability of the tenant as by the quality of the soil, the lowest rates being paid by Brahmins, Rajputs, and high-class Muhammadins, and the highest by the lower castes of Hindus and inferior orders of Muhammadins.

The following statement of the prices per cwt. of agricultural produce for the three years 1861, 1871, and 1881, which may be regarded as normal years, shows the steady advance in prices which has been made of late years—Wheat, 1861, 3s. 1½d., 1871, 4s., and 1881, 5s. 4d per cwt. Barley, 1861, 2s 7d, 1871, 3s 1½d, and 1881, 4s. 1d. per cwt. *Bijra*, 1861, 2s. 10½d, 1871, 3s 11½d, and 1881, 4s 7d. per cwt. *Jair*, 1861, 2s. 9d., 1871, 3s 11½d., and 1881, 4s 3d per cwt. Common rice, 1861, 4s. 11d, 1871, 5s 11d, and 1881, 7s 2d per cwt. Best rice, 1861, 8s 5d, 1871, 18s. 8d, and 1881, 15s. per cwt. Wages have risen in proportion. Coolies and agricultural labourers who were paid from 2d to 2½d. a day in 1859, received from 3d. to 3½d in 1882, while the wages of skilled labourers, such as smiths, carpenters, and masons, have risen from 4½d to 6d and upwards a day, in the same period.

Natural Calamities—Shahjahanpur suffers from drought and famine, though its proximity to the hills sometimes saves it from the worst extremities to which neighbouring Districts are exposed. The great famine of 1783-84, though severely felt in Rohilkhand, did not press so heavily upon this Division as upon Agra and the south west. In 1803-04, two years after the cession, rain completely failed for the autumn crops. In 1825-26, drought again occurred but did not bring about famine in the strictest sense. In 1837-38, the autumn rains failed, but a slight fall in February saved the harvest in part, though great dearth of grain ensued. The famine of 1860-61 was severely felt throughout Rohilkhand, and Shahjahanpur suffered like its neighbours, though it escaped the extreme misery which fell upon the contiguous District of Budhun. In the famine of 1868-69 Shahjahanpur escaped lightly, although during the period of pressure, lasting for seven weeks, the suffering was extremely severe.

Perhaps the District suffered more severely in the famine of 1877-79 than on any previous occasion in the present century. A series of bad harvests had followed the previous scarcity of 1865-69, and the heavy demands by the beginning of 1877 for the export of grain to Southern India caused such a depletion of stocks, as to convert what would otherwise have been a severe scarcity into actual

famine. On the 7th August 1877, the Collector reported 'roaring hot winds, and not a vestige of green anywhere.' Although a little rain fell towards the end of August, prices of grain had risen beyond the purchasing power of the poorest class early in September; and the *kharif* or autumn harvest was a total failure. A timely fall of rain, however, early in October enabled the sowings for the *rabi* or spring crops to be made, the requisite seed corn being provided by Government, while small money loans were arranged for from the *mahdjans* through the *tahsildars* in the interior of the District, on the security of the landholders. By December the spring sowings were over, and relief works were started, in the shape of earthwork and the collection of road materials for those able to labour, and a poorhouse for the helpless and infirm, while high-caste women who do not appear in public received assistance in their own homes. But the cultivating classes generally declined to submit to what they deemed the indignity of road-work, and preferred living as best they could on wild pot-herbs (*ság*), which they could gather in the neighbourhood of their own homes, to earning the wages offered on the works. For artisans and labourers in the city, work was provided by the municipality. The consequence of this entire substitution of green food for the ordinary coarse grains consumed by the peasantry was that their strength failed, and they succumbed in large numbers to the cold at the end of December and beginning of January.

The *rabi* harvest in 1878 was generally fair, notwithstanding some partial loss from hailstorms and superabundance of moisture; and the high prices prevailing did much to recoup the cultivators. But the condition of the day-labourers still caused grave anxiety. The autumn rains, although delayed, fell in sufficient abundance to ensure the prospects of the ensuing *kharif* harvest; and relief works were closed by the middle of November, and the poorhouses by the end of December 1878. The mortality caused by the famine was very heavy; 60,659 deaths are reported to have occurred between November 1877 and October 1878. The after effects of famine, in the deterioration of the strength of the people, were terribly illustrated in the fever epidemic which raged during 1879 and part of 1880. The registered death-rate, which stood at 29·37 per thousand in 1877, rose to 57·04 per thousand in 1878, and to 53·59 per thousand in 1879, falling again to 34·30 per thousand in 1880.

Commerce and Trade, etc.—The Oudh and Rohilkhand Railway is the main channel for the commerce of Sháhjahánpur. It enters the District near Kaheliá, and leaves it near Fatehganj, after a course of 39 miles within its limits. There are stations at Kaheliá, Rosa Junction, Sháhjahánpur, Tilhár, and Míranpur Katra. Four metalled roads also form great arteries of traffic, namely, the Rohilkhand Trunk

Road, the road from Pindwan through Shahjahanpur to Jalalabad, from Lucknow to Bareilly and Shahjahanpur and Ilahabad, and from Fatehgarh through Jalalabad to Miranpur Katra. Total length of roads, 337 miles. Cereals and pulses are carried down the Rāmgarā by Cawnpur traders, who send their boats to Kolaghat, near Jalalabad. Grain and raw sugar are conveyed on the Deoha from Shahjahanpur. Some through traffic exists from Pilibhit, where boats are built and despatched down stream, laden with produce. A considerable quantity of timber is also floated down from Pilibhit. Sugar is largely manufactured, and forms the chief export of the District. It formerly went by cart to Agra and other trans-Jumna marts, salt and cotton being imported in return, but most of this traffic now finds an outlet by the railway, which also conveys the cotton from Chandausi, the chief market for that staple in Rohilkhand. European goods, metals, and salt form the main items of import trade. The principal manufacture under European superintendence is that of sugar, started thirty years ago at the Kosa factory, near Shahjahanpur, by Messrs. Caren & Co. The factory was destroyed during the Mutiny, but was restored, and has been continued ever since. Rum is also distilled here, and largely sold to the Commissariat Department. The works are connected with the Oudh and Rohilkhand Railway by a short branch line $3\frac{1}{2}$ miles long, and are capable of turning out 600,000 gallons of rum, and 120,000 *maunds* of sugar. The still head duty due to Government on rum sold to the public (exclusive of that supplied to the Commissariat Department) amounts to nearly £30,000 a year.

Administration—Shahjahanpur is the seat of a Civil and Sessions Judge, whose civil jurisdiction extends also over the adjoining District of Buddaun. He holds criminal sessions at Buddaun town alternately with the Judge of Bareilly. The District staff comprises a Collector-Magistrate, Joint Magistrate, Assistant Magistrate, and uncommissioned Deputy Magistrate, besides a sub-deputy opium agent, and the usual fiscal, medical, and constabulary officials. The total amount of revenue—imperial, municipal and local—raised in the District in 1876 amounted to £191,508, or 3s. 10½d. per head of the population. Of this sum, the land tax contributed £118,442. In 1883-84, the total revenue of the District amounted to £186,162, of which the principal items were—Land revenue, £118,637, stamp, £13,786, excise, £3,807, provincial rates, £14,140, assessed taxes, £2,356, registration £753. The total cost of civil administration is represented by the pay of officials and police, in 1883-84, was £31,521. Number of civil judges, 13, number of magistrates, 30. In 1883 the regular and town police force consisted of 648 officers and men, maintained at a total cost of £6,432. There is also a village watch or rural police (*chakildars*) maintained at a

1883, maintained at a cost of £7518. The total machinery, therefore, for the protection of person and property consisted of 2729 officers and men, giving one man to every '6 square mile of area, or to every 314 of the population. Total cost, £14,153, equal to an average of £8, 2s. 1½d. per square mile of area, or 3¾d. per head of population. The District jail at Sháhjahánpur contained during the same year a daily average of 320 prisoners, of whom 15 were females. Postal communication is carried on by 9 imperial and 10 local post-offices; and the telegraph is in operation at all the stations on the Oudh and Rohilkhand Railway.

The educational returns in 1883 showed a total of 140 Government aided and inspected schools, with a roll of 4563 pupils. This is exclusive of unaided and uninspected schools. The Census Report of 1881 returned 5922 boys and 136 girls as under instruction, besides 17,080 males and 317 females able to read and write but not under instruction. The schools conducted by the American Baptist Mission have been already alluded to in a previous section of this article.

For fiscal and administrative purposes, the District is sub-divided into 4 *tahsils* and 12 *pargánds*.

Medical Aspects.—The climate of Sháhjahánpur is much damper than that of the Upper Doáb, and somewhat more so than the other portions of the Rohilkhand plain. Six weeks seldom pass at any time of the year without a fall of rain; and the prevailing wind sets easterly from the cloudy summits of the Himálayas. The heat during the hot months does not equal that of the neighbouring Districts, and excessively hot winds seldom blow for more than five or six days in each year. Except in May and June, the country has a fresh and green aspect, very unlike the parched brown stretches of the Doáb. The average rainfall for 32 years ending 1881 amounted to 38'41 inches, the maximum during that period being 54'5 inches in 1867, and the minimum 18'3 inches in 1868. From January to May, the average fall is 3'38 inches; from June to September, 33'41 inches; from October to December, 1'62 inches. The mean annual temperature is said to be about 75° F., but no accurate thermometrical returns are available. Except in the extreme north, near the *tardí*, the climate generally is healthy; but fevers prevail in that portion of the District every spring and autumn. The valley of the Sot is also very malarious. The total number of deaths reported in 1883 was 28,126, or 32'71 per thousand, as against an average of 46'58 per thousand for the previous five years. The mortality caused by the epidemic fever of 1879 and 1880 following on the famine of 1878, has been already alluded to. The District contains six charitable dispensaries—at Sháhjahánpur, Katra, Gularia, Jalálábád, Tilhár, and Pawáyan. In 1883 they afforded relief to

32,205 persons, of whom 1167 were in-door paupers. [For further information regarding Sháhjahánpur, see the *Gazetteer of the North-Western Provinces*, vol. ix., by F. H. Fisher, Esq., C.S. (Government Press, Allahábad, 1883). Also the *Report on the Settlement of Sháhjahánpur District*, between 1867-68 and 1875, by R. G. Currie, Esq., C.S., the *Census Report of the North Western Provinces* for 1881, and the several annual Administration and Departmental Reports of the Provincial Government.]

Sháhjahánpur — South eastern *tahsil* of Sháhjahánpur District, North Western Provinces, comprising the three *fargands* of Sháhjahánpur, Jamrur, and Kánt. The Garra river forms the boundary between Sháhjahánpur and Jamrur *fargands*, the latter lying between the Garra river and the Garai *nala*, which last separates it from Kánt *fargand*. Throughout Sháhjahánpur *fargand*, the surface of the country is level, except where it is broken by the Khanaut river, and the soil is a good loam called *dumai*. Well irrigation is ordinarily needed, but the soil retains moisture well, and one watering is usually sufficient for wheat. Jamrur *fargand*, with the exception of a narrow strip of *dumai* along the right bank of the Garra, lies low and is composed of a hard clay soil, requiring constant irrigation for the spring crops. Kánt *fargand*, with the exception of the valley of the Garai, is composed of a light sandy soil, which, though not equal in productiveness to the *dumai* of Sháhjahánpur *fargand*, nevertheless retains moisture well and produces fair crops in ordinary years without the necessity of any extensive irrigation.

Area, 401 square miles. Population (1881) 252,029, namely, males 133,206, and females 118,822. Average density of population, 628.5 persons per square mile. Hindus, 192,487, Muhammadans 48,113, Christians, 1362, and others, 66. Of the 467 towns and villages in the *tahsil*, 359 contain less than five hundred inhabitants, 80 between five hundred and a thousand, and 27 between one thousand and five thousand. The only place with upwards of five thousand is Sháhjahánpur city. Area assessed for Government revenue 392 square miles, namely, 242 square miles cultivated, 108 square miles cultivable, and 42 square miles uncultivable waste. Total Government land revenue, £29,062, or including local rates and cesses, £32,602. Total rental paid by cultivators, including cesses, £61,262. The chief tenure is *zamindari*, but there is not a single large proprietor in the *tahsil*. In 1884, Sháhjahánpur *tahsil* contained (including the District head-quarter courts) 3 civil and 10 criminal courts, with a regular police force of 357 constables and men.

Sháhjahánpur — Chief town, municipality, and administrative headquarters of Sháhjahánpur District, North-Western Provinces, situated in lat. 27° 53' 41" N., and long. 79° 57' 30" E., on

bank of the river Deoha or Garra, crowning the high ground just above its junction with the Khanaut. An old fort overhangs the confluence ; and a large masonry bridge, built by Hakím Mehndi Ali, spans the smaller river. The city was founded in 1647, during the reign of the Emperor Sháh Jahán, whose name it bears, by Nawáb Bahádur Khán, a Pathán. There is nothing of any special note in the history of the city, apart from that of the District generally, during the 210 years which elapsed between its foundation and 1857, when it became the scene of open rebellion during the Mutiny. The incidents of 1857 and 1858 are described in sufficient detail in the historical section of the District article (*q.v.*).

Population (1872) 72,140; (1881) 77,936, namely, males 39,293, and females 38,643. Hindus number 37,811; Muhammadans, 39,080; Christians, 979; and 'others,' 66. Number of houses, 13,776. Municipal income (1883-84), £6372, of which £5184 was derived from taxation in the shape of octroi duties; average incidence of taxation, 1s. 4d. per head. Sháhjahánpur is a station on the Oudh and Rohilkhand Railway, and is also connected by good roads with Lucknow, Bareilly, Farukhábád, Pilibhít, Muhamdi, and Hardoi. The main street runs from near the old fort for a distance of about $1\frac{3}{4}$ mile through the heart of the city to Bahádurganj market, near its northern limits. From Bahádurganj, the city extends outside the cantonments for fully a mile, crossing the road to Bareilly and stretching out along the Pilibhít road. In the opposite direction to the south-east, it extends across the Khanaut stream, near Hakím Mehndi's bridge. From north to south, the extreme length of the city is upwards of four miles, while the breadth is seldom more than one mile, and generally less. The population is only dense in certain quarters, and patches of cultivated land and gardens of fruit-trees are found everywhere.

The *tahsílí* courts, police station, and the dispensary are situated in the centre of the city, in the main street. The police lines, jail, and high school are on the edge of the city, overlooking the valley of the Khanaut. Farther north are the District, civil, criminal, and revenue courts. The civil lines consist of a small piece of land bounded on three sides by the cantonment, and on the fourth by the native city; but the house accommodation is said to be insufficient for the requirements of the civil residents. Before the Mutiny, native troops only were stationed at Sháhjahánpur. The military force now consists of a wing of a European and a wing of a native infantry regiment. The barracks, built after the Mutiny, are comfortable and well-constructed buildings. The station contains an English church, and three churches for native converts maintained by the American Methodist Mission, which also supports one large and several small schools for boys and

girls, an orphanage, and a dispensary. In addition to the high school and mission school, the town contains a Government *tahsil* school, and a municipal free school.

Shahjahanpur, taking its population into consideration, is a city of comparatively little commercial importance. The only local manufacture is sugar, which, with cereals and pulses, forms the principal export. The Rosa sugar factory and rum distillery is situated on the Garra river, a few miles from the city, with which it is connected by a short branch of the Oudh and Rohilkhand Railway. The three principal markets in the city are Bahádurganj near the cantonment and civil station, Carewganj, at the other or southern end, and a new vegetable market in the centre of the town, constructed in 1878-79 by the municipality.

Shahjahanpur.—Town in Gwalior State, Central India, situated on the Bombay Agra Trunk Road between Guna (Goonna) and Indore, 106 miles from the former, and 60 miles from the latter town. Headquarters of the Shahjahanpur District of Gwalior. Population (1881) 9247, namely, Hindus, 7168, Muhammadans, 2064, and 'others,' 15.

Shah-ki dheri.—Village and ruins in Rawal Pindi District, Punjab.—See DERRI SHAHAN.

Shahlimar—Gardens and pleasure-ground in Lahore District, Punjab, 4 miles east of Lahore city.—See SHALAMAR.

Shahpur.—A British District in the Punjab, lying between 31° 32' and 32° 42' N. lat., and between 71° 37' and 73° 24' E. long. Area, 4691 square miles. Population (1881) 421,508 souls. Shahpur forms the southernmost District of the Rawal Pindi Division. It is bounded on the north by the Pind Dadan Khan and Talagang *tahsils* of Jhelum (Jhelum) District, on the east by Gujrat and Gujranwala Districts, the Chenab river marking the boundary for a portion of the distance, on the south by Jhang District, and on the west by Dera Ismail Khan and Pannu Districts. Shahpur is divided into three *tahsils*—Bhera in the east and Shahpur in the west, forming the cis Jhelum portion of the District, and Khushk, the trans Jhelum tract. The District stands seventh in order of area and twenty-fourth in order of population, among the 32 Districts of the Punjab, and comprises 4.40 per cent. of the total area, and 2.23 per cent. of the total population, of the Province. The administrative headquarters are at the small town of SHAHRIK on the Jhelum river, but BHERA is the largest place in the District.

Physical Aspects.—The District of Shahpur consists of an irregular block of country, artificially demarcated for administrative purposes, and stretching from the western bank of the Chenab across the valley of the Jhelum, forming the heart of the Sind-Sagar Doab, and lying to the centre of the Salt Range. On either side of the Jhelum, which

bank of the river Deoha or Garra, crowning the high ground just above its junction with the Khanaut. An old fort overhangs the confluence ; and a large masonry bridge, built by Hakim Mehndi Ali, spans the smaller river. The city was founded in 1647, during the reign of the Emperor Sháh Jahán, whose name it bears, by Nawáb Bahádur Khán, a Pathán. There is nothing of any special note in the history of the city, apart from that of the District generally, during the 210 years which elapsed between its foundation and 1857, when it became the scene of open rebellion during the Mutiny. The incidents of 1857 and 1858 are described in sufficient detail in the historical section of the District article (*q.v.*).

Population (1872) 72,140; (1881) 77,936, namely, males 39,293, and females 38,643. Hindus number 37,811; Muhammadans, 39,080; Christians, 979; and 'others,' 66. Number of houses, 13,776. Municipal income (1883-84), £6372, of which £5184 was derived from taxation in the shape of octroi duties; average incidence of taxation, 1s. 4d. per head. Sháhjahánpur is a station on the Oudh and Rohilkhand Railway, and is also connected by good roads with Lucknow, Bareilly, Farukhábad, Pilibhít, Muhamdi, and Hardoi. The main street runs from near the old fort for a distance of about $1\frac{3}{4}$ mile through the heart of the city to Bahádurganj market, near its northern limits. From Bahádurganj, the city extends outside the cantonments for fully a mile, crossing the road to Bareilly and stretching out along the Pilibhít road. In the opposite direction to the south-east, it extends across the Khanaut stream, near Hakim Mehndi's bridge. From north to south, the extreme length of the city is upwards of four miles, while the breadth is seldom more than one mile, and generally less. The population is only dense in certain quarters, and patches of cultivated land and gardens of fruit-trees are found everywhere.

The *tahsíl* courts, police station, and the dispensary are situated in the centre of the city, in the main street. The police lines, jail, and high school are on the edge of the city, overlooking the valley of the Khanaut. Farther north are the District, civil, criminal, and revenue courts. The civil lines consist of a small piece of land bounded on three sides by the cantonment, and on the fourth by the native city; but the house accommodation is said to be insufficient for the requirements of the civil residents. Before the Mutiny, native troops only were stationed at Sháhjahánpur. The military force now consists of a wing of a European and a wing of a native infantry regiment. The barracks, built after the Mutiny, are comfortable and well-constructed buildings. The station contains an English church, and three churches for native converts maintained by the American Methodist Mission, which also supports one large and several small schools for boys and

wave like hillocks, between which lie undulating troughs of short coarse grass.

The north of Shahpur District is occupied by a part of the Salt Range, which runs right across the Doab, and rises to its greatest height in Mount Sakeswar, 5000 feet above sea level. It consists of two divergent chains, which unite again at either end, and enclose a number of rock bound alluvial basins, interspersed with picturesque lakes. Little patches of rich cultivation are found amid the nooks and valleys of the range, rendered fruitful by the fresh alluvial *detritus* from the surrounding peaks, and watered by the comparatively abundant rainfall of the hill tract. The southern face of the range presents a bold mass of broken and rugged cliffs, whose distorted strata and huge detached rocks give an air of sublimity to the scenery. Many torrents flow through the gorges on its side, and spread fertility over a narrow strip of lowland at the base, known as the *rokhri*. Thence an intermediate belt of pasture land, the *darda*, leads on imperceptibly to the wild sandy waste of the *thal*.

The Jehlam (Jhelum) river traverses the District throughout its entire length from north to south. In Shahpur it is a muddy river, with a current of about 4 miles an hour, average width of the stream in times of flood, about 800 yards, dwindling down in the winter months to less than half this width. A remarkable feature of this river is the sudden freshets to which it is subject. These occur after very heavy rain in the hills, when the swollen stream overflowing its banks, inundates the country for miles on either side for a day or two, and then gradually subsides within its normal bounds, leaving the soil enriched with a valuable alluvial deposit. The Chenab, which forms the boundary between Shahpur and Gujranwala for 25 miles, has a greater volume of water than the Jehlam, but its current is more sluggish, and though impetuous in flood, the average velocity does not exceed 2½ miles an hour. The flood deposits of the Chenab are inferior in richness and in quantity to those of the Jehlam.

A characteristic feature of Shahpur District is its system of inundation canals. The remains of ancient cuttings are met with along the edge of the District, but these had been allowed to fall into disuse, and have long since silted up. In 1860 one of the channels was experimentally cleared out by the District Officer, and the success of the trial induced an enterprising native gentleman to excavate an entirely new canal to irrigate a grant of waste land of which he had obtained a lease. This work was completely successful, and since 1860, twenty-two inundation canals have been constructed for irrigation purposes, of which six are Government works, aggregating 115 miles in length, and irrigating 33,700 acres, and 20 are private canals, with a total length of 235½ miles, and irrigating 43,625 acres.

The other mineral products of Sháhpur are saltpetre, the manufacture of which received a great impulse at the time of the Crimean War, but has now almost dwindled away. Lignite, iron, and lead are found in the Salt Range, but in too small quantities to be practically useful. Gypsum and mica are also found in considerable quantities in the same hills.

Fera Natura—Tigers, leopards, and wolves are found in the Salt Range, while in the *bár* and flat country generally, are found quail, partridges, sand grouse, hare, bustard, antelope, wild geese, and ducks. In the hilly tract, the *uril* or wild sheep, and the *chikor* or hill partridge, are found. The lakes of the Salt Range are the favourite abodes of the scarlet flamingo. Snakes are common in all parts of the District.

History—Though little definite information can be recovered with regard to the annals of Sháhpur District prior to the decline of the Mughal dynasty, the numerous remains studded about the *lár* clearly prove that at some remote period the whole country between the Chenáb and the Jhelam consisted of a flourishing and well watered agricultural plain. Mounds of earth, covered with fragments of brick or pottery, lie scattered over the whole table land, marking the ancient sites of towns and villages in a tract now only inhabited by half savage pastoral tribes. The historians of Alexander speak of the country as 'teeming with population,' and local tradition affirms that, so late as the time of Akbar, great prosperity extended over the entire *bár*. The present desert condition of the plateau is no doubt attributable to a gradual subsidence of the water level. There are spots where the brick work of old wells still existing does not extend more than 25 feet in depth, while now, in the same place, water cannot be obtained within 60 feet of the surface, and even when found is usually so brackish as to be unfit for the use of man or beast.

The dawn of authentic history in Sháhpur extends no further back than the reign of Muhammad Sháh when Rájá Salámat Rái, a Rájput of the Anand tribe, administered Bhera and the surrounding country, while Khusháb was managed by Nawáb Ahmadjár Khán, and the south-eastern tract along the Chenáb formed part of the territories under the charge of Mahárájá Kaura Mall, Governor of Múltán. At the same time, the *thal* was included among the dominions of the Balúch families of Dera Ghazi Khán and Dera Ismáíl Khán.

During the anarchic period which succeeded the disruption of the Mughal Empire, even this remote region became the scene of Sikh and Afghán incursions. In the year 1757, a force under Núr-ud-dín Hamírú, despatched by Ahmad Shah Duráni, to assist his son Tin úr in repelling the Maráthás, crossed the Jhelam at Khusháb, marched up the left bank of the river, and laid waste the three largest towns

of the District. Bhera and Miáni (Meeanee) rose again from their ruins; but only the foundations of Chak Sánu now mark its former site. About the same time, by the death of Nawáb Ahmadyár Khán, Khusháb also passed into the hands of Rájá Salámat Rái. Shortly afterwards, however, Abbás Khán, a Khattak, who held Pind Dádan Khán and the Salt Range for Ahmad Sháh, treacherously put the Rájá to death, and seized upon Bhera. But Abbás Khán was himself thrown into prison as a revenue defaulter; and Fateh Singh, nephew of Salámat Rái, then recovered his uncle's dominions.

After the final success of the Sikhs against Ahmad Sháh in 1763, Chattar Singh, of the Sukarchakia *misl* or confederacy, overran the whole Salt Range, while the Bhangi chieftains parcelled out among themselves the country between those hills and the Chenáb. Meanwhile, the Muhammadan rulers of Sahiwál, Mitha Tiwána, and Khusháb had assumed independence, and managed, though hard pressed, to resist the encroachments of the Sikhs. The succeeding period was one of constant anarchy, aggressive warfare, and territorial changes among the petty princes of the District, only checked by the gradual rise of Mahá Singh, and his son, the great Maharájá Ranjít Singh. The former made himself master of Miáni in 1783; and the latter succeeded in annexing Bhera in 1803. Six years later, Ranjít Singh turned his arms against the Balúch chieftains of Sahiwál and Khusháb, whom he overcame by combined force and treachery. At the same time, he swallowed up certain smaller domains in the same neighbourhood; and in 1810, effected the conquest of all the country subject to the Siál chiefs of Jhang.

In 1816, the conqueror turned his attention to the Málíks of Mitha Tiwána. The Muhammadan chief retired to Núrpur, in the heart of the *thal*, hoping that scarcity of water and of supplies might check the Sikh advance. But Ranjít Singh's general sank wells as he marched, so that the Tiwánas fled in despair, and wandered about for a time as outcasts. The Maharájá, however, after annexing their territory, dreaded their energy and influence, and therefore endeavoured to conciliate them by inviting them to Lahore, where he made a liberal provision for their support. On the death of the famous Hari Singh—to whom had been assigned the Tiwána estates—at Jamrúd, in 1837, Fateh Khán, the representative of the Tiwána family, obtained a grant of the ancestral domains from his patron at court, Rájá Dhián Singh. Thenceforward, Málík Fateh Khán took a prominent part in the turbulent politics of the Sikh realm, after the rapidly succeeding deaths of Ranjít Singh, his son, and grandson. Thrown into prison by the opposite faction, after the murder of Dhián Singh, he was released by Lieut. (afterwards Sir Herbert) Edwardes, who sent him to Bannu on the outbreak of the Múltán rebellion to relieve Lieut.

Taylor Shortly afterwards the Sikh troops mutinied, and Fateh Khan was shot down while boldly challenging the braves' champion of the Sikhs to meet him in single combat. His son and a cousin proved themselves actively loyal during the revolt, and were rewarded for their good service both at this period and after the Mutiny of 1857.

Shāhpur District passed under direct British rule, with the rest of the Punjab, at the close of the second Sikh war. At the time of annexation, the greater part of the country was peopled only by wild pastoral tribes, without fixed abodes, but moving from place to place in search of grass and water. Under the influence of settled government, they have begun to establish themselves in permanent habitations, to cultivate the soil in all suitable places, and to acquire a feeling of attachment to their regular homes. The Mutiny of 1857 had little influence upon Shāhpur. The District remained tranquil, and though the villages of the *hīr* gave cause for alarm, no outbreak of sepoys took place, and the wild tribes of the upland did not revolt even when their brethren in the Multān Division took up arms. A body of Pīwāna horse, levied in the District, did excellent service, and earned for their Mālik the coveted title of Khān Bahadur.

Population — The Census of 1855 was taken over an area so greatly altered by subsequent territorial changes (as the trans-Jehlum tract then lay chiefly within the old District of Leiah) that detailed comparison with later statistics becomes impossible. A rough calculation, however, would appear to show that the general density of population increased 25 per cent. between that date and 1868, and although this increase may be regarded as high, there can be no doubt that the number of inhabitants has grown with great rapidity ever since the annexation. The enumeration of 1868 disclosed a population of 368,288, on an area corresponding to that of the present District. At the last Census in 1881, the population of Shāhpur was returned at 421,508, showing an increase of 53,220, or 14.4 per cent., in the thirteen years between 1868 and 1881. Much of the increase is due to immigration from Gujranwala, Gujrat, and Jhang, owing to the rapid extension of canal irrigation during late years.

The results of the Census of 1881 may be summarized as follows:—Area of District, 4691 square miles, number of towns 6, and of villages 651, number of houses, 72,054, number of families, 98,971. Total population, 421,508, namely, males 221,676, and females 199,832, proportion of males, 52.6 per cent. Average density of the population, 90 persons per square mile. Put though the density of population is thus low, when the desert area is taken into account, the proportion of inhabitants to the cultivable surface is really very high, being upwards of 400 per square mile in the cultivated portions of the Salt Range. The cultivable land, indeed, is very much subdivided,

and is barely sufficient for the support of its inhabitants. Villages per square mile, 14; persons per village, 642; houses per square mile, 19; persons per house, 5·85. Classified according to sex and age, there were in 1881—under 15 years of age, boys 89,567, and girls 81,194; total children, 170,761, or 40·5 per cent. of the population: 15 years and upwards, males 132,109, and females 118,638; total adults, 250,747, or 59·5 per cent.

Religion.—Classified according to religion, the Muhammadans form the great bulk of the population, being returned at 357,742, or 84·9 per cent.; Hindus number 50,026; Sikhs, 4702; Christians, 29; and Jains, 9. The principal Muhammadan tribes include—Balúchís, 8865; Sayyids, 8625; Shaikhs, 7499; Patháns, 3076; and Mughals, 2335. These are Muhammadans by race descent. The following tribes are mainly Muhammadans by conversion of Hindus and aboriginal races in the time of the early Muhammadan invasions, and most of them still contain a proportion of Hindus—Rájput, 82,290; Awan, 48,485; Ját, 34,508; Chuhra, 28,297; Juláha, 22,472; Muchí, 15,314; Kumbhár, 11,769; Machhí, 11,156; Tarkhán, 10,270; Khokhar, 10,265; Arain, 8574; Mirási, 8344; Nai, 7541; Dhobí, 5624; Kassáb, 5202; Lohár, 5074; Sonár, 3597; and Telí, 2112. The castes which still remain almost entirely Hindus or Sikhs, are the Bráhmaṇ, 5462; Arora, 35,017; and Khattri, 15,015. The land-owning classes and the great mass of the village servants are Muhammadans; the Hindus and Sikhs being almost confined to the mercantile and official classes and their priests. The proportion of Hindus is much greater in towns than in villages. The six towns contain two-fifths of the entire Hindu population of the District, and the remainder are absorbed in the larger villages, since in the smaller ones not a single Hindu is met with, except here and there a petty shopkeeper.

Town and Rural Population.—The following six towns are returned in the Census of 1881—SHAHPUR, the civil head-quarters station of the District, population (1881) 7752; BHERA, 15,165; KHUSHAB, 8989; SHAHIWAL, 8880; MIANI, 8069; and GIROT, 2776. Total urban population, 51,631, or 12·2 per cent. of that of the whole District. These towns are all municipalities, with a total municipal income in 1883–84 of £3405, or an average of 1s. 4d. per head. Of the 651 villages or collections of hamlets comprising the rural population, 198 contain less than two hundred inhabitants; 210 between two and five hundred; 144 between five hundred and a thousand; 71 between one and two thousand; 20 between two and three thousand; and 8 between three and five thousand. As regards occupation, the Census of 1881 divided the adult male population of Sháhpur into the following seven main classes:—(1) Professional and official class, 4171; (2) domestic and menial class, 4619; (3) commercial class, including merchants, traders,

carriers, etc, 5197, (4) agricultural and pastoral class, including gardeners, 60,884, (5) industrial and manufacturing class, including all artisans, 30,635, (6) indefinite and non productive class, comprising general labourers, 13,972, and (7) unspecified, 12,631.

Agriculture—The total area under cultivation in 1883-84 amounted to 557,513 acres, of which 336,655 acres were artificially irrigated. Of the remaining area, 796,912 acres in the *Afr* tract are utilized for grazing purposes, 1,156,890 acres would be cultivable with the assistance of irrigation, while 496,773 acres are uncultivable waste. The spring harvest forms the main crop of the District. Wheat, the spring staple, covers nearly half the cultivated area, while spiked millet and cotton make up the chief items of the autumn harvest. Among the more valuable commercial crops, sugar-cane is grown only in the valley of the Chenab, and poppy in the Jehlam lowlands between Shahpur and Bhera. Wheat thrives best in the alluvial soils that fringe the two rivers, where it is the only crop grown, as after it is cut floods inundate the whole valley, and only subside in time for the next sowing. It also grows luxuriantly in the rich hollows and basins among the Salt Range, where the cool climate admirably suits it.

The area under the principal crops in 1883-84 is returned as follows—Wheat, 214,314 acres, *Ajra*, 80,860 acres, *Afr*, 17,865 acres, gram, 13,100 acres, oil-seeds, 23,468 acres, and cotton 22,901 acres. Rice was grown on only 383 acres. The use of manure and the rotation of crops are little understood. Land from which a spring crop has been taken is occasionally sown afresh for the autumn harvest. In the Salt Range, the richness of the soil admits of successive sowings without any repose, in the tract below the hills the torrent springing down perpetual supplies of fresh *detritus* in the alluvial fringe of the rivers, the floods fertilize the soil by their annual deposit of silt, and so render possible a constant succession of double crops, but elsewhere the land lies fallow every second year. The average output per acre of the principal products was returned as follows in 1883-84—Wheat, 750 lbs., inferior grains, 430 lbs., oil-seeds, 350 lbs., cotton, 140 lbs. The agricultural stock in the same year consisted of—cows and bullocks, 199,740, horses, 2826, ponies, 1527, donkeys, 10,860, sheep and goats, 202,293, camels, 18,174, carts 482, and ploughs, 51,015. An annual horse show is held every spring at which prizes are given for the encouragement of horse-breeding. A cattle fair was held in connection with the horse show in 1882-83. The anarchy which so vexed the break up of the Delhi Empire, and the grinding nature of the *Salt Range*, have resulted in the disintegration of the village communities. Most of the tenures at present in existence belong to the type known as *Chak*. Only 66 villages retain the ancient communal type. Agricultural labourers receive their wages either in kind, or in the form of a

proportion of the crops grown by their labour. Day-labourers receive from 3d. to 6d. per diem; skilled labourers, from 6d. to 1s. Prices of food-grains ruled as follows in 1883:—Wheat, 29½ *sers* per rupee, or 3s. 9½d. per cwt.; barley, 42 *sers* per rupee, or 2s. 8d. per cwt.; *joár*, 42 *sers* per rupee, or 2s. 8d. per cwt.; *bájra*, 46 *sers* per rupee, or 2s. 5d. per cwt.; and best rice, 6 *sers* per rupee, or 18s. 8d. per cwt.

Commerce and Trade, etc.—The commercial importance of the District depends almost entirely upon its connection with the Salt Range, Miáni having been from time immemorial the centre for the salt of the MAYO MINES in Jehlam District. Opium and *sajji* (carbonate of soda) are bought up by traders from Ráwal Pindi, Siálkot, and Kashmír (Cashmere); but most of the surplus produce of Sháhpur finds its way down the river in country boats to Múltán and Sukkur (Sakhar). The chief exports are wheat, cotton, wool, *ghí*, and saltpetre; the principal imports—sugar, English piece-goods, and metals. The Povindah merchants from Afghánistán bring down madder, dried fruits, gold coins, and spices in the winter, which they exchange for country cloth. Scarves of silk and cotton are manufactured at Khusháb; turned and lacquered toys at Sahiwál; felt at Bhera; and blankets throughout the District. The Salt branch of the Punjab Northern State Railway from Lála Músa to Bhera runs through Sháhpur District for a distance of 26 miles, with stations at Haria Málikwál, Miáni, and Bhera. Good fair-weather roads intersect the District in several directions, the chief being that from Lahore to Bannu and Dera Ismáíl Khán, which passes Sháhpur and Khusháb, and that which runs along the left bank of the Jehlam from Pind Dádan Khán to Múltán. Tolerable roads also open up the Salt Range; and the two main rivers are navigable throughout their whole course within this District, affording water communication for 112 miles. Total length of roads, 1077 miles.

Administration.—The District staff comprises a Deputy Commissioner, Assistant and extra-Assistant Commissioner, and the usual fiscal, medical, and constabulary officials. The total amount of revenue raised in the District in 1872–73 amounted to £469,955, of which sum the land-tax contributed only £43,514. The largest item is that of salt and customs, amounting to as much as £418,579. The collection of the salt-tax makes Sháhpur the most valuable District in point of revenue in the Punjab; but the mines from which the revenue is derived mostly lie within the neighbouring District of Jehlam. Excluding salt, which is merely a matter of account, the revenue of Sháhpur District in 1883–84 amounted to £55,290, of which £39,019 was derived from the land-tax. Number of civil judges, 10; magistrates, 6. The total regular and town police force in 1883 amounted to 463 officers and men, being at the rate of 1 policeman to every 10·1 square miles of area and every 908 of the population. The District jail, near

the civil station of Shahpur, contained in 1883 a daily average of 244 prisoners

Education still remains at a very low ebb, except in the four larger towns, while the nomad peasantry of the *Afr* regard it with positive aversion. The District contained in 1883-84, 44 Government schools, with a total of 2778 pupils. The Census Report of 1881 returned 3562 boys and 97 girls as under instruction in 1881, besides 10,588 males and 130 females able to read and write but not under instruction. There is one printing press at Shāhpur jail.

For administrative purposes, the District is sub-divided into 3 *tahsils*.

Medical Aspects—The climate of the plains is hot and dry, but in the Salt Range the temperature is cool and the rainfall more abundant. The annual rainfall at Shāhpur civil station for 28 years ending 1881 averaged 14.64 inches, the maximum during that period being 36 inches in 1868-69, and the minimum 11.2 inches in 1866-67. No record of temperature is now kept, but the registers of 1868-70 give a mean temperature in the shade of 80.65° F. The principal endemic diseases are intermittent and remittent fevers, dysentery and diarrhœa. Goitre prevails on the right bank of the Chenāb, and guinea-worm at the foot of the Salt Range. The total number of deaths reported in 1883 was 11,424, showing a death rate of 27 per thousand, of these, 7549, or 17.91 per thousand, were assigned to fevers. The District contains 11 charitable dispensaries, which afforded relief in 1883 to 82,226 persons, of whom 820 were in patients. [For further information regarding Shāhpur, see the *Gazetteer of Shāhpur District* compiled and published under the authority of the Punjab Government (Lahore, 1883-84). Also the *Revised Settlement Report of Shāhpur District*, conducted between 1854 and 1861 by Mr G. Ouseley, C.S., the *Punjab Census Report* for 1881, and the several annual Administration and Departmental Reports of the Punjab Government.]

Shāhpur.—*Tahsil* of Shāhpur District, Punjab, lying in the Jerch Doāb portion of the District, and consisting of a narrow belt of cultivation along the Jhelam (Jhelum) river, together with a wide sterile upland tract in the rear. Area, 1032 square miles, with 239 towns and villages, houses, 22,874, families, 25,423. Total population, 122,633, namely, males 64,585, and females 58,048. Average density, 119 persons per square mile. Classified according to religion, Muhammadans number 101,531, Hindus, 19,304, Sikhs, 1481, and Christians, 17. Of the 239 towns and villages, 168 contain less than five hundred inhabitants, 46 between five hundred and a thousand, 23 between one and five thousand, and 2 between five and ten thousand. Principal crops, wheat, *Afr*, barley, gram, cotton, and poppy. The administrative staff, including officers attached to the District head quarters, consists of a Deputy Commissioner, Judicial Assistant Com-

missioner, 2 Assistant Commissioners, 1 *tahsildár*, and 1 *munsif*. These officers preside over 6 civil and 5 criminal courts; number of police circles (*thánds*), 5; strength of regular police, 88 men; rural police or village watch (*chaukidárs*), 136.

Sháhpur.—Town and administrative head-quarters of Sháhpur District, Punjab; situated in lat. $32^{\circ} 16' N.$, and long. $72^{\circ} 31' E.$, two miles from the left bank of the Jehlam (Jhelum) river, exactly opposite KHUSHAB, on the road from Lahore to Dera Ismáíl Khán. It was formerly on the river bank, but of late years the Jehlam has been receding in the direction of Khusháb. Founded by a colony of Sayyids under one Sháh Shams, whose descendants still form the proprietary body. Sháh Shams' tomb is situated east of the town. He is revered as a saint, and a large annual fair, attended by some 20,000 persons, is held at the tomb. Population of Sháhpur village (1881), 5424; and of the civil station, which lies 3 miles to the east, 2328. Total population of town and civil station, 7752, namely, Muhammadans, 5253; Hindus, 2408; Sikhs, 74; and 'others,' 17. Number of houses, 1024. Municipal income, £131. The roads of the station are wide, and well shaded by trees, and watered in the hot weather from an inundation canal which passes through the town. Good crops of grain and grass are raised in the lands attached to the station, chiefly by the aid of canal irrigation. Small, neatly-laid-out *básár*, with wide streets. Hospital, two schools, and three public gardens. An annual horse and cattle fair is held at the civil station. Court-house, *tahsili*, police station, staging bungalow, *sardí* (native inn), and town hall.

Sháhpur.—Village in Kosi *tahsíl*, Muttra District, North-Western Provinces; situated in lat. $27^{\circ} 54' 5'' N.$, and long. $77^{\circ} 33' 30'' E.$ Population (1881) 2221. Now a petty agricultural village, but formerly the head-quarters of a large estate yielding £2800 a year, conferred by Lord Lake upon Nawáb Ashraf Alí, who ordinarily resided here, and the remains of whose fort lie outside the village. During the Nawáb's lifetime, Sháhpur was a populous and important town.

Sháhpur.—Town and municipality in Gurdaspur District, Punjab. Population in 1881, 1258, comprising 912 Hindus, 336 Muhammadans, and 10 Sikhs. Number of houses, 362. Municipal revenue (1880–81), £110; average incidence of taxation, 1s. 9d. per head of the population.

Sháhpur.—Village in Ságar *tahsíl*, Ságar District, Central Provinces. Population (1881) 2364, namely, Hindus, 1976; Jains, 299; Muhammadans, 88; and Christian, 1.

Sháhpur.—Village in Burhánpur *tahsíl*, Nimár District, Central Provinces. Population (1881) 3812, namely, Hindus, 3473; Muhammadans, 233; and Jains, 106.

Sháhpur.—Hill range in Mándlá District, Central Provinces; north

of the Narbuddi (Nerbudda) river, while the Johi flows below. Forming part of the watershed between Eastern and Western India. The scenery is wild and desolate, the only inhabitants being a few small colonies of Gonds and Baigas. The Gejri and Gajjar streams down from the highlands in a series of waterfalls, the finest of which is 60 feet high, behind the falls grow dark caverns tenanted by wild beasts and by reputed evil spirits. Most of the range, however, is under the immediate protection of Mahadeva.

Sháhpur—Petta State of the Hallar *patta* or division of Katliwar, Bombay Presidency, consisting of 4 villages, with a proprietor entitled to a payer Area, 10 square miles. Population (1881) 1237. Estimated revenue, £650, of which £46, 8s is paid as tribute to the British Government, and £14, 12s to the Nawab of Junagadh.

Sháhpura.—Native State in Rajputana Agency. Estimated area 400 square miles. Population (1881) 51,750, namely, males 27,217 and females 24,533, dwelling in 1 town and 117 villages, and in 10,849 houses. Density of population, 129.37 persons per square mile. Villages per square mile, 29, houses per square mile, 27.19 persons per house 4.77. Hindus number 48,333, Muhammadans 2771, Jains 643, and Christians, 3. The Hindus are sub-divided into Brahmans 6118, Kshatriyas, 1776, Mahijans, 4130, Gujars, 4806, Jats 4229, Minis 922, Thakurs, 1841, Chamars, 1172, Dhokurs, 357, Bhalas 2126 and others, 17,856. The Muhammadans by tribes—Shukhs 769, Sayyids 43, Mughals, 13, Pathans, 399, and others, 1545. Revenue, excluding alienations, about £25,000. The country is flat and treeless, but fertile. Much of it is pasture land.

The Rajá of Sháhpura also holds a fief under the Marátrá of Udaipur or Mewar, consisting of 80 villages with an estimated population of about 16,000 persons, and a revenue of £2500. Tribute of £300 is paid to the State of Udaipur. The Rajá is the sole sovereign of the British Government and of Udaipur. The ruling family is of the Sesodia Rajput clan, being descended from a former Raja of Udaipur. The founder of the house was Sujan Mall a viceroy of the Rana, from whom the late chief was descended in direct descent. Sujan Mall received as his portion the fief of Khetar in Udaipur, and his son also acquired from the Emperor Shah Jahan, in reward for his gallant services, a grant of the *surat* of Humaun of the crown lands of Ajmere, upon condition of furnishing certain horse and foot men for service. He abandoned the town of Bhilana and built the present town of SHAHPLA. In 1848, the Raja of Sujan received a *sanad* from the British Government fixing the amount of his tribute at £1000 per annum with the proviso that if the customs duties levied in Ajmere were abolished he should also receive

to collect such duties, and in consideration of the loss of revenue his tribute should be reduced to £200. The chief also holds a *sanad* guaranteeing to him the right of adoption. The present Rájá, Dhiráj Nahar Singh, was born in 1855. A dispensary; vaccination is encouraged. Two schools. The military force of the State consists of 12 guns, 20 artillerymen, 160 cavalry, and 335 infantry.

Sháhpura.—Capital of Sháhpura State, Rájputána. Lat. $27^{\circ} 23' 45''$ N., long. $76^{\circ} 1'$ E. School, in which Hindi and arithmetic are the chief subjects taught, attended in 1881 by 130 pupils. In 1875, a girls' school was established; but it was closed soon afterwards, though endeavours were being made in 1884 to resuscitate it. Population (1881) 10,652, namely, males 5453, and females 5199. Hindus number 8729; Muhammadans, 1920; and Christians, 3.

Sháhpurá.—Town in Rámgarh *tahsíl*, Mándlá District, Central Provinces. Population (1881) 2588, namely, Hindus, 2023; Muhammadans, 151; Jains, 5; Christians, 2; and non-Hindu aborigines, 407.

Sháhpuri.—Small island, situated at the mouth of the Náaf river in Chittagong District, Bengal; famous as having afforded the *casus belli* of the first Anglo-Burmese war. The Burmese claimed possession of the island, although it had for many years been in the undisputed occupation of the British. Tolls were levied upon boats belonging to Chittagong; and on one occasion, the demand being resisted, the Burmese fired upon the party and killed the steersman. This act of violence was followed by the assemblage of armed men on the eastern side of the Náaf, and universal consternation pervaded the villages in this the most remote and unprotected portion of Chittagong District. On the night of the 24th September 1823, the Burmese proceeded to enforce their claim to the island of Sháhpuri; a thousand men landed on the island, overpowered the guard, killed and wounded several of the party, and drove the rest off the island. As soon as this was known at Calcutta, a detachment of troops was sent to dislodge the Burmese, who, however, had previously retired. The occupation of Sháhpuri by a military force had the effect of arresting for a time the hostile demonstrations of the Burmese on the Chittagong frontier. But not long afterwards the Rájá of Arakan was ordered to expel the English from Sháhpuri, and officials from Ava proceeded to take possession of the island, which had been temporarily abandoned on account of its unhealthiness. This and other acts of hostility rendered war inevitable; and in a proclamation dated the 24th February 1824, the grounds on which the first Burmese war was declared were made known.

Shahr Sultán.—Town and municipality in Alipur *tahsíl*, Muzaffargarh District, Punjab; situated in lat. $29^{\circ} 35'$ N., and long. $71^{\circ} 2'$ E., $1\frac{1}{2}$ mile south of the Chenáb, on the road leading south from Muzaffargarh town. Population (1881) 2132, namely, Hindus, 1213; Muhammadans,

913, and Sikhs, 6. Number of houses, 275. Municipal income (1883-84), £155, or an average of 12 s^d per head. The town is favourably situated for trade, and as in all towns in this part of the country, beams are placed over the streets and covered with matting so as to form a shady arcade. Police station, and primary school.

Shahzādpur—Town in Siratha *tahsil*, Allahābād District, North Western Provinces, situated on the banks of the Ganges about a mile north of the Grand Trunk Road and 6 miles east of Siratha town, lat. $25^{\circ} 39' 55''$ N., long $81^{\circ} 27'$ E. Population (1881) 3496. Formerly a flourishing town, and famous for its stamped cloth and large trade in saltpetre, but now decayed and declining in population. Station of the Grand Trigonometrical Survey, post-office, ferry across the Ganges. A small house tax is raised for police and conservancy purposes.

Shaikhāwātī (*Shikha'ati*)—A Province of Jaipur State in Rājputāna, situated between lat. $27^{\circ} 20'$ and $28^{\circ} 33'$ N. and long. $74^{\circ} 40'$ and $76^{\circ} 5'$ E. It is bounded on the north-east by the Punjab States of Lohāru and Patāla, on the south-east by Jaipur proper, on the south by Jodhpur or Mārwār, and on the west and north west by Bikaner. The area is estimated at 5400 square miles, and the population, according to the Census of 1881, is 418 686 souls. In its physical aspects, the more fertile part of Shaikhawati resembles Jaipur, but a large portion of the soil is sandy desert, like that of Bikaner. There are no perennial rivers, but a small stream, which rises in the northern part of Jaipur, flows northward for some distance through Shaikhawati, ultimately losing itself in the sand. There is an important salt lake in the Province, called Kachhewas, it is not worked by any means to its full capacity, but the yearly turn-out of salt is about 6000 tons. The minerals of Shaikhawati are important, the copper mines near Khetri being perhaps the most valuable in India. The ores are copper pyrites, mixed, it is said, with grey copper-ore (sphaerocottahedrite), some carbonates also occur, and native copper has been found. Near the surface, also, in the shales, blue iron ore is produced by the decomposition of the pyrites. In the same mines cobalt is also obtained, the ore occurring in small veins. These mines have evidently been worked for a very long period. Some of the hills in the neighbourhood are honeycombed with old excavations, and the heaps of slag from the furnaces have accumulated in the course of time, until they now form a range of hills a hundred feet in length and from 30 to 40 feet high.

History, &c.—Shaikhawati is politically a confederation of Rājput chieftains, bound to each other and to the Government at Jaipur by the ties of clan-ship. The Shaikhawatis are a sept Kachwaha clan whose head is the Mahārāj of Jaipur. Their name derives its origin from the grandeur of their

younger son of the Mahārājā of Jaipur in 1389 A.D., and received a portion of this territory in appanage. Shaikhjī was so called from a famous Musalmān saint named Shaikh Burhān, whose shrine near Achrol is still regarded with veneration, and whose prayers had been successfully invoked by Shaikhjī's father for the birth of a son and heir. In commemoration of this incident, every Shaikhāwat boy wears for two years from his birth the Musalmān *badiā* or threads, as well as the blue tunic and cap; and the Shaikhāwat sportsmen never hunt the wild hog or touch its flesh, although by other Rājputs it is commonly eaten once a year. Moreover, although the lands surrounding the saint's *dargah* belong now to the demesne of the Jaipur Mahārājā, the *dargah* itself is a sanctuary, and rent-free lands are held by about a hundred families descended from Shaikh Burhān. Shaikhjī's father and grandfather had paid as tribute to the Mahārājā all the colts reared on their land; but Shaikhjī so enlarged his power that for some generations the lords of Shaikhāwati became independent of the parent State.

From Shaikhjī's great-grandson, Rāi Sīl, are descended the chieftains of Southern Shaikhāwati, who hence have always been known as Rāisilots; and from a younger son of Rāi Sīl are descended the principal chieftains of Northern Shaikhāwati, called the Sādhānis. The chief settlement of the Rāisilots, and the most important principality of Shaikhāwati, was at Khandela; whilst the early seat of the Sādhānis was at Udaipur, another town of this territory, not to be confounded with the capital of Mewār. There have been, and still are, many other branches of the family, between whom feuds, conquests, and reconquests have been interminable. Rāi Sīl himself became chief both of Khandela and of Udaipur by the help of the Delhi Emperor; and he is mentioned in the *Ain-i-Akbarī* as a *mansabdār* of 1250 horse under Akbar. After the fatal battle of Merta, in 1754, had laid Rājputāna prostrate at the feet of the Marāthās under De Boigne, Shaikhāwati suffered severely from their ravages; most of the towns were sacked, the capital, Khandela, being saved from that fate only by heavy payment. Later on, it was the scene of some of the exploits of the famous adventurer George Thomas, who was called in by a chief of Khandela to aid him against Jaipur. Finally, however, the Shaikhāwat chieftains acknowledged the suzerainty of Jaipur, though the bond seems never to have been very close. The leading chiefships are those of Sikar and Khandela, Khetri, and Kotputli.

The custom of equal division on succession to land in Shaikhāwati is similar to that which prevails in Malāni, a dependency of Jodhpur that holds much the same kind of relation to its parent State that Shaikhāwati does to Jaipur; and therein the custom differs from that prevalent elsewhere throughout Rājputāna, where the eldest son suc-

ceeds. The custom, however, does not appear to extend to the larger estates and chiefships in Shaikhiwati.

Shaikh Budin (*Shekh Budin*)—Hill sanatorium (so called from the shrine of a famous Muhammadan saint, Shaikh Bahā ud-dīn, which crowns its summit) in Binnu (Bunnoo) and Dera Ismā'il Khān Districts Punjab, lying in lat $32^{\circ} 17' 48''$ N., and long $70^{\circ} 50' 48''$ E., on the border of the two Districts, and jointly administered by the Deputy Commissioners of both Districts. Elevation above sea level, 4516 feet. Distant from Dera Ismā'il Khān town 40 miles north, from Binnu town 64 miles south. The sanatorium crowns a bare limestone rock, which rises abruptly from the low range of Mohar, whose highest point it forms. A few stunted wild olives and acacias compose the only vegetation on the shadeless slope. The heat is frequently excessive, the thermometer ranging inside a bungalow from 88° to 94° F., though mitigated from June to October by a cool south western breeze. This drawback, combined with the want of sufficient water supply and the paucity of building sites, renders Shaikh Budin a very inadequate sanatorium. Persons who go up in good health are seldom attacked by illness, but the climate is not bracing enough for constitutions which require a radical change.

Shaikhpurā—Town in Monghyr District, Bengal. Lat $25^{\circ} 8' 30''$ N., long $85^{\circ} 53' 11''$ E. Population (1881) 11,517, namely, males 5945, and females 6572. Hindus number 8411, and Muhammadans 4106.

Shakargarh—*Tahsil* of Gurdāspur District, Punjab, comprising the whole trans Ravi portion of the District, except Narot *farq*. Area, 501 square miles, towns and villages, 709, houses, 29,592, resident families, 47,508. Total population, 219,511, namely, males 114,617, and females 104,894. Classified according to religion, Hindus number 109,241, Muhammadans, 105,176, Sikhs, 5090, and Christians, 4. Average density of population, 438 persons per square mile. Of the 709 villages and towns, 594 contain less than five hundred inhabitants, 83 between five hundred and 1000, and 132 between one thousand and five thousand. The average annual area under cultivation for the five years ending 1881-82 is returned as 323½ square miles, or 207,079 acres. The principal crops being—wheat 76,457 acres, barley, 48,195 acres, rice, 11,603 acres, Indian corn, 8523 acres, *moth*, 7009 acres *far*, 6899 acres *barley*, 2845 acres, gram, 2687 acres, sugar-cane, 9519 acres cotton 5783 acres, tobacco 1151 acres, and vegetables 1723 acres. Revenue of the *tahsil*, £27,783. The administrative staff consists of a *Deputy Commissioner*, who preside over 1 criminal and 2 civil courts, 10 sub-divisional police circles (*thanas*), 3, regular police, 481 constables, 1000 irregular rural police (*chakdar*), 673.

Shakargarh.—Town and fort in Pesháwar District, Punjab.—*See* SHABKADAR.

Shálamár (*Sháhlímár*).—Gardens and pleasure-ground in Lahore District, situated 4 miles east of Lahore city. These gardens were laid out in 1667 by Alí Mardán Khán, the celebrated engineer of Sháh Jahán, in imitation of the garden planned by the Emperor Jahángír at the sources of the Jehlam (Jhelum) river in Kashmír (Cashmere). The garden consisted of seven divisions representing the seven degrees of the Paradise of Islám, of which only three are included in the present area of about 80 acres, the remainder having fallen into decay. In the centre is a reservoir bordered by an elaborately indented coping and studded with pipes for fountains. A cascade falls into it over a slope of marble corrugated in an ornamental carved diaper. During the troublous times of Ahmad Sháh the gardens were neglected, and some of the decorative works were defaced and removed. Ranjít Singh restored them; but at the same time he laid ruthless hands upon the marble pavilions of the central reservoir, using them to adorn the Rámbágh at Amritsar, and substituting structures of brick and whitewash in their stead. The Shálamár Gardens are a favourite resort for fêtes and picnics, and the luxuriant foliage of the mango and orange trees lends itself with admirable effect to illuminations.

Sháli.—Hill in Bhajji State, Simla District, Punjab. Lat. $31^{\circ} 11' N.$, long. $77^{\circ} 20' E.$ Described by Thornton as rising in a steep and almost inaccessible peak 4 miles south of the Sutlej (Satlaj), and containing on its summit a wooden temple where human sacrifices were formerly offered to the goddess Káli. Elevation above sea-level, 9623 feet.

Shalvari.—Town in Dhárwár District, Bombay Presidency; situated 32 miles east by north of Dhárwár town. Population (1872) 5220; not separately returned in the Census Report of 1881.

Shami.—Town in Rádhanpur State, Bombay Presidency; situated on the river Saraswatí, in lat. $23^{\circ} 41' 15'' N.$, and long. $71^{\circ} 50' E.$ Population (1881) 5306, namely, Hindus, 2592; Muhammadans, 2173; and Jains, 541.

Shámli.—North-western *tahsíl* of Muzaffarnagar District, North-Western Provinces; comprising a level upland, traversed throughout by the Eastern Jumna Canal, whose distributaries extend over every part of its surface. Area, 461 square miles, of which 268 square miles are cultivated. Population (1881) 202,233, namely, males 108,479, and females 93,754. Hindus number 139,522; Muhammadans, 61,262; Jains, 1439; and 'others,' 10. Average density, 438.7 persons per square mile. Of the 253 villages and towns, 146 contain less than five hundred inhabitants; 59 between five hundred and a thousand; 43 between one and five thousand; and 5 upwards of five thousand inhabitants. Land revenue, £32,099; total Government revenue,

£37,548, rental paid by cultivators, £71,239. The *tahsil* comprises the five *parganas* of Shāmlī, Thānī Bhāwan, Jhānjhānī, Kairānī and Bidaulī. In 1884 it contained 1 civil and 2 criminal courts, strength of regular police, 68 officers and men, rural police or village watch (*chaukidars*), 424.

Shāmlī.—Town in Muzaffarnagar District, North Western Provinces, and head quarters of Shāmlī *tahsil*, situated in lat 29° 46' 45" N., and long 77° 21' 10" E., on the bank of the Eastern Jumna Canal, 24 miles west of Muzaffarnagar town, on a low unhealthy site. Population (1881) 7359, namely, Hindus, 5607, Muhammadans, 1664, and Jains, 88. The town contains a handsome *li-fir*, and carries on a considerable trade with the Punjab, consisting of exports of sugar and imports of salt. The place was originally known as Muhammadpur Zanīrdār, but derives its present name from one Shām, who built a market in Jahāngīr's reign. Held in 1794 by a Marāthā commandant, who fell under suspicion of intriguing with the Sikhs. Lakshī Dada, the Marāthā governor, despatched George Thomas against the commandant. Thomas stormed the town and cut to pieces the suspected parties. In 1804, Colonel Burn was surrounded at Shāmlī by an overwhelming force of Marāthās, but escaped from a desperate position through the opportune advance of Lord Lake. During the Mutiny of 1857, the native *tahsildar* held the town bravely for the British, but fell at last gallantly defending his post against the insurgents of BHĀWAN. Police station, post office. A small house-tax is raised for police and conservancy purposes.

Shāmsābād.—Town in Larukhībīd District, North Western Provinces, situated in lat. 27° 32' 15" N., and long 79° 28' 40" E., on the south bank of the Bari Ganga river 18 miles north west of Lathgarh town. Population (1881) 8271, namely, Hindus 4467, Muhammadans, 3800, and Jains, 4. The town is composed of 33 *challas* or wards, which are divided into scattered groups by patches of cultivation. The wards consist as a rule of great clusters of mud huts, surrounding a few large brick houses or hemming in a road. The principal thoroughfare is a long brick paved street of mixed dwellings and shops, from which branch many narrow lanes. A small grain market opens on the south into a larger market place, shaded by fine timarind and *sim* trees. Shāmsābād is no longer the seat of any important trade or manufacture, but prior to the introduction of English cloth, it was noted for its fine textures, known as *mithī* and *ghura*. Police station, post office, school, and *sardī* (native inn). A small house-tax is raised for police and conservancy purposes.

Shamsha (or *Shimshaf*, also called the *Andhra* and the *Andra* *Andra*)—Tributary of the Kāven (Cauvery) river, in Mysore. It rises in lat 13° 25' N., long 77° 15' E., in Tūmkūr District near

Deveráy-durga, and flows in a southerly direction to join the Káveri, in lat. $12^{\circ} 19' N.$, long. $77^{\circ} 18' E.$, just below the falls of Sivasamudaram, in Mysore District. In Túngkúr District its waters are utilized to form the great Kadaba tank; and in Mysore District it is crossed by a dam or anicut 9 miles above Maddúr. This anicut has recently been rebuilt by the Public Works Department of hewn stone. It feeds the Maddúr tank, and supplies irrigation channels 12 miles in length, capable of irrigating 2240 acres, and yielding a revenue of £671.

Shámsherganj.—Village in Sylhet District, Assam; situated in lat. $24^{\circ} 43' N.$, and long. $91^{\circ} 34' E.$ There is a considerable river trade, the exports being—rice, oil-seeds, molasses, *sítalpáti* and bamboo mats; and the imports—piece-goods, pulses, spices, and tobacco.

Shanor.—Petty State of the Sankheda Mehwas group, Rewá Kántha, Bombay Presidency. Area, $11\frac{1}{2}$ square miles, containing 6 villages. Estimated revenue, £1013, of which £135 is paid as tribute to the Gáekwár of Baroda. The chief is a younger branch of the Mándwa family.

Shápur.—Petty State of the Hallár *prant* or division of Káthiáwár, Bombay Presidency.—*See* SHAHPUR.

Sháradánadí (or *Anakapalli*).—River in Vizagapatam District, Madras Presidency. Rises in the Mádgula Hills, and flowing south-west past Anakapalli and Kásimkota, enters the sea at Wattada. It is much used for irrigation, being crossed by six large anicuts. The total length of the river is about 45 miles.

Shárapur.—*Tahsíl* of Lahore District, Punjab, comprising the whole trans-Rávi portion of the District. Area, 887 square miles; towns and villages, 379; houses, 21,002; families, 25,033. Total population, 121,451, namely, males 66,485, and females 54,966. Classified according to religion, Muhammadans number 97,244; Hindus, 16,993; Sikhs, 17,210; and Christians, 4. Average density of population, 137 persons per square mile. Of 379 towns and villages, 316 contain less than five hundred inhabitants, 48 between five hundred and a thousand, and 15 between one and five thousand. Principal crops—wheat, barley, rice, Indian corn, gram, and cotton. Revenue of the *tahsíl*, £11,619. The administrative staff consists of a *tahsildár* and *munsif*, presiding over 1 criminal and 2 civil courts; number of police circles (*thánás*), 2; regular District and town police, 51 men; village watch or rural police (*chaukidárs*), 102.

Sharakpur.—Town in Lahore District, Punjab, and head-quarters of Sharakpur *tahsíl*; situated in lat. $31^{\circ} 27' N.$, and long. $74^{\circ} 6' E.$, west of the Rávi, and on the bank of the river Degh. Population (1881) 4595, namely, Muhammadans, 3853; Hindus, 546; and Sikhs, 196. Municipal income (1883–84), £345, or an average of 1s. 6d. per head. The town is surrounded by a high and thick mud wall, intersected by

streets paved with brick. The public buildings include the Sub-divisional courts and offices, police station, school house, and dispensary. The best rice produced in the District is grown in the neighbourhood of this town, on land irrigated from the Deh. Sharikpur is the only town of any importance in the trans-Ravi tract of Lahore, and the centre of a considerable trade in local produce.

Sharavati ('*The Arrow*')—River of Southern India, which rises in lat $13^{\circ} 44' N$, long $75^{\circ} 11' E$, at Amburthi in Shimoga District Mysore State, flows in a north westerly direction through the District of Shimoga, and after breaking through the line of the Western Ghats by a sheer leap of 830 feet over the magnificent Falls of Gersoppa into a pool 350 feet deep falls into the sea at Honavar in the Bombay District of North Kanara. In Shimoga District, the stream is crossed by 70 weirs or dams, from which irrigation channels are drawn having an aggregate length of 26 miles.

Sharretalai—*Taluk* or Sub division of Travancore State, Madras Presidency. Area, 129 square miles, containing 38 *karas* or collections of villages. Population (1875) 114,931, (1881) 113,704, namely, males 56,204, and females 57,500, occupying 29,662 houses. Density of population, 881 persons per square mile. Hindus number 83,580, Christians, 26,416, Muhammadans, 3,706, and Jews 2. Of the total Christians, Roman Catholics number 15,738, Syrians 10,600, and Protestants, 78.

Sharretalai—Chief town of the Sharretalai *taluk* of Travancore State, Madras Presidency, situated in lat $9^{\circ} 41' 30'' N$, and long $76^{\circ} 23' 20'' E$. Population (1871) 9,228 (among whom are many Christians), dwelling in 2,190 houses, not separately returned in the Census Report of 1881. The town contains a pagoda, which is the scene of an annual festival, and a Syro-Roman Church, built about 1550 A.D.

Shatal (*Shirul*)—Mountain pass in Bashahr (Bussahir) State, Punjab, on the road from Chauri to Kunwar, over the southernmost ridge of the Himalayas. Lat $31^{\circ} 23' N$, long $78^{\circ} 31' E$. Mentioned by Thornton as dangerous on account both of the deep snow and cold wind. Elevation above sea level, 15,555 feet.

Shegaon—Town in Akola District, Perar, and a station on the Nagpur branch of the Great Indian Peninsula Railway, situated in lat $20^{\circ} 18' N$, and long $76^{\circ} 46' E$, 24 miles west of Akola town, and about 11 miles from Bilaspur and Khamgaon. Population (1881) 11,079, namely, males 5,753 and females 5,326. Hindus number 9,891, Muhammadans, 1,067, Jains, 72, Christians 41, Parsis 7, and Jews 3. Before the opening of the railway in 1863, Shegaon had little commerce, but considerable supplies of cotton have of late been brought to the market here instead of to Akola. There are several cotton presses, some under European superintendence.

Travellers' bungalow, *sardī* (native inn), and police station; Government school, and post-office.

Shekhāwati.—Province or Division of Jaipur State, Rājputāna.—*See* SHAIKHAWATI.

Shekh Budin.—Sanatorium and mountains in Derā Ismāil Khān and Bannu Districts, Punjab.—*See* SHAIKH BUDIN.

Shekohpura.—Ancient town in Hāfizābād *tahsīl*, Gujranwāla District, Punjab; situated on the road between Hāfizābād and Lahore, 22 miles from the former town. Contains a ruined fort, built by the Emperor Jahāngīr. Prince Dāra Shekoh, grandson of Jahāngīr, from whom the town probably derives its name, is said to have connected it by a cut with the Aik rivulet, and this cut now forms the main channel of the stream. Under Ranjit Singh, Shekohpura became the residence of one of his queens, Rānī Rāj Kauran, better known as Rānī Nakāyan, whose cumbrous brick palace still remains the most conspicuous object in the town. After British annexation, the headquarters of the District were fixed for a time at this spot; but since the removal of the civil station to Gujranwāla, Shekohpura has possessed no importance of any sort, except as a resort for sportsmen. About two miles distant from the town, is a large tank surrounded by handsome flights of steps, with a three-storied *baradārī* in the centre. The tank, however—to fill which the cut from the Aik rivulet above mentioned was made—is dry, and indeed is said to have never had water in it. A lofty watch-tower stands beside the tank.

Shellā.—Petty State or confederacy in the Khāsī Hills, Assam; presided over by four elective chiefs of equal authority, with the title of *wāhadāddrs*. Population (1881) 6032; revenue, £70. The natural products include oranges, pine-apples, and betel-nuts. Bamboos are worked into mats and baskets. Limestone is extensively quarried, and both coal and iron are found. Shellā has been for many years a station of the Welsh Calvinistic Mission, who maintain several schools in which English and vernacular are taught, and also a girls' school.

Shendamangalam.—Town in Námkal *tāluk*, Salem District, Madras Presidency. Lat. 11° 40' 30" N., long. 78° 10' 20" E. Population (1881) 12,575, namely, males 5866, and females 6709, occupying 2268 houses. Hindus number 11,687; Muhammadans, 683; and Christians, 205. A considerable amount of iron is smelted here.

Shendúrjāna.—Town in Amráoti District, Berar.—*See* SENDURJANA.

Shendurni.—Town in Khándesh District, Bombay Presidency; situated in lat. 20° 39' N., and long. 75° 39' E., 60 miles south-east of Dhulia, and 12 miles east of Páchora station on the Great Indian Peninsula Railway. Population (1881) 5644. Hindus number 4566; Muhammadans, 924; Jains, 128; Christians, 2; and 'others,' 24.

Shendurni was a grant made to the family priest of the Peshwā, Bājī Rāo. An annual Hindu fair is held here. Post-office.

Sheng dha-wai (*Shin-da-ai*)—A highly venerated pagoda in Tavoy District, Tenasserim Division, Lower Burma.—See SHIN DA WAI.

Sheng maw (*Shin-mar*)—Pagoda on Tavoy Point, Tenasserim Division, Lower Burma.—See SHIN MAW.

Sheng māt ti (*Shin-mot-ti*)—The most famous pagoda in Tavoy District, Tenasserim Division, Lower Burma.—See SHIN MUT TI.

Shenkotta.—*Taluk* or Sub-division of Travancore State, Madras Presidency. Area, 65 square miles, containing 70 *kras* or collections of villages. Population (1881) 30,477, namely, males 14,688, and females 15,789, occupying 8759 houses. Density of population, 469 persons per square mile. Hindus number 27,513, Muhammadans, 2145, Christians, 819. Of the Christians, Roman Catholics number 386, Protestants, 375, Syrians, 58.

Shenkotta—Chief town of the Shenkotta *taluk* of Travancore State, Madras Presidency, situated in lat $8^{\circ} 59'$ N., and long $77^{\circ} 17' 45''$ E., on the main road from Frevandrum and the South Travancore ports, across the Ghāts, to Tinnevely, from which place it is distant about 40 miles. Population (1881) 7882, inhabiting 2214 houses. Several coffee estates have been opened in the neighbourhood of Shenkotta, which is an important centre of trade.

Sheogāon—Sub-division and town of Ahmadnagar District, Bombay Presidency.—See SHEGON.

Sheopur—Town in Gwalior State, Central India.—See SHEOPUR.

Sher—River of the Central Provinces, rising in lat $22^{\circ} 34'$ N., long $79^{\circ} 44'$ E., near Khimrit in Seoni District, which, after a north-westerly course of 80 miles, falls into the Nerbadi (Nerbudda), in lat $23^{\circ} 4'$ N., long $79^{\circ} 10'$ E., near the centre of Narsinghpur District. It is spanned by a fine stone bridge at Sonā Dongri in Seoni, which carries the Nagpur and Jabalpur road, and the Great Indian Peninsula Railway crosses it by a lattice girder bridge 8 miles east of Narsinghpur. Coal, but of no commercial value, has been found in the river bed near Sihori in Narsinghpur. Principal affluents—the Michha, Kewā, and Bād Riwā.

Sheraingal.—*Taluk* or Sub-division of Travancore State, Madras Presidency. Area, 143 square miles, containing 88 *kras* or collections of villages. Population (1881) 87,072, namely, males 42,193 and females 44,879, occupying 18,994 houses. Density of population, 609 persons per square mile. Hindus number 72,029, Muhammadans, 13,132, Christians, 1911. Of the Christians, Roman Catholics number 1824, Protestants, 49, Syrians, 34.

Sher Ali—Port in North Kanara District, Bombay Presidency.—See SHIRALI.

Shergarh.—Town in Chhāta *tahsíl*, Muttra (Mathūra) District, North-Western Provinces; situated in lat. $27^{\circ} 46' 40''$ N., and long. $77^{\circ} 39' 50''$ E., on the right bank of the Jumna (Jamuná), 8 miles north-east of Chhāta town. Population (1881) 4712. The town derives its name from a large fort, now in ruins, built by the Emperor Sher Sháh. The original *samindárs* of Shergarh were Patháns, from whom, with the exception of a small share held by a Muhamminadan descendant of the old family, the estate passed by purchase to a wealthy banker, Seth Gobind Dás, and was devoted by him to the maintenance of the temple of Dwárakádis at Muttra. A small house-tax is raised for police and conservancy purposes.

Shergarh.—Ruined village in Sháhábád District, Bengal; situated in lat. $24^{\circ} 49' 45''$ N., and long. $83^{\circ} 46' 15''$ E., 20 miles south-west of Sásserám. This spot was selected by Sher Sháh as the site of a fortress soon after he had begun strengthening ROHTAS, which he abandoned on discovering the superior advantages of Shergarh.

Shergháti.—Town and municipality in Gayá District, Bengal; situated at the point where the Grand Trunk Road crosses the Murahar, in lat. $24^{\circ} 33' 24''$ N., and long. $84^{\circ} 50' 28''$ E. Population (1881) 5862, namely, Hindus 3649, and Muhammadans 2213. Municipal income (1883–84), £112, all derived from taxation; average incidence, $4\frac{1}{2}$ d. per head. The town has declined in importance since the construction of the East Indian Railway. There are still to be found here the descendants of skilled artisans, workers in brass, wood, and iron. When Shergháti formed part of the District of Rámgarh it was known as a centre of crime, which led to the appointment of a special Joint Magistrate in 1814.

Sherkot.—Town in Bijnáur (Bijnor) District, North-Western Provinces; situated in lat. $29^{\circ} 19' 25''$ N., and long. $78^{\circ} 38' 10''$ E., on the bank of the Kho river. Population (1881) 15,087, namely, males 7428, and females 7659. Muhammadans number 10,213; Hindus, 4756; and Jains, 118. Sherkot was formerly the head-quarters of Dhámpur *tahsíl*, and is still the residence of a powerful Rájput family, owners of the Sherkot estate, whose handsome palace, with two Hindu temples attached, stands just outside the town on the north-west. The principal places of business are the Kotra and Sherkot *bázárs*—the former a wide brick-paved roadway, standing on high ground, and flanked with good shops; the latter a long irregular and narrow street in which two carts can scarcely pass each other. The town has a considerable trade in sugar, and is noted for its manufacture of embroidered carpets. The public buildings include a police station, post-office, dispensary, Anglo-vernacular school, and *sarái* or native inn. The police and conservancy arrangements of the town are provided for by a small house-tax, yielding about £400 annually.

Shermādevī (*Sheranmahidei*)—Town in Ambāsumudaram *taluk*, Tinnevely District, Madras Presidency, situated in lat $8^{\circ} 40' 40''$ N., and long $77^{\circ} 35' 13''$ E., on the Tímbraparni river, 12 miles west of Tinnevely. Formerly head-quarters of the *taluk* of the same name, at present residence of the Head Assistant Collector of the District. Population (1881) 7624, number of houses, 1738. Hindus number 7191, Muhammadans, 61, and 'others,' 372.

Sheroda—State in Kāthiāwār, Bombay Presidency.—See SHIRODA.

Sherpur.—Town in Zamānrah *tahsil* Ghazīpur District, North Western Provinces, situated in lat $25^{\circ} 34' 40''$ N., and long $83^{\circ} 50'$ E., on a large island formed by the Ganges, 10 miles east of Ghazīpur, and 17 miles north west of Zamānrah town. Population (1881) 9030, namely, Hindus 8756, and Muhammadans 274. Number of houses, 1787. Although returned as one town in the Census Sherpur itself is divided into two parts, and also includes three outlying agricultural villages. Village school.

Sherpur—Town and municipality in Bogra District, Bengal. Lat $24^{\circ} 40' 20''$ N., long $89^{\circ} 25' 20''$ E. Population (1881) 3991, namely, Hindus 2712, and Muhammadans 1279. Municipal income (1883-84), £390, of which £298 was derived from taxation, average incidence of taxation, is 8½d per head. Though the number of Hindus is so great, the town is surrounded on all sides by Muhammadan places of worship, which are held in much esteem. The proportion of brick built houses is unusually large, and the principal landholders of the District reside here. But it is as a place of historical interest that Sherpur is most deserving of notice. It is mentioned in the *Ain Akbari*, 1595 A.D., as the site of a fort called Salimnagar, in honour of Salim, the son of Akbar, afterwards famous as the Emperor Jahangir. It also figures in the writings of other Muhammadan historians as an important frontier post, previous to the conquest of South Eastern Bengal, and the establishment of the Government at Dacca. These writers always refer to the place as Sherpur Murchā to distinguish it from another Sherpur in Maimansingh, and it is marked on Van den Proucke's Map (1660) as 'Ceerpoor Mirts.' Rājā Man Singh, Akbar's Hindu general, is said to have built a palace at Sherpur, and it is very probable that he would make use of so convenient a centre, from which to dominate Southern Bengal, and particularly Jessor, which then included a large part of the present District of Pabna, and was held by the rebel *Amir* Rājā Pratāpīditya, against whom Man Singh specially directed his arms.

Sherpur—Town and municipality in Maimansingh District, Bengal. Lat. $25^{\circ} 0' 58''$ N., long $90^{\circ} 3' 6''$ E., lies between the rivers Shiri and Mirghi, about half a mile from the former and 1 mile from the latter, 9 miles north of Jamalpur. Population (1881) 8710, including the

suburbs of Náráyanpur and Barukpára. Muhammadans number 4467; Hindus, 4161; and 'others,' 82. Municipal income (1883-84), £456, of which £383 was derived from taxation; average incidence of taxation, 10½d. per head. There is no water carriage to the town, and even water for drinking and household purposes is obtained solely from tanks. Sherpur contains a fine Hindu temple; its buildings in general are in bad repair, and the place has a decayed and neglected appearance. Police station, post-office, *munsif's* court, and a good school. Considerable river trade. In 1876-77, the registered exports comprised 27,100 *maunds* of jute (mostly sent to Náráyananj), 35,100 *maunds* of rice and paddy, and 30,600 *maunds* of mustard seed; the imports included European piece-goods, valued at £5770, and 1200 *maunds* of betel-nuts. Owing to an alteration in the system of trade registration, no later statistics are available. A weekly newspaper, the *Charu Bartha*, is published at Sherpur, the proprietor being one of the leading Hindu *zamíndárs*.

Sherpur.—Sub-division and town of Khándesh District, Bombay Presidency.—See SHIRPUR.

Sher Sháh.—Large village in Múltán District, Punjab; situated in lat. 30° 6' 45" N., and long. 71° 20' E., upon the Chenáb river. Until the opening of the Indus Valley State Railway in 1879, Sher Sháh was the terminus of the line from Múltán, and the port of the steam flotilla that plied to Karáchi (Kurrachee).

Shervaráyar Malai.—Hills in Salem District, Madras Presidency.—See SHEVAROY.

Shetrunja (*Satrunjaya*).—Place of Jain pilgrimage in Pálitána, Gujarát, Bombay Presidency.—See PALITANA TOWN.

Shevaroy.—Hill range in Salem District, Madras; situated between 11° 43' and 11° 55' N. lat., and between 78° 13' and 78° 24' 30" E. long. The hills occupy a total area of 151·67 square miles, with a plateau of about 20 square miles; a high plateau (Yercaud) on the southern portion of the eastern block of about 10 square miles; and plateaux (Púliyúr and Nagalúr) on the east and west sides of the Green Hills. The last-named form the western portion of the Shevaroy, and are separated from the eastern portion by the valley of the Vanniar. Average elevation, 4500 feet; highest point in the Green Hills, 5410 feet above the sea. The total population of the hills was returned in 1881 at 10,513.

Three regular *gháts* or passes lead to the table-lands—(1) the Salem *ghát*, on the south, which commences at the fifth milestone from Salem, about 5½ miles long, is the favourite *ghát* pass, as coolies are more easily obtained; it is in some parts very steep: (2) the Ahtúr *ghát* commences at the Shevaroy Hills station on the Madras Railway south-west line; the distance by it to Yercaud is about 11 miles: (3) the

Mallapuram *g/it* on the north, distance from Mallapuram station on the Madras Railway south west line to Vercaud, about 19 miles. This *g/it* is of easy gradient for the first 9 miles, but very steep in its ascent to the Nagaldr plateau. Besides these well known *g/its*, the hills are accessible by footpaths from many other points.

The native inhabitants of the plateau and slopes consist of Vellalirs or Malaylis (See SOUTH DISTRICT). Their former mode of cultivation was *kumdra* or nomadic tillage which consists in clearing and burning a piece of forest or jungle after which the soil is turned up with a hoe and sown, the next year this land is abandoned for a fresh spot. This system, however has been put a stop to by the Forest Department, as it was extremely destructive. The number of Malaylis inhabiting the hills is not known but they are supposed to be increasing, looking to the amount of revenue received from them.

Monumental remains are common and consist of urns or cromlechs, much resembling those found on the Nilgiris. The present inhabitants have no traditions relating to them.

The vegetation does not differ materially from that of other hill ranges of Southern India. The base of the Shevaroy contains is covered with the common forms of vegetation found in the adjoining low country. The middle region is clothed with a zone of bamboo jungle, which reaches to a height of about 3000 feet where it abruptly terminates. Oak, blackwood and sandalwood are also found, in favourable situations up to these elevations. The oak in a stunted form, is met with on the mountain plateau at an elevation of 4500 feet. The soil and climate seem to be peculiarly adapted for horticultural operations. Among important plants which thrive richly may be mentioned the pear, loquat, peach, apple, guava, strawberry, guava, orange, lime, lemon, and Brazil cherry. The Australian acacia, eucalyptus and the casuarina grow. The silk oak (tree leather) flourishes. Cinchona has been introduced and is thriving. The coffee plant was introduced in these hills about forty years ago by Mr. Cassin, an officer of the Madras Civil Service, and in 1893 the total area taken up by plantations was about 10,000 acres, of which, however, only 5000 is now cultivated. The number of coffee plantations is now 1500. The tea plant grows luxuriantly though it has not yet been cultivated with a view to the manufacture of tea. Oranges are common especially the Seville and sweet varieties. The lemon lime and shaddock succeed equally well.

The most common animals are the goat, bear and hog; jungle sheep, mouse-deer, hyena, jackal and leopard are also met with. Tigers are sometimes met with. A few bison exist on the neighbouring hills, but of late years have not been seen on the Shevaroy. Among birds mentioned the jungle and spur fowl, jungle thrush, quail, wild pigeon,

woodcock, and snipe. Cobras, vipers, scorpions, and centipedes are seldom found.

When the Shevaroy's first began to attract notice forty years ago, the Government revenue derived from the whole of the hill villages was £35 yearly, which by 1883 had increased to upwards of £800. The great present want is a cart road from Salem, and the improvement of the interior roads. The revenue from coffee land is about £500, and from land under native cultivation, £300. A small detachment of police from Salem District is stationed on the hills. A Deputy *tahsildár* resides at Yercaud, and the Salem *munsif* visits the place once every three months to decide suits. There are European residents at Yercaud, and visitors resort to the station for the hot weather and holidays; accommodation is scarce. Church, post-office, dispensary, reading-room, club, and hotel.

The principal localities on the Shevaroy's are Yercaud, the Green Hills, Nagalúr, Púliyúr, Pútipádi, Maramangalam, and the Talasholay spur.

YERCAUD (Yerkádu) is the oldest and largest European settlement in the hills. It is situated on that portion of the plateau nearest to the town of Salem. The land in the valleys is undulating, and a great portion of it is already under coffee cultivation. The hill peaks are for the most part bare of soil, and the steep slopes are covered with low jungle.

The Green Hills are higher than any other portion of the range, and vary from 4500 to 5400 feet above sea-level. They differ much in appearance from any other portion of the Shevaroy's. The tops of the hills are rounded, and covered only with grass and low stunted shrubs; the ravines are wooded, as on the Nilgiris (Neilgherries). The rounded and undulating appearance of this portion of the Shevaroy's contrasts markedly with the rugged peaks and wooded slopes about Yercaud. This difference is due chiefly to the Green Hills being capped with laterite, in some places of considerable thickness. Several coffee plantations have been opened by Europeans and Eurasians upon the Green Hills; and there is a fine expanse of table-land, partly under cultivation by the hill tribes, which has been pointed out as a site well adapted for a sanitarium for European troops. This site occupies about 250 acres of land, and appears to be eminently suited for building.

The Shevaroy range possesses a very equable climate. Partaking as it does of both monsoons, the rainfall is considerable, being an annual average of from 65 to 70 inches, or double that of the rainfall on the surrounding plains. The moisture of the air is tolerably constant during the year. In a room without fire, and with open windows, the thermometer seldom stands below 65° F., and rarely

covered with caper and thorn jungle, constitute a distinctive feature in the landscape. The desert portion of the Rohri Sub-division, known as the *Registhán*, possesses extensive sandhills, bold in outline and often fairly wooded. The forests of Shikárpur cover a total area of 207 square miles.

History.—The Districts of Upper Sind can hardly be said to have a history separate from that of the whole Province. Before the Muhammadan invasion, in 712 A.D., this portion of Sind was ruled by a Bráhma race, with their capital at Aror (or Alor), 5 miles distant from the modern town of Rohri. Shikárpur continued for some time a dependency of the Ummayid dynasty, and subsequently of the Abassides. In conjunction with the rest of Sind, it was conquered by Mahmúd of Ghazní, about 1025 A.D.; but his rule was of short duration, being replaced, about 1032, by the Súmra dynasty. The latter was succeeded in its turn by the Samma family, and this again by the Arghúns; for an account of all of which, see the article on SIND.

Upper Sind does not come into any prominence till the accession to power of the Kalhora dynasty, in the early part of the 18th century. Previous to this, the country, which had been annexed in 1591–92 to the Delhi Empire by Akbar, was ruled by a succession of governors; and a powerful tribe, the Dáúdputras, had arisen and displaced the Mahars, an influential clan, whose chief town was then at Lakhi, 9 miles south-east of Shikárpur town. These Mahars had themselves some time before driven out the Jatois, a race of Balúchís, in a manner thus described by Captain (now Major-General) Sir F. G. Goldsmid, in his historical memoir of Shikárpur, written in 1854:—

‘There were seven brothers of the tribe (Mahars) in Ubauro, near the present Baháwalpur frontier, of whom one, by name Jaisar, not finding a residence with his near kindred to accord with his views of independence, turned his steps to Bukkur (Bakkar), then occupied by the noted Mahmúd, governor, under Sháh Beg Arghún, of the fort in 1541 A.D.

‘The Jatois, a race of Balúchís, held the country on the west bank of the river between Búrdika and Lárkhána. This included the town of Lakhi, then a flourishing place, so called from Lakhu, as Gosarji was from Gosar, and Adamji from Adam Jatoi. Jaisar crossed the river and took up his abode among the villages of this people. The Mahars and their new comrades disagreed; but the former had a friend at court, one Músa Khán Mehr, who was a man of influence with Mahmúd, and obtained the assistance of some hundred men to quell the disturbance, by asserting the rights of his own side. The consequence was the subjection of the Jatois, and a partition of their country. Jaisar received the tract extending from Mehláni to Lárkhána as a free gift (*tindad* and *madad-mash*), on the condition that, after the lapse of a generation, one-tenth of the produce would be claimed by the

Government. The Jatois obtained the northern allotment, from Mehlan to Jurdika, on payment, however, of the customary land tax. Jaisar Khán remained at Lakhi, which thus became, as it were his property, and at his death, his son Akil in conjunction with a brother, Bakkar, and a cousin, Wadera Suján Khán, determined on building a new town to replace the old one. The fort which they erected may still be traced. Suján also built a village called Marúlo, after his son Maru, now known as Wazirabád, from Sháh Walí, the Wazír of Ahmad Sháh Durrání, whose perquisite it in after years became.

But the Mahars had to contend with the Daudputris, who were by profession both warriors and weavers. The results of the contest, and consequent foundation of the city of Shikárpur are thus narrated by General Sir I. G. Goldsmid — 'The weavers (Dáúdputras) appealed to spiritual authority, as represented in the person of Pir Sultán Ibráhím Sháh, whose tomb still bears testimony to the fact of his existence. He was a holy man of eminence, and numbered the Mahars, as well as their opponents, among his disciples, and he moreover himself resided at Lakhi. He took up the cause of the appellants, and eventually obtained permission for them to resume their hunting in the Shikárgahs, from which they had been warned off by the Mahars. Again, however, they were stopped and again did they seek the Pir for redress. The Mahars were summoned a second time, and ordered to desist. They remonstrated, and finally informed their venerable mentor that they would never spare the intruders till they had exterminated the whole body, or at least driven them from the vicinity of the Shikárgah, adding, 'If you wish to be their comrade, good, be it so.'

'Baffled and distressed, the Pir bethought him of the final resource in such cases. He invoked curses on the rebelling Mahars, and blessings upon the oppressed Dáúdputras. He told his *protégés* that they were as the iron scale, and their enemies as grass or chaff, and promised them the victory in the event of an engagement. The plot prospered. The crisis drew on, and the battle became inevitable. According to the story of the sons of Dáúd their ancestors on this occasion could only muster a force of 300 or 400 fighting men, while their opponents numbered 12,000. A sanguinary conflict ensued on the meeting of the hostile forces, which after the most determined endeavours on either side, eventually terminated in favour of the Dáúdputris, who were left masters of the field. Strange to say, while some 3000 dead bodies of Mahars strewed the ground, but few were killed on the side of the victors. A vigorous pursuit succeeded this victory. It was known that the wealthy *sarrafis* of Lakhi had hoards of rupees concealed in that city. Thence went the Dáúdputras, and it is by no means unlikely that, on this particular occasion, they found

means of improving the condition of their financial and commissariat departments.

'The Pír received his successful pupils with as much mundane satisfaction as could be expressed by so holy a man. He congratulated them, and, mounting his palfrey,' continues General Goldsmid, 'he led the weavers to the scene of their exploits. He halted at the ground on which now stands the commercial capital of Upper Sind. Muttering some mysterious words, which immediately instilled a dramatic awe into the hearts of the bystanders, he raised his hand high in the air, and gracefully dropped an iron nail, which had long been held there unnoticed. The nature of the movement brought the point well into the earth. It remained transfixed in an admirable position for the chief performer of the play. He pointed to the instrument upon which all eyes were drawn. "Here," said the Pír, "let a city be built, and let it bear the distinguished name of Shikárpur!" The air rang with shouts, and the proceedings terminated in the usual manner on such occasions. The jungle was cut and cleared; neighbours were summoned, threatened, and cajoled; the work proceeded with vigour and rapidity, and by degrees a town appeared. The town in due course became a city, noted for the wealth and enterprise of its merchants, the size and business of its *bázár*, a hot-bed of intrigue, debauchery, bribery, oppression, evil-speaking, and many other kinds of corruption; and so passed away the years till the dawn of the 18th century.'

The Kalhoras had, during the 17th century, been gradually laying the foundation of their subsequent sovereignty in Sind, and the career of Yár Muhammad, the first ruler of this line, is thus described by Goldsmid:—'Mírza Bakhtawar Khán, son of Mírza Panni, was ruler of Siwi, and held a large tract on the west bank of the Indus, in the environs of Shikárpur. Yár Muhammad, associated with Rájá Likki and Iltas Khán Brahui, recommenced aggressive measures by a movement in the country bordering on the Manchhar Lake. He possessed himself of Samtáni, expelling the Panhwars and their head-man, Kaisar; and despatched his brother, Mír Muhammad, to extend his acquisitions by a diversion in an opposite quarter. His objects were achieved with skill and rapidity. His career of conquest made Iltas leave him. "You have no need of me; heaven is on your side; that suffices," said the rough Brahui. Kandiáro and Lárhána were taken, among less important places. The latter had been held by Málík Alá Bakhsh, brother of Bakhtawar. The Mírza, upon these reverses, appealed to the Sháhzáda in Múltán, Moiz-ud-dín (afterwards Jahándar Sháh), who no sooner heard the report than he turned to the scene of disturbance. Then Bakhtawar's heart misgave him, for he did not wish to see the country entrusted to his charge overrun by the troops of his master. He had probably private and particular reasons for the objection

unknown to the historian. He prayed the prince to withhold his march, and on the refusal of his request, had actually the audacity to oppose the advancing hosts. He was slain, and Moiz ud-din repaired to Bukkur. Yār Muhammad does not appear to have suffered severely for his offences, on the contrary, the Shāhzada came gradually round to favour his views of aggrandizement. One after another, new governors were appointed for Siwt which Province in course of time was handed over to the Wākils of the Kalhoras. Yār Muhammad received the imperial title of Khuda Yār Khān.

The reigns of the several Kalhora princes will be found described in some detail in the section treating of the history of the Province. During the Talpur rule, various parts of Upper Sind, such as Būrdikar, Ruppur, the town of Sukkur, and other places, which were dependencies of the Durāni kingdom, had, between the years 1809 and 1824 been gradually annexed to the possessions of the Khairpur Mīrs, Sohrāb, Rūstam, and Mubārak. Shikārpur was the only spot that remained to Afghānistān, and that town eventually came into the peaceable possession of the Mīrs in 1824, at a time when Abdūl Mansūr Khān was governor of the place, and when the Sikhs were said to be contemplating an attack upon it. Goldsmid thus refers to this circumstance in his memoir—'Three or four months after the departure of Rahim Dil Khān, it began to be rumoured that the Sikhs were contemplating an attack upon Shikārpur. At this time the Chevalier Ventura was with a force at Dera Ghazī Khān. The Mīrs of Sind—Karam and Murād Ali of Haidarābād, and Sohrāb, Rūstam, and Mubārak of Khairpur—seeing that it would be of great advantage that they should at this juncture take the city into their own hands, deputed the Nawāb Wali Muhammad Khān Lughāni to dispossess the Afghāns, and carry out the wishes of his masters. The Nawāb commenced by writing to Abdūl Mansūr several letters to the following effect—

“Undoubtedly the Sikhs did wish to take Shikārpur, and were approaching for that particular purpose. Its proximity to the Mīrs' possessions in Sind made it very inconvenient for them that it should fall into the hands of this people, moreover, the capture of the place, under the circumstances, would be disgraceful, or at least discreditable, and it was the part of wise men to apply a remedy in time when available. The Afghāns were not in a position to oppose the coming enemy, their Sindhīs in Khorasan were in the habit of eating superior mutton, Peshāwar rice, luscious grapes, raisins, delicious cold melons, seedless pomegranates, and rich comfits, and of drinking iced water, it was on account of this application of cold to the body that a martial and lordly spirit possessed them which it is not the property of heat to impart. It was, moreover, necessary to the well

being of their hardy constitution. While the army was coming from Khorasán, the city would glide from their hands." A well-known Persian proverb was here judiciously interpolated, viz., On calling the closed fist to remembrance after the battle, it will be necessary to let the blow fall upon one's own head. "In fine, taking all things into consideration, how much better would it be for the Mírs to occupy Shikárpur; they were Muhammadans as well as the Afgháns. Once having driven away the Sikhs, and deprived the infidels of their dominions, Shikárpur was at no distance; let it then become the property of the Sardárs. Now, in the way of kindness, let them (the Afgháns) return to Khorasán, and join their comrades at table in discussing the *pílaus* and fruits, whereby cure is obtainable of this most destructive heat."

'Abdúl Mansúr Khán, upon receiving these communications, became greatly perplexed, and thought of returning to Khorasán. The Mírs, much as they desired to take possession of the town, were obliged to content themselves with assembling an army without its walls, on the plea of protection against a Sikh invasion. They encamped in the Sháhi Bágh. The Nawáb sent for Júma Khán Barakzai, and through him opened fresh communications with the governor, and tried every artifice to persuade the latter to quit his post. Finding a bold stroke of diplomacy necessary, he urged that he would hold him responsible for the town revenues accruing after the date of the original proposition for transfer to the Mírs. This argument had the desired effect; Abdúl Mansúr refused to refund, but agreed to abandon Shikárpur. In this interval, Diláwar, Khitmatgár to the Nawáb, entered the city, and coming to the house of Shaukár Muya Rám, established his head-quarters there, and caused the change of Government to be notified throughout the *bázár* and streets. The Mírs' followers came gradually in, and at length were regularly installed, and obtained the keys of the eight gates.

'The next day, Abdúl Mansúr Khán, at Júma Khán's instigation, visited the Nawáb in the Sháhi Bágh. The latter, after much flattery and compliment, gave him his dismissal. The ex-governor repaired with his effects to Garhi Yásin, a town in the neighbourhood, and stayed there to execute some unfinished commissions. In a few days, the Nawáb ordered him to depart from thence, which he did, and was soon far on his way to Kandahár. Wali Muhammad felt relieved, and applauded his own handiwork, in that he had won a bloodless victory. He had deprived the Afgháns of a much-loved settlement, and added it to the possessions of the Mírs. The revenue was divided into seven shares; four became the property of the Mírs of Haidarábád, and three of their relatives of Khairpur. Kazim Sháh was the new governor.'

In 1833, during the Talpur rule, Shāh Shūja, the dethroned Afghān monarch, made an expedition into Upper Sind to recover his lost territory. He marched with a force of 12,000 Bahāwalpur towards Shikārpur. He was met near Khairpur by Kāzīm Shāh, the former governor of Shikārpur, and escorted to the city with all honour, where he was to stay forty days and receive 40,000 rupees (£4,000). But though he took the money, he did not leave at the appointed time. Public feeling in Sind ran high. Those who declared for the Shāh on the west bank were taken under his especial protection. He appointed local officials, and commenced legislating for his Sindian *proteges*, treating them in the light of subjects. The climax was a burst of indignation from the offended Mīrs and a rising of their Balūch retainers. A Balūch army, under Mīr Mubārak and Zangī Khān, crossed the river at Kohri, and took up a position at Sukkur, while Shāh Shuja despatched a force of 2,000 men under his lieutenant, Samandhar Khān, to meet it. The Mīrs had been drawn up near the Lālāwāh Canal which the Shāh's general attacked, throwing the Balūchis into instant confusion, and ultimately defeating them. This victory resulted in the payment to the Shāh by the Mīrs of 4 *lakh*s of rupees (say £40,000), and 50,000 rupees (£5,000) for his officers of State, while 500 camels were made over for the king's use. The Shāh subsequently marched on his expedition against Kandahār, but being defeated by Dost Muhammad he retreated to Sind and proceeded to Haidarābād, where he obtained sufficient money from the Mīrs to enable him to return to Ludhiāna in the Punjab.

In 1843 on the conquest of the Province by the British all Northern Sind, with the exception of that portion held by the Khairpur Mīr, Ali Murīd Talpur, was formed into the Shikārpur Collectorate and the Frontier District. In the previous year (1842) the towns of Sukkur, Bukkur, and Kohri had by treaty been ceded to the British in perpetuity. In 1851, Mir Ali Murīd Talpur of Khairpur was, after a full and public inquiry, convicted of acts of forgery and fraud in unlawfully retaining certain lands and territories which belonged of right to the British Government. The forgery consisted in his having destroyed a leaf of the *Kurān* in which the Naunahar, concluded in 1842 between himself and his brothers Mīr Asir and Mubārak Khān was written, and having substituted for it another leaf in which the word 'village' was altered to 'district,' by which he fraudulently obtained possession of several large districts instead of villages of the same name. On 15th January 1852, the Governor General of India (Marquis Dalhousie) issued a proclamation depriving the Mir of the districts wrongfully retained, and degrading him from the rank of *Pāi* (or Lord Paramount). Of the districts so confiscated Ubauro, Bādāka, Mirpur, Saidābād, and other parts of Upper Sind on the left bank of the Indus,

now forming the greater part of the Rohri Sub-division, were added to the Shikárpur Collectorate.

Population.—The population of Shikárpur District, according to the Census of 1872, numbered 776,227; and according to that of 1881, 852,986, scattered over an area of 10,001 square miles, inhabiting 6 towns and 1367 villages, and dwelling in 137,702 houses. Total increase of population in the nine years, 76,759, or 9·88 per cent. The Census of 1881 gives the following results:—Persons per square mile, 85·2; villages per square mile, 0·13; persons per village, 621; and persons per house, 6·1. Classified according to sex—males number 461,033, and females 391,953; proportion of males, 54·05 per cent. Classified according to age, there were—under 15 years, boys 189,272, and girls 153,962; total children, 343,234, or 40 per cent.: 15 years and upwards, males 271,761, and females 237,990; total adults, 509,751, or 60 per cent. of the population.

As regards religious distinctions, Shikárpur is an essentially Muhammadan District, the Census showing a total of 684,275 Muhammadans, as against 93,341 Hindus. The Muhammadans include 679,132 Sunnis, 5142 Shiás, and 1 Wahábí. Divided into tribes, there were 132,301 Balúchís, 6539 Patháns, 13,158 Sayyids, 17,313 Shaikhs, 492,733 Sindhís, 22,231 'other' Muhammadans. The Hindus include 3336 Bráhmans, 271 Rájputs, 77,491 Loháns, and 12,243 'other' Hindus; 5892 are returned as aboriginal tribes; while 736 Christians, 64 Pársís, 9 Jews, 68,655 Sikhs, 6 Buddhists, and 8 Brahmos complete the total.

As regards occupation, the male population is divided by the Census into the following main groups:—(1) Professional class, including civil and military, 7124; (2) domestic servants, inn and lodging-house keepers, 5305; (3) commercial class, including bankers, merchants, carriers, etc., 8866; (4) agricultural and pastoral class, including gardeners, 165,440; (5) industrial class, including all manufacturers and artisans, 55,174; (6) indefinite and non-productive class, comprising general labourers, male children, and persons of unspecified occupation, 219,124.

Of the 1373 towns and villages in the District, 468 contain less than two hundred inhabitants; 431 between two and five hundred; 251 between five hundred and one thousand; 161 between one and two thousand; 43 between two and three thousand; 12 between three and five thousand; 3 between five and ten thousand; 2 between ten and fifteen thousand; and 2 between twenty and fifty thousand. The chief towns are—SHIKARPUR, population (1881) 42,496; SUKKUR, 27,389; LARKHANA, 13,188; ROHRI, 10,224; KAMBAR, 6133; and GARHI YASIN, 5541. The above-named six towns, together with GHOTKI, population 3240; RATO-DERO, 3170; UBAURO, 2267; MEHAR, 1944; and KHAIRPUR NATHESHAH, are municipalities: total income (1883–84),

£28,488, incidence of taxation varied from 8½d. to 5s. 2½d per head in different towns

Agriculture—Agriculture supported (1881) 465,522 persons, or 54.58 per cent of the population, only 181,679 were agricultural workers. In 1883-84, in the Government villages of the District, 660,016 acres were cultivated land bearing assessment and in occupation, 336,354 acres were fallow, while 247,739 acres, though cultivable and assessed, were not in occupation. The area under actual cultivation was 579,527 acres, of which 113,715 acres were twice cropped. Cereals and millets occupied 512,570 acres, of which nearly half, or 234,617 acres, were under rice, pulses, 110,912 acres, orchards, 4235 acres; drugs and narcotics, 3460 acres, chiefly tobacco, sugar-cane 726 acres, oil seeds, 44,883 acres, indigo, 2780 acres, fibres, 7985 acres nearly all under cotton, and 'other' products, 5691 acres. The prices of agricultural produce, per maund of 80 lbs., ruling during 1883-84 were as follows—wheat, 5s. 7d., barley, 3s., best rice, 7s. 10½d., common rice 5s. 1d., *hyra* (*Pennisetum typhoideum*) 3s. 3½d., *jowar* (*Sorghum vulgare*), 3s. 1½d., gram, 3s. 10d., salt, 5s. 10d., flour, 6s. 6½d., *dali* (split peas) 6s. 4½d., *ghhi*, £2. 9s. 0½d. The wages of skilled labour were in the same period 2s. per day, of unskilled labour, 7½d. Cart hire, 2s. a day, camel hire, 5d. a day for baggage camels and 1s. 0½d. a day for riding camels.

Natural Calamities—In 1874, the Indus inundated a large portion of the District, breaching the railway and other embankments. The flood waters reached their greatest height from the 14th to 16th August, but began steadily to subside about the 27th of that month. No less than 536 villages were flooded, and several Government buildings were washed away. The floods of 1874 were from 5 to 6 feet higher than those which occurred in 1872. The net loss to Government in Mchir Sub-division alone was estimated at £15,000.

Commerce and Trade, &c.—The Sind Punjab and Delhi (now the North Western State) Railway runs through the District from Sitá to Reti, for about 170 miles, with 22 stations, the principal ones being Radhan, Ruk junction, Sukkur, where it crosses the Indus to Rohri on the opposite bank, and Keti. The Sind Pishin Railway, starting from Ruk junction, crosses the District boundary a little beyond Jacobabad, a distance of about 40 miles, with 4 stations. But the facilities for trade afforded by the railway have not materially affected the boat traffic on the Indus. The trade through the Bolan Pass passes through the District and the value is estimated at from £250,000 to £300,000, large quantities of wheat being sent to Karachi. The principal manufactures are carpets and coarse cotton cloth.

Administration—The total revenue of Shikarpur District in 1880-83 amounted to £234,792. The land revenue collected was £151,868, stamps, £12,550, excise, £12,120, and licence duty, £3500. The

local fund revenue was £13,920, while the 11 municipalities raised an income of £23,050. Shikárpur is administered by a Collector-Magistrate with assistants; the Civil and Sessions Judge has his head-quarters at Shikárpur town. In 1882-83, there were 6 civil judges and 39 stipendiary magistrates in the District; maximum distance of a village from nearest court, 40 miles; average distance, 6 miles. The police force numbered in 1882-83, 1091 officers and men, showing 1 policeman to every 7·5 square miles of area and to every 732 of the population. The police were maintained at a cost of £20,097. Schools (1882-83), 116, with 8104 pupils.

Medical Aspects.—The climate of Shikárpur District is hot and dry, with a remarkable absence of air-currents during the inundation season; and it is, in consequence, very trying to a European constitution. The hot weather commences in April, and ends in October; it is generally ushered in by violent dust-storms; the cold season begins in November, and lasts till March. The maximum, minimum, and mean temperatures in the shade are on an average 100°, 61°, 81° F. The average yearly rainfall, from the observations of 18 years ending 1881, is only 4·93 inches. The diseases are principally malarious fevers and ulcers. Cholera occurs at times, chiefly in the months of June and July. In 1883-84, 15,865 births were registered, and 13,450 deaths, or 15·77 per 1000. In the same year, 27,256 persons were vaccinated. [For further information regarding Shikárpur District, see the *Gazetteer of the Province of Sind*, by Mr. A. W. Hughes (London, George Bell & Co., 1876, second edition). Also Mr. Stack's *Memorandum upon the Current Land Revenue Settlements in the temporarily settled parts of British India*, pp. 532-543; the *Bombay Census Report* of 1881; and the several annual Administration and Departmental Reports of the Bombay Government.]

Shikárpur.—*Táluk* of the Sukkur (Sakkar) Sub-division, Shikárpur, Sind, Bombay Presidency. Area, 487 square miles. Population (1872) 73,383; (1881) 75,112, namely, males 40,600, and females 34,512; occupying 11,187 houses, in 1 town and 66 villages. Hindus number 19,483; Muhammadans, 43,944; Sikhs, 10,816; non-Hindu aborigines, 766; Christians, 96; Pársis, 6; Jew, 1. Area assessed for land revenue (1882-83), 37,409 acres, of which 31,007 acres were under cultivation. In 1883 the Sub-division contained 1 civil and 5 criminal courts; police circles (*thindís*), 6; regular police, 367 men. Land revenue, £9824.

Shikárpur.—Chief town of Shikárpur District, Sind, Bombay Presidency. Lat. 27° 57' 14" N., long. 68° 40' 26" E.; connected by good roads and railway with Jacobábád, from which it is distant 26 miles south-east, with Sukkur (Sakkar) 23 miles north-west, and Larkhána 40 miles north-east. Situated in a tract of low-lying country, annually flooded by canals from the Indus, the nearest point of which

river is 18 miles west. The elevation of the town is only 194 feet above sea level. Two branches of the Sind Canal—the Chhota Begari and the Rāiswah—flow on either side of the town, the former to the south, and the latter to the north. The soil in the immediate vicinity is very rich, and produces heavy crops of grain and fruit. Population (1881) 42,496, namely, males 22,889, and females 19,607. Hindus number 16,218, Muhammadans, 16,480, Christians, 70, Parsis 4, and 'others,' 9724. Shikarpur is the head-quarters of the principal Government officials of the District, and contains the usual public buildings, and is a station on the Sind Pishin State Railway. The total number of police is 311. Municipal revenue (1883-84) £6819, incidence of taxation, 2s 9d per head. The Municipal Act was brought into force in 1855, since which date great sanitary improvements have been effected. Before that time, Shikarpur was notorious for its unsightly appearance. The Stewartganj Market (so called after a popular District officer) is a continuation of the old *baḍār*, and is a commodious structure. To the east of the town are three large tanks, known as Sarwar Khan's the Gillespie, and the Hazari tank.

The trade of Shikarpur has long been famous, both under native and British rule. The town is situated on one of the great routes from Sind to Khorāsān via the Bolān Pass, and its commerce in 1841 was thus described by Postans—'Shikarpur receives from Karachi, Mirpur, Multān (Mooltan) Bahawalpur Khairpur, and Ludhiana—European piece goods, raw silk, ivory, cochineal, spices of sorts, coarse cotton cloth *kirkhāt* manufactured silk, sugar candy, cocoa nuts, metals, *kirānī* (groceries) drugs of sorts, indigo and other dyes, opium and saffron, from Kachhi, Khorāsān, and the north west—raw silk (Turkestan), various kinds of fruit, madder, turquoises, antimony, medical herbs, sulphur, alum, saffron, assafetida, gums, cochineal, and horses. The exports from Shikarpur are confined to the transmission of goods to Khorāsān through the Bolān Pass, and a tolerable trade with Kachhi (Bugh, Gandāva, Kotri, and Dindar). They consist of indigo (the most important) henna, metals of all kinds, country coarse and fine cloths, European piece-goods (chintzes etc.) Multāni coarse cloth, silks (manufactured) groceries and spices raw cotton, coarse sugar, opium hemp-seed, shields, embroidered horse cloths, and dry grains. The revenue of Shikarpur derivable from trade amounted in 1840 to Rs. 54,736 (say £5473), and other taxes and revenue from lands belonging to the town, Rs. 16,645 (say £1664), making a total of Rs. 71,381 (say £7138), which is divided among the Khairpur and Bahawalpur Mirs in the proportion of three-sevenths and four-sevenths respectively.'

Since Postans wrote as above, Shikarpur has lost much of its commercial importance owing to the opening of the Indus valley

The present name was given in the time of Haider Ali, on account of the abundance of game found in the neighbourhood. The old fort is now in ruins. A festival held for three days in April is attended by 8000 persons. Weekly fair on Saturdays.

Shikohábád—South western *tahsil* of Munpuri District, North Western Provinces. It is conterminous with Shikohábád *pargana*, and consists of an almost level plain, intersected by undulating sandhills, and much cut up by ravines along its southern border, where it abuts upon the river Jumna (Jamuna). The Sarsa river flows through the midst of the *tahsil*, and the East Indian Railway traverses it from end to end, with stations at Bhádrin and Shikohábád. It is also thoroughly opened by good roads in every direction. Canal irrigation is afforded by the Bhognipur branch of the Ganges Canal. Area, 293 square miles, or 187,588 acres, of which 200½ square miles, or 128,172 acres, were returned as under cultivation at the time of the last land revenue settlement of the District in 1870. 8845 acres were cultivable, including 2629 acres under groves. 1288 acres were held free of revenue, and 49,283 acres were uncultivable waste. Population (1881) 144,882, namely, males 79,316, and females 65,566. Average density, 494.5 persons per square mile. Hindus number 132,434, Muhammadans, 11,374, Jains, 1065, and 'others' 9. Of the 284 towns and villages, 191 contain less than five hundred inhabitants, 63 between five hundred and 1 thousand, 26 between one and five thousand, and 1 between ten and fifteen thousand inhabitants. The principal crops are *lúya*, *jút*, cotton, and sugar cane for the *kharif*, and wheat, *tejhar*, barley, and gram for the *rabi* harvest. The former occupies about 60 and the latter 40 per cent. of the cultivated area. Land revenue (1882) £27,625, or including local rates and cesses, £30,958. In 1884, Shikohábád *tahsil* contained 1 civil and 1 criminal court, number of police circles (*tháns*), 2, regular police, 42 men, village watch or rural police (*claulidárs*), 370.

Shikohábád—Town in Munpuri District, North Western Provinces, and head quarters of Shikohábád *tahsil*, situated in lat. 27° 6' 5" N., and long. 78° 38' 10" E., on the Agra road nearly 2 miles from Shikohábád station on the East Indian Railway, and 34 miles west of Munpuri town. Population (1881) 11,826, namely, males 6347, and females 5479. Hindus number 6741, Muhammadans, 4757, Jains, 122, and Christians 6. The old town, a large straggling collection of houses, lies east and south of the main road, but the principal *thán* lies the highway itself, and contains 9 *tháns* (native inns) for the accommodation of travellers. An ancient mound, once the site of the fort, is now covered by houses. The town contains numerous temples and mosques, and is the birth place of several Hindu and Muhammadan saints. Has some *tháns*, police station, post office, school, tehsildar's office at

railway station. Named after Prince Dára Shikoh, traces of whose residence, garden, and wells still remain. The British obtained possession of Shikohábád in 1801, and established a cantonment south of the town. In 1802, a Maráthá force under Fleury surprised the British detachment; after which the cantonment was removed to Máinpuri. Formerly a great emporium for raw cotton, but the trade has declined. Manufacture of sweetmeats and cotton cloth. A small house-tax is levied for police and conservancy purposes.

Shillong.—Chief town of the Khási and Jaintia Hills District, and administrative head-quarters of the Chief Commissioner of Assam; situated in lat. $25^{\circ} 32' 39''$ N., and long. $91^{\circ} 55' 32''$ E., on a table-land 4900 feet above sea-level, and 64 miles south by road from Gauháti (Gowhatty). Shillong first became the civil station of the Khási and Jaintia Hills in 1864, in substitution for Cherra Poonjee. In 1874, on the constitution of the Chief Commissionership of Assam, it was chosen as the head-quarters of the new administration, on account of its salubrity and its convenient position between the Brahmaputra and Surmá valleys.

The Chief Commissioner permanently resides at Shillong, and also the heads of all the departments of Government. A considerable native population is already settled, which increases from year to year. Population (1872) 1363; (1881) 3640. Municipal taxation (1883–84), £374, or an average of 3s. 6d. per head of the population (2137) within municipal limits. Large sums of money have been expended on the erection of public buildings. A printing press has been established, from which issue all the official documents and reports of the Province. A church has been built, at which a chaplain officiates alternately with Gauháti. The nominal area of the station is 7 miles in length by $1\frac{1}{2}$ mile broad. An excellent water-supply has been introduced through an aqueduct, which has its source in the neighbouring hill streams; the water is distributed by means of pipes to every house in the civil station, and by hydrants in the public *bázárs* and other convenient places. Sanitary measures are stringently enforced. The cart-road from Gauháti, the old capital of Assam on the Brahmaputra, was opened for traffic in 1877. The entire distance of 64 miles is now accomplished by *tonga dák* in a single day; and the sanatorium is thus rendered easily accessible from the fever-stricken plains of the Brahmaputra valley. The gradients on this road are a model of engineering skill. In 1885, the cantonments at Shillong were occupied by the 42nd Regiment of Bengal Infantry, with 2 mountain guns. A large weekly market is held in the *bázár*. A model farm established in the neighbourhood in 1873 did not prove successful, either from a financial or an agricultural point of view, and has been abolished. (See *The Statistical Account of Assam*, vol. ii. p. 229.)

The climate of Shillong is singularly mild and equal to. A temperature higher than 80°F is seldom recorded. Hoar frost lies upon the ground almost every morning during the months of December, January, and February. Shallow water occasionally freezes over, but snow never falls. Fires are necessary from November to March or April, the fuel used being coal, obtained at great cost from the beds at Máo beh lytkar. The price fluctuates much, depending on the cost of carriage, it has been known to reach as high as £3 per ton. The rainfall registered during the fifteen years ending in 1881 averaged 87.44 inches a year. The prevailing diseases are dysentery, bowel complaints, and disorders of the liver, but when once European residents have passed through a short period of acclimatizing indisposition, they generally enjoy excellent health.

Shillong—Mountain range in the Khasi and Jaintia Hills District, Assam, overlooking the station of the same name. The highest peak (lat $25^{\circ}34'18''\text{N}$, long $91^{\circ}55'43''\text{E}$) attains a height of 6450 feet above the sea, being the most elevated point in the District. The crown of the ridge is covered with a sacred grove of large timber trees. This peak is the site to which the name Shillong properly belongs, the neighbouring station is known to the natives as Lábán from a village of that name which adjoins it.

Shimoga.—District forming the north western portion of the Nagar Division of Mysore, lying between $13^{\circ}30'$ and $14^{\circ}38'\text{N}$ lat, and between $74^{\circ}44'$ and $76^{\circ}51'\text{E}$ long. Area, 3797 square miles, population, according to the Census of 1881, 499,725 souls. Bounded along the north and west by the Districts of Dhárár and North Kánara, in the Bombay Presidency. The administrative head-quarters are at SHIMOGA TOWN, on the left bank of the Tungá river just above its junction with the Bhadrá.

Physical Aspects.—The District constitutes part of the principal watershed of Southern India. The river system is twofold—the rivers in the east, the Tungá, the Bhadrá and the Varáda uniting to form the Tungá-Bhadrá, which ultimately falls into the Kistná, and so into the Bay of Bengal, while in the west, a few minor streams break through the barrier of the Western Ghats and reach the Kánara coast. The whole region is covered with hills and valleys but it naturally divides into two distinct portions. The larger half towards the west, known as the Maláid or hill country, gradually rises towards the Western Ghats, where isolated peaks attain a height of more than 4000 feet above sea level. The general elevation of the District is about 2100 feet, and towards the east it opens out into the Maláid or plain country, which forms part of the general plateau of Mysore. The Maláid presents a wealth of picturesque scenery and wild life. A park of giant timber trees, overgrown with brilliant creepers, exerts continuously for miles,

returned at 14,694, including 13,429 Maráthás and 1265 Rájputs; the Vaisyas are poorly represented by only 1106 persons, all Komatis. Of inferior castes, the most numerous are Wokligas (68,219), who are agricultural labourers; Idigas (58,252), whose caste occupation is that of toddy-drawers; and Vaddárs (13,467), of whom many are also cultivators. The Lingáyats, who have always been influential in this part of the country, number 51,504; agricultural castes, 26,861; Kunchigars (brass and coppersmiths), 11,186; Kurubás (shepherds), 21,792; Uppárs (salt-makers), 8815; Tiglárs (market gardeners), 236; Gollárs (cowherds), 3009; Bedárs (hunters), 21,010; Bestárs (fishermen), 13,331; Banajigárs (traders), 3282; Neyigás (weavers), 21,866; Kumbhárs (potters), 3604; Agasás (washermen), 11,864; Darjis (tailors), 888; Nápits (barbers), 2777; Ganigárs (oil-pressers), 825; Myadárs, 3046. Out-castes are returned at 61,472; wandering tribes, 10,726.

The Musalmáns, who muster strongest in the *táluk* of Shimoga, are mostly all described as Deccani Musalmáns of the Sunni sect. Shiás number 388; Wahábís, 5; Daira or Mahadavi, 45; and 'others,' 604. Out of the total of 1476 Christians, 34 were Europeans and 51 Eurasians (chiefly residing on the coffee plantations), leaving 1391 for the native converts. According to another principle of classification, 100 are Protestants and 1376 Roman Catholics.

With reference to occupation, the Census distributed the male population into the following six main groups:—(1) Professional, civil, and military class, 8433; (2) domestic servants, inn and lodging keepers, 1535; (3) commercial class, including bankers, merchants, and carriers, 6523; (4) agricultural and pastoral class, including gardeners, 131,477; (5) industrial class, including all manufacturers and artisans, 10,693; and (6) indefinite and non-productive class, comprising general labourers, male children, and persons of unspecified occupation, 100,635.

The District contains 1973 populated towns and villages, with a few houses of the better class, or over £50 in value. Of the total number of towns and villages, 1099 contain less than two hundred inhabitants; 626 from two to five hundred; 205 from five hundred to one thousand; 34 from one to two thousand; 7 from two to three thousand; 1 from three to five thousand; and 1 from ten to fifteen thousand. The only place in the District with more than 5000 inhabitants is SHIMOGA TOWN, the head-quarters of the District, on the Tunga river; population (1881) 12,040. Its prosperity dates from the introduction of British rule. There are many sites of ruined cities in the District, which have been already alluded to. The chief are—Nagar or Bednúr, Ikkeri, and Keladi, all associated with a family of Lingáyat *pálegárs*; Basvapatna, the early residence of the Tarikere chiefs; the Jain ruins of Humcha;

and Banavasi, with its Buddhist memorials. The most important modern towns after Shimoga itself, are Chennarayana and Sagar. There are altogether ten municipalities in the District, with an aggregate municipal income, in 1881-82, of £2249.

Agriculture—The staple food crop of the District is rice, which is especially cultivated in the terraced valleys of the Malnad or hill country. The names of 60 different varieties are enumerated. The crop is sown from April to July, and reaped from November to February. In some tracts, the cultivation of 'dry crops' predominates. Of these, *ragi* (*Holcus corocina*) is preferred by the natives for their own food, while rice is largely exported. Next to rice, the most important crop is sugar-cane, which is largely grown in the *taluk* of Shikarpur. The canes are planted from January to June, and gathered after a full twelve months. The juice is for the most part converted into jaggery. The tract about Nargur produces the finest areca nuts in Mysore. Miscellaneous crops include oil seeds, a great variety of vegetables and fruits, pepper, and cardamoms. The coffee zone of the District is estimated to extend over 1000 square miles, but a considerable portion of this area is not of the most favourable character. There are altogether 250 plantations, of which 6 are owned by Europeans. In 1861, an unsuccessful attempt was made to improve the indigenous production of cotton by the distribution of American seed.

The following agricultural statistics are merely approximate.—Out of the total area of 3797 square miles, only 1110 were returned in 1880-81 as under cultivation, and 433 as cultivable. The area under rice is 209 217 acres, with an out turn valued at more than £350 000, other food grains, 303 908 acres; cotton, 921, cocoanut and areca nut, 16,942, coffee, 4846, sugar-cane, 7245, oil seeds, 6000, fibres, 1600 tobacco, 500, vegetables, 762, pepper, 532 acres total area under actual cultivation 552,473 acres. Average rent per acre for rice land, 9s, wheat land, 6s, land producing inferior grains, 9d; cotton, 3s, oil seeds, 3s 3d, fibres, 3s 6d, sugar-cane 4s, and tobacco, 5s. Average produce of rice land per acre, 671 lbs, wheat 40 lbs, inferior food grains 671 lbs, cotton, 29 lbs, oil-seeds, 170 lbs, fibres 500 lbs, sugar, 360 lbs, tobacco, 240 lbs, and coffee, 34 lbs. Current prices per *maund* of 80 lbs.—rice, 4s 1½d, wheat, 4s 9d, cotton £1, 17s 7½d, salt, 8s 11½d, gram, from 3s 2½d to 4s 9½d, *rigi* 1s 5½d, oil 5s 10½d, tobacco £3 7s 6d, unrefined sugar, 8s, *ghee* the Indian substitute for butter, lard, &c, £2, 9s 2½d. A *bullock* bullock costs from £2 to £20, sheep, from 4s to £1. Iron sells at 12s per 80 lbs. Skilled labour costs 1s 3d to 2s, unskilled labour from 6d to 1s. The hire of a cart per day is 1s 6d to 2s, of a donkey, 7½d to 1s, of a boat, 1s to 2s.

Irrigation is carried on both from tanks and from canals at different

drawn from the rivers by means of anicuts or weirs. The total number of tanks is 8313, including the great reservoir of Sulekere, in the *táluk* of Chennagiri, which is 40 miles in circumference, and ranks as the second largest in Southern India. In this same neighbourhood are to be found the best cattle in the District; and there are several grazing-grounds for the *amrita mahál*, or royal breed maintained by the State. Buffaloes are largely used for agricultural purposes, and pack-bullocks are bred to carry the through traffic across the Gháts. The returns of 1880-81 showed a total of 401,153 cows and bullocks, and 47,643 sheep and goats; horses, 316; ponies, 2091; donkeys, 2317; and pigs, 2678.

Manufactures, etc.—The chief industries in the District are the weaving of coarse cotton-cloth and rough country blankets or *kambliis*, and the making of iron implements, brass-ware, pottery, and jaggery from the sugar-cane. Oil is expressed from a great variety of vegetable products. At certain localities are special manufactures of striped carpets, chintz, coarse brown paper, stone jugs, and rope from various fibres. The carving of sandal-wood constitutes a speciality of the *gúdi-gárs* of Soráb, whose delicate and elaborate workmanship is considered superior to that of either Bombay or Canton. The chief articles turned out are caskets and cabinets, ornamented either with leaves and figures from the Hindu pantheon, or with a copy of any design that may be ordered. Carving of inferior merit is also produced in other villages. The manufacturing stock of the District is returned at 1205 looms, and 63 oil-mills.

The trade of Shimoga is conducted with both the east and west coasts, and also with Bangalore. The chief exports are rice and other food-grains, jaggery from the sugar-cane, areca-nuts, coffee, pepper, and iron articles. The imports received in exchange are European piece-goods, copper vessels, oils of various kinds, tobacco, betel-leaf, and gold and silver ornaments. There are four passes across the Western Gháts, of which the two most important leave the District near the Falls of Gersoppa and at the town of Agumbi. The local trade is mostly in the hands of the Lingáyats, whose centres of operation are at Ságar, Tirthahalli, and Nyampti. There are five weekly fairs, each attended by more than 1000 people; and several annual religious festivals, at which much buying and selling is done. There is no railway in the District. The returns furnished for the first edition of this work showed an aggregate length of State roads of 225 miles, maintained at an annual cost of £3425; District roads, 171 miles, costing £971.

Administration.—In 1881-82, the total revenue of Shimoga District, excluding education and public works, amounted to £190,941. The chief items were, land revenue, £120,467; *sáyar* or customs, £27,870;

forests, £955. The District is now divided into 9 *taluks* or fiscal divisions, with 50 *tehsils* or minor fiscal units. In 1881-82, the total number of estates on the register was 96,557. The District in 1883 contained 3 civil and 6 criminal courts. During the year 1881, the average daily prison population of the District jail was 343.82, and of the *thaluk* lock ups 81.85 total 425.67, of whom 18.78 were women showing 1 person in jail to every 1173 of the population. In the same year, the District police force numbered 18 officers and 458 men, and the municipal police, 1 officer and 34 men total 511 men of all ranks maintained at a cost of £4917. These figures show 1 policeman to every 8 square miles of area or to every 978 of the population, the cost being £1.55 per square mile and 2d per head of population.

The number of schools aided and inspected by Government in 1881 was 114 attended by 4462 pupils being 1 school to every 33 square miles and 9 pupils to every 1000 of the population. Of the schools three were for girls attended by 168 pupils. Besides these schools, there was 1 jail school attended by 148 scholars and 1 college. The Census of 1881 returned 8674 boys and 317 girls as under instruction, together with 19,888 males and 274 females able to read and write. The returns furnished for the first edition of this work showed, in addition to the aided and inspected schools 80 indigenous schools, with 1009 pupils.

Medical Aspects.—Shimoga District offers great varieties of climate. The Ghâts on the western frontier are in some places only 8 miles distant from the sea, and here the south west monsoon strikes with its full force, bringing a rainfall of more than 150 inches in the year. But the District stretches from the Ghâts for about 100 miles towards the central table land of Southern India and the rainfall gradually diminishes, until it only amounts to about 25 inches at Chennagiri most of which falls in October during the north-east monsoon. The sea breeze from the west is distinctly felt as far as Shimoga town. During the two years 1873 and 1874 the maximum temperature registered was 90° F. in the month of April, and the minimum 75° F. in December. In 1881, the maximum in April was 99° F. the minimum in January 70° F. The average rainfall at Shimoga town calculated over a period of forty-four years ending 1881 was 79.6 inches. As much as 170 inches has been known to fall within the year 1872.

Malarious fever of a persistent type prevails in the Malnad or hill country, and the natives appear to be even more susceptible to it than Europeans, when once the latter have become acclimated. The vital statistics are far from trustworthy, but it may be mentioned that out of the total of 10,543 deaths reported in 1881-82 661 were caused by fevers, 1083 to bowel complaints, 204 to influenza, 21 to snake

bite or wild beasts, and 21 to suicide, 6 to woundings, 54 to accidents, and 3407 to other causes. In 1874, the dispensary at Shimoga town was attended by 302 in-patients, and by 9963 out-patients. [For further information regarding Shimoga District, see the *Mysore and Coorg Gazetteer*, by Mr. Lewis Rice, vol. ii. pp. 339-400 (Bangalore, 1876); and also the *Census Report of Mysore* for 1881.]

Shimoga.—*Táluk* in Shimoga District, Mysore State. Area, 547 square miles, of which 203 are cultivated. Population (1881) 81,919, namely, males 40,876, and females 41,043. Hindus number 71,651; Muhammadans, 9327; and Christians, 941. Land revenue (1881-82), exclusive of water rates, £11,614. The west and south is hilly and overgrown with jungle, which gives shelter to many wild beasts. In 1883 the *táluk* contained 1 civil and 2 criminal courts; police circles (*thánds*), 7; regular police, 83 men; village watch (*chaukidárs*), 311. Gross revenue, £18,154.

Shimoga (*Shiva-mukha*, 'face of Siva,' or *Shí-moge*, 'sweet-pot').—Chief town of Shimoga District, and head-quarters of Shimoga *táluk*, Mysore State; situated in lat. 13° 55' 30" N., and long. 75° 36' 5" E., on the right bank of the Tunga river, 171 miles by road north-west from Bangalore. Population (1881) 12,040, namely, males 5947, and females 6093. Hindus number 8152; Muhammadans, 3131; and Christians, 757. Municipal revenue (1880-81), £2886. The early history of the town is unknown. In 1791, a battle was fought in the neighbourhood, in which the Maráthás defeated a general of Tipú Sultán, and sacked the town. Its growth in wealth and prosperity dates from the time when it was made the head-quarters of the District. A weekly fair, held on Tuesdays, is attended by 1500 persons.

Shimshupa (or *Shimsha*).—River in Túngkúr District, Mysore State.—See SHAMSHA.

Shin-da-we.—A highly venerated pagoda in Tavoy District, Tenasserim Division, Lower Burma. It is 77 feet high, and 301 feet in circumference at the base. The shrine is supposed to enclose a relic of Gautama, which, released by its possessor, the miraculously-born Thin-gan-Min, alighted at the spot where the pagoda now stands, and was received by the people in a golden basket.

Shingnapur.—Municipal town in Mán Sub-division, Sátára District, Bombay Presidency; situated in lat. 17° 51' 20" N., and long. 74° 42' 6" E., 46 miles east by north of Sátára town, and 13 north-east of Dahivadi, the Sub-divisional head-quarters. Population (1881) 1167. Shingnapur is a famous place of pilgrimage, situated in a nook of the Shikhar Shingnapur hills. The hill, crowned with a temple of Mahádeo, to which the village owes its celebrity, appears like the point of a very obtuse-angled cone. The great fair is held in March-April. The attendance sometimes reaches 50,000. Great pains are taken as to the

sanitary arrangements during the fair. Government provides a hospital assistant at the expense of the municipality. Care is taken to prevent the water from pollution. The transactions are valued at £5000. The Bhrwanti Ghat road which connects this town with NATEPUTE, a trade centre in Sholapur District, is under construction. Municipal income (1883-84), £614, incidence of taxation, Rs 4½d. per head of population.

Shin maw—Pagoda on Tavoy Point, Tenasserim Division, Lower Burma. Founded in 1204 A.D. by Nara pad-dia si thu, king of Burma, when he visited this part of his dominions. It is highly revered as containing a tooth of Gautama.

Shin-mut ti—The most famous pagoda in Tavoy District, Tenasserim Division, Lower Burma, 58 feet high and 308 feet in circumference at the base. It is said to have been built to enshrine an image which was miraculously floated from India to the spot where the sacred edifice now stands. A sacred stone and a banian tree are shown near the pagoda. An annual festival is held here.

Shirali—Port on the south-western coast of North Kanara District, Bombay Presidency. Situated at the mouth of the Vanktapur river, about 20 miles south of Honavar, and 4 miles north of Bhatkal. There was formerly a trade in salt which was manufactured here, but this has been abolished. Average annual value of trade for four years ending 1881-82—imports, £1095, exports, £1881. Custom house and school.

Shiroda (or *Chiroda*)—Petty State in the Gohelwar *prant* or division of Kathiawar, Bombay Presidency, consisting of 1 village, with 1 shareholder or tribute payer. Area, 72 square miles. Population (1881) 241. Estimated revenue £90 of which £12, 0s. 6d. is paid as tribute to the Gohelwar of Baroda, and £1, 4s. to the Nawab of Junagarh.

Shirol—Town in Kolhapur State, Bombay Presidency. Lat. 16° 44' 10" N., long. 74° 38' 10" E. Population (1881) 6944. Hindus number 6251, Muhammadans 384, and Jains 309.

Shiron—Town in Baroda State, Bombay Presidency. Population (1881) 6047. Delightfully situated on the Narmada, with a noble flight of 100 stone steps from the houses to the water side.

Shirpur—Sub-division of Khindesh District, Bombay Presidency. Area 651 square miles. Population (1872) 34642, (1881) 43321, namely, males 22356, and females 20965, occupying 676510 acres in 1 town and 98 villages. Hindus number 34817, Muhammadans 2859, and 'others' 5646. A broken range of the Shikardi running from east to west, divides this Sub-division into two parts, each with distinct natural features. The northern part consists of a well-watered country, richly irrigated by the Shikardi. The southern is an unwatered plain,

with no trees except near village sites. The population is dense near the banks of the Tápti, but becomes scanty as the hills are approached. Although the Sub-division has three rivers that run throughout the year—the Tápti, forming the southern boundary for 26 miles, and its tributaries the Anar and the Arunávati, and numerous other streams from the Sátpurás—the supply of surface water is on the whole scanty. The prevailing black soil is a rich loam resting on a yellowish subsoil. In 1865–66, the year of settlement, 3500 holdings (*khátás*) were recorded, with an average area of 20·9 acres, and an average rental of £3, 1s. 10½d. In 1878–79, the area under actual cultivation was 87,635 acres. Cereals and millets occupied 58,193 acres; pulses, 3386 acres; oil-seeds, 9539 acres; fibres, 15,583 acres; and miscellaneous crops, 934 acres. In 1883 the Sub-division contained 1 civil and 2 criminal courts; police circle (*tháná*), 1; regular police, 42 men; village watch (*chaukidárs*), 132. Land revenue, £14,327.

Shirpur Sub-division was in 1370 granted in *jágir* by Firoz Tughlak, the Emperor of Delhi, to Malik Rájá, founder of the Khándesh kingdom. In 1785 it became part of Holkár's possessions. In 1818 it was ceded to the British.

Shirpur.—Town in Khándesh District, Bombay Presidency, and head-quarters of Shirpur Sub-division. Situated 30 miles north of Dhulia, in lat. 21° 21' N., and long. 74° 57' E. Population (1881) 7613, namely, Hindus, 6116; Muhammadans, 1024; Jains, 247; and 'others,' 226. Shirpur suffered severely in the floods of 1875, when water stood in places six feet deep, destroying property to the value of £3200. Municipal income (1883–84), £373; incidence of taxation, 9½d. per head of population. Sub-judge's court, post-office, school, dispensary, rest-house.

Shiurájpur.—*Tahsíl* in Cawnpur District, North-Western Provinces, conterminous with Shiurájpur *parganá*, lying along the south-west bank of the Ganges, and traversed by several distributaries of the Ganges Canal. Of the total cultivated area, 23 per cent. is watered from these channels, and a good deal of *dúmat* soil in the south of the *tahsíl* has been improved by the substitution of canal for *jhíl* or marsh irrigation. Notwithstanding the abundance of canal water, wells are extensively used. Excepting in the tract along the cliff of the Ganges, where, owing to the elevation of the surface, water lies at a great depth, the sub-strata are so sandy and treacherous as to render well-digging a perilous venture; while the unevenness of the ground prevents the spread of canal irrigation in this direction. The East Indian Railway passes through the southern corner of the *tahsíl*, with a station at Bhánpur. Shiurájpur is connected with Cawnpur by the Grand Trunk Road, and the *tahsíl* is well provided with roads.

Area, 264 square miles, of which 132 square miles are cultivated.

The chief autumn crops consist of cotton, *jadr*, and indigo, and the spring crops of wheat and *bjra*. Poppy, tobacco, and *sun* are largely grown. Population (1881) 150,728, namely, males 79,465, and females 71,243. Average density of population, 570.9 persons per square mile. Classified according to religion, Hindus number 144,621, and Muhammadans 6107. Of the 320 towns and villages in the *tahsil*, 225 contain less than five hundred inhabitants, 61 between five hundred and a thousand, and 34 between one and five thousand. Land revenue, £27,409, total Government revenue, including rates and cesses, £30,698. Rental paid by cultivators, £49,568. In 1885, Shiurajpur *tahsil* contained 2 criminal courts, and 2 police stations (*thanas*), strength of regular police, 31 men, village watch or rural police (*chaukidars*), 271.

Shiurajpur—Town in Cawnpur District, North Western Provinces, and head-quarters of Shiurajpur *tahsil*, situated on the Grand Trunk Road, 21 miles north west of Cawnpur city. Population (1872), including the neighbouring villages of Rajpur and Barrampur 7883. Not returned separately in the Census of 1881. Besides the sub-divisional courts and offices, the town contains a police station post-office, and Government school. A fort, formerly the seat of a Chandela Raja, was razed to the ground after the chief's rebellion in 1857-58.

Shiurajpur—Small village and station on the East Indian Railway in Bara *tahsil*, Allahabad District North Western Provinces. Population (1881) 477. Noted for its stone quarries. Rising market, post office, police station.

Shiurajpur—Village in Kalinpur *tahsil*, Latchpur District, North Western Provinces, situated in lat. 26° 10' 20" N. and long. 80° 35' 30" E., on the Ganges, 22 miles from Latchpur town. Population (1881) 1425, chiefly Brahmans. The village is the site of the largest fair in the District, which is held on the occasion of the *Purnamasi* festival in October-November.

Shivagangā.—*Lamindari* and town in Madura District, Madras Presidency.—*See SHIVAGANGA*.

Shivagangā.—Hill in Bangalore District, Mysore.—*See SHIVAGANGA*.

Shivbara.—Petty *Princely State* in Khandesh District, Bombay Presidency.—*See PRINCIPAL STATES*.

Shivgaon.—Sub-division of Ahmadnagar District Bombay Presidency. Area, 670 square miles. Population (1881) 87,113, namely, males 43,093 and females 43,020, occupying 16,100 villages, in 1 town and 179 villages. Hindus number 79,208, Muhammadans, 5776, and 'others,' 2129. Shivgaon is the most easterly sub-division of the District. With one or two exceptions, the streams which drain the tract all rise in the hills on the south and south-west, and flow northward into the Godavari. The villages are for the most part

well supplied with water, which throughout the low grounds is always to be found at a moderate depth. Near the Godávári, the soil is deep and stiff, but near the hills it is of a lighter composition, and more easily worked. Early and late crops are grown in about equal proportions. In 1881-82, the actual area under cultivation was 222,759 acres. Cereal and millets occupied 177,102 acres; pulses, 17,612 acres; fibres, 19,531 acres; oil-seeds, 7001 acres; and miscellaneous crops, 1513 acres. About 3000 looms are worked in the Sub-division, of which about 2000 are in the town of Páthardi, and 200 in Tisgáon. The principal manufacture is of various kinds of cotton cloth, mostly coarse. In 1883 the Sub-division contained 2 civil and 2 criminal courts; police circle (*tháná*), 1; regular police, 34 men; village watch (*chaukidárs*), 272. Land revenue, £19,914.

Shivgáon.—Town in Ahmadnagar District, Bombay Presidency, and head-quarters of Shivgáon Sub-division; situated 40 miles north-east of Ahmadnagar city, in lat. $19^{\circ} 21' N.$, and long. $75^{\circ} 18' E.$ Population (1881) 2948. Shivgáon is a ruined town on a wide plain; joined with Paithan and Ahmadnagar by a good road. It is surrounded by a wall. Sub-divisional offices, post-office, dispensary, school, temples, and weekly market on Sundays.

Shivner.—Hill fort of the town of Junnar, in Poona (Púna) District, Bombay Presidency; situated not far from Harischandragarh, and about 50 miles north of Poona city. The hill of Shivner rises over a thousand feet, and stretches about a mile across the plain. It is triangular in shape, narrowing from a southern base of about 800 yards to a point of rock in the north. Near the south, the lower slopes of its eastern face are crossed by a belt of rock 40 or 50 feet high. The south-west of the hill is broken, and from about half-way up is strengthened by outworks and bastioned walls. Shivner is interesting as having been the birthplace of Sivají the Great.

During the first and second, and probably the third century after Christ, the hill seems to have been a great Buddhist centre. About 50 cells and chapels remain. They are found on three sides of the hill, but most of them are cut in its eastern face. Shivner was granted in 1599 to Sivají's grandfather, Málojí Bhonsla; and here, in 1627, Sivají was born. It was often taken and retaken; and once, in 1670, the forces of Sivají himself were beaten back by its Mughal garrison. Besides its five gates and solid fortifications, it is celebrated for its deep springs. They rise in pillared tanks of great depth, supposed by Dr. Gibson to be coeval with the series of Buddhist caves which pierce the lower portion of the scarp. The fort commands the road leading to the Náneghát and Málsejghát, formerly the chief line of communication between this part of the Deccan and the coast. [For further information respecting Shivner fort and caves, see the *Gazetteer of the*

Bombay Presidency, vol. xviii. part iii. pp. 153-163, and pp. 184-201 (Bombay, 1885)]

Shivali (Siyali)—*Taluk* or Sub-division of Tanjore District, Madras Presidency. Area, 159 square miles. Population (1881) 114,031, namely, 55,465 males and 58,576 females, occupying 19,647 houses, in 1 town and 190 villages. Hindus number 106,621, Muhammadans 4614, and Christians, 2806. In 1883 the *taluk* contained 1 civil and 2 criminal courts, police circles (*th in is*) 5, regular police, 41 men. Land revenue, £27,883.

Shivali (Siyali)—Town in Shivali *taluk*, Tanjore District, Madras Presidency. Lat $11^{\circ} 14' N$, and long $79^{\circ} 46' E$. Head-quarters of the *taluk*. A station on the South Indian Railway.

Sholágarh.—Town in Munshiganj Sub-division, Dacca District, Bengal. Lat $23^{\circ} 33' 45' N$, long $90^{\circ} 20' E$. Population (1881) 6079.

Sholangipuram.—Town in North Arcot District, Madras Presidency.—*See* SHOLINCHAR.

Sholápur.—British District in the Deccan, Bombay Presidency, lying between $17^{\circ} 13'$ and $18^{\circ} 35' N$ lat, and between $74^{\circ} 39'$ and $76^{\circ} 11' E$ long. Area 4521 square miles. Population in 1881, 585,487 souls. Except *Barsi taluk* which is surrounded by the *Nizam's* territory, Sholapur District is bounded on the north by Ahmadnagar District, on the east by the *Nizam's* Dominions and Akalkot State, on the south by Bijapur District and the Jath and Patwardhan States and on the west by Sátara, Poona, and Ahmadnagar Districts and the States of Phaltan and Atpadi. On the west, in some places Patwardhan villages are included and in others isolated Sholapur villages lie beyond the District limits. The administrative head-quarters are at the city of SHOLAPUR.

Physical Aspects.—Except north of *Barsi* west of *Madhya* south west of *Malsiras* and *Karmali* where there is a good deal of hilly ground the District is generally flat or undulating. Most of the surface rolls in long low uplands separated by hollows, with an occasional level. The shallow soiled uplands are suited for pasture and the deeper soiled lowlands under careful tillage yield the richest crops. The uplands are gently rounded swells of trap, overgrown with a low situated spear grass. Sholapur District is very bare of vegetation and presents everywhere a bleak treeless appearance. The chief rivers are the Bhima (Bheema) and its tributaries, the Manjira, the Nira and the Sind, all flowing towards the south-east. Besides these there are several minor streams. Of the principal rivers the Bhima and Nira are near Sholapur city, one is at Koregaon and one at Parbhani. Wells are to be seen every where, but water for agricultural purposes is scarce. The rainfall being very uncertain, a scarcity of water is

annually felt during the hot weather. Stunted *bábuls* and mangoes, and a few *níms* (*Azadirachta indica*) and *pípals* (*Ficus religiosa*), are the only timber-trees found in the District. As these afford no cover, the District is without wild animals of the larger kinds, except the wild hog and wolf.

History.—Sholápur is one of the Districts which formed the early home of the Maráthás, and the birthplace of the dynasty. It is still a great centre of Maráthá population and mercantile activity. As full an account of the rise and progress of the Maráthá power as is consistent with the scope of this work will be found in the article on INDIA, vol. vi. pp. 317–324, and further local details are given in the notice of the adjacent District of SATARA. An excellent monograph has been written on Poona, Sátára, and Sholápur Districts by W. W. Loch, Esq., of the Bombay Civil Service.

Sholápur, in the early centuries of the Christian era (B.C. 90–A.D. 300?), probably formed part of the territories of the Shatákarni or Andhrabhritya dynasty, whose capital was Paithan on the Godávári, about 150 miles north-west of Sholápur city. Probably also during the 500 years previous to the Muhammánadan overthrow of the Deogiri Jádavs in the beginning of the 14th century, Sholápur, like the neighbouring Districts of Bijápur, Ahmadnagar, and Poona, was held by the Early Chalukyas from 550 to 760, by the Ráshtrakutas to 973, by the revived or Western Chalukyas to 1184, and by the Deogiri Jádavs till the Muhammánadan conquest of the Deccan about 1300.

The first Muhammánadan invasion of the Deccan took place in 1294, but the power of the Deogiri Jádavs was not crushed till 1318. From 1318, Máharashtra began to be ruled by governors appointed from Delhi, and stationed at Deogiri, which name was changed in 1338 by Muhammad Tughlak to Daulatábád, the 'Abode of Wealth.' In 1346 there was widespread disorder, and Delhi officers plundered and wasted the country. These cruelties led to the revolt of the Deccan nobles under the leadership of an Afghán soldier named Hasan Gangu. The nobles were successful, and freed the Deccan from dependence on Northern India. Hasan founded a dynasty, which, in honour of his patron, a Bráhmaṇ, he called Bahmani; and which held sway over the Deccan for nearly 150 years. In 1489, Yusaf Adil Sháh, the Governor of Bijápur, assumed independence, and overran all the country north of Bijápur as far as the Bhíma. For nearly 200 years, Sholápur belonged either to the Bijápur or to the Ahmadnagar kings as the one or the other succeeded in retaining it. In 1668, by the treaty concluded at Agra between Aurangzeb and Alí Adíl Sháh of Bijápur, the fort of Sholápur and territory yielding £63,000 of annual revenue was ceded to the Mughals as the price of peace. The general

decay of the Mughal Empire from 1700 to 1750 opened the way for the Maráthá supremacy.

Sholápur formed part of the Peshwá's dominions, until the downfall of his dynasty in 1818, and the incorporation of his territories in the Bombay Presidency. It was at first included with the District of Poona, but was erected into a separate Collectorate in 1838. Since then its progress has been rapid. Roads have been constructed, and the country is now traversed by the Great Indian Peninsula Railway. From time to time its prosperity receives checks owing to drought, to which its situation and the trackless surface of the country expose it. It suffered especially in the famine of 1877, when it was the first District to manifest distress in the Bombay Presidency. Extensive relief works were at once opened and every possible means were taken to avert the starvation of the people. Much has been done by the opening of canals and ponds, such as the Fkrak and Asht tanks, to secure a better water supply, and to protect the husbandmen from the cruel vicissitudes of the seasons. But the situation and physical characteristics of Sholapur will always render it liable to the calamities arising from drought.

Population—The census of 1872 returned a total population of 719,375 persons. The census taken on February 17th 1881 disclosed a total population of 552,457 in Sholapur, showing a decrease of 136,888, or 19.02 per cent, since 1872 due entirely to mortality or emigration as the results of the famine of 1876-78.

The following are the main details shown by the census of 1881—Area, 4521 square miles, towns, 6, villages, 726, walled houses, 81,203, unwalled houses, 161,772. Average density, 122.54 persons per square mile, villages per square mile, 0.15, houses per square mile, 21.6, persons per village or town, 815, persons per house, 7.17. Males numbered 294,514 and females 257,943, proportion of males, 50.6 per cent. Classified according to sex and age there were under 15 years of age, boys 111,468 and girls 104,134, total children, 215,772, or 37.03 per cent. 15 years and upwards, males 183,346, and females 183,369, total adults, 366,715, or 62.97 per cent.

Classified according to religion, Hindus 4,00,000, Muslims 1,43,967, Jains 7514, Christians 22, Parsis 15, Jews, 94; Sikhs, 8, Buddhist, 1. The Hindus were subdivided into Brahmins (priests and government servants), 270,000; Rajas, 2,250; Chattris, 11,381; Barjis (tailors), 6222; Dharmis, 57,000; Dharmis (caste men), 4085; Natis (barbers), 5953; Kantis (soldiers), 178,905; Kohis (cultivators), 7530; Kantis, 10,658; Lakhatis (traders), 21,509; Lohars (blacksmiths), 2938; Malis (gardeners), 21,678; Mangis (depressed caste), 19,233; Mhars, 44,001; Sonars (goldsmiths), 3057; Telis (oilmen), 6750; Berids, 3404; Jangams, 3838; Kantis,

(potters), 3852; Sutárs (carpenters), 4824; and Banjárás (carriers), 3397. The Muhammadan population by race, as distinguished from descendants of converts, consisted of—Patháns, 4350; Sayyids, 3905; Shaikhs, 35,177; and 'others,' 535. According to sect, the Muhammadans were returned—Sunnís, 43,358; Shiás, 391; Wahábís, 3; and unspecified, 215. Among the Christians, 343 were Roman Catholics, 147 Protestants, and 135 of other Christian creeds. Adopting another principle of classification—native Christians numbered 399; Eurasians, 68; and Europeans, 158.

With regard to occupation, the Census distributes the male population into the following six main groups:—(1) Professional class, including all State, civil and military, officials, 11,314; (2) domestic servants, inn and lodging keepers, 3607; (3) commercial class, including bankers, merchants, carriers, etc., 5516; (4) agricultural and pastoral class, including gardeners, 135,064; (5) industrial class, including all manufacturers and artisans, 39,276; and (6) indefinite and non-productive class, comprising general labourers, male children, and persons of unspecified occupation, 100,037.

Of the 712 towns and villages in Sholápur District, 111 contain less than two hundred inhabitants; 243 from two to five hundred; 230 from five hundred to one thousand; 96 from one to two thousand; 16 from two to three thousand; 10 from three to five thousand; 3 from five to ten thousand; 2 from fifteen to twenty thousand; and 1 over fifty thousand. The most important towns are SHOLAPUR (city, 59,890; cantonment, 1391), PANDHARPUR (16,910), BARSÍ (16,126), KÁRKAMB (6421), KÁRMALA (5071), and SANGOLA (4726). All these, except Kárkamb, are municipalities. Total municipal population (1881) 102,723; municipal income (1883–84), £25,839; the incidence of taxation per head of population varied from 4½d. (Pandharpur) to 5s. 2½d. (Sholápur).

Agriculture.—Agriculture supported (1881) 389,224 persons, or 66·82 per cent. of the population; 210,292 were agricultural workers.

The soil of Sholápur is of three kinds, *káli* or black, *barad* or coarse grey, and *tambdi* or reddish. Except in the Bársi Sub-division, where black soil is the rule, and coarse grey is rare, most of the District is either grey or red. The black soil is almost confined to the banks of rivers and large streams.

Of the total area of the District, 4521 square miles, 3413 square miles were cultivated in 1881, of which 188 square miles were revenue-free. Area assessed for revenue, 3800 square miles. Total amount of Government assessment, including local rates and cesses on land, £111,965; average incidence of assessment, including local rates and cesses, 11½d. per cultivated acre.

The total area of Government land is 2,646,136 acres, namely,

2,100 243 acres, or 90 70 per cent, cultivable, of which 215,115 acres are alienated, 155,709 acres or 5 88 per cent, uncultivable, 5449 acres, or 0 21 per cent, grass or *kurin*, 29 553 acres, or 1 12 per cent, forest, and 55,182 acres, or 2 09 per cent, village sites roads, and river beds. In 1883-84 1,763 340 acres were under actual cultivation, of which 22,282 were twice cropped. Cereals and millets occupied 1,330 781 acres, of which 923 706 acres were under *jair* (*Sorghum vulgare*), pulses, 185 528 acres, orchards, 3640 acres, drugs and narcotics, 2323 acres, condiments and spices, 7728 acres, sugar-cane, 5151 acres, oil seeds, 189,235 acres, dyes, 468 acres, and fibres (cotton), 60,768 acres.

In 1883-84 the agricultural stock consisted of—cows and bullocks, 340 258, buffaloes, 72 499, horses, 11,158, donkeys, 4191, sheep and goats, 420 616, ploughs, 21,014, and carts, 11 901. Prices of produce, per *maund* of 80 lbs—wheat, 5s 5d, rice, best, 7s 5½d, rice common, 6s 10½d, *Lhra* (*Pennisetum typhoideum*), 3s 5½d, *Jir*, 3s 1d, gram, 3s. 10½d, salt, 6s. 0½d, flour, 6s 7½d, *dāl*, split peas, 4s 3½d, *ghl*, £3 12s 6½d. The wages of skilled labour are from 6d to 1s 9d per day, and of unskilled labour, 3d to 1s.

On garden land manure is always used, and also on dry crop land when available. The usual mode of manuring a field is by turning into it a flock of sheep and goats, for whose services their owner is paid according to the length of their stay. Scarcity of manure is the main reason why so little land is watered compared with the area commanded by the *Ikruk* lake and other water works. An industrious farmer ploughs his land several times before he sows it and weeds it several times while the crop is growing. An irregular rotation of crops is observed and about a fifth or sixth part of the holding is often left unsown. As a rule, the poorer landholders neither weed nor manure their land. They run a light plough over it sow the seed broadcast, and leave it to itself. They expect to get from it at best merely a bare food supply for the year, and while the crop is ripening they have to supplement their field profits by the wages of labour. Much of the best land is in the hands of money lenders who have either bought it or taken it on mortgage. The tendency seems to be for the petty landholders to diminish, and the land to fall into the hands of men of capital who employ the old holders as their tenants or labourers. It may be accepted that only about 10 per cent of the agricultural classes are free from debt, and that the remaining 90 per cent are involved advances from time to time under some shape being a necessity to them. The Relief Act by protecting their property from attachment and sale for debt, has rendered this necessity less urgent. In 1883-84 in the irrigated lands, the total number of holders was 49 536, with an average area of about 48 acres.

Ironworks 7.—The ironworks in *Sholapur District* are the

Koregáon, Ashti, and Ekruk lakes. The first-named is an old work improved, and the two last are new works. Koregáon lake lies 13 miles north-east of Bársi, and is formed by throwing two earthen dams across two separate valleys. The smaller of the dams was breached in 1870. It is proposed to restore it. The lake will then have a capacity of 81 millions of cubic feet. The Ashti lake lies in the Mádhá Sub-division, 12 miles north-east of the town of Pandharpur. The lake when full holds 1499 millions of cubic feet of water. The Ekruk lake, the largest artificial lake in the Bombay Presidency, lies 5 miles north-east of Sholápur. The lake is 60 feet deep when full, and holds 3350 millions of cubic feet of water.

Forests.—The dry, shallow soil of the uplands of Sholápur District is ill suited for trees. The present area reserved for forests is 242 square miles, or about 5·35 per cent. of the total area of the District. The forest area is much scattered. It may be roughly divided into two tracts of forest land, on the hills between Bársi and the Nizám's territories in the extreme north-east, and on the hills to the south of Málsiras and SÁNGOLA in the extreme south-west. Before December 1871, when forest conservancy was introduced, Sholápur was extremely bare of trees and brushwood. Almost the whole land was taken for tillage. In December 1871, two square miles of scattered grass land or *kuran* were transferred to the Forest Department. During the twelve years ending 1883, these two miles have spread to 242 square miles. In the whole of the Sholápur forest area, no timber-cutting rights are admitted to exist. The forest lands are of two classes—scrub forest and *bábul* (*Acacia arabica*) meadows. The scrub forest is found on the hills, and *bábul* meadows occur all over the District. Of the total area, 24,885 acres consist of scrub forest, and 129,955 acres of *bábul* meadows.

Forest receipts are comparatively small, amounting to only £829 in 1882–83. About one-fifth of the forest reserves are yearly leased for grazing. The remaining four-fifths are leased yearly for grass-cutting, and in these, tree plantations are formed. Besides for fuel, the timber of the *bábul* and the *nim* (*Melia Azadirachta*) are used in making beams, posts, doors, carts, ploughs, and other field tools. The bark of the *bábul* and of the *tarrad* (*Cassia auriculata*) is used for tanning, and the pods as well as the flowers of the *palís* (*Butea frondosa*) are used for dyeing. The bark of the *ápta* (*Bauhinia racemosa*) is made into ropes.

Natural Calamities.—The earliest recorded famine is the great Durgá Devi famine, which began about 1396 A.D., and is said to have lasted nearly twelve years. It arose from want of seasonable rain; and it is said to have spread over the whole country south of the Narbadá, and to have depopulated whole Districts. Next came the famine of 1460

AD About 1520, a great famine is said to have military hordes destroying and plundering the crops. 1791 was very severe, especially in the Karnatak, entirely failed. In the Deccan the yield was one-fourth of the usual output, but as thousands flocked from the Deccan for food, the distress became very severe. Grain sold at 3 lbs the shilling. In 1802, the plagues of crops by Holkar and the Pindaris caused a series of failures of the rain in October and November. A famine of ruinous severity. In 1818 partly owing to the Peshwa's armies and partly owing to the failure of the rain, the District again suffered from famine accompanied by the destruction of thousands of lives. Other famines occurred in 1824, 1832-33, 1845, 1854 and 1862, owing to scanty rain.

In 1876, the scanty rainfall of 9.11 inches led to famine and distress, amounting to famine resulted over the District. In September and October except one or two local showers, no rain, and no cold weather crops were sown. The poorer classes began to show signs of distress, and in September, Government sanctioned the opening of a public granary, at the opening of the rainy season of 1877, another long drought, which caused great suffering. It continued till September and October, when a heavy rainfall brought down prices and gave much relief. In November the demand for special Government rice was taken on the 19th of May 1877, when the general and severe showed that of 62,712 persons, 21,347 were manufacturers or craftsmen, 21,347 were holders of land and 37,401 were labourers. The famine was estimated at £206,500, of which £100,318 on charitable and civil works, and £106,182 on charitable works. A large number of people, chiefly husbandmen, perished in the Berar and the Nizam's territory. The number of cattle died. The cultivated area fell from 1,136,988 in 1876-77 to 1,136,988 in 1877-78.

During the cold season of 1879 from January to March rats and mice appeared and ate the grain before the harvest. Many fields were entirely ruined, and a large portion was saved by ploughing the earth. About seven-eighths of the crops was lost. The Government, about £660 was paid as reward for the hunt.

Trade Commission of 1880 — Between 1880 and 1881 the Great Indian Peninsula Railway was opened.

District at Pomalvádi in the north-east corner, and crossing in a south-easterly direction towards Gulbarga in the Nizám's Dominions, and eight miles of the East Deccan line of the Southern Maráthá Railway, there are 382 miles of made roads. Of these, three are provincial and seven local fund. The three provincial lines are—the Poona-Haidarábád road, 78 miles; the Bársi road with its extension towards the Nizám's territory, 62 miles; and the Sholápur-Bijápur road, 19 miles. Of the seven local fund roads four are first-class—the Bársi-Pandharpur road, 30 miles; the Mohol-Pandharpur, 24 miles; the Pandharpur-Janoni, 42 miles; and the Jeur-Kármála with its extension towards Ahmadnagar and the Nizám's territory, 27 miles: three are second-class—the Sholápur-Bársi, 42 miles; the Sholápur-Akalkot, 15 miles; and the Jeur-Pandharpur, 43 miles.

Since the opening of the railway in that portion of the District between the Nizám's Dominions and Poona, trade has greatly increased. Next to cotton, a large proportion of which comes from without, the chief exports are oil, oil-seeds, *ghí*, turmeric, and cotton cloth. The imports are salt, piece-goods, yarn, gunny-bags, and iron-ware.

Trade is carried on at the towns and in markets, fairs, village shops, and also by travelling carriers. The largest centres of internal trade are Sholápur, Bársi, and Pandharpur, and next to these Vairág, Mádha, Mohol, Kármála, Akluj, Wate-Pate, and Sângola. Of these, Sholápur, Mohol, and Mádha are near the railway. The number of traders is about 6000, the chief being Lingáyats, Bhátiás, Gujárs, Vánis, Nagars, Márwáris, Bráhmans, Borahs, and Kshattriyas. Forty-two weekly markets are held in the District, at which petty traders, pedlers, and hawkers set up booths and offer for sale their goods, consisting of cotton, grain, groceries, spices, cloth, yarn, oils, earthenware, *ghí*, hides, fuel, etc. Of 19 trading fairs held in the District, one held at Sholápur on the 12th January, three held in Pandharpur in April, July, and November, and one held at Sonári in April, are the most important. The chief articles for sale are cloth, pots, grain, glass bangles, and live stock.

After agriculture, the chief industries of the District are spinning, weaving, and dyeing. The silks and finer sorts of cotton cloth—such as *dhotís* and women's robes—prepared in Sholápur bear a good name. Blankets are also woven in large numbers. Besides hand-loom weaving, a steam spinning and weaving mill, with 20,888 spindles and 175 looms, has lately been established at Sholápur city. Oil-presses of the native type are worked by Telís in many places, and saltpetre is manufactured to some extent by Mhars and Mángs.

Administration.—The revenue collected in 1882-83 from land was £98,990; from stamps, £6890; from excise, £13,110; and by the licence-tax, £3210. Forest proceeds amounted to £820; the local

fund receipts were £6970; and the five municipalities raised an income of £21,615, the only peculiarity being a pilgrim tax in Pandharpur, and a water rate in Sholapur. The administration of the District in revenue matters is entrusted to a Collector and 4 Assistant Collectors, three of whom are covenanted civilians. The District is provided with the court of a senior Assistant Judge. For the settlement of civil disputes, there are 4 courts besides the above. Nineteen officers share the administration of criminal justice. The total strength of the regular police force for the protection of person and property consisted of 92 officers and 438 constables, giving 1 man to every 1099 of the population. The total cost was £8724, equal to £1, 18s. per square mile and 3½d per head of population. There is one jail in the District.

Compared with 45 schools and 516 pupils in 1865, there were, in 1877, 115 schools, with a roll-call of 4648 names, or, on an average, 1 school for every five villages. In 1882-83, there were 176 Government schools, or an average of 1 school for every four villages, with an average attendance of 5708 pupils. Besides these Government schools, there were 4 primary schools inspected by the Educational Department. In 1869, the first girls' school was opened in Bārsi. In 1882-83, the number was 4 with 176 names, and an average attendance of 105. The Census of 1881 returned 8795 boys and 204 girls as under instruction, besides 18,824 males and 214 females able to read and write but not under instruction. Four vernacular papers were published in 1884.

Medical Aspects—The climate, except from March to May, is healthy and agreeable. In the hot season, the mean temperature is 86° F., very hot and oppressive in the day time, but cool at night. Mean temperature—January, 71° 8' F., February, 76° 8' F., March, 83° 7' F.; April, 88° F., May, 88° 9' F., June, 82° 1' F., July, 78° 9' F.; August, 77° 9' F.; September, 77° 1' F., October, 77° 3' F.; November, 73° 8' F., December, 70° 7' F. annual mean, 78° 9' F. In 1883, the maximum temperature at Sholapur was 109° F. in May; the minimum, 46° 2' F. in December. The rainy season is pleasant; the sky is more or less overcast, and the rain falls in heavy showers, alternating with intervals of sunshine. The average annual rainfall for a period of 25 years ending 1881 was 256 inches. In 1883-84, the rainfall was 39.93 inches. The rainfall is generally unequally distributed, the fall in the western subdivisions being very scanty compared with that in the east. During the cold season, from November to February, the atmosphere, with keen easterly and north-easterly winds, is clear and bracing.

Besides fever of an intermittent type, skin diseases such as guinea worm, itch, and ringworm are prevalent in the Bārsi and Kārīdās subdivisions, brought on chiefly by the badness of the well water. Fever

Bahmani dynasty (1345) On the dissolution of that kingdom in 1489, Sholapur was held by Zein Khán. But during the minority of his son it was, in 1511, besieged and taken by Kamál Khán, who annexed it, with the surrounding Districts, to the Bijápur kingdom. In 1523, Sholapur formed part of the dowry of Ismáíl Adil Sháh's sister, given in marriage to the King of Ahmadnagar. But not being handed over to the Ahmadnagar kingdom, it formed for forty years a source of constant quarrels between the two dynasties, until it was given back to Bijápur as the dowry of the Ahmadnagar princess Chánd Bibí (1562). On the overthrow of the Bijápur kingdom (1686), Sholapur fell to the Mughals, from whom it was taken by the Marathás. At the close of the war with the Peshwá in 1818, it was stormed by General Munro.

Since then, the town, no longer exposed to the raids of robbers, has been steadily increasing in importance. Its convenient situation between Poona and Hüdarábád has made it, especially since the opening of the railway in 1859, the centre for the collection and distribution of goods over a large extent of country. The chief industry of Sholapur is the manufacture of silk and cotton cloth more than 5000 persons being engaged as hand loom weavers, spinners, and dyers. A steam weaving and spinning mill has been established in the town. The machinery is driven by two engines each of 40 horse-power, works 20 888 spindles and 175 looms and employs 850 hands.

Sholapur town is situated in the centre of a large plain 1800 feet above sea level, on the watershed of the Adil a feeder of the Sina. To the south-west, close to the city wall, lies the fort of Sholapur and farther on are the officers' bungalows of the old cavalry line, now mostly occupied by railway servants, and the railway station. To the south of the city is the Sidheswar lake, with a temple in the centre. On the south-east bank of the lake is the municipal garden and about 1000 yards more to the south-east are the Collector's office and bungalow.

About 100 to 500 yards south-west of the Collector's office stretch the officers' bungalows of the old cantonment, from 50 to 100 yards west of the officers' bungalows are the Protestant church, the Roman Catholic chapel and the post-office. About 1000 yards south-east of the *Sidheswar* are the Native Infantry lines, and to the south of the lines are the officers' bungalows in the present cantonment limits. The greater part of the old military cantonment of Sholapur has been transferred to the civil authorities, and is now included within municipal limits. The present cantonment covers an area of about 1000 acres, just enough for a Native Infantry regiment. Since the removal of the Native Infantry regiment in 1877, the fort has been placed in charge of the civil authorities.

The city was formerly enclosed by a wall 2½ miles in circumference. In 1872, to give room to the growing town, the municipal corporation ordered the

the whole of the east wall and parts on the south-west and north. The walls, where standing, are 8 to 10 feet high, 4 to 6 feet wide at the base, and 3 to 4 feet wide at the top.

Sholápur fort is an irregular oblong about 230 yards by 176, enclosed by a double line of lofty battlemented and towered walls of rough stone 10 to 20 yards apart, and surrounded, except on the east or Siddheswar lake side, by a wet moat 100 to 150 feet broad and 15 to 30 deep. The whole work is Muhammadan, the outer wall dating from the 14th century, and the inner wall and four great square towers from the 16th and 17th centuries. The outer wall, with battlemented curtains and four corner and 23 side towers, is pierced for musketry; and with openings and vaulted chambers for cannon, rises 20 to 30 feet from the edge of the moat. About 20 yards behind, the inner wall, also towered and battlemented, rises 5 to 10 feet above the outer wall. The inner wall has about 25 towers, exclusive of the four square towers.

Besides the courts of the Sub-divisional and District revenue officers, there are the senior assistant's and the subordinate judge's courts. The houses are mostly built of mud, but sometimes of stone and burnt bricks, and are covered with flat roofs. On account of the absence of any high ground in the neighbourhood, Sholápur is on all sides exposed to the winds. The climate, except during the months of March, April, and May, is agreeable and healthy. The municipality, established in 1853, had an income in 1883-84 of £15,496; incidence of taxation, 5s. 2½d. per head of population. The chief municipal undertaking has been the water-works, which form the chief source of the city water-supply. They were constructed by the municipality between 1879 and 1881, and give a daily supply of about 6 gallons a head. The water is drawn from the Ekruk lower level canal through a line of 10-inch pipes into a settling tank, and thence pumped by steam-power.

Sholavandan. Town in Madura *taluk*, Madura District, Madras Presidency; situated in lat. 10° 2' 30" N., and long. 78° 2' E., 12 miles from Madura city, on the Vaigai river. Population (1881) 3050, inhabiting 528 houses. Hindus number 2817; Muhammadans, 163; and Christians, 70. The town was built in 1566 by a colony of *Velalars*, relatives of the Vijayanagar Governor. The fort commanded a pass on the main road from Dindigul to Madura, and was occupied by Muhammad Yusuf in 1757, to cover the operations of Calliaud against Madura. In the same year it was captured by Haidar Ali, and taken by the British.

Sholinghar (Sholinghar). Town in North Arcot District, Madras Presidency. Lat. 13° 7' N., long. 79° 20' E. Population (1881) 2077, inhabiting 207 houses. Hindus number 5483; Muhammadans, 100; and Christians, 0. Ten miles from Ranavaram station, on the south-western railway. The scene of one of Ceote's greatest

and open-air pursuits. Their moral code is high, and they are said never to violate their oath; but they are illiterate. [For an account of the Bedars and their customs, see Meadows Taylor's *Story of My Life*, pp. 210, 211 (second edition).]

Shorkot.—South-western *tahsíl* of Jhang District, Punjab. Area, 1220 square miles; number of towns and villages, 174; houses, 17,197; families, 20,615. Population (1881) 95,342, namely, males 52,727, and females 42,615. Average density, 79 persons per square mile. Classified according to religion, Muhammadans number 77,616; Hindus, 17,355; Sikhs, 367; and Christians, 4. Of the 174 towns and villages, 109 contain less than five hundred inhabitants; 39 from five hundred to a thousand; and 26 from one to five thousand. Principal crops—wheat, *jowár*, gram, and cotton. Revenue of the *tahsíl*, £11,985. The administrative staff consists of a *tahsildár*, and an honorary magistrate; number of police stations (*thánás*), 2; strength of regular police, 51 men; village watch or rural police, 102.

Shorkot.—Ancient town in Jhang District, Punjab, and headquarters of Shorkot *tahsíl*; situated in lat. $30^{\circ} 50'$ N., and long. $72^{\circ} 6'$ E., among the lowlands of the Chenáb, about 4 miles from the left bank of the river, and 36 miles south-west of Jhang town. The modern town stands at the foot of a huge mound of ruins, marking the site of the ancient city, surrounded by a wall of large antique bricks, and so high as to be visible for 8 miles around. Gold coins are frequently washed out of the ruins after the rains. General Cunningham identifies Shorkot with a town of the Malli attacked and taken by Alexander, and visited by Hiuen Tsiang ten centuries later. General Cunningham infers, from the evidence of coins, that the town flourished under the Greek kings of Ariana and the Punjab, as well as under the Indo-Scythian dynasties up to 250 A.D. It was probably destroyed by the White Huns in the 6th century, and reoccupied in the 10th by the Bráhmaṇ kings of Kábul and the Punjab. The modern town is a place of little importance. Population (1881) 2283, namely, Hindus, 1167; Muhammadans, 1104; and Sikhs, 12. Number of houses, 365. Municipal income (1883-84), £153. The town is surrounded by fine groves of date-palms. Many of the buildings are lofty, but most of them are more or less in a state of ruin. A good *bázár*, with a gate at each end, and lined with shops built on a uniform plan; but few of the shops are tenanted. *Tahsílí*, police station, dispensary, school, and rest-house.

Shrávan-belgola (lit. 'Tank of the Śrávans or Jains').—Village in Hassan District, Mysore State; situated in lat. $12^{\circ} 51' 10''$ N., and long. $76^{\circ} 31' 31''$ E., between two rocky hills called Chandra-betta and Indra-betta. Population (1881) 1315. According to Jain tradition, Bhadrá Báhu, one of the six immediate disciples of the founder of

their religion, died here while leading a colony from Ujjain into Southern India. He is said to have been accompanied by the celebrated Emperor Chandragupta, who had abdicated the throne and adopted the life of a hermit. These events, borne out by a rock inscription of great antiquity, are assigned to the 4th century B.C. The grandson of Chandragupta is also related to have visited the spot.

On the summit of Chandra betta stands the colossal statue of Gomateswara, 60 feet high, surrounded by numerous buildings. The hill itself is 3250 feet above sea level. An inscription on the foot of the statue states that it was erected by Chimunda Rāja, whom tradition places about 60 B.C. The surrounding enclosures bear the name of Ganga Rāja, who belongs to the Hoysālā Billāla period.

The statue is nude, and stands facing the north. The face has the serene expression usually seen in Buddhist statues, the hair is curled in short spiral ringlets over the head, while the ears are long and large. The figure is treated conventionally, the shoulders being very broad, the arms hanging down the sides with the thumbs turned outwards, the wrist small. The feet are placed on the figure of a lotus. Here representations of ant hills rise on either side, with figures of a creeping plant springing from them, which twines over the thighs and arms, terminating in a tendril with bunches of fruit. These symbolize the complete spiritual abstraction of a *yogi*. According to the most reasonable hypothesis, the statue must have been cut out of a rock which projected above the hill, or perhaps the solid summit of the hill may have been itself cut away. The workmanship is still as sharp as if the stone had been newly quarried. Within the enclosure are 72 small statues of a similar description in compartments.

On the face of the opposite rock of Indra betta are inscriptions cut in ancient characters a foot long. Shravan belgoḷa is known to have been an ancient seat of Jaina learning and is still the residence of the chief *guru* of that sect, but the establishment was deprived of many of its privileges and emoluments by Tipu Sultan. There is a considerable manufacture of brass utensils, which are exported to distant parts.

Shrīgonda.—Sub-division and town in Ahmednagar District, Bombay Presidency.—*See* **SRIGONDA**.

Shrivardhan.—Town in Rajapur State, Bombay Presidency.—*See* **SRIVARDHAN**.

Shujābād.—*Tahsil* of Mull in District Peshawar. Area 352 sq. miles, number of towns and villages 80, 1 towns, 12301 families, 13658. Population (1881) 61672, namely, males 33391 and females 28228. Average density, 191 per square mile. Classified according to religion, Muhammadans number 20700, Hindus 10747, Sikhs, 141, Jains, 1. Of the 80 towns and villages in the *tahsil* 37 are in

less than five hundred inhabitants; 22 between five hundred and a thousand; 20 between one and five thousand; and 1 between five and ten thousand. Average area under cultivation for five years ending 1881-82, 110 square miles, or 70,580 acres; principal crops—wheat, 25,839 acres; rice, 5018 acres; *jowar*, 4533 acres; indigo, 14,710 acres; cotton, 5880 acres; and sugar-cane, 4180 acres. Revenue of the *tahsil*, £16,452. One *tahsildar's* court; strength of regular police, 59 men; village watch or rural police, 99.

Shujábád.—Town and municipality in Múltán District, Punjab, and head-quarters of Shujábád *tahsil*; situated in lat. 29° 53' N., and long. 71° 20' E., about 5 miles from the present left bank of the Chenáb. Population (1881) 6158, namely, Hindus, 3970; Muhammadans, 2476; Sikhs, 9; and 'others,' 3. The fort was built by Shujá Khán, one of the Nawábs of Múltán under Ahmad Sháh Duráni, in whose time the town possessed some importance. Municipal income (1883-84), £724, or an average of 2s. 2½d. per head. The town is chiefly built of brick, and contains some fine native houses. It is the trade centre for the richest portion of the District, and is intersected by two broad *bázárs* which cross each other. North-west of the town is the palace of Shujá Khán, a collection of rather fine brick buildings, now used as the *tahsil* and police station. Dispensary, school of the Church Missionary Society, *sarái* or native inn, and encamping ground. The surrounding country is irrigated by the Gajjúhatta and Bakhtúwah canals, and yields fine crops of indigo and sugar-cane. Municipal income in 1875-76, £656, or 2s. 1d. per head of population (6268) within municipal limits.

Shútar Gardan.—Mountain pass in Afghánistán, dividing the Kurám and Logar valleys. An important position, commanding the road to Kábul, the possession of which, on the occasion of the retributive campaign after the massacre of Sir Louis Cavagnari in September 1879, enabled General Sir F. Roberts' force to advance on that city and occupy it almost without opposition. The ascent of the pass from the Indian side is slight, though the descent into the Logar valley is long and very steep.

Shwe An-daw.—Pagoda in Thayet-myo District, Pegu Division, Lower Burma; situated a few miles north of Thayet-myo town. It dates from the time of Nara-pad-di-si-thu, King of Burma (about 1167 A.D.), who is noted for his piety, his communication with Ceylon, and his frequent journeys through his dominions. He is said to have received from Ceylon a sacred tooth of Gautama; and while escorting it to his capital, he was warned by portents to deposit it at the place where this pagoda now stands.

Shwe-Dagon.—The great Pagoda of Rangoon, Lower Burma, and the most venerated object of worship in all the Indo-Chinese countries.

Lat $16^{\circ} 46' 40''$ N, long $96^{\circ} 13' 50''$ E. The annual festival in March is attended by pilgrims from all parts, and so great is its renown that the King of Siam, not long ago, had a handsome *salat* or resting place built near it. The pagoda stands upon a mound partly natural, partly artificial, in the angle formed by the junction of the Rangoon and Pegu rivers. This mound has been cut into two terraces, the upper of which is 166 feet above the level of the ground, and 900 feet long by 685 wide. The southern approach is covered with handsomely carved wooden roofs, supported on massive teak and masonry pillars, and has at its foot two immense griffins one on each side. From the centre of the platform rises the profusely gilt, solid brick pagoda, springing from an octagonal base, with a perimeter of 1355 feet and a gradually diminishing spheroidal outline, to a height of 321 feet, and supporting a gilt iron network or umbrella in the shape of a cone, and surrounded with bells.

The space around the pagoda is left free for worshippers, but all along the edge of the platform are numerous idol houses, facing inwards, containing images of Gautama in the usual sitting posture, and in a previous existence receiving from Dipengara one of his predecessors, the prophetic announcement that he too should, after the lapse of four *thin kye* (a *thin kye* consists of a unit followed by 140 cyphers) and the creation and destruction of 100 000 worlds attain to Buddha hood. Strictly speaking, the word *thin kye* is a corruption of the Sanskrit *asankhya*, meaning innumerable. Between these idol houses and the main edifice are several bells and *ta gun dain*, or sacred pots each surmounted by the figure of a *karawak* (the carrying bird of Vishnu). The bells are struck by the worshippers with deer antlers left near for that purpose. On the east side is an enormous bell, 7 feet $7\frac{1}{2}$ inches in diameter at the mouth which was presented by Bodan Paj.

The whole of the early history of this pagoda must be rejected as untrustworthy, but the legend concerning its erection assigns it to the year 588 B.C. The story goes that it was built by two brothers who were guided by a *nat* or spirit into the presence of Gautama, who presented them each with four hairs and bade them deposit them with certain other relics which had been left by his predecessors on a mountain in Pegu. The guardian of the earth pointed out this peak to the young men and the sacred gifts were deposited on it under a tree. The first accounts in which any confidence can be placed are those relating to Shin Sawbi a queen who ruled over in the 16th century. The pagoda has been several times added to and repaired—the last time in 1871, when, with the sanction of the British Government, the King of Siam sent a new *ti* from Mandalay, valued at £62 000. The name Shwe Dagon is derived from the Tamil word *shwe* meaning silver.

or log lying athwart,' which has been corrupted in Burmese into Dagon or Dagon. The Burmese word *shwe* means 'golden.' During the first Anglo-Burmese war in 1825-26, the site of the pagoda was abandoned by the Burmese on the fall of Rangoon, and occupied by British troops till the close of the war. In 1852, during the second war, the Burmese anticipated that the British would attack from the south side, which was accordingly defended. But an entrance was effected by our troops on the east, and the great Shwe-Dagon pagoda fell a second time into the hands of the British. The hill on which it stands has been strongly fortified.

Shwe-daung.—Township in Prome District, Pegu Division, Lower Burma. Lat. $18^{\circ} 28'$ to $18^{\circ} 50' N.$, long. $95^{\circ} 10'$ to $95^{\circ} 23' E.$ Bounded by Tharawadi on the south, and by the Irawadi on the west. The eastern limit is marked by the low Taunggyi Hills, which extend from near Prome town into Tharawadi District, and are covered with *eng* trees, forming a tract called the In daing or *eng* country. Area, 204 square miles. Population (1881) 55,140; imperial revenue, £11,293, and land revenue, £2555. The township comprises 16 revenue circles, each under a *thuza*. It consists for the most part of a plain, almost entirely under rice. Tobacco and vegetables are grown along the bank of the Irawadi. In the north-east, below Shwe daung town, palm-trees are cultivated, and from these are extracted large quantities of *tari* (toddy). In the rains, the south-west corner of the township is separated by the Dún ka-la channel from the Irawadi, and becomes an island. About 5 miles south of Shwe daung is the Thin-bhyu Lake, supplied by the Irawadi, and 15 feet deep in the rains. The great northern road and the Burma State Railway from Rangoon enter the township through the In-daing, striking the Irawadi at Shwe daung, whence it proceeds northwards to Prome. This township contains the Shwe-nat-taung Pagoda, the scene of an annual religious fair.

Shwe-daung.—Chief town of the Shwe-daung township, Prome District, Pegu Division, Lower Burma; situated about 8 miles below Prome, on the left bank of the Irawadi, and on the great road from Rangoon to the north. Lat. $18^{\circ} 42' N.$, long. $95^{\circ} 17' 30'' E.$ Divided into two quarters by the Kula-chaung. This town is of recent growth, the old Shwe-daung or Shwe-daung Myoma, mentioned in ancient records, being now only a village some miles farther south, opposite Pa-daung. Population (1881) 12,373, namely Buddhists, 12,118; Muhammadans, 214; Hindus, 25; Christians and 'others,' 16. Accessible by large boats, Shwe-daung forms the port of the Paung-de and In-ma rice plains, the produce of which is largely sent to Prome. The town contains the courts and usual public buildings; also numerous pagodas, monasteries, and *zayats*, or rest-houses.

Shwe-gyin.—District in the Tenasserim Division, Lower Burma;

lying in the valley of the Sit taung river Area, 5567 square miles Population (1881) 171,144 souls Bounded on the north by Taung ngu District, on the east by the Paung laung range and the Salwin Hill Tracts, on the south by Amherst District, and on the west by the Pegu Yoma Hills After the second Anglo-Burmese war, this District included the Salwin Hill Tracts and also the Tha tun Sub division of Amherst District, and was first called the Martaban Province, and then Martaban District In 1864-65, Martaban was joined to Amherst, and the District was called Shwe gyin In 1872, the Sub-division of Yun za lin was formed into an independent jurisdiction now known as the Salwin Hill Tracts Several small transfers have taken place since Head-quarters at SHWE-GYIN TOWN

Physical Aspects—In the north, the District is highly mountainous, both the eastern and western ranges sending down numerous spurs which on the east approach to within a few miles of the Sit taung Both chains diminish in height towards the south, and the Pegu Yomas recede, leaving a wide stretch of fertile land South of Kyau to, a town at the southern base of the Paung laung Hills, the whole country between the Sit taung and the Bi lin consists of vast monotonous plains, covered with scrub forest or almost impenetrable elephant grass At places, a pagoda, or a group of houses surrounded by a few tall palms, marks the village of some fishermen or salt boilers who gain a precarious livelihood from the muddy waters of the tidal creeks or the salt impregnated soil At high tides the whole of the coast for miles inland is inundated, and so rapidly does the sea advance over the flats that little or no chance is offered to the fisherman or turtle seeker should he have neglected the warning sound of the approaching waters During the dry season, the upper portion of these plains is easily passable by carts, but in the rains they become one vast sheet of water, with the tops of the tall elephant grass showing above, and almost concealing the pagodas, by which alone the boatman can guide his course

Both the Pegu Yomas and the Paung laung mountains are densely wooded, and drained by small perennial streams The passes over the former are mere tracks winding up ravines and along the crests of spurs Across the Paung laung range are three principal routes,—the northern runs up the valley of the Biw ga ta and across the Thavet pin kin dat Hill to Kaw lu do, the northern police post in the Salwin Hill Tracts, the central road goes up the valleys of the Mut ta ma and the Me de to Pa pun, the southern leads from the source of the Mut ta ma to Pi wa ta The Paung laung range, at the Sek le hill opposite Shwe-gyin attains a height of about 4000 feet, and terminates above Kan jwa in Ke la tha, a peak crowned by a conspicuous pagoda, said to have been founded many years ago at the same time as Kyauk i jo, above S' tau.

The chief rivers of Shwe-gyin District are the SIT-TAUNG, also called the Taung-ngu and the Paung-laung; and the BI-LIN or Dun-wun. The Sit-taung rises in Upper Burma, and enters Shwe-gyin at its northern end, and, after an exceedingly tortuous course, falls into the Gulf of Martaban by a funnel-shaped mouth 7 or 8 miles wide, up which the spring-tides rush with great violence, forming a bore. This river is navigable throughout its entire length in this District by large boats and steam launches. A chopping sea follows the rolling crest of the bore, and sometimes wrecks a boat in a few minutes.

The most important affluents of the Sit taung are—the Kun, rising in the Pegu Yomas, and, after an east-south-east course of 60 miles, joins the main stream near Anan-baw; the Yenwe, which flows into the Sit-taung, after a south easterly course of 90 miles, about 6 miles north of Shwe-gyin town; the Youk thwa, navigable for a few miles above its mouth; the Mun; the Shwe-gyin; and many smaller streams.

The Bi-lin rises in the Salwin Hill Tracts, and runs a southerly course to the Gulf of Martaban. At first it is a rocky mountain torrent, but as soon as it emerges into the plains it deepens rapidly. During the rains it forms the highway between the Sit-taung and Maulmain. At spring-tides, a bore rushes up this river also, inundating the country around for miles. Its feeders are few and insignificant; but during the rains it communicates on the east with the Dun-tha-mi, and on the west with the Sit-taung and intervening rivers.

Shwe-gyin contains five lakes, viz. Tun-daw, Sa-win, Mwe-din, Mi-chaung-gaung, and Nga-thwe-zut. The District has never been surveyed from a geological point of view. The Paung-laung range is composed of gneissose rocks, and the whole of the level and alluvial plains are occupied by a sandy and very homogeneous deposit. Laterite formations prevail at places. The District is said to be rich in minerals. Gold occurs in most of the tributaries of the Shwe-gyin river (lit. 'gold-washing'), but the quantity found does not repay the labour of washing. Copper, lead, tin, galena, antimony, and coal also exist, but are not worked. The chief varieties of timber are teak, *pyin-gado* (*Xylia dolabriformis*), *pyin-ma* (*Lagerstroemia Flos-Reginæ*), and *thit-tsi* (*Melanorrhæ usitata*).

Population.—The Census of 1872 disclosed a population of 129,485, and that of 1881, 171,144 persons, on an area of 5567 square miles, dwelling in 1 town and 558 villages, and occupying 31,868 houses; unoccupied houses numbered 1617. Density of population, 30·74 persons per square mile; villages per square mile, 0·10, or one village to each 9·9 square miles; houses per square mile, 6·01; persons per occupied house, 5·37. Total population, 171,144, namely, males 89,687, and females 81,457. Classified according to sex and age, there were—under 15 years, boys 39,072, and girls 35,523; total children,

74,595, or 43.6 per cent of the population—15 years and upwards, males 50,615, and females 45,934, total adults, 96,549, or 56.4 per cent. Classified according to religion, Hindus numbered 958, Muhammadans, 855, Christians, 1250, Buddhists, 158,149, Nat worshippers or persons of indigenous race whose sole religion consists in a kind of worship of spirits or 'demons,' 9932. Christians were divided into European British subjects, 14, Eurasians, 16, and native converts, 1196. Of the last named, 1169 were Baptists. The Muhammadans were thus returned according to sect—Sunnis, 673, Shis, 132, and 'others,' 50.

Classified ethnologically, in the language table of the Census Report, Karens numbered 52,400, Burmese, 80,195, Taluings, 22,282, 'Laungthas, 5715, Shins, 8135, natives of India, 1780, Chinese, 280, Europeans and Eurasians, 54, 'others,' 303. The Karens are most numerous in the tract east of the Sitoung, and belong to two great families, Sgaw and Pao, many of them have been converted to Christianity by the American Baptist missionaries. The Taluings chiefly inhabit the plains, the Burmese, the country lying north of the Sitoung. The Yabangs, who are engaged in the rearing of silkworms, are found mainly on the eastern slopes of the Pegu Yomas in Bawm. The Hindus, Muhammadans, and Chinese are all immigrants since the British occupation, as are also many of the Shins, of whom a whole colony settled some years ago at Winkamin, at the junction of the Mutama and Shwegyin rivers.

As regards occupation, the Census of 1881 returned the following six groups—(1) Professional, including civil and military officials, males 2086, and females 108, (2) domestic servants, inn and hotel-keepers, males 80 and females 52, (3) commercial class, including bankers, merchants, carriers etc., males 2977, and females 2419, (4) agricultural and pastoral class, including gardeners, males 30,393 and females 27,351, (5) industrial class, including all manufacturers and artisans, males 6768, and females 10,332, and (6) indefinite and non-productive class, comprising children, general labourers, and persons of unspecified occupation, males 47,353 and females 41,165. The total population numbered 1312, namely, males 1122, and females 190, living in 290 boats.

The only place in the District with more than 5000 inhabitants is Sitoung town, founded in the last century before the Burmese conquest by Mongla. It contains the usual public buildings, population (1881) 7519. Other towns are—Kawm, an old town at the foot of the Paunglaung range, containing a court house, police station, and post office, with a population of 2000, founded in 1812 and containing a court house and the usual public offices. Sitoung, on the Sitoung river, said to have been built in 1555 A.D., contains

court-house, etc.; WIN-BA-DAW, noted for its manufacture of pottery, and as the chief halting-place for boats proceeding up the Sit-taung; KYAUK-GYI, at the foot of the Paung-laung mountains, 34 miles above Shwe-gyin, with trade in areca-nuts; MÚN, Thú-yeh-tha-mí, Pú-zun-myaung, with manufacture of pottery; Nyaung-le-bin, etc. Out of the 559 towns and villages in the District in 1881, no less than 233 contained less than two hundred inhabitants, and 250 from two to five hundred; while 61 had from five hundred to one thousand, 14 more than one thousand, and only 1 above five thousand.

Agriculture.—Agriculture supports 117,263 persons, or 68·52 per cent. of the population. Of the total area of the District (5567 square miles), 174 square miles were cultivated in 1881, of which 10·2 square miles were non revenue-paying; the remainder, 163·8 square miles, were assessed for revenue; the area still available for cultivation being 3581 square miles. Total amount of Government assessment, including local rates and cesses on land, £15,892; average incidence of assessment, 3s. 0½d. per acre of cultivated land. Average number of acres per head of agricultural population, 0·95. The most fertile portions lie along the right bank of the Sit-taung river, towards the south. The principal crop is rice, of which 25 varieties are enumerated. Areca-nuts are very largely grown on the hillsides, near running streams, the water being diverted into the palm groves by artificial channels. Cotton is sown in the *taungyas* or hill-clearings, where the hill tribes carry on a nomadic agriculture. Tobacco, vegetables, and oil-seeds are also produced, but the out-turn is small. Rice is the only crop of which the cultivation has steadily increased. In 1883–84, the area under rice was 87,908 acres; sugar-cane, 3040; vegetables, 1357; areca-nuts, 3738; mixed fruit-trees, 2284; cotton, 1; oil-seeds, 724; plantains, 885; betel-leaf, 414; tobacco, 57; cocoa-nut, 7; *taungyas* cultivation, 15,050; and land under miscellaneous cultivation not assessed, 649 acres; total area of cultivated land, 116,114 acres, or 181·4 square miles. The area under rice in 1871–72 was 50,773 acres. The chief rice tracts are in the Kaw-li-ya, Kwin-da-la, Nyaung-le-bin, Ye-hla, Kyauk-gyi, and Gamun-aing circles, the last being the most important. The average size of a holding is between 3 and 4 acres. As a general rule, the land is held by small proprietors, and is very rarely rented out, and never for a long term of years. Occasionally labourers are hired for rice cultivation, and are always paid in kind.

In 1883–84, the average rate of rent of land suited for rice was returned at 5s. 6d. an acre; the average produce per acre being 900 lbs. Price of produce per *maund* of 80 lbs.—rice, 6s. 6d.; cotton, 11s.; sugar, 11s.; salt, 4s. 9d.; tobacco, £4, 5s. 3d.; oil-seeds, 8s.; peas, 5s. The price of a plough bullock is £7; sheep and goats, each

16s, fish, per lb, 3d The agricultural stock consisted of—cows and bullocks 19 110, horses and ponies, 211, sheep and goats, 1075, pigs 5000, elephants, 161, buffaloes, 34 938, carts, 7556, ploughs, 7321, and boats, 1571

Manufactures, etc—The only manufactures in the District are pots, salt, and silk spinning. The pots are made at Pu zun myaung a village a few miles above Shwegyn town, where clay is procured on the spot, at Kwin-dah, a little lower down, at Sheip-gyi in the Kyauk-gyi township, and at Win ba-daw in the Sit tung township. At Pu zun myaung, the pots are made for export to Rangoon and Maulmain and intermediate towns, but at the other places for local use only. The largest sized pots are sold for 10s, and the others for 3s per hundred. Each kiln holds 1000 pots, among which are about 200 of the largest kind. The annual produce of one man's labour is estimated at 1000 unburned pots a month, or 7000 in the season i.e. from November to May. The industry has been in existence for about thirty years. The pots made at Win ba-daw are solely for the salt boilers; the pot makers exchanging for salt, delivered at the rate of 365 lbs. for every 100 pots. The yearly out turn averages 15 000 000.

In the Bhaw ni and Anan hwa circles, at the foot and on the lower slopes of the Pegu Yomas, silkworms are bred by the villagers as in Prome District. The annual produce of silk is about 9000 lbs. the value of which on the spot is £450. The quantity exported chiefly to Prome in Shwe-dung where, on account of the number of skilled weavers there is the best market for it, is estimated at two thirds of the total produce, or about 6000 lbs.

Of made roads there are 55 miles in the District. But cart travelling is easy in the plains, and along the left bank of the Sit tung river a fairly good road leads to Bilin in Sit tung. Kwin to and Kyau King Labin Shwa ti, who reigned over the Salween kingdom from 1540 to 1550, made a road from Pegu to Taung-nu with rest houses and gardens at intervals for the use of travellers. This road still exists, but is passable in dry weather only. During the rains communication is carried on almost everywhere by boat: the total length of waterway is 250 miles. The journey from Maulmain to the Salween is made via Win ba-daw on the west, and the Sincle Canal on the east, which is connected with the Bilin river. To facilitate communication with Rangoon, an artificial canal has been cut from Myittha on the Sit tung, to the Kaya-shu creek, and thence by the Par-kyun channel into the Pegu river.

Administrative—In 1857-58, the total revenue of Shwegyn District amounted to £29 200. At the end of 1865-66 the whole of the Mandalay Sub-division was transferred to British India. In 1881-82, the Imperial income of the District was £41 900 200. VOL. XII 2 E

local funds yielded £5141, making altogether a gross revenue of £47,136, of which the land and capitation taxes and the fisheries form the chief items. For administrative purposes the District is divided into 4 townships, viz. Sit-taung, Bi-lin, Kyauk-gyi, and Shwe-gyin. These comprise 26 revenue circles, each of which is in charge of a *thugyi*, under the Deputy Commissioner or his subordinates.

For some years after British annexation, the country continued in a disturbed state. Whilst Min-laung was in rebellion in Yun-za-lin, a Shan prisoner, formerly a *thugyi*, effected his escape, and openly proclaimed himself on the side of Min-laung. The native officer in charge was murdered in cold blood, but a small detachment was immediately sent against the rebels, who were quickly dispersed. A strong police force was then constituted, which in 1881 consisted of 356 officers and men, giving 1 man to every 16 square miles and every 480 of the population. The total cost was £7505. The number of prisoners confined in the small lock-up at Shwe-gyin town was 57 in 1881. Besides the ordinary jail service, they are employed in oil and rice-cleaning mills.

The State middle-class school in 1881 had an average daily attendance of 62 pupils, all studying English. The American Baptist missionaries have also boys' and girls' schools for the Karens. But with these exceptions, the education of the people is entirely in the hands of the Buddhist monks and of a few laymen, who have opened village schools for instruction in reading and writing. The Census of 1881 returned 8743 boys and 666 girls as under instruction, besides 23,838 males and 5551 females able to read and write but not under instruction.

Climate.—Except in the hills, the climate is generally healthy. The heat is excessive from March till May; but a refreshing breeze blows from six to seven P.M. In 1883–84, the highest reading of the thermometer in the shade in May was 101° F.; the lowest reading in December was 56° F. Towards the end of May, the rains are ushered in by violent thunderstorms. The average annual rainfall for thirteen years ending 1881 was 144·5 inches. In 1883 the rainfall was 139·7 inches. The prevalent disease is fever. Number of patients treated at the dispensary (1883), 9881, of whom 289 were in-patients. In 1883, 4611 births and 2647 deaths were registered. [For further particulars regarding Shwe-gyin District, see the *British Burma Gazetteer*, compiled by authority (Government Press, Rangoon, 1879), vol. ii. pp. 643–662. Also the *British Burma Census Report* for 1881, and the several annual Administration and Departmental Reports of the Government of Burma.]

Shwe-gyin.—Township in the centre of Shwe-gyin District, Tenasserim Division, Lower Burma; lying on both sides of the Sit-taung

river. Bounded north by Taungngu District, east by the Paunglaung range, south by Pegu, and west by Tharawadi and Prome Districts. The eastern and western borders are mountainous, and covered with dense forest, but between the lower slopes of the hills and the Sit taung is fertile tracts of rice land. The other principal rivers are the Kyu and the Da la nun on the east, and the Shwe gyin on the west. Most of these are navigable for some distance during the rains. In the west the township is traversed by numerous fair weather cart tracks, and the Sit taung Valley (State) Railway also runs through it. The town of Shwe gyin lies within this township but it is not under the charge of the Extra Assistant Commissioner. Chief villages—Pá run myung the seat of a large manufacture of earthen pots and Nyaun le bin. Population (1881) 58,255, gross revenue, £10,691.

Shwe gyin—Chief town and head-quarters of Shwe-gyin District, Tenasserim Division, Lower Burma, situated in lat. $17^{\circ} 55' N$, and long $96^{\circ} 57' 30'' E$, on the left bank of the Sit taung river at the confluence of the Shwe gyin river. Population (1881) 7519, namely, Hindus, 283, Muhammadans 427, Christians 124, Buddhists 6684, and 'others' 1. Extending across the angle formed by the junction of the two rivers is a low line of laterite hills on which stand the barracks of the small garrison and a few houses, the remnant of the large cantonment established here after the second Anglo-Burmese war. Where these abut on the Sit taung north of the town is the old fort and stockade, which the Burmese evacuated on hearing of the advance of the British column from Martaban to Taung na in 1853. The main portion of the town, which is built regularly, lies in the low land between the Sit taung and the Shwe gyin and during the rains is to a great extent flooded. The inhabitants are principally engaged in trade. The town contains the usual offices of a Deputy Commissioner, police station post and telegraph offices, hospital and dispensary, school and forest office for the examination of timber floated down the Sit taung. Shwe gyin is a place of modern growth.

Shwe gyin.—River in Shwe-gyin District, Tenasserim Division, Lower Burma. It rises in the high mountains north east of Shwe gyin and falls into the Sit taung at that town. Above Shwe gyin where it receives the Ma-da-ma from the south and where its channels often deepens, the river is only navigable by the smallest boats. Its bed is sandy, and in places rocky.

Shwe laung.—Township in Thungwa District, Tenasserim Division, Lower Burma, extending northwards from the sea-coast for about 100 miles, between the Patheingyi and the Irrawaddy rivers. Area, 26,1150 sq. miles. In the north the country consists of a plain covered with scrub forest, the lower portion is cut up into patches by numerous intercommunicating creeks, and is divided into a variety

fishing hamlets. Shwe-laung comprises 6 revenue circles. Population (1881) 46,716; gross revenue, £19,203.

Shwe-laung.—Head-quarters of Shwe-laung township, Thun-gwa District, Lower Burma, and the seat of an Extra-Assistant Commissioner; situated in lat. $16^{\circ} 44' 30''$ N., and long. $95^{\circ} 23' 30''$ E., on the Irawadi.

Shwe-le.—River in Prome District, Pegu Division, Lower Burma; rising in the western slopes of the Ko-dek spur of the Pegu Yomas. It flows in a south-westerly direction, traversing the centre of the plain between the Yomas on the east and the Prome hills on the west, till it falls into the Myit-ma-ka, north of the village of Kin-than. This river is known by the names of Shwe-le, We-gyi, Wek-put, and Kyun-kyun-gya, in various portions of its course. During the rains, boats of 500 bushels burden can ascend the river as far as Tha-bye-paung-gyi village. The Shwe-le drains a rich teak country; and several attempts have been made to facilitate the removal of the felled logs to the Irawadi, but without success. This is owing to the numerous hill torrents that rush into the Shwe-le during the rains, and bring with them the forest debris, which during the dry season has rolled into their beds. Thus obstructions are formed; and the foaming water in a few hours bursts the banks, and either continues its course onward in the old channel, or cuts for itself a new one in the soft soil of the plain.

Shwe-le.—Township in Prome District, Pegu Division, Lower Burma; extending along the western slopes of the Pegu Yomas from lat. $18^{\circ} 28'$ to $18^{\circ} 51'$ N., and from long. $95^{\circ} 30'$ to $95^{\circ} 58'$ E. It includes the old townships of Shwe-le, Ywa-bein, and Myo-daung, and is divided into 12 revenue circles. The whole country, except in the south-west, is hilly and covered with valuable timber. The other chief products are rice, cotton, and mulberry. The principal streams are the North and South Na-win and the Tin-gyi, but all are unnavigable within this township. Population (1881) 32,301; gross revenue, £3804.

Shwe-maw-daw.—Pagoda in the old fortified town of Pegu, Rangoon District, Lower Burma. It is a pyramidal, solid brick building, rising to a height of 324 feet from an octagonal base, each side of which is 162 feet long. It stands upon two terraces, the lower one being a parallelogram, with its sides 1390 feet long. The pagoda is surrounded by two tiers of smaller temples; the lower tier contains 75, and the upper 53.

The Shwe-maw-daw, in common with most of the sacred edifices in Burma, is connected with a legendary visit of Gautama. Tradition asserts that whilst Gautama was staying on the Mat-ku-la Hill, near the sources of the Yun-za-lin river, he was visited by the two brothers Ma-ha-tha-la and Tsu-la-tha-la of Zaung-du, a village about 20 miles above the modern town of Pegu. To them Gautama gave two hairs;

and, foreseeing that in the 1116th year of his religion the capital of a powerful kingdom would be founded at Han tha wad-di, he directed that these sacred relics should be enshrined on a hill close by Ma ha tha li, and I su la tha la obtained the aid of the Thagya king of their native town in carrying out Gautama's instructions. The king of Zaung-du placed certain *nat*s or spirits to guard the shrine, made grants of money and land to the pagoda, and dedicated a number of people to its service.

The Burmese chronicle is very vague and fragmentary, until it comes to what may be called the historical period. In the year 1116 of Gautama's era (573 A.D.) Thama-la and Wimala established the kingdom and city of Han tha wad-di of which Thama-la was the first sovereign. Finding the Shwe maw daw still in existence, he added to it and dedicated 25 families to its service. Successive sovereigns kept the pagoda in repair. In 1209 A.D. Anu-ma-ra-za, the twelfth king of the original dynasty, obtained a holy tooth from the King of Sri-tun to enshrine in this pagoda, and Shham-ma-ze-di who came to the throne in 1502, received from the king of Ceylon a present of 100,000 paving stones, of which 50,000 were used in paving the court or upper terrace. Towards the end of the 18th century, on the occasion of a visit from the king of Burma the pagoda was thoroughly repaired and the *nat* or umbrella canopy regilt. In June 1852, on the outbreak of the second Anglo-Burmese war, the Shwe maw-daw was the scene of some sharp fighting previous to the capture of the town of Pegu by the British.

Shwe myin din.—Pagoda in the Kana township of Thavet myn District, Pegu Division, Lower Burma. Its name, which means 'conspicuous,' is derived from its position. It is said to date from about 100 A.D., and subsequently, as it was found that the desires of many who visited this shrine were accomplished, it received its second name of Shwe-tsu taung bin, or 'prayers fulfilled.'

Shwe nat taung.—Pagoda in Irome District, Pegu Division, Lower Burma, about 16 miles south of Prome town. It is said to have been erected by Sanda-de-wi, the queen of Dutta-haung the founder of Irome (circa 442 B.C.). The building has been since added to and repaired, and being profusely gilt, stands out conspicuously on a low hill. Behind it are six other pagodas. The annual festival held in March is attended by about 20,000 people.

Shwe nyaung bin.—River in Bassein District, Pegu Division, Lower Burma. Falls into the Bassein river in lat. 17° 15' N., lon. 94° 55' E., and communicates with the Daga-lay several creeks. It is 600 to 1,000 feet wide in its lower portion, but navigable by large boats only during the rains.

Shwe san daw.—Pagoda near Irome in Irome District, Pegu

Division, Lower Burma; more venerated by the Talaings than even the great Shwe-Dagon of Rangoon. According to its sacred history, it was erected in 577 B.C. by Thamein-taw-byin-yan, the King of Ka-bin, and his queen, as a shrine for three of Gautama's hairs given to him by three pilgrims from Ceylon, on the occasion of their visiting him whilst he was tarrying in the Zin-gyaik Hills. Subsequently, in 538 B.C., four more holy hairs were deposited in the pagoda by King Thamein-taw-byin-gnya-kan-de and a hermit named Gyi-ri-ren-ga. Near the Shwe-san-daw is a grove of *thwt-ta-bat* trees (*Sapota* sp.), seven in number, the only ones in Pegu. The trees were cut down, it is said, by order of the Talaing rulers, when the Burmese conquered their country, because the produce was a royal fruit to be eaten by none but the monarch, and the present trees are shoots of the old stumps.

Shwe-san-daw.—Pagoda in Prome town, Prome District, Pegu Division, Lower Burma. It is situated on a hill about half a mile from the bank of the Irawadi, and gives its name to a quarter of the town. The building is gilt all over, and is solid. Its height is 180 feet, and it occupies an area of 11,025 square feet. It is surrounded by 83 small gilt niches, called *Ze-di-yan*, each containing an image of Gautama. The pagoda stands on a paved platform, approached by four flights of steps, two of which, the northern and the western, are covered with elaborately carved roofs supported on massive teak posts. The gilt iron network *ti*, or conical top, is 10 feet in diameter at its base. There are on the platform 12 or 13 bells attached to massive cross-bars, which are struck with deers' antlers by those who come to worship.

This pagoda is supposed to have been first erected by two brothers, *I-zi-ka* and *Pa-li-ka*. Tradition alleges that when Gautama arrived near Prome, and was walking on the island of *Zin-yan*, he was accosted by a *naga* or dragon, who begged for some sacred hairs to enshrine in a temple. Gautama refused this request, saying that the glory of building a pagoda to contain his relics must be reserved for two brothers who had gone on a trading expedition to *Thu-wun-na-bhu-mi* or *Tha-htun*. The *naga* then presented to Gautama an emerald box, praying that as he could not receive the sacred hairs, he might at least contribute the receptacle for them. His gift was accepted, and shortly afterwards *I-zi-ka* and *Pa-li-ka* anchored at a place known to this day as *Mya-ywa* or 'Emerald Village,' and discovered the relics. Having heard of Gautama's prediction, that on the site of the modern Prome the capital of a powerful kingdom would be founded, they proceeded thither, and after considerable difficulty built the pagoda on the hill on which it now stands. Seven days after their departure for their native place, the pagoda sank into the earth. Owing to the prayers of King *Dut-ta-baung*, the founder of ancient Prome, the pagoda reappeared, and the king restored it.

The Burmese records give no further account of the building and oral tradition is all we have to rely upon. In 1753 Alung-payá coated it with gold, and in 1831, King Thirawadi thoroughly repaired the pagoda, which had been damaged by an earthquake and put on it a new *ti* studded with jewels. Since then it has been again partially destroyed by another earthquake. It has lately been rebuilt, at an estimated cost of about £2500 raised by public subscription. The annual festival is held on the full moon of Tabauing corresponding to March.

Shwe thek lut (lit. '*Golden Life Preserved*')—Pagoda in Thayet myo town, Thayet myo District, Pegu Division, Lower Burma. It was erected by Mingyi swa saw ke, the second king of the Ala dynasty about 1373 A.D. as a thankoffering for the preservation of his life when he, as a child was taken captive in Thayet myo by the King of Arakan. This building is remarkable as being one of the most southern hollow pagodas, in Upper Burma there are many of this kind but in the lower country the great majority are of the solid bell shaped pattern.

Shwe-tsu-taung-byí—Pagoda in Thayet myo District Pegu Division Lower Burma—See SHWE MYA TUN.

Shwe tsway daw—Pagoda in Thayet myo District Pegu Division Lower Burma—See SHWE AN DAW.

Sidldah—Village in the Twenty four Parganas District, Bengal situated just outside the limits of Calcutta. Lat. 22° 35' N. long. 88° 26' E. Terminus of the Eastern Bengal and Calcutta and South Eastern Railway. Seat of a large transit trade.

Sialkot (*Serik te*)—British District in the Lieutenant Governor's ship of the Punjab lying between 31° 44' and 32° 50' N. lat. and between 74° 12' and 75° 31' long. Area, 1958 square miles population (1881) 1,012,148 souls. Sialkot forms the north western District of the Amritsar (Umritsar) Division. It is bounded on the north west by the river Chenab and its tributary the Jhelum, which separate it from Gujrat District, on the north-east by the Jammu Province of Kashmir State, on the east by Gurdaspur District, on the south-east by the Ravi, which separates it from Amritsar and Gurdaspur Districts, and on the west by Gujranwala and Lahore Districts. It is an oblong tract of country, occupying the salmon arc portion of the Keelna or Ravi Chenab delta, having a length from north west to south east of a little over 50 miles with an average breadth of 44 miles. Sialkot stands twenty fourth in order of area and second in order of population among the thirty two British Districts of the Punjab and comprises 184 per cent. of the total area, and 539 per cent. of the total population of the Province. The administrative headquarters are at the town of SIAIKOT.

Hydrological Area—The District of Sialkot, occupying the uppermost

portion of the Rechna Doáb, stretches in a comparatively unbroken level from the valley of the Rávi on the south-east, to that of the Chenáb on the north-western border. Along the coast of either great boundary river, a narrow fringe of alluvial lowland marks the central depression in which they run; while above them rise the high banks which form the limits of their wider beds. Parallel to the Rávi, another stream, the Degh, which rises in the Jamú (Jummoo) Hills, traverses the south-eastern corner of the District, fringed on either side, like the greater rivers, by a strip of alluvial soil. The remainder of the surface consists of a level plain, slightly submontane in character, lying at a distance of 20 miles from the outermost range of the Himálayan system. Midway between the Rávi and the Chenáb, however, a high dorsal tract stretches from beyond the Jamú border far into the heart of the Doáb. Spreading in its northern portion from the valley of the Degh to the high bank of the Chenáb, it narrows gradually as it runs south-westward, till it finally terminates in an apex about 10 miles beyond Pasrúr, thus forming an irregularly triangular wedge.

The neighbourhood of the hills has imparted to the general aspect of the District a greenness and fertility rare among the Punjab plains. More than two-thirds of its area have already been brought under the plough; and of the remainder, perhaps a third more is capable of being brought under cultivation by careful tillage. The upper portion of the District, especially close to the hills, produces excellent crops; but the southern portion, farther removed from the influence of the rains, shows a marked decrease of fertility. The poorest lands lie in the triangular dorsal ridge, where the naturally arid soil depends entirely for its water-supply upon the local rainfall. Elsewhere, irrigation from wells or hill streams has turned the whole country into a waving sheet of crops. The alluvial lowlands of the Chenáb and the Degh, however, suffer in parts from the injurious saline efflorescence known as *reh*. Between the Degh and the Rávi, too, the wild and unproductive upland grows more and more impregnated with saltpetre as it recedes from the hills, till near the Lahore border it merges into a tangled jungle of brushwood and reeds.

Numerous small torrents traverse the north-eastern tract. Several swamps (*jhils*) studded over the face of the country are useful for irrigation, and many of them have had their capacity considerably increased by artificial embankments, in which cases the water is made available by means of ducts. The two largest marshes are those of Satrah and Manjke. The first is artificial, and covers an area of 450 acres, supplying water to 12 villages. The Manjke marsh is 687 acres in area, with a depth in parts of 8 feet, and also irrigating 12 villages. The Daskah and Luriki marshes, formerly very large, have been recently drained. They do not now retain water, and almost the whole of their area has

been brought under the plough. Some of the minor tracts are mere swamps, the beds of which are to a great extent cultivated with rice as the water dries up in the winter months. Traces of ancient canals may still be observed, some of which might repay the trouble of restoration. The most remarkable owed its origin to Ali Mardān Khān, the famous engineer of Shāh Jahān, and once brought the waters of the Tāvi to supply the imperial gardens at Shāhdāra.

There is nothing approaching the description of a forest, or even of a good sized wood, in the District; old trees are rare. The trees commonly found in the low lying country are of recent growth occurring here and there singly or in clumps around villages and wells. Much has been done of late years in planting trees along the public roads. The people also are beginning to take interest in arboriculture, and orchards and gardens are springing up all over the District.

The mineral products are few and unimportant. Beds of *Larkar* (limestone nodules) of good quality occur in abundance along the high bank of the Chenāb 3 miles north of Silkot cantonment, and at Marākwal, Godhīūr, and Ballanwāl; the latter a mile west from the cantonment. At the same localities limestone is found, but lime of a better quality is obtained from the boulders of certain streams or from the banks of the Tāvi below Jamū. The marsh at Sattah is famous for yielding a clay called *rim*, which is used for pottery and is valued for its property of receiving a colour when baked. Good pottery clays are also procured on the *Lundī* *rahi* above Pāsur. Saltpetre is found in the earth of old village sites (*hujra*), but the manufacture is extremely limited.

A few wolves are the only representatives of the carnivora in the District, while even deer and hares find little cover in so highly cultivated a tract. A few wild hogs and anelope are found. Wild geese, ducks, and water fowl are abundant in the coldest her in the marshes and upon the river banks and islands. Quail abound particularly in the rice.

History—*Haslu* *Kājā* of Silkot who lived somewhere about the first century after Christ, forms the great centre of all the local legends. General Cunningham identifies this possibly mythical hero with the son of Śiśu thina, the Vikramāditya who expelled the Sakas about 75 A.D. Tradition universally points to the town of *Sakot* as the *Kājā's* capital, while at the sand stones keep alive his memory among the Hindus of the hills and the suburbs are sacred. After Pāsur's death, however, his kingdom fell under a curse, and remained desolate for three hundred years.

About 643 A.D. the Rājā of Jāmū crossed the District and they held it in subordination with the Muhammadans for a

while the Hindu rulers managed to retain their possessions in the plains by the payment of a tribute to the Delhi Emperors; but under the Mughals, Siálkot formed part of the Province (*subah*) of Lahore, and did not revert to its ancient princes until after the dissolution of the Mughal organization in the days of Ahmad Sháh Duráni. During that stormy period, however, the Rájput Rájás of Jamú once more made good their claim to the fertile and level belt which stretched at the foot of their mountainous principality. In 1740, Ranjít Deo, the ruling Rájá, under a grant from the Duráni Emperor, possessed himself, by force of arms, of a strip of territory stretching from Dinga in the Jetch Doáb to the valley of the Rávi. A powerful Pathán family then occupied the town of Siálkot itself; while the remainder of the District was harried by bands of Sikhs, under the command of the Bhangi chieftains and of Charrat Singh, grandfather of Ranjít Singh, the Mahá-rájá of the Punjab. In 1774, Brij Ráj Deo, son of the Jamú Rájá, rebelled against his father, and called in the aid of Charrat Singh. The Sikh chieftain gladly embraced the opportunity; but Ranjít Deo met him on the banks of the river Basantar, as he marched on Jamú, and utterly defeated the Sikh forces, while Charrat Singh himself lost his life in the engagement. The Bhangi chieftains, who had just wrested Siálkot town from its Pathán masters, and dreaded the rising power of their co-religionist, gave their aid to the Rájá in this campaign. Mahá Singh, son and successor of the defeated chief, then turned southward, and began to establish his authority in the lower part of the Doáb.

Meanwhile, Ranjít Deo died in 1783, and was succeeded by his rebellious son, Brij Ráj Deo, a man of debauched habits, quite unfit to hold his own against the active and vigorous Sikhs. Mahá Singh seized upon the opportunity, and advanced upon Jamú in 1784 with a considerable force. The new Rájá fled to the hills on his approach, and Mahá Singh sacked the defenceless capital without striking a blow. He did not attempt, however, to secure his conquest, but retired at once to his head-quarters at Gujránwála. The Bhangi chiefs of Siálkot and the Kanhyas from the Bári Doáb thereupon completed the overthrow of the Jamú prince, and wrested from him, by 1786, all his father's acquisitions in the plains. Brij Ráj Deo himself finally fell in battle, making a last effort to resist the Sikh encroachments. The whole District thus passed into the hands of the rising sect, and the greater part became the appanage of retainers of the Bhangi confederacy or *misl*. The Kanhya chiefs took the rest, except a few villages which fell to Mahá Singh.

But Ranjít Singh, son of the last-named prince, soon disturbed this amicable arrangement of territory in the Rechna Doáb. In 1790, the future Mahárájá appropriated part of the Bhangi domains; and in 1807 he made himself master of Pasrúr. In the same year, the Sardárs of

Sialkot ventured to question his title to these new acquisitions, where Ranjit Singh promptly attacked and defeated them, adding Sialkot to his growing dominions. By the end of 1810 the whole District had been swallowed up, while, a few years later, the Maharaja made himself supreme from the Sutlej (Satlej) to the Sulaiman Mountains.

British rule was extended to Sialkot in 1849 after the second Sikh war. On the first distribution of the Province into Divisions and Districts, the whole upper portion of the Rechna Doab was formed into a single charge, having its head-quarters at Wazirabad. In 1850 however, this extensive District underwent sub-division, being formed into the two new Districts of Gujranwala and Sialkot, while portions were made over to Gurdaspur and Lahore. Subsequent transfers of territory have brought the boundaries to their present shape.

During the Mutiny of 1857, Sialkot was the scene of an outbreak of the native troops stationed in the cantonments, who murdered the Brigadier commanding the station besides other British officers, and the chaplain with his wife and child. The mutineers laid siege to the European residents in the fort, and remained masters of the whole District for a short time. The treasury was plundered and all the records destroyed, the prisoners in jail were released and the houses of the residents were looted by the mutineers, aided by the bad characters from jail and by the police and the inhabitants of the neighbouring villages. The District however was soon recovered. The ringleaders including the two principal native officers of police, and the jail over-see, were summarily executed and soon afterwards 141 of the rebellious sepoys, who had taken refuge within Kashmir territory, were handed over by the Maharaja's officers, tried by court martial and most of them hanged at Gurdaspur and Sialkot.

Population—The area at present included in Sialkot District had a population of 805,837 at the Census of 1855. By 1868 the number had increased to 1,004,692, showing an increase of 198,855 or 24·7 per cent. At the last Census in 1881 the population of Sialkot was returned at 1,012,148, showing a further slight increase of 7453 or less than 1 per cent, in thirteen years. Sialkot ranks third in population density among the Punjab Districts, being only exceeded in this respect by Jalandhar and Amritsar. The slight increase is due to the fact that the emigration to other Districts in the Punjab greatly exceeds the immigration. Indeed were it not for the large number of fugitives from the Kashmir famine in 1878-80 who contributed more than three-fifths of the immigrants, the Census of 1881 would have shown an actual decrease of population, the emigration having more than counterbalanced the natural increase of births over deaths.

The results of the Census of 1881 may be summarised as follows—
—Area of District, 1958 square miles, with 9 towns and 1303 villages.

number of houses, 143,205, namely, occupied 114,262, and unoccupied 28,943; number of families, 224,052. Total population, 1,012,148, namely, males 539,661, and females 472,487; proportion of males, 53·3 per cent. Average density of population, 517 persons per square mile; towns or villages per square mile, 1·18; houses per square mile, 73; persons per village, 438; persons per house, 8·8. Classified according to sex and age, there were in 1881—below 15 years, males 217,883, and females 186,633; total children, 404,516, or 40 per cent. of the whole population: 15 years and upwards, males 321,778, and females 285,854; total, 607,632, or 60 per cent. of the whole population.

Religion.—As regards religious distinctions, the Muhammadans form the great bulk of the population, and in 1881 numbered 669,712, or 66·16 per cent. of the total. Hindus numbered 299,311, or 29·57 per cent.; Sikhs, 40,195, or 4 per cent.; Jains, 1388; Christians, 1535; and Parsís, 7. The principal Muhammadan tribes include—Sayyids, 12,849; Shaikhs, 11,636; Pathans, 4118; Mughals, 4537; Kashmirís, 19,153; and Khojahs, 5550. These are the Muhammadans by race descent, as apart from the descendants of converts from Hindu castes. The Játs, the most numerous tribe in the District, who form the great bulk of the agricultural class, number 266,040, of whom 170,878 are Muhammadans, 95,147 Hindus and Sikhs, and 15 of other religions. The Rájputs number 57,269, consisting of 45,534 Muhammadans and 11,735 Hindus and Sikhs. The Awáns, the leading race of the submontane tract, are a tribe of great social and political importance, 19,753 in number, and exclusively Muhammadans. Arains, 65,241, and Gújárs, 11,642, are almost exclusively Muhammadans. Of the Chuhras, 78,980 in number, 19,617 are Hindus and Sikhs; Tarkháns, 41,781, include 9290 Hindus or Sikhs; and Kumbhárs, 29,713, include 10,304 Hindus and Sikhs. The following are the other principal classes met with in the District, mainly Muhammadans, but nearly all of them with a greater or lesser Hindu and Sikh element—Jhinwárs, 35,314; Megs, 28,705; Náís, 20,569; Lohárs, 18,584; Barwálas, 16,901; Mochís, 15,003; Dhobís, 13,988; Telís, 13,652; Batwáls, 13,190; Mirasís, 12,921; Sonárs, 8947 (chiefly Hindus); Chamárs, 8076; Changars, 7139; Labánas, 6584; Fakírs, 6156; and Bhatiás, 5784. The purely Hindu castes are—Bráhmans, 36,100; Khattrís, 18,440; Aroras, 15,793; and Baniyás, 10,795.

The Christian population consists of—Europeans, 1264; Eurasians, 18; and Natives, 253: thus classified according to sect—Church of England, 923; Roman Catholic, 300; Church of Scotland, 144; Protestants, undistinguished by sect, 64; American Church, 20; Methodists, 13; unspecified and others, 71. The American Presbyterian Mission have had a station at Siálkot since 1855, and the Church

of Scotland since 1857. The Rev T Hunter, the first Scotch missionary, was murdered, together with his wife and child, by the mutineers a few months after the establishment of the Mission, and a handsome church has been erected at Sialkot in his memory.

Urban and Rural Population — The District contains three towns with upwards of five thousand inhabitants, namely, SIALKOT TOWN (1881), 45,762, PASKRU, 8,378, and DASKAHI, 5,525. Six other towns, with less than five thousand inhabitants, are also municipalities, namely, ZAFARWAL, 4,978, NAROWAL, 4,558, KHAUSIYANICH, 4,521, JAMALI, 4,157, MITRAWALI, 3,730, and SAKHATRA, 2,381. The total urban population thus disclosed amounts to 83,990, or 8.3 per cent of the District population, leaving 928,158, or 91.7 per cent, for the rural population. The total municipal income of the nine towns above mentioned amounted in 1883-84 to £6981, or an average of 12.73d per head of the municipal population. Of the 2312 towns and villages in the District, 806 contain less than two hundred inhabitants, 957 between two and five hundred, 373 between five hundred and a thousand, 142 between one and two thousand, 19 between two and three thousand, 12 between three and five thousand, 2 between five and ten thousand, and 1 between twenty and fifty thousand inhabitants.

As regards occupation, the Census of 1881 returned the adult male population under the following seven classes — (1) Professional class, including all Government servants, civil and military, 16,692, (2) domestic and menial class, 24,318, (3) commercial class, including merchants, traders, carriers, etc., 5730, (4) agricultural and pastoral class, including gardeners, 152,932, (5) industrial and manufacturing class, 83,916, (6) indefinite and non-productive class, including labourers, 21,921, and (7) unspecified, 14,269.

The houses are built either of mud or of baked brick. An ordinary village is a mere collection of flat roofed mud huts separated by narrow alleys, plastered over with a mixture of earth, chopped straw, and cow dung, surrounded outside by rows of cow-dung (used for fuel), stacks of straw, sheds for weavers, goat pens, places for drying, and temples for worship, huddled together in disorderly array. While every yard of available space is filled up with heaps of village refuse required for manure. Only in the larger and wealthier villages may be seen a few brick houses. Each family lives in a separate courtyard, but here all pretence of privacy is at an end. Cattle and their owners come together and may even be seen herding in the same apartment, without a total disregard of order or cleanliness prevailing. While there are two or three different castes in the same village, they are usually grouped into separate quarters.

Except among the upper classes, there does not seem to be much fondness for dress. A large number of white or light cloth round the neck, a

scarf over the shoulder, a turban (*pagri*) of limited dimensions, and a pair of shoes, compose the clothing of the great majority of the people, except on high days and holidays. The Rájputs are very partial to ear-rings, and to English chintzes for jackets. In tracts where thorny brushwood abounds, yellow leather trousers are worn. The Hindu Játs sometimes wear short baggy trousers. Women are given to wearing coarse jewellery and nose-rings; and a small looking-glass, attached to a ring on the finger, is part of the adornment. Nearly all the cloth is made in the village by a race of weavers maintained for the purpose; the spinning, the early manipulation, and subsequent ornamentation being the work of the females of the family.

The food of the people consists chiefly of grain and vegetables; meat is a luxury which few can afford, except on days of rejoicings, when a sheep or goat is killed and distributed. Fish is seldom eaten, even by those residing near rivers. During the spring, barley, *kangni*, *sawánk*, and *bájra* form the staples of diet; during the autumn and winter, wheat and rice. The grain, done up into a dry cake and baked, is eaten with lime or mango pickle, or with clarified butter and salt, or with a few chillies or onions and salt. To make it more palatable, a wash of vetches or country pea, called *salind*, is sometimes added. The favourite drink is *lassi*, or buttermilk. Intoxicating liquors are not much drunk, though some Játs have a habit of taking a decoction of poppies. Two meals are ordinarily taken in the day, morning and evening; but day-labourers engaged in hard manual labour indulge in a mid-day meal, when able to afford it.

Agriculture.—Out of a total area of 1958½ square miles, or 1,253,559 acres, as much as 902,996 acres were under cultivation in 1883–84. Of the remainder, 22,815 acres were returned as grazing lands, 124,119 acres as cultivable, and 203,629 acres as uncultivable waste. The area under each crop in 1883–84 (including lands bearing two harvests in the year) was as follows:—*Rabí* or spring harvest, 600,959 acres, namely, wheat, 374,501 acres; barley, 101,000; gram, 18,281; pulses, 35,685; tobacco, 6066; oil-seeds, 13,496; spices and drugs, 1060; vegetables, 5144; and other crops, 45,726 acres. *Kharíf* or autumn harvest, 330,179 acres, namely, rice, 67,915 acres; Indian corn, 61,880; millets, 63,051; pulses, 21,375; oil-seeds, 11,465; sugar-cane, 48,644; cotton, 38,374; vegetables, 3120; and other crops, 14,355 acres. Wheat forms the great staple of the *rabí*, and rice and millets of the *kharíf*. The best sugar-cane grows on the land watered by the Degh, and in the lowlands of the Chenáb north of Siálkot town. Millets, on the other hand, occupy the dry uplands in the centre of the District. Irrigation is widely practised, as much as 559,731 acres (or nearly two-thirds of the total cultivated area) being artificially supplied with water, according to the latest returns. In the tract known as the

Bijwāt, nearly every field derives an abundant supply from a network of cuts and watercourses in connection with the Chenāb and its branches. Elsewhere, irrigation is carried on from wells, or by means of Persian wheels working upon the banks of streams. The value of manure is universally appreciated and rotation of crops is carried out to a considerable extent.

The agricultural stock of the District in 1883-84 was returned as follows—Cows and bullocks 233 556, horses 3252, ponies 1131, donkeys, 6114, sheep and goats 44 792 pigs 521, camels 95, ploughs 98 395. The indigenous supply of cattle is insufficient to meet the local demand and large numbers are bought at the cattle fairs in Amritsar, or are imported from other Districts. An annual cattle fair is held at Silkot in September lasting for a week, at which from 8000 to 10 000 head of cattle—chiefly buffaloes—are exhibited. The attendance is estimated at about 70 000 and in 1883 the value of the cattle sold amounted to £15 000.

The village tenures belong as a rule to the intermediate type known as *fattidārī*. Rents are paid almost equally in kind and in money. Where money rents prevail the following are the minimum and maximum rates varying according to the quality of the land and the caste or social status of the tenant—rice lands from 10s to £1 15s an acre, wheat (irrigated) from 5s 4d to £2 an acre, wheat (unirrigated) from 3s 2d to £1 5s 10d an acre, cotton from 3s 6d to £1 5s an acre, sugar cane, from 5s to £3 8s 6d an acre and tobacco from 9s 4d to £4 10s an acre. Day labourers are seldom employed upon agricultural work except at harvest time when they receive their wages in grain. Skilled labourers in towns now receive from 8d to 10d per diem, unskilled, from 3d to 4d per diem. Prices of food grains ruled as follows on the 1st of January 1884. Wheat 24 *seers* per rupee or 4s 8d per cwt, barley 39 *seers* per rupee or 2s 11d per cwt, grain and *dhya* 33½ *seers* per rupee or 3s 4½d per cwt. Indian corn, 32 *seers* per rupee or 3s 6d per cwt. *Jowar* 36 *seers* per rupee or 3s 1d per cwt, rice, 13 *seers* per rupee or 5s 7d per cwt.

Commerce and Trade, &c.—The local commerce centres in the town of Silkot which gathers into its *hads* more than half the raw produce of the District. The large markets of Ludhiana and Amritsar (Umnisar) afford a ready market for its produce while the great rivers on either side furnish natural channels of communication with the lower parts of the Punjab. Grain of all kinds is exported to Multan, Lahore and Amritsar, sugar and *dhya* to Peshawar, Kohat and Kandahar (Kandahar). The fine *raw silk* which is manufactured at Kotli is a large source of revenue. The *raw silk* is carried for sale by the railways thence to a junction at Itan. Spun *raw silk* is manufactured by hand in the district at a large

and Kilá Sobha Singh, is sent to Amritsar; and country cloth to the hill tracts. The import trade includes—grain from Batála and the Bári Doáb uplands; salt from Pind Dádan Khán; rice, tobacco, and potatoes from Kángra, Núrpur, Murree, and Dalhousie; *ghí* from Jalálpur and the hills; timber, spices, hides, fruits, valuable shawls, and woollen fabrics from Kashmír; hemp from the submontane tracts of Jamú; and indigo from Múltán.

The indigenous manufactures of the District comprise silk, saddlery, shawl-edging, coarse chintzes, pottery, brass vessels, country cloth, cutlery, *koftgári* ware, and paper. In 1869, an undertaking was started at Siálkot under the name of the Belfast Flax Company, to encourage the growth of flax for exportation to England; but though an excellent fibre was raised in the District, the difficulty of procuring good seed, and the apathy of the peasantry (who would not adopt the new methods necessary to the production of first-class flax), caused the enterprise to prove a failure after some years' trial.

Means of Communication.—The metalled road from Wazírábád to Siálkot, and thence on to Jamú in Kashmír territory, was the principal line of communication in the District before the railway was opened. It has a length of about 35 miles in the District. Other lines communicate with Gujránwála, Amritsar, Lahore, *viâ* Eminábád, Gurdáspur, and Dalhousie. Total length of District roads (1883–84), metalled 43 miles, and unmetalled 747 miles. A branch of the Punjab Northern State Railway from Wazírábád to Siálkot, a distance of 27 miles, was opened for traffic on the 1st January 1884. The Chenáb and Rávi rivers are navigable by ordinary flat-bottomed boats of from 250 to 400 *maunds* burden, according to the season of the year. Ferries are established at all the principal crossings.

Administration.—The District staff usually comprises a Deputy Commissioner, a Judicial Assistant, an Assistant Commissioner, and 3 Extra-Assistant Commissioners, besides a Cantonment Magistrate, the ordinary medical, fiscal, and constabulary officials. The total imperial revenue raised in the District in 1872–73 amounted to £125,768; of which sum £108,598, or more than five-sixths, was derived from the land. By 1883–84, the total imperial revenue had increased to £145,531, of which £111,712 was derived from the land. Besides these imperial receipts, a small provincial and local revenue is also raised. The total number of civil and revenue judges in 1883–84 was 21; and the total number of magistrates, 20. The regular police force in the same year numbered 377 officers and men, while the cantonment and the municipalities maintained a separate constabulary of 178 men. This force is supplemented by a body of 2525 village watchmen (*chaukidárs*). The total machinery, therefore, for the protection of person and property amounted to 3080 officers and men,

being 1 policeman to every 0.6 square miles of the area and to every 328 of the population. The jail at Sialkot contained in 1883 a total of 1428 prisoners, with a daily average of 345.

Education has made a considerable start since the introduction of British rule. In 1872-73, the District contained 427 schools of all grades (besides the normal school at Sialkot town), with a roll of 8491 pupils. The total expenditure on education during that year amounted to £3275. In 1883-84, the Government schools in Sialkot District consisted of 1 high school, 9 middle schools, 72 primary boys' schools, and 38 primary girls' schools attended by a total of 5416 pupils, of whom 880 are girls. The above are exclusive of 4 missionary or church schools, a convent school for Europeans and Eurasians, a municipal school, and a school for vernacular teachers. It also excludes indigenous uninspected village schools which were returned at 604 in 1882-83, with 6831 pupils. The Census Report of 1881 returned 9525 boys and 455 girls as under instruction, besides 19,988 males and 408 females able to read and write but not under instruction.

The District contains four printing presses—one at the jail, and another at Hajipur belonging to the American Mission which print in English, Urdu, Persian, and Hindi and two native presses in Sialkot town, which print in the vernacular only. One of these publishes a vernacular newspaper, the *Rafai Am* which has a fair circulation.

Medical Aspects—The climate of Sialkot may be considered as free from excessive heat, judged by the ordinary standard of the Punjab. Even in the hottest weather, a storm in the hills produces a pleasing change, while in May and September cool breezes from the Hindustan moderate the prevailing heat. The mean monthly temperature for a period of fifteen years ending 1881 is returned as follows—January, 51.5° F., February, 56.5°, March 65.3°, April 76.7°, May, 84.9°, June, 90.5°, July, 63.8°, August, 84.9°, September, 83.1°, October 74.5°, November, 61.8°, and December 52.7°. Average annual mean 72.4°. In 1883 the thermometer in May ranged from a maximum of 113.5° to a minimum of 64.2°, with a mean of 89.6°. In July 1883 the maximum was 114.9°, minimum 68.5°, mean 91.3°. In December 1883 the maximum was 73.1°, minimum 34.1° mean 54.7°. The average annual rainfall for twenty-four years ending 1881 was 37.83 inches, distributed as follows—January to May 7.94 inches, May to September, 27.83 inches, October to December, 20.6 inches. In 1883 the total rainfall amounted to 28.9 inches or 5.9 inches below the average.

Sialkot bears a good reputation as a healthy town. Malarial fever, small pox, dysentery, and pneumonia are the principal diseases. The climate also proves itself to be very healthy for the aged and infirm. The

total number of deaths from all causes reported in 1883 was 28,686, or 28 per thousand. Of these no less than 16,021, or 15·8 per thousand, were assigned to fevers. The District contains 11 Government charitable dispensaries, which afforded relief in 1883 to 78,754 persons, of whom 987 were in-patients. The leper asylum at Pathán-wáli consists of three barracks, capable of accommodating about 100 lepers. Cattle disease occurs in the form of a murrain called *waba*, which carries off a large number of beasts every year. [For further information regarding Siálkot, see the *Gazetteer of Siálkot District*, compiled under the authority of the Punjab Government (Lahore, 1883-84). Also *Report on the Revised Settlement of Siálkot District*, 1850-1860, by E. A. Prinsep, Esq.; the *Punjab Census Report* for 1881; and the several annual Administration and Departmental Reports of the Punjab Government.]

Siálkot.—*Tahsil* of Siálkot District, Punjab; consisting of a fertile agricultural country, lying round the town of Siálkot. Area, 637 square miles; number of towns and villages, 794; houses, 44,195; families, 83,106. Population (1881) 402,825, namely, males 215,094, and females 187,731. Average density of population, 632 persons per square mile. Classified according to religion, Muhammadans number 157,341; Hindus, 129,039; Sikhs, 14,182; Jains, 876; Christians, 1380; and Pársís, 7. Of the 794 towns and villages in the *tahsil*, 595 contain less than five hundred inhabitants; 122 between five hundred and a thousand; 75 between one thousand and five thousand; 1 between five and ten thousand; and 1 between twenty and fifty thousand. The average area under cultivation for five years ending 1881-82 is returned at 290,658 acres; the principal crops being—wheat, 96,513 acres; barley, 60,752 acres; rice, 19,208 acres; Indian corn, 23,170 acres; *joár*, 16,111 acres; gram, 5361 acres; other food-grains, 4050 acres; cotton, 17,882 acres; sugar-cane, 15,848 acres; vegetables, 3820 acres; tobacco, 1851 acres; and poppy, 142 acres. Revenue of the *tahsil*, £25,989. The administrative staff, including the head-quarters officers of the District, consists of a Deputy Commissioner, Judicial Assistant Commissioner, 3 Assistant or Extra-Assistant Commissioners, 1 Judge of Small Cause Court, 1 *tahsildár*, and 2 *munsifs*. These officers preside over 9 civil and 7 criminal courts; number of police-circles, 4; strength of regular police, 131 men; village watch or rural police (*chaukidárs*), 525.

Siálkot.—Town, municipality, military cantonment, and administrative head-quarters of Siálkot District, Punjab; situated in lat. 32° 31' N., and long. 74° 36' E., on the northern bank of the Aik torrent, upon the edge of the high triangular ridge which extends southward from the Jamú Hills. Distant from Lahore 72 miles north-east.

The town was founded, according to tradition, by Rájá Sál or

Shāl, mentioned in the *Mahābhārata* as an uncle of the Pāṇḍava princes. Restored about 65 or 70 A.D. by Śālwan or Śālvaḥana, otherwise called Vikramāditya, father of the great Punjab hero, Rasālu, whose capital Sialkot is also stated to have been, and whose exploits form the subject of countless Punjab legends. Towards the end of his reign, Rasālu became involved in wars with a Rājā Hūdī, popularly stated to have been a Ghakkar chieftain. Being worsted in battle, Rasālu as the price of peace was forced to give his daughter in marriage to his conqueror, who, on Rasālu's death without heirs, is said to have succeeded to the rule of Sialkot. According to a further legend related to Mr Prinsep—'After the death of Rājā Rasālu, the country is said to have fallen under the curse of Puran (brother of Rasālu, who had become a *śakir*) for 300 years, lying totally devastated from famine and incessant plunder.' The country was afterwards occupied in the 7th century A.D. by the Rājput princes of Jammu, and under the Mughal Emperors, Sialkot became the head-quarters of a fiscal district (*sarkār*). In the centre of the town stand the remains of an ancient fort, popularly believed to have been the original stronghold of Rājā Śālwan, although recent excavations show that it has not in all probability existed more than 1000 years. Other similar mounds stand among the outskirts of the town. In modern days, the old fort is of historical interest for its gallant defence by the few European residents who took refuge here during the Mutiny of 1857. It is now dismantled, and the few buildings it contains are used for public purposes.

The population of Sialkot town was returned in 1881 at 33,850, and that of the cantonment at 11,912. Total population of town and cantonment, 45,762, namely, males 25,767, and females 19,995. Classified according to religion, Muhammadans numbered 28,865, Hindus, 12,751, Sikhs, 1942, Jains, 876, Christians, 1321, and Parsis, 7. Municipal income (1883-84), £5052, derived almost entirely from octroi duties.

The town is very extensive, and is steadily increasing in size and commercial importance, especially since the opening of the railway connecting it with the main line of the Punjab Northern State Railway at Wazirabad. It is fairly handsome, well built, and clean. Its main streets are wide and open, and either paved or metalled, with good drainage on both sides. The principal are the Kanak *mandi*, or grain market, running north and south, and the *Chandni Chowk*, containing the shops of all the principal dealers in cloth, jewellery, fruits, etc. The principal buildings, shrines, &c., within the town include the following—The ruined and dismantled fort alluded to above. A temple erected by Rājā Tej Singh has a conspicuous spire visible from all parts of the town. The shrine of the first Sikh guru, Pīṭā

Nának (*see* AMRITSAR DISTRICT), is the scene of a famous annual fair, largely attended by Sikhs from all parts of the District. The Darbár Báoli Sáhib, a covered well, erected by a Rájput disciple of Bába Nának, also ranks high in religious consideration among the Sikhs. A Muhammadan shrine of Imám Alí-ul-hak is a handsome building of ancient construction. The public and municipal buildings include the *tahsíl*, police station, dispensary, town hall, post-office, mission school, and four female schools, two *saráis* or native inns, rest-house for village notables and head-men visiting the city, and poorhouse, where cooked food is daily distributed. The roads from Amritsar, Lahore, Gurdáspur, and Gujránwála converge on the Aik stream, which is crossed by an ancient but well-built and substantial bridge. The railway station is situated just outside the town on the north.

The civil station is situated about half a mile north-east of the town, and contains, besides the dwellings of the civil residents, the District court-house, treasury, jail, and police lines. The cantonment lies about a mile north of the town, being built on an elevated ridge of land affording good natural drainage. The cantonment is exceedingly well laid out, and occupies an area of 5 miles in length east and west, by 3 miles north and south. Most of the roads are lined with trees. The principal public buildings in the cantonment are the post-office, telegraph office, two churches, a Roman Catholic chapel, and the general military prison for the Punjab. There are recreation grounds, racquet courts, and a well-kept public garden 27 acres in extent, provided with tennis-courts, station library, and reading-room.

As a local trade centre, Siálkot is fast rising in importance. It has several wealthy bankers and merchants, of whom the most prominent belong to the Jain tribe of Bhábrás. The distinctive industry of the place is the manufacture of paper, carried on in three hamlets forming suburbs to the city. The manufacture is said to have been introduced four centuries ago; and under the Mughal Emperors Siálkot paper was noted for its excellence, being largely used at the Delhi court. In those days, the yearly value is said to have amounted to £80,000; but under the Sikhs it declined rapidly until only twenty mills remained, turning out paper to the value of £2500 a year. At the time of the Settlement of the District (1850-1860) there were 82 mills at work, with an annual out-turn valued at £7500. At the present time the manufacture is again on the decline, owing to the exclusive use by Government of prison-made paper. A description of cloth known as *susi* is also manufactured to a considerable extent; and, next to paper, it forms the principal export. The imports are grain, salt, European piece-goods, metals, and raw sugar.

Siáltek.—Village in Cachar District, Assam; situated on the Barák river, near the boundary of Sylhet, where toll is levied on the

timber, bamboos, etc. floated down stream Up to 1876, the river tolls at Sialtek *ghat* were farmed out to a contractor, who paid rent at the rate of £1500 a year Since that date the toll station has been taken under direct Government management, and the receipts have rapidly declined In 1876-77 they fell to £854, and in 1881-82 to £332 One of the largest *bidars* in Cachar is held at Sialtek

Siana.—Town in Bulandshahr District, North Western Provinces — See SIANA

Siarsol.—Coal mine in Bardwan District Bengal being a part of the RAIGANJ coal field The mineral is a variety of non coking bituminous coal, with a large portion of volatile matter and ash The brighter portions consist of very pure coal, a sample of which gave the following results — Volatile matter 40 per cent fixed carbon, 57.5 per cent, ash, 2.5 per cent The composition varies, however, considerably, that of one sample being — fixed carbon 51.1 per cent, volatile matter, 38.5 and ash 10.4 while selected rich layers gave the following analysis — fixed carbon 57.25 per cent volatile matter, 41 per cent, and ash, only 1.75 per cent The output of coal from the Siarsol mine, which is the property of a private company amounted in 1883 to 39,911 tons against an average of 34,460 tons in the three previous years The mine gives employment upwards of 500 men, women, and children

Sibi — District of Southern Afghanistan ceded to the British by the terms of the treaty of Candahar in 1881 It lies between 29° 20' and 29° 45' N lat, and 67° 45' and 68° 15' E long It is the most northerly portion of the Kachi plain from the remainder of which it is separated by a low stony ridge broken in two places by wide gaps, through one of which the Nari river passes and through the other the Thali torrent Beyond this ridge lies the Mal district which is politically connected with Sibi though physically separated by the ridge mentioned above is divided into two parts the western part, including Didar is politically connected with the Nari river held district of Kachi while the eastern part is under the former subordinate to the Afghan Governor of Kandahar

Physical Aspects.—The boundary between the western and eastern parts of the Nari and the low ridge mentioned above is the only one which separates the boundaries are the outer ranges of the Sulaiman and Maris and the Dumar Pathans The only river which flows up of low, pebbly hillocks in the centre of the plain is one of the principal streams issuing from the northern hills is the Nari, a considerable river of the Indus drainage system south of the

Gúmal pass. Its drainage basin probably includes the plain of Thal Chotiáli and the greater part of the Kakar country. It affords a perennial supply of water as far south as Bágh. After leaving the hills it flows through a depressed alluvial plain from 2 to 3 miles wide, bounded on either side by a high bank. The centre channel of the river brings down a perennial supply of water, and other channels to the east and west are filled during flood. The alluvial plain between the high banks is called the Nari Kach, and is very seldom inundated.

The stream of next importance to the Nari is the Thali torrent, which drains a considerable portion of the Marri hills and emerges into the plain through a narrow defile called the Thali Tonkh, the whole length of which is occupied by a deep pool. The perennial supply of water flowing in and out of the pass is not great, and serves in the cold weather to fill only one canal, which waters some of the Thali lands. Heavy floods come down in the hot weather, and the water is used to irrigate the *kharíf* crops of cotton and *joár* at Thali and Mal.

Between the Nari and the Thali some minor torrents drain the outer range of hills. These are the Arand, Ghází, and Chimmar, the water of which is available for land cultivation for the *kharíf* crops.

The soil of the greater part of the plain is clay, of the same nature as that of Kachi generally. In the Nari Kach, or the depressed basin of the Nari, it is a fertile, sandy loam, covered with a dense jungle, which reproduces itself in two or three years after clearing. It is composed mostly of tamarisk, *Tamarix articulata* (*gazlai*) and *Tamarix dioica* (*gas, lawa kar lawa*); the thorn or thand tree (*kakar, kandi*), *Prosopis spicigera*; the *jál* tree, *Salvadora oleoides* (*phir, kabbar, jál*); the *babíl*, *Acacia Jacquemonti* (*chighird, babhar*); and a great variety of grasses, the most valuable kinds for grazing being *gandil, sain* (*sui, garkha*), and *afdrík* or *mamhar*, *Panicum antidotale* (*gom gomadh*), valuable only for its small grain, eaten in time of scarcity. *Saccharum Sara* (*kikh*) and *Cymbopogon twarancusa* (*nadakh*) are also common, as well as the camel-thorn, *Alhagi maurorum* (*shins jowaha*). On the central plain the jungle is not so dense as in the Kach. The ground, wherever it has lain fallow for a year or two, is covered with patches of scrubby jungle; and extensive tracts are overgrown with different salsolaceous plants (*lana* and *khál*) and camel-thorn. In some places, especially west of Khajak, there is dense jungle of *Prosopis spicigera*, *Zizyphus nummularia*, and *Capparis aphylla*. *Salvadora persica* (*tozh, zhit*) is occasionally found; and near the hills *Arthanthra Vimivea* (*khip, hidhishk*) and *Calligonum polygonoides* (*phog*). Near the village the *kikar* (*Acacia arabica*) and *ber* (*Zizyphus jujuba*) are cultivated.

Wild hog and ravine deer are abundant; and, among birds, the black

and grey partridge, the *haubara*, *kunj*, sand grouse, quail, and pigeon are the commonest

Agriculture—Cultivation depends entirely on irrigation, which is mainly from the Nari river. Just below the exit of this stream from the hills, a rough embankment of stones and turf has been thrown half way across the stream, and by this means a supply of water is turned into four canals.

The crops chiefly cultivated are wheat, barley, and mustard seed in the cold weather, and *jodr*, cotton, and *til* or sesamum in the hot. The amount of land under cultivation is small. The land is allowed two years' fallow between each crop, and the crops are consequently of good quality. Wheat, which is the staple crop, is extremely fine, especially in the Kach, where the soil is lighter and more sandy than on the central plain, and does not require the same amount of water. The cotton is also very fine, the bushes attaining a great size, especially near Thali. They are planted in lines at a sufficient distance apart to allow of their expanding to their full size. Much of the ground, especially in the Kach, seems well suited for the cultivation of rice, but this is not understood or practised, the reason being probably the uncertainty of the water supply in the hot weather. Near the villages a few trees are planted, chiefly *ber* or *kunar* (*Zizyphus jujuba*) and *likar* (*Acacia arabica*).

Population—The population consists of Patháns, Rind Balúchís, Brahuís, Játs, and Hindus, distributed as follows—Patháns, 6150, Balúchís, 750, Brahuís, 300, Játs, artisans, etc., 4600, and Hindus, 2100 total, 13,900.

The Patháns are the most influential. Their tribes are the Bírakzais, Pannis, and Khajaks, besides scattered families of other tribes. The Nodáni Hassanis are also commonly classed as Patháns, although they claim to be part of the Hassani tribe who formerly inhabited the Sham plain, and are now scattered about Barkhan and Thal Chotáli, and this tribe is usually classed as Balúchi. The Silinchis of Thali also rank as Patháns. The Rind Balúchís are mostly of the Ghulám Boliak tribe. There are scattered families of the Per, Chandya, Gurchani, Lashari, Pitafi, Bughti, Gurgej, Lund and Gishkoni tribes. The Brahuís are mostly of the Gwaharamzai tribe, and live at Mal and Kurk.

Játs are found in most of the villages, and there are also a considerable number of artisans and workmen, such as warblers, potters, barbers, carpenters, blacksmiths, butchers, etc. Hindu shopkeepers are also numerous.

The Bírakzai family hold the foremost rank in Sibi. The chief of the Pannis is a Bírakzai, and under the Afghan Government the office of Naib was always held by him.

Khorasán The local products exported are wool, *ghí*, banilla or *saffr*, and wheat, barley, and *jodr*

History—Of the early history of Sibi, but little is known Tradition represents it as having been at one time the centre of a considerable kingdom which embraced the whole of the hill country to the north, and which still bears the name of Sewistán The communications with Thal Chotíálí are easy, and the route through Sibi to that part of Afghánistán was a well known one till closed by the depredations of the Maris

The earliest historical mention of Sibi occurs in Babar's autobiography (Leydn's *Bábar*, ed 1826, p 164) Bábar was marching from the Indus to Chotíálí, probably via the Sakhi Sirwar pass He passed through the country of Rudi, which seems to be the Barkhan valley, and there found Fazil Gokaltash, the Darogah of Sibi, who had come out with 20 men to reconnoitre Fazil Gokaltash was in the service of Sháh Beg Arghan This was in A H 911 (A D 1505) Sháh Beg was son of Zulnun Beg, Governor of Kandahár, under the Khorasán kings, and ultimately (in A H 928, A D 1521) conquered the whole of Sind, and established the Arghan dynasty there (Briggs' *Ferishta*, ed 1829, vol II p 432) Bábar's conquests do not seem to have extended so far south as Sibi, which probably remained in the hands of the Arghans

To this period belongs the legendary hero of the Balúchís, Mír Chakar, who is said to have founded the fort of Sibi He appears to be identical with Mír Chakar Rind, who is mentioned by Ferishta as having come to Multán and obtained a *jaqír* at Uchh in A D 1520 (Briggs' *Ferishta*, vol II p 396) The Balúchís seem to have been very powerful at Multán, and were able to afford protection to Daulat Khán Lodí when he fled from Ibráhím Khán in A D 1524 (Briggs' *Ferishta*, vol II p 38)

The legends represent Mír Chakar to have been at perpetual war with Humáyún (Humán Chughatta), and this may have a historical foundation in the attacks made on Humáyún by Balúchís on his flight towards Kandahár (Erskine's *Bihar* and *Humáyún*)

After the conquest of Sind by the Mughals, Sibi must have formed part of the Mughal Empire, and so continued till the rise of the Duráni kingdom under Ahmad Shah The settlement in Sibi of the Kharak, Barakzais, Pannis, and other Patháns had probably taken place before this, and the country remained attached to the power holding Kandahár As the Duráni kingdom broke up, Sibi passed with the rest of Afghánistán under the rule of the Barakzai Sardárs, the chief of the Barakzais acting as Naib under the rulers of Kandahár From 1839 to 1842, Sibi was occupied by the British in the name of Sháh Shujá The old fort was put into repair and used as a corn granary depot

Granaries were built, which are still in existence, and are now undergoing repairs. The revenue was collected in kind at one-third of the gross produce. The Khajaks refused to pay on one occasion, and a force was sent against them, which destroyed their town. After their submission, they were allowed to pay only one-fifth of the gross produce as revenue, in order to enable them to repair their houses.

In 1843, Sibi came again under Bárakzai rule, Khán Díl Khán and Sádik Muhammad Khán being Sirdárs of Kandahár. They continued to collect the revenue in kind till 1846-47, when the cash assessment, which has prevailed till the present day, was introduced. The country was for long in a distracted condition owing to internal dissensions and the ravages of the Marris.

Sibi is one of the Afghán districts assigned to the British Government by the treaty of Gandamak. Since then its condition has been uneventful and prosperous. Its administration is carried on under the control of the Governor-General's Agent in Balúchistán. It forms part of the charge of the Political Agent of Thal Chotiáli, in subordination to whom there are a native Assistant Agent, a *tahsildár*, and a *munsif*. No troops are regularly stationed in the district, but there are police and tribal levies.

Under Afghán rule, the revenue of the district was represented by a fixed payment of £1000, which was remitted to the Amír's treasury by the chief of the Bárakzais. Under British administration, the revenue is collected in kind at uniform rates of one-fifth of the gross produce in the *rabí* crop, and one-sixth in the *kharíf*, amounting in value to £11,215 in 1884-85.

The town of Sibi has developed very largely of late, and is now administered on municipal principles. It is a station on the newly opened Sind-Pishín Railway, the head-quarters of the Political Agent, and in the cold weather of the Agent to the Governor-General in Balúchistán.

Sibi.—Village with religious fair in Túm-kúr District, Mysore State.
—See SHIBI.

Sibpur (*Shibpur*).—Suburb of Howrah town, Húgli District, Bengal; situated in lat. $22^{\circ} 34' N.$, and long. $88^{\circ} 16' E.$, opposite Fort William. The place has grown since the beginning of this century from a small village into a flourishing town; inhabited chiefly by Government and other clerks, and by labourers employed on the various mills and foundries, and on the East Indian Railway works. On the river-side are the Albion works, consisting of a flour-mill and a distillery. To the south of Sibpur are the Royal Botanical Gardens, one of the finest of their kind in the world. A little above the gardens, an important technical school of industry—the Sibpur Engineering College—occupies the buildings and premises of the old 'Bishops

College,' now transferred to Calcutta. Sibpur is a permanent mart for District produce, bricks are largely made and exported to Calcutta.

Sibsagar (Sebsaugor)—A British District in the upper valley of Assam, lying between $26^{\circ} 19'$ and $27^{\circ} 16'$ N. lat., and between $93^{\circ} 21'$ and $95^{\circ} 25'$ E. long. Area, 2855 square miles. Population (as ascertained by the Census of 1881), 370,274 souls. Bounded on the north and east by Lakhimpur District, the Brahmaputra marking the boundary for the greater part of the distance, on the south by the Naga Hills District, and on the west by Nongong District. The administrative head quarters are at SIBSAGAR TOWN, situated about 11 miles inland from the south bank of the Brahmaputra.

Physical Aspects—The District presents the appearance of a level plain, much overgrown with grass and jungle, and intersected by numerous tributaries of the Brahmaputra. Along the bank of the great river and its branches, the land lies very low and is exposed to annual inundation, in the interior, the country rises towards the Naga Hills in the background, and the cane-brakes and grassy swamps of the valley give place to jungles of heavy timber. The District is divided by the little stream of the Disai into two tracts, which differ in soil and general appearance. East of the Disai the surface is very flat, and the soil consists of a heavy loam of a whitish colour, which is well adapted for rice cultivation. The general level is only broken by the long lines of embankments which were raised by the Ahom kings, to serve both as roadways and as a protection against floods. West of the Disai, though the surface soil is of the same character, the general aspect is diversified by the protrusion of the subsoil. The latter is a stiff clay, abounding in iron nodules, and furrowed by frequent ravines and watercourses, which divide the cultivable fields into innumerable small sunken patches, locally known as *lolds*.

In the inner part of the District towards the hills, the country is clothed in dense forest with an underwood of thorny creepers, which swarm with leeches when the rains begin to set in. This latter region is generally preferred for tea cultivation, as high forest glades are considered more suitable for the tea plant than grass land. Where the land still lies waste in the tract in which the husbandmen cultivate rice, it is overgrown with tall grass from 15 to 20 feet high, and which are isolated patches of cultivation.

There are no mountains within the limits of the District. The chief river is the Brahmaputra, forming the continuous northern boundary, which is navigable all the year through by steamers and large native boats. Its principal tributaries, beginning from the north-east, are the Dihing, which for part of its course divides Sibsaigar from Lakhimpur District, the Disang, Dikhu, Thanzi, Disai, Kakadung, and the Dhaneswar or Dhansiri, which all flow in a northerly direction from

the Nágá Hills. The most signal example of alluvion in the whole Province is afforded by the Májuli *char*, included within the District of Sibságar. This island is included between the present stream of the Brahmaputra, which forms its southern boundary, and the old bed which forms its northern. The latter is now known as the Lohit river, and derives most of its water from the great affluent, the Subansiri, which brings down from the north much of the silt of which the island is formed. The soil is a rich alluvium suitable for every kind of crop. It contains an area of about 400 square miles, almost entirely overgrown with grass and jungle. The fisheries of the District, which are Government property, yield an annual revenue of about £2300 a year. There are no lakes, canals, or artificial watercourses in Sibságar; but there are many extensive marshy wastes, in which rattans and canes grow wild, and long-stemmed varieties of rice are cultivated.

Wild beasts of all kind abound, including elephants, rhinoceros, tigers, bears, buffaloes, and deer. In 1882-83, £800 was paid to Government for the privilege of capturing wild elephants.

Among the trees indigenous to the forests of Sibságar, and producing valuable timber, are the *sím* (*Artocarpus Chaplasha*), *gamari* (*Gmelina arborea*), *pomá* (*Cedrela Toona*), and some species of *Lagerstroemia* and *Dillenia*. All these trees grow to a great height, and throw out numerous branches. Their wood is used for many purposes, and the most durable canoes are made from it. Next in importance to these timber trees are the *káthál* (*Artocarpus integrifolia*), *uriam* (*Bischoffia javanica*), *kálá jám* (*Syzygium Jambolana*), *tilli* (*Tamarindus indica*), some specimens of *takrá* (*Bauhinia*) and *nahor* (*Mesua ferrea*). Of all the plants of the District, the bamboo is the most useful. The natives have several specific names for the different varieties of the bamboo; such as *jánti-báns*, *bháluhá-báns*, *mákál-báns*, *bazal-báns*, etc. The trees used for rearing silkworms on are the *adakur* (*Tetranthera quadrifolia*), *sím* (*Machilus odoratissima*), *pílá-champá* (*Michelia pulneyensis*), and *eríá* (*Ricinus communis*). Rattans grow wild throughout the waste lands, so luxuriantly as to form an almost impenetrable jungle. Innumerable varieties of creepers are found. The jungle products consist of caoutchouc, lac, beeswax, and various fibres and dyes. Ivory is also exported. The Málo Kaliáni Diha and Arali Tál are large patches of grazing ground, used during the winter months as pasturage for thousands of buffaloes and cows, but covered with water during the rains. The mineral wealth of the District is said to comprise coal, iron, petroleum, and salt, but none of these have been profitably worked. A little gold dust is washed in several of the hill streams. Some hot sulphur springs are situated near the banks of the Dhaneswarí, and its tributary the Nambár; but they lie beyond the border in the Nágá Hills District.

History—Sibságar District first rose into prominence as the head quarters of the Ahom dynasty, which ruled Assam for about 400 years before the British annexation. Prior to the advent of the Ahoms, the dominant race was the Chutiás, of a kindred origin to the Ahoms, who only subjugated the Chutiás after a fierce contest. At the present day, these two tribes form nearly one half of the total population. The Ahoms, a people of Shan origin, are said to have first made their appearance in Upper Assam in the 14th century, after the downfall of the legendary Hindu kingdom of Kámrúp. They gradually spread down the valley of the Brahmaputra, until in the 17th century they were able to hold their own at Gauhati against repeated invasions of the Mughals. It does not appear that they brought any religion with them from their native hills, but in course of years they fell under the influence of Hinduism, and at the same time lost the virtues of military and civil administration, by means of which they had founded their empire. At last, in order to protect themselves against internal dissensions, they were compelled to call in the assistance of the Burmese, who tyrannized over the country with great severity, until they were in their turn driven out by the British in 1823.

The original capital of the Ahoms was at GARHGAON in this District, on the Dikhu river, a short distance south-east of Sibságar town, where numerous ruins are still to be seen. The city and its suburbs appear to have extended over many square miles, and the royal palace itself was surrounded by a brick wall, about 2 miles in circumference. It has been noticed that one of the many gateways is built of large blocks of stone bearing marks of iron crampings which show traces that they once belonged to a far more ancient edifice—thus attesting the primitive Hindu traditions of Kámrúp as told in the *Mahábhárata*. The whole is now overgrown with dense jungle, and the natural course of decay has been hastened by the hand of man, for the old bricks are found serviceable on the tea-gardens of the present day.

The second Ahom capital was at RANGPUR, immediately to the south of Sibságar town, which is said to have been founded in 1698 by Rájá Rudra Singh, the first Ahom prince who submitted himself to the Brahmans. The ruins of his palace, and a temple which he built at Jaiságar, still exist amid the deep jungle. To the eldest son of this monarch is assigned the excavation of the great tank, 114 acres in area, around which has been built the modern station of Sibságar. Rangpur continued as the royal residence until 1784 when the Ahom kingdom began to be dismembered. The Rájá, named Garinath, fled before his rebellious subjects, who had advanced against him from the east. He first stopped at Jorhat on the Disa river, in the centre of Sibságar District, but was ultimately compelled to retire to Gauhati.

With British assistance, he was enabled to return to Jorhát, where he died in 1793.

Apart from the ruins of successive capitals, the Ahams have left permanent traces of their power in the great lines of embankment running through the country, which are locally known as *ális*. These were constructed by a system of forced labour, and served both as roads and as protections against river floods. The entire method of Aham administration was based upon personal servitude. The country was parcelled out into executive Districts, each of which was under the control of a taskmaster; no money revenue was demanded, but compulsory service was exacted from every individual among the subject races as his contribution to the needs of the State. The recollection of this organized slavery still lives in the minds of the people. At the present day, it is found almost impossible to obtain labourers to work on the roads, or other Government undertakings. The peasantry are willing to take employment on the tea-gardens, when not occupied on their own little plots of rice; but to work for Government is held to involve indelible disgrace. Hence it is that the great works of the Aham period have been suffered to fall into disrepair, and the incursions of the rivers have thrown much good land out of cultivation.

When the British expelled the Burmese from Assam in 1823, the Government was indisposed to undertake the responsibilities of administration beyond what seemed absolutely necessary. A military outpost was stationed at Sadiyá, at the extreme head of the Brahmaputra valley, but the civil government by European officials was not extended farther east than the confines of Nowgong. The tract that now forms Sibságar District, together with the southern portion of Lakhimpur, was handed over to a native ruler, Rájá Purandhar Singh, who was guaranteed the secure exercise of his authority on condition of paying a tribute of £5000 a year. This unsatisfactory arrangement produced the results which might have been anticipated. The Rájá, protected by the British name from the consequences of his misrule, indulged himself in the most wanton oppressions upon his helpless subjects, and rendered their condition even more miserable than it had been under the Burmese invaders. It is on record that the country became so depopulated that it was unable to furnish the British tribute. Under these circumstances it was found necessary in 1838 to dispossess Purandhar Singh, and to place Sibságar under the direct management of an English officer. The early reports of those days are confined to complaints of the extreme misery to which the country was reduced. The tea industry, however, has now brought back prosperity; and at the present time the Sibságar peasants rank among the most contented and wealthy in Assam.

Population—Mr Robinson, in his *Description and Account of Assam* (1840), roughly estimated the population of Sibsagar District, which then included great part of Lakhimpur, at 200,000 souls. Another estimate in 1853 gave a total of 211,477. The first regular Census was taken in 1871, and the enumeration, instead of being taken in a single night as in Bengal, was prolonged over the two months of November and December. The results disclosed a total of 296,589 persons, on an area corresponding to the present District. The Census of 1881 was synchronous, and was, as elsewhere throughout British India, effected on the night of the 17th February. It returned a total population of 370,274, showing an increase of 73,685, or 24.83 per cent., for the nine years between 1872 and 1881. The natural increase of births over deaths accounts for about half this increase, the remainder being made up by immigration from Bengal.

The results of the Census of 1881 may be summarized as follows—Area of District, 2855 square miles, with 1 town and 1982 villages, and 63,576 houses. Population, 370,274, namely, males 195,194, and females 175,080, proportion of males, 52.7 per cent. Average density of population, 129.7 persons per square mile, towns or villages per square mile, 62, persons per town or village, 187, houses per square mile, 22.3, persons per house, 5.8. Classified according to sex and age, there were in 1881—under 15 years of age, boys 77,164, and girls 73,849, total children, 151,013 or 40.8 per cent. of the population. 15 years and upwards, males 118,030 and females 101,231, total adults, 219,261, or 59.2 per cent.

The ethnical division of the people shows—Europeans 168, Gurkhas, 139, aboriginal and semi-aboriginal tribes and castes, 215,224, Hindus, 139,075, Muhammadans, 15,665, and Chinese, 3. The chief feature in this classification is the large proportion of semi-Hinduized aborigines, as compared with the rest of Assam. On the one hand, the hill tribes of the northern Himalayas and of the eastern Burmese Mountains are poorly represented, while, on the other, the castes of Bengali Hindus have not penetrated so far east. The great bulk of the population are pure Assamese more or less converted to Hinduism. The once dominant race of Ahoms, numbering 117,872, still supplies nearly one third of the total population. Though they have now sunk to the level of common cultivators, they retain many of their ancient habits and institutions. Some of them eat beef and pork, and also bury instead of burning their dead. Next in number come the Chutias (29,952) who have already been referred to as of the same original stock as the Ahoms, and their predecessors in the government of the upper valley of the Brahmaputra. The Kacharis (24,248) are members of a tribe whose present headquarters are in the Bengal State of Kuch Behar, but who ruled at one time over the

greater part of Assam, before the arrival of the Ahams. The Doms (22,867) are a curious race, who lay claim in Assam to high-caste purity, but reject the ministrations of Bráhmans. Bhumis number 18,492. The aborigines proper include—the Cacharis (19,753), who are largely employed on tea-gardens; Míris from North Lakhimpur (10,836); Míkirs (1403); Nágás (1405); Shans (275); Lalungs (319); Mechs (228); Gáros (185); Manipuris (50); besides a sprinkling of Kols, Uráons, and Santáls, who are imported labourers from Chutiá Nágpur.

Among the Hindus proper, Bráhmans number 11,607, being especially numerous for an Assam District; Rájputs, 1428; Káyasths, 3109; and Jain traders, from the north-west of India, 997. The most numerous caste in the District is the Kalitá (33,812), who supplied the priesthood for the Kochs, Doms, and Ahams before the introduction of Bráhmanism. The Kalitás now rank as pure Súdras, on a level with the Káyasths, and are generally engaged in agriculture or Government service. Other Hindu castes include the following:—Keut or Kewat, 17,736; Katáni, 5404; Munda or Murah, 3420; Kurmí, 3314; Boriá, 2791; Nat, 1963; Ganak, 1531; Harí, 1374; Kumbhár, 1296; Baurí, 1207; Tántí, 1198; Goálá, 920; Ghátwál, 732; Nápit, 718; and Kahár, 436.

Religion.—Classified according to religion, the population consists of—Hindus (as loosely grouped together for religious purposes), 339,663, or 91·8 per cent.; Musalmáns, 15,665, or 4·2 per cent.; Christians, 804 (including 462 native converts); Buddhists, 275; Jains, 37; Brahmo, 1; and non-Hindu aboriginal tribes, 13,829. There are five principal Hindu *sástrás* or religious institutions of a monastic character, each presided over by its own high priest or *gosáin*; and 83 minor *sástrás*. The *gosáins* have a large number of followers, and hold much revenue-free land, both in this and the other Assam Valley Districts. The Bráhma Samáj is represented by a few followers, who are all immigrants from Bengal. The Muhammadans of Sibságar are said to be descended partly from artisans introduced by an early Aham Rájá, and partly from soldiers left by the invading Mughal armies. Many of them have joined the Faráízí or reformed sect, but they are not actively fanatical, and have ceased to make proselytes. The native Christians are under the care of a branch of the American Baptist Mission, which has been established in Sibságar since 1840. The Society is represented by two missionaries, one of whom usually resides in a village on the lower slopes of the Nágá Hills, where he has charge of a considerable number of converts.

Urban and Rural Population.—The population of the District is entirely rural, being employed either on rice cultivation or the tea-gardens. They evince no tendency to gather into towns or seats of

commerce, and very few natives of Sibsagar depend upon trade as a means of livelihood. Some few petty traders buy small quantities of goods from the Marwari merchants who visit the District, and retail them in the village shops, but these have, almost without exception, their little patches of arable land which they cultivate themselves, and from which their household wants are supplied. The only place with a population of more than 5000 is SIBSAGAR TOWN, which contains (1881) 5868 inhabitants. It is situated about 9 miles inland from the south bank of the Brahmaputra, and, besides the houses of the civil officials, possesses a large *bazar*, in which a brisk business is conducted during the cold season with the neighbouring hill tribes. JORHAT, on the Disai river in the centre of the District (population 1978), is the home of several Marwari and Muhammadan traders, who supply the wants of the labourers on the tea-gardens. GOLAGHAT, on the Dihineswar (population 1754), is the only seat of river traffic in the District, being accessible to steamers from May to November. It is now a fairly large station, with a good *bazar*, treasury, telegraph office, and *dist* bungalow, it is also the seat of an Assistant Commissioner. NAZIRA on the Dikhu, about 9 miles from Sibsagar by road is the head-quarters of the Assam Tea Company, containing a large *bazar*, several good European houses, steam mill, and store for English goods. The ruins of GARHGAON and RAANGPUR have been already referred to.

Of the 1983 villages or clusters of hamlets, 1548 contain less than two hundred inhabitants, 413 between two and five hundred, 19 between five hundred and 1 thousand, and only 3 more than one thousand.

As regards occupation, the Census of 1881 returned the male population of Sibsagar District under the following six main headings—(1) Official and professional class, 1337, (2) domestic class, 666, (3) commercial class, including merchants, traders, carriers, &c. 3242, (4) agricultural and pastoral class, including gardeners, 119,608, (5) industrial class, including all manufacturers and artisans 1681, (6) indefinite and non-productive class, comprising general labourers and male children, 68,660.

Material Condition of the People—The inhabitants of the District are described as a contented and happy people, having but few wants, and those very easily supplied, as rice is almost the only article grown for food, the rest being obtainable from the jungles and streams. They still live, however, in the same primitive manner as their forefathers, their agricultural implements and cattle, their food and clothing, being all exactly as they were fifty years ago. A marked indication of the prosperity of the people is the great difficulty experienced in obtaining labour, even at high rates of wages. If there be any exception to the general prosperity, it is amongst a few families of the better class the members of which are, or consider themselves to be, above manual

labour. They find it getting more and more difficult to get their holdings cultivated for them, and to keep up the social position they formerly enjoyed.

The shopkeeping class generally live in somewhat substantial buildings, consisting of two or more rooms under a single roof ; while the dwelling of a common husbandman usually consists of two or three small detached huts, each containing from two to four rooms, and constructed of wood, bamboo, grass, and reeds. These huts are very low, damp, ill-ventilated, and built so close to one another as to render them almost inaccessible to light and air. Each hut seldom has more than one small door, just large enough to admit one man at a time, and has no windows at all. The houses are grouped together into villages, without any regard to arrangement or sanitary considerations. They are generally surrounded with clumps of bamboos, plantain, betel-nut, and *sím* trees, and, viewed from a distance, present a very picturesque aspect. Small quantities of tobacco, mustard, and sugar-cane are cultivated in the immediate vicinity of the villages, each family raising sufficient to supply its own household wants.

The ordinary food of the people consists of rice, pulses, fish, and vegetables. The use of flesh as an article of food is very rare. The vegetables used by all classes of natives consist chiefly of leaves and tender stems, generically called *ság*. Other vegetables, such as potatoes, carrots, cabbages, turnips, onions, etc., are grown to a small extent, for sale to the European residents. Milk is very little used by the mass of the people, though *dahi* (butter-milk) is much consumed by the higher classes. The lower classes seldom use oil ; and instead of salt, they use potash procured by burning plantain leaves. Clarified butter and sugar are only consumed by the comparatively wealthy. Both shopkeepers and cultivators raise nearly every article of food they require for domestic consumption.

Agriculture, etc. — The staple crop throughout the District is rice, which furnishes two great harvests in the year. The *sálí*, corresponding to the *áman* of Bengal, is sown on low lands about June, transplanted in the following month, and reaped in November. Its finer varieties are sometimes comprised under the generic term of *láhi*. The *dhu* or *dus* is sown on high lands about March, and reaped in July, leaving the field ready for a cold-weather crop of pulses or oil-seeds. A third crop of rice, called *báo*, is grown on the borders of marshes or the banks of rivers, being sown about April, and reaped in November. This is a long-stemmed variety, and can keep pace in its growth with the rise of flood water. The other crops include Indian corn, several varieties of pulses, mustard grown as an oil-seed, sugar-cane, *pán* or betel-leaf, and cotton and indigo raised only by the hill tribe of *Mírís*. The *sím* tree (*Machilus odoratissima*) is an important object of attention

in the neighbourhood of villages, for the sake of the silk-worm that feeds on its leaves.

According to the most recent statistics, the area under cultivation in 1883-84 was 327,221 acres, or less than one fifth of the total area of the District, though the greater part of the remainder is capable of tillage. Crop-area in 1883-84—Rice, 211,332 acres, sugar-cane, 4311 acres; tea, 40,532 acres, oil seeds, 10,157 acres, other food-grains, including pulses, 5895 acres, other crops, 62,869 acres, total, 335,096 acres, of which 7875 acres produced two crops in the year. Manure, in the form of cow-dung, is only used for sugar-cane and other special crops. Irrigation is adopted in the case of *sift* rice, when water can be easily obtained from natural watercourses. It is not customary to allow land to lie fallow. Spare land abounds on all sides, and the present tenures are favourable to the cultivator. As throughout the rest of Assam, the State is the general landlord, but the cultivators, either by contract or status, possess a heritable and transferable right in all land cultivated permanently. Under native rule, the main source of revenue was a sort of capitation tax, raised at the rate of 4s on each plough, and 2s. on each hoe. The first land settlement commenced in 1859 assessed the revenue at 1s 6d in acre on *rist* or moist lands, on which *sift* rice is grown, and 9d in acre on all other lands. In 1844 these rates were raised respectively to 1s 10d and 1s 4d. At the present time, *basta* or homestead land pays 1s in acre *rust*, 3s 9d an acre, and *farinphati* on which *mur* and other crops are grown, 3s an acre. The average outturn of paddy from an acre of rice land is estimated to amount to about 14 cwt. with straw £2 13s, after husking, would give about 9 cwt. of rice fully worth £3, 6s.

Spare Land—There is a very large quantity of spare land in Sibsagar, and the present tenures are undoubtedly favourable to the cultivator. Waste lands for the extension of tea cultivation have been granted at very favourable rates. Those granted to the Assam Company were ten years rent free for twenty years, after the expiration of that term a rent of 1s 2d per acre for three years, and thereafter 2s 3d per acre for a further period of twenty-two years. All the other lands in the District are held by the cultivators on a lease direct from Government.

Landless Labouring Classes—There appears to be no tendency towards growth of a separate class of day labourers in the District mentioned; nor possessing land of their own. On the contrary, the class formerly to cultivate the lands of others seems to be decreasing in number, and the want of labour is seriously felt. Men who are not in the fields of others are termed *Kasuts*, and generally receive in return for their labour merely their food and clothing, with a small

allowance of money. The Assamese form a comparatively small part of the labourers employed in the tea-gardens, coolies being imported from Bengal for this purpose. Those natives of the District who do seek employment on the tea plantations generally have small farms of their own, on which they cultivate sufficient for their own household wants. The Cacharis furnish a considerable proportion of the labour on the tea-gardens. Women and children are not largely employed in the fields except at the sowing and harvesting seasons.

The rate of wages for ordinary unskilled labour is said to have doubled within the past twenty years, owing to the extension of tea cultivation; and the demand for skilled labour has risen in a still greater proportion. Indeed, labour of all kinds requires to be imported from Bengal. A common day-labourer is procurable with difficulty at 6d. a day. Male coolies on the tea-gardens are engaged at 10s. a month, and women at 8s.; but these rates can be almost doubled by taking taskwork. A second-rate blacksmith or carpenter receives £3 or £4 a month, and a bricklayer £1, 12s. The prices of food-grains have risen in like proportion. The following are the rates for 1872, which were somewhat above the average of recent years:—Common rice, 7s. 2d. per cwt.; pulses, from 9s. 9d. to 13s. per cwt.; oil, £2, 6s. per cwt.; salt, 10s. 8d. per cwt. In 1866, the year of the Orissa famine, the price of common rice rose to 14s. per cwt.

Sibságar District is not especially exposed to either of the calamities of flood or drought. The valley of the Brahmaputra is subject to annual inundation, owing to the old embankments having been allowed to fall into a bad state of repair; but it is not known that the general harvest of the District has ever been affected thereby. Partial drought is sometimes caused by deficiency of local rainfall. The season of 1857 is still remembered by the people as having resulted in a scarcity from this cause, which raised the price of common unhusked rice to 7s. 6d. per cwt. The people mainly depend for their food supply on the *sálli* rice crop; and if this were to fail, it would be difficult to supply its place either from the other crops or by importation.

Manufactures, etc.—The local industries are limited to the weaving of silk and cotton cloth, the making of domestic utensils from brass and bell metal, and a coarse description of pottery. The silk cloth is woven of various degrees of fineness, and is divided into four classes:—*mejánkuri*, the finest of all from the cocoons of a worm fed on the *adákuri* tree; *pát*, from the Chinese silkworm fed on the mulberry; *mugá*, the best known, from a worm fed on the *sím* tree; and *eriá*, which is very coarse, from a worm fed on the castor-oil plant. The finest raw silk has been sold for as much as £1, 16s. per pound; but the manufacture has greatly fallen off in recent years, owing to the

competition of cotton piece-goods imported from Europe. The farmers are almost entirely supported by a system of advances made by Márwari capitalists, at the rate of 6d per pound for brass, and 1s. per pound for bell metal.

Commerce and Trade—The trade of the District also is mainly confined to the Márwaris. The principal seats of commerce are Jorhat, Golághat, and Sibságar town. The two latter places are the resort of large numbers of Nágas during the cool season, who bring down raw cotton and vegetables to barter for salt fish, poultry and cattle. Cotton is commonly exchanged for half its weight of salt. There are no large annual fairs, similar to those held in Lower Assam. The principal exports from the District are tea, silk, mustard seed, cotton and jungle products, the imports are salt, oil, opium, piece-goods, and miscellaneous hardware.

Tea—The cultivation and manufacture of tea is largely carried on by European capital and under European supervision, and in this industry Sibságar ranks as the first District in Assam. It has not only surpassed in the whole of India by Cachar District in the sum of sales. The Assam Tea Company, which commenced its operations in Lakhimpur, had opened fifteen factories in Sibságar by 1852 with 2000 acres under cultivation, and an out turn of 267,000 lbs. Since that date, many private gardens were taken up by Europeans and natives, and in 1869, after the recovery from the panic caused by excessive speculation, there were 110 gardens in cultivation managed by 13 Europeans and 233 native assistants, and employing a monthly average of 15,377 imported and 790 local labourers. The statistics for 1874 show 2253 acres under cultivation, out of a total of 105,050 acres taken up, mostly in a simple, and an out turn of 4,976,419 lbs. of tea, being an increase of 554,898 lbs. on the previous year. By 1885, 54 the area under cultivation had increased to 40,532 acres, and the estimated out turn (devised never to be excessive) to 12½ million lbs. The average out turn per acre plant being 335 lbs. per acre.

The chief means of communication in the District are at present the Brahmaputra and Dhaneswari rivers, both navigable by steamers, the latter only during the rains. The roads are few, and the lines of old embankments constructed by the British under the kings. The Trunk Road maintained by the Public Works Department, runs through the entire length of the District, a distance of 142 miles, of which 305 miles were carried as carriage roads at river crossings.

Administration—The District administrative staff ordinarily consists of a Commissioner, two Assistant Commissioners, and 10 District Commissioners.

missioners, District Engineer with two Assistants, Civil Surgeon, and Superintendent of Police. In 1870-71, the total revenue of Sibságar District amounted to £93,853, of which the land-tax contributed £43,976, or 47 per cent., and *ábkári* or excise £42,090, or 46 per cent.; the expenditure was £35,194, or about two-fifths of the revenue, and the item of 'cost and conveyance of opium' absorbed £13,842, which is properly a debit against the revenue from excise. By 1882 the revenue had increased to £125,645, while the expenditure was £27,994. As throughout the rest of Assam, owing to the circumstance that an assessment is made annually with the cultivators, the land-tax is a very elastic source of revenue, having increased from £7013 in 1840 to £11,120 in 1850, and £48,758 in 1875. In 1883 there were 3 covenanted European officers stationed in the District, and 10 magisterial and 7 civil and revenue courts open. The regular and municipal police force consisted of 335 officers and men, maintained at a cost of £6188; showing 1 policeman to every 8.5 square miles of area, or to every 1106 of the population, and an average cost of £2, 3s. 4d. per square mile and 4d. per head of population. There is no village watch or rural police in the District. In the same year, the total number of persons convicted of any offence, great or small, was 458, or 1 to every 388 of the population. By far the greater number of the convictions were for petty offences. There is 1 jail at Sibságar town, and Sub-divisional lock-ups at Golághát and Jorhát. In 1883, the daily average number of prisoners was 91.7, of whom 2.2 were females; the labouring convicts numbered 83.7.

As is the case in Assam generally, education until recently had made but little progress among the people. In 1856, the number of schools in the District was only 12, attended by 794 pupils. The figures for 1860 show a positive decrease; but by 1870 the number of schools had risen to 29, and the pupils to 1084. The reforms of Sir G. Campbell, by which the benefit of the grant-in-aid rules was extended to the village schools or *páthsálás*, have produced scanty effect in this part of the country. In 1873, there were 39 schools under inspection, attended by 1440 pupils. By 1883, the number of State aided and inspected schools had increased to 159, attended on the 31st March 1884 by 5767 pupils. Indigenous vernacular unaided schools numbered 11, with 177 pupils. The Census Report of 1881 returned 2828 boys and 79 girls as under instruction, besides 6765 males and 171 females able to read and write but not under instruction. The chief educational establishments are the Government English school at Sibságar town, attended on 31st March 1884 by 224 pupils; the Jorhát high school, with 255 pupils; the Assam Company's school at Nazirá, with 137 pupils; and the normal school, with 13 pupils.

For administrative purposes, the District is divided into the 3 Sub-

divisions of Sibságar, Jorhát, and Golághát, and into 4 *talukás* or police circles, namely, Sibságar, Bartola, Jorhát, and Golághát, with outposts at Selung, Kamlabari, and Dhansirimukh. The number of *muráts* or revenue collections of villages, each under a *maazádar* or revenue official, is 65. The only municipality in the District is Sibságar town.

Medical Aspects—The climate of Sibságar, like that of the rest of the Assam valley, is comparatively mild and temperate. Scarcely a single month passes without some rain, but the year may be roughly divided into two seasons—the dry and cold season, extending from October to the end of April, and the hot and rainy season, occupying the remainder of the year. Dense fogs prevail in the early mornings from November to February. The prevailing direction of the wind is from the north-east, and it seldom rises above the strength of a moderate breeze. The mean annual temperature at Sibságar town for a period of eight years ending 1881 is returned at 73.3° F., ranging from a mean monthly maximum of 83.5° in June to a mean minimum of 58.6° in January. The average annual rainfall for a period of twenty-five years ending 1881 is returned at 94.67 inches thus distributed—January to May, 29.28 inches, June to September, 58.47 inches, October to December, 6.92 inches.

The prevailing diseases are fevers of a remittent and intermittent type, dysentery and diarrhoea, pulmonic affections, rheumatism, cutaneous disorders, leprosy, elephantiasis, and gout. Sporadic cases of cholera occur almost every year, and in 1869 this disease made its appearance in an epidemic form from February to June, and is reported to have carried off about 700 persons. Epidemic small pox breaks out about every fourth or fifth year being propagated by the practice of inoculation. In 1883, out of a total number of 8655 deaths registered for the rural tracts, 4241 were assigned to fevers, 1851 to bowel complaints, 1112 to cholera, and 225 to small pox. The total rural mortality was at the rate of 24.02 per thousand for the rural population, and in the three towns of Sibságar, Jorhát, and Golághát at the rate of 24 per thousand. Three charitable dispensaries in the above towns afforded relief to 7701 in-door and out-door patients in 1883–84. Since 1869, a terrible epizootic has been raging among the cattle and buffaloes of the District. It is identified with the rinderpest of Europe, and is supposed to have been introduced from Bengal. The mortality has been very great, about two thirds of the total number of cattle having been carried off. [For further information regarding Sibságar District, see *The Statistical Account of Assam*, by W. W. Hunter, vol. 1 pp. 227–287 (London, Trübner & Co., 1879), *A Descriptive Account of Assam*, by W. Robinson (1841), *Report on the Progress of Assam*, by A. J. Moat Mills (1854), the *Assam Gazette*.

Report for 1881; and the several annual Administration and Departmental Reports of the Assam Government.]

Sibságar.—Sub-division of Sibságar District, Assam, comprising the two police circles (*thánds*) of Sibságar and Bartola. Population (1881) 129,166, residing in 648 villages, and occupying 20,771 houses. Hindus number 118,691; Muhammadans, 6776; and 'others,' 3699.

Sibságar.—Chief town and civil head-quarters of Sibságar District, Assam; situated on the Dikhu river, 9 miles from the south bank of the Brahmaputra, in lat. $26^{\circ} 59' 10''$ N., and long. $94^{\circ} 38' 10''$ E. Population (1881) 5868, namely, Hindus, 4425; Muhammadans, 1351; and Christians, 92. Municipal income (1882-83), £660. Sibságar was one of the capitals of the Aham dynasty, shortly after their conversion to Hinduism. There still exists a magnificent tank, covering an area of 114 acres, with several old temples on its bank. These works are said to have been constructed by Rájá Sib Singh about the year 1722. There are but few houses in the native town which are not in a dilapidated condition. The *bázár*, which runs along both banks of the Dikhu river, has been greatly improved of late years, and contains many iron-roofed houses and several good shops. Large daily market. The public buildings, and the houses of the European residents, are built along the embankment of the tank. Sibságar is the seat of some river trade. The trading community consist chiefly of up-country Márwáris, who have their head-quarters in Sibságar town, and branch shops at many of the larger tea-gardens. The exports are cotton, rice, and, most important of all, tea; the imports, piece-goods and brass-ware. During the cold season, parties of Nágás from the hills bring down raw cotton and vegetables, to barter for salt, poultry, cattle, and dried fish. During the rainy season, a small steamer plies on the Dikhu river from Dikhumukh to Nazirá, calling at Sibságar.

Siddhápur.—Sub-division of North Kánara District, Bombay Presidency; situated in the south-east corner of the District. Area, 239 square miles. Population (1872) 34,183; (1881) 35,658, namely, males 20,446, and females 15,212, occupying 5527 houses in 95 villages. Hindus number 34,606; Muhammadans, 827; and 'others,' 225.

Siddhápur is covered with hills in the west, which in the south-west are thickly wooded, and in the north-west are bare. The valleys among the western hills are generally full of gardens. The centre of the Sub-division is a series of low hills, crossed by rich valleys and many perennial streams. In the east the hills are few, and the country stretches in wide fairly-wooded plains, in parts dotted with sugar-cane and rice-fields; the extreme south-east is hilly and thickly wooded, mostly with evergreen forests. The small streams are of great value for garden irrigation. In the west the soil is red, and in the valleys a rich alluvial mould. In the east the soil is red in places, but is not rich.

The chief products are—rice, sugar-cane, Bengal gram (*Cicer arctinum*), *Lulhi* (*Dolichos biflorus*), areca nuts, pepper, cardamoms, betel leaves, lemons, and oranges. Except in the west, where fever prevails during the later rains and the cold weather, the Sub-division is fairly healthy, and during the hot months the climate is agreeable. In 1883 the Sub-division contained 2 criminal courts, police circles (*thirsis*), 5, regular police, 47 men, village watch (*chaukidars*), 25. Land revenue, £9054.

The forests of the Sahyādris are the best in this region. They consist mostly of fine evergreens, admirable for their girth and height. The Siddhāpur forests have not been worked for profit, trees required locally and for public works are alone felled. The only exception is sandal wood, which, when fit, is cut by the Forest Department. The felling and carrying charges are about £4 per ton, and the sale price ranges from £48 to £54 per ton. Canes are general property, other products, such as myrobalans and soap nuts, are gathered by the Forest Department.

Siddhāpur—Village and head-quarters of Siddhāpur Sub-division, North Kānara District, Bombay Presidency, situated about 20 miles west of Honāwar. Population (1881) 1920. Dispensary and market.

Siddhaur—*Pargani* in Bara Banki District, Oudh, bounded on the north by Partābganj, on the east by Surajpur, on the south by Haidarganj and Subeha, and on the west by Satrkh *pirgaris*. Area, 141 square miles, of which 95 square miles are under cultivation. Government land revenue, £11,986. The *pirgaris* is divided into two sections, north and south. Population (1881) 82,699, namely, Hindus, 70,019, Muhammadans, 12,680, number of villages 224, houses, 12,177. The tract was originally in the hands of the Bhars, who were expelled by the Muhammadans at the time of the invasion of Sayyid Salār Masūd. Sayyids still form a great part of the population. The *pargana* was first formed in the time of Akbar.

Siddhaur—Town in Bara Banki District, Oudh, and head-quarters of Siddhaur *pargani*, situated 16 miles west of Bara Banki town, in lat. 26° 46' N., and long 81° 26' 10" E. Population (1881) 3520, namely, Hindus 1811, and Muhammadans 1709. Number of houses, 743. School, registration office, and post-office. The village contains an old Sivaite temple, and a Muhammadan mosque and tomb, in memory of one Kāzi Kutab, at which fairs are held on the occasion of the *Suara* and the 'Id and *Bakr 'Id* festivals.

Siddheshwara.—Peak on the eastern frontier of Coorg in the Western Ghats, 10 miles from Siddhāpur. Lat 12° 21' N., long 76° 3' E. This hill guards the pass by which the hill-tribes of Coorg entered from the east. On the summit stands a temple dedicated to Siva.

Siddheswar.—Village at the foot of the Saraspur range, which forms the boundary between the Districts of Cachar and Sylhet, Assam, on the south or left bank of the Bárak river. There is a celebrated Hindu temple here; and about the 18th March an annual fair is held, attended by 3000 persons. At the same time, a religious gathering for bathing takes place on the opposite bank of the river. The place is traditionally stated to have been the abode of the famous *Rishi* Kapilamuní, a fellow-worker of Patanjali, the founder of one of the six systems of Hindu philosophy.

Sidhaut.—*Táluk* or Sub-division of Cuddapah (Kadapá) District, Madras Presidency. Area, 610 square miles. Population (1881) 59,076, namely, males 30,015, and females 29,061, occupying 13,237 houses in 79 villages. Hindus number 55,202; Muhammadans, 3866; and Christians, 8. The soil is divided into red, sandy, and black. To these may be added saline and stony soils. The best land is in the Penner (Ponnaiyár) valley, where water is easily obtained by sinking wells. Little land is cultivated except in the valleys, owing to the hills by which the *táluk* is cut up. These hills are the Lankamallai, the Mallamakonda, and the Pálkonda ranges. In addition to the ordinary grains, the principal products are indigo and cotton. The north-west line of the Madras Railway traverses the southern portion of the *táluk*. In 1883 the *táluk* contained 3 criminal courts; police circles (*thánás*), 5; regular police, 49 men. Land revenue, £10,007.

Sidhaut (*Sidhāwat*).—Town and head-quarters of Sidhaut *táluk*, Cuddapah (Kadapá) District, Madras Presidency; situated on the Penner (Pennár or Ponnaiyár) river, in lat. 14° 27' 56" N., and long. 79° 0' 40" E. Population (1881) 3816, residing in 784 houses. The town formerly belonged to Chitwáil State, and later to the Patháns of Cuddapah; it was taken by Haidar Ali in 1779. In early British times it was the capital of the District, and is now the head-quarters of a Deputy Collector and Magistrate. Sidhaut is a place of some importance and of considerable sanctity. Owing to fancied resemblance in its position on the Penner, and to the relative position of some neighbouring villages and rivers, it is sometimes known as *Dakshina Kási*, or the 'Southern Benares.' It is notable for its melons.

Sidhpur.—Town in Baroda State, Gujarát, Bombay; situated on the Saraswati river, in lat. 23° 55' 30" N., long. 72° 26' E. Population (1872) 3534. Sidhpur is a very old town, and a place of Hindu pilgrimage.

Sidlaghata (*Sidlagatta*).—*Táluk* in Kolár District, Mysore State. Area, 163 square miles, of which 78 are cultivated. Population (1871) 91,849; (1881) 60,807, namely, males 29,798, and females 31,009.

Hindus number 58,885, Muhammadans, 1839, and Christians, 83. Land revenue (1883), exclusive of water rates, £11,810. Forms the upper valley of the Papaghni river. In 1883 the *tluk* contained 1 criminal court, police cycles (*thdnás*), 6; regular police, 54 men; village watch (*chaukidárs*), 591.

Sidlaghata—Town and municipality in Kolár District, Mysore State; situated in lat $13^{\circ} 23' 40''$ N, and long $77^{\circ} 54' 41''$ E, 30 miles north west of Kolár town. Head quarters of the Sidlaghata *tluk*. Population (1881) 5804, namely, Hindus, 5062, Muhammadans, 710, and Christians, 2. Said to have been founded in 1524 by Sivangi Gauda, a freebooter, whose family extended their power, and held the place for 87 years. Afterwards it passed successively through the hands of the Maráthas, the Mughals, and the *talégar* of Chik ballapur.

Sidli—One of the Dwárs or submontane tracts forming the Eastern Dwárs of Goalpárá District, Assam. Area, 361 square miles, reserved forest area, 68 square miles, including several valuable forests of *sal* timber, cultivated area, 41.77 square miles. Population (1881) 23,657. Sidli, like the rest of the Dwár tract, was ceded to the British at the close of the Bhután war of 1864-65. In 1870, a settlement for seven years was made with the Rájá at a land revenue of £1939, but this amount was never actually collected, and the estate was forthwith, at the Rájá's request, placed under the Court of Wards, under whose management it has continued ever since. In 1877, when the first settlement expired, a change was introduced in the system of management. The tract was divided into five *mauzas* or village circles, each placed under a *mauzáddár*, who collects the rents direct from the cultivators, to whom annual leases are given for the land they actually cultivate, as in the Assam valley. Twenty per cent of the net collections are made over to the Rájá Gaurináráyan Deb. In 1881-82 the net receipts amounted to £3531.

Sigúr Ghát, the corrected spelling for SEGUR (q r) — Mountain pass in the Nilgiri Hills, Madras Presidency.

Si Honda—Ancient and decayed town in Bándi District, North Western Provinces; situated near the right bank of the Ken river, a short distance to the right of the Bándi Káhnjár road, distant from Bándi town 11 miles south. Population (1881) 1277, chiefly Muhammadans. Local tradition declares that the town possessed great importance during the heroic period, but the remains belong chiefly or entirely to Muhammadan times. Capital of an important Division under the Mughals. In 1630 A.D. the rebel Khan Jahán fell at this place in battle against the imperial troops. Si Honda has been gradually declining since the days of Aurangzeb. It is said to have once contained 700 mosques and 900 wells, all the former have disappeared except 4, and most of the latter are now choked up.

Ruins of a large fort on a neighbouring hill ; a temple to Devī Angaleswari crowns another height near the town. Village school. Sihonda was formerly the head-quarters of a *tahsíl*, which after the Mutiny was removed to the neighbouring village of Girwán.

Sihor.—Town in Bhaunagar State, Káthiawár, Bombay Presidency ; situated in lat. $21^{\circ} 42'$ N., and long. $72^{\circ} 1' 45''$ E., about 13 miles west of Bhaunagar town, on the slope of the Sihor range of hills. Called in former times Singhpur or Singhpurí, 'the lion city.' A still more ancient name is Sáraswatpur. It formed the capital of the Bhaunagar branch of the Gohel Rájputs until Bhaunagar town was founded. The old site of the city is about half a mile to the south. Population (1881) 9528, namely, Hindus, 7511 ; Muhammadans, 1249 ; Jains, 764 ; and Pársís, 4. Sihor is famous for its brass and copper work, snuff, and mortar (*chunám*). The dyers are numerous and skilful, and dye women's scarves (*sádlás*) with various colours, but they are especially famous for their chocolate dye. Sihor is also a great place for oil-pressers. Two boys' and one girls' school. Station on the Bhaunagar-Gondal Railway.

Sihor.—Town in Bhopál State, Central India.—See SEHORE.

Sihorá.—Petty State in Rewá Kántha, Bombay Presidency. Area, $15\frac{1}{2}$ square miles. The State is watered by the Mahi, Mesri, and Goma rivers. Furrowed by ravines ; and much of the land near the river covered with brushwood. The cultivated parts are rich, yielding cotton, rice, millet, and gram. The chief is named Suda Parmar Nar Singhjí. Estimated revenue, £1400 ; of which £480 is paid as tribute to the Gáekwár of Baroda.

Sihorá.—Central *tahsíl* or Sub-division of Jabalpur (Jubbulpore) District, Central Provinces. Area, 1197 square miles ; number of towns and villages, 725 ; houses, 51,772. Population (1881) 192,722, namely, males 96,387, and females 96,335 ; average density of population, 161 persons per square mile. Of the total area of the *tahsíl*, 111 square miles are held revenue-free, leaving the assessed area at 1086 square miles. Of these, 526 square miles are returned as under cultivation, 265 square miles as cultivable but not under tillage, and 295 square miles as uncultivable waste. The total adult agricultural population (male and female) was returned in 1881 at 69,296, or 35·96 per cent. of the whole population of the *tahsíl*. Average area of cultivated and cultivable land available for each adult agriculturist, 7 acres. Total Government land revenue, including local rates and cesses levied on the land, £19,754, or 1s. $2\frac{1}{2}$ d. per cultivated acre. Total rental, including cesses, paid by the cultivator, £57,732, or 2s. $4\frac{3}{4}$ d. per cultivated acre. In 1883 the *tahsíl* contained 1 criminal and 2 civil courts, 3 police circles (*thánás*), and 4 outpost stations (*chaukís*) ; regular police, 79 men ; rural police (*chaukidárs*), 476.

Sihorá—Town and municipality in Jabalpur (Jubbulpore) District, Central Provinces, and head quarters of Sihorá *tahsil*, situated in lat. $23^{\circ} 29' N$, and long $80^{\circ} 9' E$, 27 miles from Jabalpur city, on the road to Mirzápur, 4 miles north of the Hiran river, and $2\frac{1}{2}$ miles from Sihorá station on the Jabalpur extension of the East Indian Railway. Population (1881) 5736, namely, Hindus, 4820, Muhammadans, 783, Jains, 119, and 'others,' 14. Municipal income (1882-83), £258, of which £237 was derived from taxation, average incidence of taxation, 9½d per head. Sihorá does a brisk trade in grain and country produce.

Sihorá (Tironi)—Town in Bhandárá District, Central Provinces, situated in lat $21^{\circ} 24' N$, and long $79^{\circ} 58' E$, 30 miles north-east of Bhandárá town. Population (1881) 2781, namely, Hindus, 2476, Muhammadans, 200, Kabirpanthis, 82, Jains, 2, non Hindu aborigines, 21. Cotton cloth of inferior quality is manufactured. A large tank, south of the town, always contains water. Government school and police outpost.

Siyakpur—Petty State in the Jhaláwár division of Káthiáwár, Bombay Presidency.—*See SEJAPUR*

Siyauli—Village in Kora *tahsil*, Fatehpur District, situated in lat $25^{\circ} 59' 28'' N$, long $80^{\circ} 30' 45'' E$. Population (1881) 2807, prevailing caste, Rájpút.

Siyáwal—*Taluk* of Lárkhna Sub division Shikarpur Sind Bombay Presidency. Area, 192 square miles. Population (1881) 18,362, namely, males 10,003 and females 8359 occupying 495 houses in 86 villages. Muhammadans number 16,666, Sikhs 904, and Hindus, 792. In 1882-83, the area assessed for land revenue was 65,875 acres. Area under actual cultivation, 31,616 acres. Revenue £6382.

Siju—Village in the Garo Hills District, Assam, on the Sameswari river, with a considerable population engaged in fishing. In the neighbourhood are coal mines, which were at one time worked by the Mahárájá of Sising. Several curious caverns are situated in the lime stone formation of the Sameswari river. The largest of these is in the neighbourhood of Siju village. The entrance is about 20 feet high, with a spacious dome-shaped chamber within. A small stream trickles through the cave, which has been explored for a whole day without the stream having been traced to its source. The cave is filled with swarms of bats.

Sikandarábád (Secunderábád)—North western *tahsil* of Buland shahr District, North Western Provinces, comprising the three *parganas* of Sikandarábád, Dádrí, and Dinkaur, stretching inland from the east bank of the Jumna (Jamuná), and watered by two branches of the Ganges Canal. The East Indian Railway traverses the *tahsil* from end to end, with two stations (at Sikandarábád and Dádrí). Area of

tahsíl, 524 square miles, of which 370 are cultivated. Population (1881) 236,066, namely, males 127,442, and females 108,624. Hindus number 196,932; Muhammadans, 38,612; Jains, 495; and 'others,' 27. Of the 415 towns and villages, 248 contain less than five hundred inhabitants; 124 between five hundred and a thousand; 41 between one thousand and five thousand; and 2 upwards of five thousand inhabitants. Land revenue (1872), £28,996; total Government revenue, £32,173; rental paid by cultivators, £76,132. In 1883 the *tahsíl* contained 2 criminal courts; number of police circles (*thánás*), 8; strength of regular police, 91 men; village watch or rural police (*chaukidárs*), 638.

Sikandarábád (*Secunderábád*).—Town and municipality in Bulandshahr District, North-Western Provinces, and head-quarters of Sikandarábád *tahsíl*. Situated on the Delhi branch of the Grand Trunk Road, in lat. 28° 27' 10" N., and long. 77° 44' 40" E., 10 miles east of Bulandshahr town; the station on the East Indian Railway is 4 miles south of the town. Population (1881) 16,479, namely, males 8702, and females 7777. Hindus, 10,094; Muhammadans, 6050; Jains, 320; and 'others,' 15. Municipal income (1883–84), £1105, of which £912 was derived from taxation; average incidence of taxation, 1s. 1½d. per head. Two good *bázárs*, the centre of the local trade in cotton, sugar, and grain. Founded by Sikandar Lodi in 1498; head-quarters of a *mahál* under Akbar; centre of the fief of Najíb-ud-daulá. Saádat Khán, Viceroy of Oudh, attacked and defeated the Maráthá force here in 1736. The Ját army of Bhartpur encamped at Sikandarábád in 1764, but fled across the Jumna (Jamuná) on the death of Suráj Mall and defeat of Jawáhir Singh. Station of Perron's brigade under the Maráthás. Occupied by Colonel James Skinner after the battle of Aligarh. During the Mutiny of 1857, the neighbouring Gújars, Rájputs, and Muhammadans attacked and plundered Sikandarábád; but Colonel Greathed's column relieved the town on September 27th, 1857. *Tahsili* and police station; charitable dispensary; vernacular school. Several small mosques and temples. Residence of Munshí Lakshman Sarúp, a large landholder and honorary magistrate. Manufacture of fine muslins for turbans, scarves, and native dresses.

Sikandarábád.—Town and cantonment in the Nizám's Dominions.—See SECUNDERABAD.

Sikandarpur.—*Parganá* in Unao *tahsíl*, Unao District, Oudh; bounded on the north by Pariar, on the east by Unao, on the south by Harha, and on the west by Cawnpur District in the North-Western Provinces. Area, 58½ square miles, or 37,453 acres. Population (1881) 31,416, namely, males 14,923, and females 16,493. Chief products, barley and sugar-cane. Government land revenue, £5807, or an

average assessment of 35 $\frac{1}{2}$ d per acre. The *farqan* comprises 51 villages, of which 48 are in the hands of Purihar Rājputs. The history of this clan is thus described in Mr Elliott's *Chronicles of Unao*, pp 58-60 —

'The present Purihars in Unao District inhabit the *farqan* of Sirosi, or, as it has recently become habitual to call it Sikandarpur. According to their own traditions, they came from a place called Jigini (which is not to be found on the map), or Srinagar, *re* Kashmir. From that high hill country they were driven—we know not by what cause—to inhabit the sandy plains of Mārwār. Expelled thence, they were broken into innumerable little principalities, which found no abiding place, and have undergone continual changes, till we meet with a small portion of the clan who settled, comparatively a short time ago, in a little corner of Oudh, and even here the name of the beautiful valley from which they came ten centuries ago is still common in the mouths of men.

'The story of the settling of the ancestors of the clan in Sirosi is thus told. About three hundred years ago in the time of Humāyūn, Emperor of Delhi, a Dikhit girl from Purenda was married to the son of the Purihar Rāja, who lived at Jigini across the Jumna. The bridegroom came with a large escort of his friends and brotherhood to celebrate the marriage and the party on their journey passed through Sirosi. As they sat down around a well (the site of which is still shown) they asked who were the lords of the fort which stood not far off. They were told that the fort was held by Dhobis (washermen) and other Sūdras who owned the neighbouring country. The procession then went on to Purenda, and returning conducted the bride to her home. Just before the *Jhili* festival a party headed by Bhagé Singh, returned, waited for the evening of that notorious feast and then, when the guards of the fort were heavy with wine and no danger was looked for, suddenly attacked and slaughtered them and made themselves masters of the fort and the surrounding country.

'Bhagé Singh had four sons, and they divided the eighty-four villages he had conquered at his death. Asis and Salhu the two eldest sons, took the largest portion of the estate—twenty villages falling to the former, and forty-two to the latter. The third son Marik, was a devotee, and refused to be troubled with worldly affairs. All he asked for was one village on the banks of the Ganges, where he might spend his life in worship, and wash away his sins three times a day in the holy stream. The youngest son Bhuledhān, was quite a boy at the time of his father's death, and took what share his brothers chose to give him, and they do not seem to have treated him badly.

'The law of primogeniture did not exist among the family. Every son, as he grew up and married, claimed his right to a separate share of his father's inheritance, and thus the ancestral estate continued to

dwindled as fresh slices were cut off it, till at last the whole family were a set of impoverished gentlemen, who kept up none of the dignity which had belonged to the first conquerors, Bhagé Singh and his sons. For six generations they stagnated thus, no important event marking their history till the time of Hira Singh. The family property in his time had grown very small, and he had five sons to divide it amongst; and, to add to his misfortunes, he was accused of some crime, thrown into prison at Faizábád, and loaded with chains. With the chains on his legs he escaped, arrived safely at Sarosi, and lay in hiding there. His pride being thus broken, he resolved to send his third son, Kalandar Singh, to take service in the Company's army. He rose to be Subahdár Major in the 49th Regiment of Native Infantry; and in this position, through his supposed influence with the Resident, became a very considerable man. He knew that as long as he was at hand, no *chakladár* or governor would venture to treat the Purihar *zamindárs* with injustice; but on his death they would be again at the mercy of the local authorities. He therefore collected all the members of the brotherhood who were descended from Asis, and persuaded them to mass their divided holdings nominally into one large estate, of which his nephew Ghuláb Singh should be the representative *tálukdár*; so that while in reality each small shareholder retained sole possession of his own share, they should present the appearance of a powerful and united *táluk*, making Ghuláb Singh their nominal head. Thus the *chakladárs* would be afraid to touch a man who seemed to hold so large an estate, though in reality he only enjoyed a small portion of it. The brotherhood consented to this; and from 1840 till the British annexation the estate was held in the name of Ghuláb Singh alone, and they had no further trouble from the oppressions of the *chakladárs*.

Sikandarpur.—Town in Bánsdih *tahsíl*, Ballia District, North-Western Provinces; situated in lat. 26° 02' 18" N., and long. 84° 05' 45" E., 2 miles from the right bank of the Gográ, 14 miles from Bánsdih, and 24 miles from Ballia town. Population (1881) 7027, namely, Hindus 4349, and Muhammadans 2678. The town was founded in the 15th century, during the reign of Sikandar Lodi of Jaunpur, after whom it was named. Its former importance is attested by the ruins of a large fort, and of houses extending over a large area. Its decadence is locally ascribed to the wholesale migration of the inhabitants to Patná, but nothing is known as to the cause or even the date of this abandonment. The local market is still famous for its *atar* of roses and other essences, of which there is a considerable export to Bengal. Police station, post-office, and middle-class school. For police and conservancy purposes, a small house-tax is raised, which realized £86 in 1881–82.

Sikandra.—Village in Agra *tahsíl*, Agra District, North-Western

Provinces, situated in lat $27^{\circ} 12' 59''$ N., and long $77^{\circ} 59' 34''$ E., 5 miles north west of Agra city, on the Muttra road. Population (1881) 1745. Founded by Sikandar Lodi of Jaunpur, who built a palace here in 1495, but now chiefly noticeable as containing the tomb of Akbar, commenced by that monarch, and finished by his son Jahangir in 1613. Fergusson describes the mausoleum as the most characteristic of Akbar's buildings. It is quite unlike any other tomb in India erected before or since, and the design is believed by Fergusson to be borrowed from a Hindu, or, more correctly, a Buddhist model. It is surrounded by an extensive garden of 150 acres, still kept in order, and is approached on each side by archways of red sandstone, the principal gateway being of magnificent proportions.

In the centre of this garden, on a raised platform, stands the tomb itself, of a pyramidal form. The lower terrace measures 320 feet each way, exclusive of the angle towers. It is 30 feet in height, and pierced by ten great arches on each face, and with a larger entrance, adorned with a mosaic of marble in the centre.

On this terrace stands another far more ornate, measuring 186 feet on each side, and 14 feet 9 inches in height. A third and fourth, of similar design, and respectively 15 feet 2 inches and 14 feet 6 inches high, stand on this, all these being of red sandstone. Within and above the last is a white marble enclosure, 157 feet each way, or externally just half the length of the lowest terrace, its outer wall entirely composed of marble trellis work of the most beautiful patterns. Inside, it is surrounded by a colonnade or cloister of the same material, in the centre of which, on a raised platform, is the tombstone of the founder, a splendid piece of the most beautiful Arabesque tracery. This, however, is not the true burial place, but the mortal remains of the great king repose under a far plainer tombstone in a vaulted chamber in the basement, 35 feet square, exactly under the simulated tomb that adorns the summit of the mausoleum.

The total height of the building now is a little more than 100 feet to the top of the angle pavilions, and a central dome, 30 or 40 feet higher, which is the proportion that the base gives, seems just what was wanted to make this tomb as beautiful in outline and in proportion as it is in detail. Had it been so completed, it certainly would have ranked next to the Taj among Indian mausolea.

An asylum was established at Sikandra in 1837-38, for the orphans whose parents had perished in the terrible famine of that year. The orphanage is still maintained by the Church Mission Society.

Sikandra.—Village in Phulpur taluk, Allahabad District, North Western Provinces, situated in lat $25^{\circ} 35' 15''$ N., long $82^{\circ} 1' 6''$ E. Population (1881) 2005. About 1 mile north west of the village is the tomb of Mahmud of Ghazni's famous general Sayyid Salim Mahmud.

Chundr, in lat $25^{\circ} 8' N$, and long $82^{\circ} 53' E$. Garrisoned in 1781 by the rebellious Rájá Chait Singh, but stormed by the British under Lieutenant Polhill.

Sikkim — Native State in the Eastern Himalaya Mountains, bounded on the north and north-east by Tibet, on the south-east by Bhután, on the south by the British District of Darjiling and on the west by Nepal. Situated between $27^{\circ} 9'$ and $27^{\circ} 58' N$ lat, and between $88^{\circ} 4'$ and $89^{\circ} E$ long, covering an area of about 1550 square miles with an estimated population of 7000. The capital is Tumlong where the Rájá resides during the winter and spring usually going to his estates at Chumli in Tibet in summer to avoid the heavy rains of Sikkim. The Tibetan name for Sikkim is *Dirzjüng* or *Den-jung*, and for the people *Deunjong Mars*; the Gurkha name for the people of Sikkim (which has been adopted by English writers) is *Tepchú* but they call themselves *Rong* according to Mr Clements Markham.

Physical Aspects — The whole of Sikkim is situated at a considerable elevation within the Himalayan mountain zone. Between Darjiling and Tumlong the mountains are generally lower than those of Darjiling itself. North of Tumlong the passes into Tibet have been recently visited by Mr Blinford and Mr Edgar, and found to be of great height. The most southerly of these passes (as described by Mr Markham in the introduction to his *Tibet* second edition 1879) is that of Jeylep-la, about 50 miles beyond Tumlong, 13,000 feet above sea level. The two next to the north are those of Guatuli and Yak-la, the latter 14,000 feet high. These Mr Markham says are rarely interrupted by snow for many days and form the easiest route into the Chumli valley of Tibet. Farther to the north is the Chola Pass 15,000 feet high, on the direct road from Tumlong to Chumli. The Yak-la Chola and Jeylep-la Passes cross the lofty spur of the Himalayas separating the Chumli and Lister valleys. Then comes the Lankra-la Pass 16,083 feet high the most snowy pass in Sikkim.

Sikkim is drained by the river Fista and its affluents the Lachen the Lachung the Buri Ranyit, the Moine, the Kangei and the Kangehi. The Am machu rises near Parjiong at the foot of the Chimali Peak (23,929 feet) and flows through the Chumli valley which is a strip of Tibetan territory separating Sikkim from Bhutan. In its lower part of its course, the Am machu passes into the British District of Jalpaiguri under the name of the LORSHU. The rivers of Sikkim generally run in very deep ravines between the mountains, and the ascent from the bank, for the first thousand feet, is almost perpendicular. All the rivers are very rapid. According to Dr Hooker's measurements the Fanyit, in a course of 23 miles, between the first above the Kanchi river and that at the cane bridge below Darjiling, falls 987 feet, while

the Tista falls 821 feet in about 10 miles, and flows in places at the rate of 12 miles an hour.

Near Mirugong are some copper mines, worked by Nepālese. Mr. Edgar (*Report on a Visit to Sikkim and the Tibetan Frontier*, 1872, p. 82) found that the Bhutia population are superstitiously averse to any search for metals below the earth's surface: and consequently little is known of the mineral resources of the country. Mr. Edgar, however, was of opinion that every mine is abandoned long before the vein of ore has been exhausted.

The valleys and slopes of this mountainous land are clothed with dense jungle, the vegetation in which varies, according to the elevation, from the cotton, banian, fig, and other tropical trees, which are found in the lower zones, to the fir, rhododendron, and dwarf bamboo, which appear above the level of 10,000 feet. The bamboo grows to enormous size, often attaining a diameter of 7 to 9 inches. The canes used in the construction of the well-known Himalayan cane-bridges grow principally in the bamboo jungles. The cane is found of the diameter of $1\frac{1}{2}$ to 2 inches: and a single piece was once traced through the jungle by Colonel Gawler (*Sikkim: Mountain and Jungle Warfare*, 1873, p. 13) for a distance of 80 yards without finding the end.

The wild animals are the same as those found in the jungles of DARJILING. Travellers in Sikkim suffer greatly from the *pitya*, and from the leeches which abound everywhere. Colonel Gawler writes of them: 'The jungles are infested with leeches, which penetrate loosely woven clothes, and deprive the wearer of a good deal of blood before he finds them out. They get far up the noses of horses, goats, etc., and cannot be removed without subjecting the poor animal to a couple of days without water, which, being afterwards offered to him, the leeches also want to drink, and may be seized. If the leeches are allowed to remain, the animals become reduced to a skeleton.'

History.—Sikkim was known to early European travellers, such as Horace della Penna and Samuel Van de Putte, under the name of *Dumastan* (see Markham's *Tibet*, p. 64): whilst Bogle called it *Dumtong*. Local traditions assert that the ancestors of the Rājās of Sikkim originally came from the neighbourhood of Lhasa in Tibet, and settled at Ganak. About the middle of the 16th century, the head of the family was named Pencho Namgay; and to him repaired three Tibetan monks, professors of the *Dagpa* (or 'Red Cap') sect of Buddhism, who were disgusted at the predominance of the *Gelupa* sect in Tibet. These Lamas, according to Mr. Edgar's *Report*, succeeded in converting the Lepchas of Sikkim to their own faith, and in making Pencho Namgay Rājā of the land. The *gratias* of two of these Lamas are now the heads, respectively, of the great monasteries of Pemiongchi and Tassiding. In 1788 the Gurkhas invaded

Sikkim, in the governorship of the Morang, and only retired, in 1789 on the Tibetan Government ceding to them a piece of territory at the head of the Kott Pass. But in 1792, on a second invasion of Tibetan territory by the Gurkhas, an immense Chinese army advanced to the support of the Tibetans, defeated the Gurkhas, and dictated terms to them almost at the gates of Khatmandu.

On the breaking out of the Nepál war in 1814, Major Latter, at the head of a British force, occupied the Morang, and formed an alliance with the Rájá of Sikkim, who gladly seized the opportunity of revenge on the Gurkhas. At the close of the war, in 1816, the Rájá was rewarded by a considerable accession of territory, which had been ceded to the British by Nepál, and by the usual guarantee of protection. In February 1835, the Rájá ceded Dárjiling to the British, and received a pension of £300 per annum in acknowledgment thereof.

There was, however, a standing cause of quarrel between the Rájá and the paramount power, due to the prevalence of slavery in Sikkim: the Rájá's subjects were inveterate kidnappers, and the Raja himself was most anxious to obtain from the British authorities the restoration of runaway slaves. With some absurd notion of enforcing the latter demand, two gentlemen (Dr Campbell, the Superintendent of Dárjiling, and Dr Hooker, the famous naturalist) were seized in 1849, whilst travelling in Sikkim, and detained for six weeks. As a punishment for this outrage, the Rájá's pension was stopped, and a piece of territory, including the lower course of the Litra and the Sikkim *tardi*, was annexed. The practice, however, of kidnapping Bengálí subjects of the British Crown was not discontinued: and two specially gross cases, in 1860, led to an order from Calcutta that the Sikkim territory, north of the Rammín river and west of the Bidri Range, should be occupied until restitution was made. Colonel Gawler, at the head of a British force, with the Hon Ashley Eden as envoy, advanced into Sikkim, and proceeded to Tumlong, when the Rájá was forced to make full restitution, and to sign another treaty, in March 1861, which secured the rights of free trade, of protection for travellers, and of road making.

Since the ratification of this treaty, relations with Sikkim have been uniformly friendly, and the country has been repeatedly explored by travellers, who have followed in the footsteps of Dr Hooker. In 1871, the Rájá of Sikkim, accompanied by his brother and minister, Chingied Ribu (a man of great abilities and predominating in power) and other members of his family, paid a visit to the Lieutenant Governor of Bengal at Dárjiling; and in the following winter, Mr Edgar, C.S.I., returned the Rájá's visit, as the representative of the Bengal Government, and obtained the materials for the valuable *Report* quoted above.

Population, &c.—The population of Sikkim was estimated by Dr Campbell at 7000, of whom about 3000 are Lepchas, 2000 Bhotias,

and 1000 Limbus. Eastward of the Tista, Colonel Gawler found some Tibetans. The Buddhist monks—each monastery under its own head Lama—form a numerous and influential section of the population. The chief villages are Tumlong (the capital) and Gantak; the chief monasteries are those of Labrong near Tumlong, Pemiongchi, and Tassiding. The head of the Labrong monastery is called the Kupgain Lama; and Mr. Edgar states that he is also the superior of Pemiongchi, and of nearly two-thirds of the monasteries of Sikkim. On the Tumlong Hill, besides the Rájá's palace, there are a number of other substantially built houses belonging to the various officials of the State. Each house is surrounded by some cultivated land, in which are generally a few clumps of bamboos or fruit-trees. During the rainy season, many of these houses are vacant, the officials being absent with the Rájá at Chumbi in Tibet. The house of the Kázi at Gantak is described as 'a very ornamental building of wattle and dab, raised on stout posts.'

Agriculture, Land Tenures, and Revenue System.—The chief cultivated crops in the valleys and in the clearings on the hills of Sikkim are wheat, buckwheat, barley, *marná*, maize, and a little rice; but no more grain is grown than suffices for local consumption. Cardamoms and oil-seeds are cultivated in the low valleys in the extreme west of the State. Plantains, oranges, and other fruits are grown in the gardens. Cattle and ponies are imported from Tibet. Between Pemiongchi and the little Ranjit, there is a curious tract of level country, described by Mr. Edgar as a great even ledge, several square miles in extent, with hills rising abruptly from it on three sides, whilst on the fourth side there is a precipitous fall of many hundred feet. The soil of this plain is exceedingly rich, as it catches all the silt of the upper hills; and every inch of it is highly cultivated, chiefly with cardamoms, oil-seeds, and other valuable crops.

Mr. Edgar gives the following interesting account of the revenue system and land tenures:—

'There are twelve Kázis in Sikkim, and several other officers with various names exercise jurisdiction over specific tracts of land. Each of these officers assesses the revenue payable by all the people settled on the lands within his jurisdiction, and, as far as I can make out, keeps the greater portion for himself, paying over to the Rájá a certain fixed contribution. At the same time, he has no proprietary right in the lands, though the Kázis have at least a kind of hereditary title to their office. The Kázis and other officers exercise limited civil and criminal jurisdiction within the lands the revenue of which they collect, all important cases being referred to the Rájá, and decided by Changzed (the minister) and the Diwáns, who are at present three in number. The cultivators have no title to the soil, and a man can settle down

and cultivate any land he may find unoccupied without any formality whatever, and when once he has occupied the land, no one but the Rájá can turn him out. But the Rájá can eject him at any time, and if he should cease to occupy the land, he would not retain any lien upon it. There is a kind of tenant right, however, under which cultivators are enabled to dispose of unexhausted improvements. Thus, as it was explained to me, a man who has terraced a piece of hillside could not sell the land, but is allowed to sell the right of using the terraces. This custom is acknowledged not to be absolutely a right, but more of the nature of an indulgence on the part of the Rájá, by whom it was allowed to grow up for the sake of convenience.

The land is not assessed, and pays no revenue. The assessment is on the revenue payer personally. I think that in theory he is allowed the use of the Rájá's land in order that he may live and be able to render to the Rájá the services which he is bound to perform as the Rájá's live chattel, and possibly if the system were carried to theoretical perfection, he would be bound to give over to the Rájá all the net produce of the land—that is, all the fruit of his labour beyond what might be actually necessary to support himself and his family. In practice, the subject is only bound to give a certain portion of his labour, or of the fruit of his labour, to the State, and when he does not give actual service, the amount of his property is roughly assessed, and his contribution to the State fixed accordingly. But such assessment is made without the slightest reference to the amount of land occupied by the subject. The value of his wives and children, slaves, cattle, furniture, &c., are all taken into account, but not the extent of his fields.

The Lamás are not bound to labour for the Rájá and they pay no dues of any kind no matter how much land may be cultivated by themselves or their bondsmen.

Commerce, &c.—There are several trade routes through Sikkim, from the British District of Darjiling into Tibet, but owing partly to the natural difficulties of the country, and partly to the jealousy of the Tibetans, these are not much used. At Kangpo-tan, on the Teesta, and at other points, there are good cane bridges and in some places there are raft-ferries, but all roads are mere hill bridle paths, and communication is exceedingly imperfect and difficult. The *Régent* of the British envoy in 1861 stated that a considerable trade between Bengal and Tibet would be the almost certain result of improved communications through Sikkim, the Tibetans exporting gold, silver, ponies, musk, borax, wool, turquoise, silk, and *marble* or *malak*, in exchange for broadcloth, bleached goods, tobacco, and pearls. In addition to this transit trade, Sikkim supplies ponies, silver, and other produce to the British territory of Darjiling, and imports from the British manufactures, tobacco, &c. A regular trade in the

been established at Ranjít. In 1876-77, the total exports from Sikkim into Dárjiling were valued at £80,265, of which timber alone represented £70,870; the total imports were valued at £14,164, chiefly indigo (£6600), cattle (£2322), metals (£1773), piece-goods (£1357), tobacco (£967). In 1883-84, the total exports from Sikkim into Bengal had fallen to £2215; and the total imports from Bengal into Sikkim to £1127.

Climate and Medical Aspects.—The ranges between Dárjiling and Tumlong are lower than Dárjiling itself, and generally less cool; whilst the deep narrow valleys of most of the rivers have a hot and stifling climate, notorious for its malaria and jungle-fever. The rainfall, like that of Dárjiling, is very heavy. There is usually a little dulness, and perhaps rain, late in December and early in January; after which the weather remains bright and clear until May, when storms, growing more and more frequent, usher in the rainy season, which lasts till October.

Sikrol (*Sírol*).—Western suburb of BENARES CITY, containing the military cantonments, civil station, and European quarter. Lat. $25^{\circ} 20' 20''$ N., long. $83^{\circ} 1' 20''$ E. The little river Barná flows through the suburb, dividing it into two parts. Church, official buildings, numerous well-built bungalows, standing amid gardens and groves.

Silái.—River of Bengal; rises in the Fiscal Division of Ládthurká, Mánbhúm District, and flows in a south-easterly direction into the District of Midnapur. After a tortuous course it falls into the RUPNARAYAN, of which it forms the chief tributary, near the point where that river touches the eastern boundary of Midnapur. The Silái is subject to destructive floods; it is only navigable throughout the year for a short distance in its lower reaches, which are within tidal influence. It is fed by two small streams from Bánkura District, on the north—the Purandhar-nadí and Gopa-nadí. The other and principal feeder of the Silái is the Buri-nadí, which takes its rise in the north-west of Midnapur District, and flows east into the Silái near Nárájol.

Silána.—Petty State in the Soráth *prant* or division of Káthiáwár, Bombay Presidency; consisting of 1 village, with 2 shareholders or tribute-payers. Area, 4 square miles. Population (1881) 691. Estimated revenue, £300; of which £10 is paid as tribute to the Gáekwár of Baroda.

Silánáth.—Village in Darbhāngah District, Bengal; situated on the Kamlá river, in lat. $26^{\circ} 34' 30''$ N., and long. $86^{\circ} 9' 45''$ E. Population (1872) 2520. Not returned separately in the Census Report of 1881. Noted for its fairs held in November, and again in February or March, for about 15 days, and attended by 15,000 people, chiefly from the *tarái*. Grain forms the principal article of commerce; from the Nepal Hills are brought iron-ore, hatchets, *tezpát* or bay-leaves, and musk. The fair doubtless had its origin in pilgrims coming to visit a temple of

Mahadeo, which stood here, but the Kami has changed its course, and washed the temple away, and now no traces of it remain.

Silang—Mountain range and town in the Khasi and Jaintia Hills District, Assam.—See **SILHONG**.

Silchar—Chief town, municipality, and administrative head-quarters of the District of Cachar, Assam, situated in lat. $24^{\circ} 49' 40''$ N., and long. $92^{\circ} 50' 48''$ E., on the south bank of the Barak river. Population (1881) 6567, namely, Hindus, 4807, Muhammadans, 1647, Christians, 75, and 'others,' 38. Municipal income (1881-82) £1168, or an average of 3s. 4½d. per head of the population (6869) within municipal limits. Silchar is also a military cantonment. In 1885, the 42nd Bengal Native Infantry was stationed here, together with 2 guns of mountain artillery. The town is also the head-quarters of a company of rifle volunteers. A handsome new church has been erected since the earthquake of 1869. The town is built on a neck of land formed by a bend in the river. The surface is swampy in some parts, but in others it rises into low sandy hillocks, locally called *tildr*. In recent years, much attention has been paid to sanitary improvements. A large trading fair or *melâ* is held annually in January, lasting for about seven days. The average attendance is estimated at 20,000 persons, the articles sold include cotton goods and ponies from Manipur. On 10th January 1869, a severe shock of earthquake was felt at Silchar. The church and public buildings fell down and the greater part of the *Ad-ir* was laid in ruins. The surface was rent into deep fissures, and in some parts sank down as much as from 15 to 30 feet. Another severe shock occurred on the 13th October 1882, causing much damage to masonry buildings.

Silhetî—*Zamindârî* or petty chiefship in Drug *tahsil* Raipur District, Central Provinces, 60 miles north-west of Raipur town, comprising 24 villages, formerly part of Gandu chiefship. Area, 83 square miles. Population (1881) 4475 occupying 1369 houses, average density of population, 54 persons per square mile. The chief is a Gond. The village of Silhetî lies in lat. $21^{\circ} 47'$ N., and long. $81^{\circ} 9'$ E.

Sillâna—Native State in Central India.—See **SAILANA**.

Siler (*Selere*)—River in Vizagapatnam District, Madras Presidency. Flows east, then north to Umrâ, where it turns west and finally south-west, and joins the Saveri at Moat, about 20 miles north-east of the junction of the latter stream with the Godavari. The Siler has a very tortuous course through mountainous country, total length, about 150 miles.

Silondî—Town in Sihori *tahsil*, Jabalpur (Jubbulpore) District, Central Provinces. Population (1881) 2022, namely, Hindus, 1593, Khatris, 42, Jains, 31, Muhammadans, 49, and others, 10. 2400 acres, 10

Silpāta.—Village in Chatgiri Dair, Darrang District, Assam, at which a large fair is held annually during the *Bor Bihu* festival, chiefly attended by the Cachari population.

Simgá.—Northern *tahsil* or Sub-division of Raipur District, Central Provinces. Area, 1401 square miles; number of villages, 751; houses, 95,743. Total population (1881) 275,626, namely, males 136,171, and females 139,455; average density of population, 196·7 persons per square mile. Of the total area of the *tahsil*, 11 square miles are held revenue free, leaving the assessed area at 1390 square miles. Of these, 770 square miles are returned as under cultivation, 541 square miles as cultivable but not under tillage, and 79 square miles as uncultivable waste. The adult agricultural population (male and female) was returned in 1881 at 127,251, or 46·17 per cent. of the total population of the *tahsil*. Average area of cultivated and cultivable land available for each adult agriculturist, 7 acres. Total Government land revenue, including local rates and cesses levied on land, £15,027, or an average of 7½d. per cultivated acre. Total rental, including cesses, paid by the cultivators, £20,813, or an average of 1s. 2½d. per cultivated acre. In 1881, Simgá *tahsil* contained 1 criminal and 2 civil courts, with a regular police force numbering 112 men.

Simgá.—Town in Raipur District, Central Provinces, on the Seo river, and head-quarters of Simgá *tahsil*, 28 miles north of Raipur town, on the road to Bilaspur. Population (1881) 2277, namely, Hindus, 1633; Muhammadans, 326; Kabirpanthis, 131; Satnamis, 88; Jains, 1; and non-Hindu aborigines, 98. Besides the usual Sub-divisional courts and offices, Simgá has a town school, girls' school, police office, and post-office.

Simháchalam.—Temple in Vizagapatam District, Madras Presidency.
—*See* SINGHACHALAM.

Simla.—British District in the Lieutenant-Governorship of the Punjab, consisting of several detached plots of territory; situated among the hills of the lower Himálayan system. These plots are surrounded on all sides by the territories of independent chiefs under the control of the Deputy Commissioner of Simla, who is *ex officio* Superintendent of the Hill States. Area of British territory, 81 square miles. Population (1881) 42,945 souls. The administrative head-quarters are at SIMLA, the summer capital of the Government of India, in lat. 31° 6' N., and long. 77° 11' E.

Physical Aspects.—The mountains of Simla District and the surrounding Native States compose the southern outliers of the great central chain of the Western Himálayas. They descend in a gradual series from the main chain itself in Bashahr State to the general level of the Punjab plain in Ambála (Umballa) District, thus forming a transverse south-westerly spur between the great basins of the Ganges and the Indus, here

respectively represented by their tributaries the Jumna (Jumuná) and the Sutlej. A few miles north east of Simla, the spur divides into two main ridges, one of which curves round the Sutlej valley toward the north west, while the other, crowned by the sanitarium of Simla, trends south eastward to a point a few miles north of Subúthu, where it merges at right angles in the mountains of the Outer or Sub-Himálaya system which run parallel to the principal range. South and east of Simla the hills between the Sutlej and the Lohs centre in the great peak of Choor 11,982 feet above the sea. Throughout all the hills, forests of *deodar* abound while rhododendrons clothe the slopes up to the limit of perpetual snow. The scenery in the immediate neighbourhood of Simla itself presents a series of magnificent views embracing on the south the Ambala plains with the Subúthu and Khasuli Hills in the foreground, and the massive block of the Choor a little to the left while just below the spectator's feet a series of huge ravines lead down into the deep valleys which score the mountain sides. Northwards the eye wanders over a network of confused chains rising range above range, and crowned in the distance by a crescent of snowy peaks, standing out in bold relief against the clear background of the sky. The principal torrents of the surrounding tracts are the Sutlej Pabbar the Giri Ganges, the Gambhar, and the Sarva.

Inclusive of military cantonments Simla District comprises an area of less than 81 square miles distributed over five detached *stikas*. The first of these *stikas* is Kálka a small tract about one square mile in area, acquired by gift from the Maharaja of Patiala as a site for a *hazár* and depot at the spot where the road to Simla first enters the hills. The second *stika* is Bharuili with which are included the isolated villages of Kalá and Kalag and a small detached group of four villages near Khasuli, known as the Shiwa Haka. The area of the whole is about 15 000 acres, which have remained in our possession since the close of the Gurkha war, when the old ruling family was found to be extinct. The main Bharuili territory consists of a narrow valley in the hollow of the hills stretching from Subúthu to Khasuli on the Simla road. The third *stika* is Simla, a small tract of less than 4000 acres, chiefly occupied by the hill station of Simla the celebrated area being less than 200 acres. The whole *stika* was acquired in 1830 from the Raja and Keshri in exchange for other land. The fourth is Keshri a small territory of about 22 000 acres lying 20 miles east of Simla and the sources of the Giri. It was acquired in 1828 by the Maharaja from the Ráná Bhagwán Singh. The fifth and last *stika* is Kotehli otherwise known as Kotgarh. It is another small tract of less than 11 000 acres lying along a spur of the Hathu mountains on the bank of the Sutlej 22 miles north-east from Simla on the main line. It was acquired by the Maharaja from the Kothli Rajpoots, was then acquired by the

Rájá of Kúlu, from whom it was forcibly taken by Bashahr, in whose possession it remained for forty years, when it was seized by the Gúrkhas. On our invitation it was again occupied by Kúlu troops during the Gúrkha war of 1815, and was eventually retained by us when these hostilities were brought to a close.

History.—The acquisition of the patches of territory composing Simla District dates from the period of the Gúrkha war in 1815–16. At a very early time the Hill States, together with the outer portion of Kángra District, probably formed part of the Katoch kingdom of JALANDHAR (Jullundur); and, after the disruption of that principality, they continued to be governed by petty Rájás till the beginning of the present century. After the encroachments of the Gúrkhas led to the British invasion of their dominions in 1815, our troops remained in possession of the whole block of hill country between the Gogra and the Sutlej. Kumáun and the Dehrá Dún became a portion of British territory; a few separate localities were retained as military posts, and a portion of Keunthál State was sold to the Rájá of Patiála. With these exceptions, however, the tract conquered in 1815 was restored to the Hill Rájás, from whom it had been wrested by the Gúrkhas. Garhwál State became attached to the Lieutenant-Governorship of the North-Western Provinces; but the remaining principalities rank among the dependencies of the Punjab, and are known collectively as the Simla Hill States. From one or other of these, the plots now composing the little District of Simla have been gradually acquired. Part of the hill over which the Simla sanatorium now spreads was retained by Government in 1816, and an additional strip of land was obtained from Keunthál in 1830. The spur known as Jutogh, $3\frac{1}{2}$ miles from the station, was acquired by exchange from Patiála in 1843, as the equivalent of two villages in Barauli. Kotkhái Kotgarh, again, fell into our hands through the abdication of its Ráná, who refused to accept charge of the petty State. The Kasauli Hill originally belonged to Bija, but was relinquished in consideration of a small annual payment. Subáthu Hill was retained from the beginning as a military fort; and the other fragments of the District have been added at various dates.

Population.—The results of the Census of 1881 can hardly be regarded as fairly representing the actual state of the District, for with the exception of Barauli and Kotkhái, the British territory possesses no rural population of its own. Nor do the figures show the normal number of inhabitants on the plots which compose the District, as the Census was taken in February, one of the months when Simla and Kasauli are almost empty. Nevertheless, for the sake of uniformity, the statistics may be appended for what they are worth. The enumeration extended over an area of 81 square miles, and disclosed a total population of 42,945 persons, inhabiting 263 towns and villages, and 6559

houses. Classified according to sex, there were—males 27,503, females, 15,352; proportion of males, 64·2 per cent. This great discrepancy between the sexes is due to the number of male immigrants connected with the sanatoria of Simla and Kasauli, who do not bring their families with them. According to religion—Hindus numbered 32,428, or 75·5 per cent, Muhammadans, 6935 or 16·1 per cent, Sikhs, 202, or 0·5 per cent, Jains, 23, Buddhists, 4, and Christians, 3353, or 7·8 per cent. The Bráhmans numbered 2567. Among these the Sásani grade ranks highest in popular estimation, and supplies the Rájyas and Ránis of the Hill States with priests. Others of the Bráhmans engage in agriculture. The Rájputs numbered 1849, of whom 359 were Muhammadans, they resemble their hill brethren in Kángra. The Kanets (9090 in number) form the characteristic tribe of Simla, and are popularly supposed to be Rájputs who have lost caste by buying wives and permitting the remarriage of widows. Kohis numbered 3795, and Chamérs 3384. The Muhammadans, classified by race as apart from religion, included—Shaikhs, 3676, Patháns, 1420, Síváids, 315 and Kashmírs, 215. The Christian population included—Europeans, 2898; Eurasians, 245, and natives, 210. All classes of the hill population are simple minded, orderly people, truthful in character and submissive to authority, so that they scarcely require to be ruled.

The chief towns (or stations) are SIMLA (13 258 in February 1881), KASAU LI (2807), DARSHAI (3642) SLEATHU (2329) SOHAN and KATKA. Of the 263 villages scattered over the Simla territory 242 contain less than two hundred inhabitants and 15 between two hundred and one thousand, while only 6 contain upwards of one thousand inhabitants.

Agriculture, etc.—The time of sowing and harvesting in the hill country depends very greatly upon the elevation. Cultivation is carried on among all the lower valleys, but even more rudely than in the similar glens of Kángra District. The fields are artificial terraces built up against the mountain sides, and sown with maize, pulses or millet for the autumn, and with wheat for the spring harvest. Potatoes, hemp, turmeric, ginger, and potatoes form the principal staples raised for exportation to the plains. The last named crop, introduced under British rule, has rapidly grown in favour, and now occupies many fresh clearings on the hill sides in the neighbourhood of Simla. Land is measured, not by superficial extent, but by the quantity of seed which is required to sow it. Most of the cultivators till their own little plots, and rent is practically unknown. Throughout the hill country the employment of hired labour for agricultural purposes is almost unknown, the people combining together to aid one another in special undertakings, and expecting to receive similar help in return whenever they may require it. Wages for artisans and day labourers in

1883-84 ranged from 9d. to 1s. 6d. for skilled hands, and from 6d. to 9d. for coolies. Prices of food-grains ruled as follows on the 1st of January 1884:—Wheat, 15 *seers* per rupee, or 7s. 6d. per cwt.; barley, 19 *seers* per rupee, or 5s. 11d. per cwt.; Indian corn, 14½ *seers* per rupee, or 7s. 9d. per cwt.; best rice, 4½ *seers* per rupee, or 25s. 5d. per cwt.

Commerce, Communications, etc.—The trade of the District centres mainly in the *bázárs* of SIMLA, which forms a considerable entrepôt for the produce of the hill tracts. RAMPUR, on the Sutlej, has also some importance as a depôt for the shawl-wool (*pashm*) brought in by the mountaineers of Spiti and of Chinese Tartary. Part of it is worked up on the spot into coarse shawls, of the kind now made also at Ludhiána and Amritsar (Umritsur), and known as Rámpur *chadars*; but the greater part is bought up by merchants for exportation to British India. The hill paths are so steep that most of the wool is brought down on the backs of the sheep, which are then sheared, and laden with grain for the return journey. The Rámpur fair, on the 10th and 11th of November, attracts a large number of hillmen and of traders from the plains. The main roads of the Simla Hills are those which lead from Kálka to Simla, and from Simla towards Rámpur and Chíni on the Tibetan border. Only small portions of these, however, lie actually within British territory. The old road from Kálka to Simla, *viâ* Kasauli and Subáthu, is practicable for horses, mules, ponies, or cattle, but not for wheeled conveyances. The distance by this route is 41 miles, and the journey can be performed by relays of ponies in eight hours. The new cart-road takes a more circuitous route, *viâ* Dagshai and Solan. The distance amounts to 58 miles, and two-wheeled carts traverse the whole distance in about nine or ten hours. All the heavy traffic between Simla and the plains passes by this route. Staging bungalows have been built on all the roads at frequent intervals. A line of telegraph follows the old road, with stations at Kálka, Kasauli, and Simla.

Administration.—The Simla Hill States are under the superintendence of the Deputy Commissioner of Simla, subordinate to the Commissioner at Ambála (Umballa). The total imperial revenue of the British District amounted in 1883-84 to £15,259, of which sum the land-tax contributed £1360. The other items of importance were stamps and excise. The number of civil and revenue judges in the same year was 8, and the number of magistrates 7. The regular and municipal police force numbered 280 officers and men, being at the rate of 1 man to every 153 of the population. The Simla jail contained in 1883-84 a total of 172 prisoners, with a daily average of 20. Including the Lawrence Military Asylum for soldiers' children, there were 1263 children receiving education in 1883-84, in 29 Government aided or inspected schools; besides 10 indigenous village schools, with about 120 pupils. The educational establishments include Bishop

Cottons School, a District School, Roman Catholic Clerical Orphanage, Punjab Girls' School, Mayo Industrial Girls' School, and American Presbyterian Mission at Subathu. The Lawrence Military Asylum established in 1857, stands upon the crest of a hill facing Karsauli from which it is distant by road 3 miles. The only municipality is that of Simla.

Medical Aspects—The climate of the Simla Hills is admirably adapted to the European constitution, and the District has therefore been selected as the site of numerous sanitarium and cantonments. The average mean temperature at Simla for each month of the year over a period of ten years ending in 1881 is as follows—January, 40.2° F., February, 41.8°, March 49.2°, April 58.7° May, 63.5°, June, 67.6°, July, 64.3°, August 63.1°, September, 61.3° October 55.6°, November, 48.7°, December 44.7° F. Mean annual average, 54.9°. The average annual rainfall amounts to 70.42 inches according to a calculation made in 1881 upon observations extending over twenty years, distributed as follows—January to May 15.96 inches, June to September, 52.27 inches, October to December 2.19 inches.

Cholera visited Simla Karsauli Subathu and Dagshui in 1857, 1867, 1872, and 1875, though one or other station escaped in each visitation. In 1857, the death rate among Europeans from cholera was 3.5 per thousand, and in 1867, 4.2 per thousand. The registered death rate of Simla in 1883 was 18 per thousand. Gout, leprosy and syphilis are reported to be prevailing endemic diseases, and syphilis is said to be very common amongst the hill people. The only disease usually contracted by Europeans is that known as hill diarrhoea, a very trouble some form of the ailment. Government maintains three charitable dispensaries—at Simla Karsauli and Dagshui. In 1883, they gave relief to a total number of 16,185 persons, of whom 655 were in-patients. In 1885 a large first class hospital, with special wards for European patients, was opened in Simla. [For further information regarding Simla, see the *Report on the Industrial and Social Conditions of Simla District*, by Colonel F. G. Wace (Calcutta 1884) and the *Parliamentary Report for 1881*, and the several annual Administration and Departmental Reports of the Punjab Government.]

Simla.—*Tahsil* of Simla District Punjab, consisting of the two detached *parganahs* of Simla and Birauli. Area 4 square miles. Population (1881) 33,095, namely, males 22,739 and females 10,356. Hindus number 22,753. Muhammadans, 6804. Sikhs 209. 'Others,' nearly all Christians 3341. Revenue of the *Tahsil*, £100. The administrative staff including the *Deputy Commissioners* of *Simla* and *Birauli*, a Deputy Commissioner, 2 Assistant or Extra Assistant Commissioners, Judge of Small Cause Court, *Magistrate*, and one *Inspector of Police*. These officers preside over 5 civil and 6 criminal courts, 12 police circles (*thanas*) 6, *Police Stations* and *Police Circles*, 124 *Police*.

Simla.--Town, municipality, and administrative head-quarters of Simla District, Punjab; chief sanitarium and summer capital of British India. Situated on a transverse spur of the Central Himālayan system, in lat. $31^{\circ} 6' N.$, and long. $77^{\circ} 11' E.$ Mean elevation above sea-level, 7084 feet. Distant from Ambāla (Umballa) 78 miles; from Kālka, at the foot of the hills, by cart-road, 58 miles. Population in January 1868, 7656; in July 1869, at the beginning of the season, 14,848, of whom 1434 were Europeans and 13,414 natives. In February 1881, at the time when the population of the station was at its lowest, the Census returned the population at 13,258, namely, males 9881, and females 3377. Hindus numbered 8377; Muhammadans, 3153; Sikhs, 164; Jains, 14; and 'others,' nearly all Christians, 1550. In August and September, when the season is at its height, the population considerably exceeds this number. The municipal income, which in 1875-76 was only £5281, had by 1884-85 increased to £20,391.

A tract of land, including part of the hill now crowned by the station, was retained by the British Government at the close of the Gūrkhā war in 1815-16. Lieutenant Ross, Assistant Political Agent for the Hill States, erected the first residence, a thatched wooden cottage, in 1819. Three years afterwards, his successor, Lieutenant Kennedy, built a permanent house. Officers from Ambāla and neighbouring stations quickly followed the example, and in 1826 the new settlement had acquired a name. A year later, Lord Amherst, the Governor-General, after completing his progress through the North-West, on the conclusion of the successful Bhartpur campaign, spent the summer at Simla. From that date, the sanitarium rose rapidly into favour with the European population of Northern India. Year after year, irregularly at first, but as a matter of course after a few seasons, the seat of Government was transferred for a few weeks in every summer from the heat of Calcutta to the cool climate of the Himalayas. Successive Governors-General resorted with increasing regularity to Simla during the hot weather. Situated in the recently annexed Punjab, it formed an advantageous spot for receiving the great chiefs of Northern and Western India, numbers of whom annually come to Simla to pay their respects to the British Suzerain. It also presented greater conveniences as a starting-point for the Governor-General's cold-weather tour than Calcutta, which is situated in the extreme south-east corner of Bengal. At first only a small staff of officials accompanied the Governor-General to Simla; but since the administration of Sir John Lawrence (1864), Simla has practically been the summer capital of the Government of India, with its secretariats and head-quarters establishments, unless during exceptional seasons of famine on the plains, as in 1874.

Under these circumstances, the station grew with extraordinary rapidity. From 30 houses in 1830, it increased to upwards of 100 in

1841, and 290 in 1866. In February 1881, the number of occupied houses was 1141. At present, the bungalows extend over the whole length of a considerable ridge, which runs east and west in a crescent shape, with its concave side pointing southward. The extreme ends of the station lie at a distance of 6 miles from one another. Eastward, the ridge culminates in the peak of Jako, over 8000 feet in height, and nearly 1000 feet above the average elevation of the station. Woods of deodar, oak, and rhododendron clothe its sides, while a tolerably level road, 5 miles long, runs round its base. Another grassy height, known as Prospect Hill, of inferior elevation to Jako, and devoid of timber, closes the western extremity of the crescent. The houses cluster thickest upon the southern slopes of Jako, and of two other hills lying near the western end. The Viceregal Lodge, formerly named Peterhof, stands upon one of the latter, while the other is crowned by a large building erected for an observatory, but now used as an ordinary residence. A new and more commodious Viceregal residence is now (1886) in course of erection on the Observatory hill, a little to the west of the present Government House. The church stands at the western base of Jako, below which, on the south side of the hill, the native *hazir* cuts off one end of the station from the other. The eastern portion bears the name of Choti Simla, while the most western extremity is known as Boileauganj. A beautiful northern spur running at right angles to the main ridge, and still clothed with oak and old rhododendron trees, has acquired the complimentary designation of *Ilisium*. Three and a half miles from the western end, a battery of artillery occupies the detached hill of Jutogh. The exquisite scenery of the neighbourhood has been described in the article on SIMLA DISTRICT.

The public institutions include the Bishop Cotton School, the Punjab Girls School, the Mayo Industrial Girls School, a Roman Catholic convent, a hospital, a dispensary, and a handsome Town Hall now (1886) approaching completion. The Government buildings comprise a District court house and treasury, *tahsil* and police offices, post office, telegraph station, etc. Until recently, the various public offices were located in ordinary private houses, in many cases widely distant from each other. Since 1883 the offices of the Imperial Government have been concentrated in blocks of handsome buildings, centrally situated, and constructed at a cost of upwards of half a million sterling.

The commerce of the town consists mainly in the supply of necessaries to the summer visitors and their dependants, but a brisk export trade exists in opium, *chutai* (an intoxicating preparation of hemp), fruits, nuts and shawl wool, collected from the neighbouring hills or bought in from beyond the border and *kedanjir*. Numerous European shops supply the minor wants of visitors, most of them being the work of

of Calcutta firms. The station has three English banks, a club, and several churches; and two European breweries are situated in the valley below. The great deficiency of Simla lies in its inadequate water-supply. A water-supply by means of pipes supplies Simla with water from the Mahásu range; but the constantly increasing population puts a strain upon the works which they are at times scarcely able to bear, and a further extension of the works, by the construction of additional reservoirs, is now well advanced towards completion. The springs are few in number, and several of them run dry during the summer months, when the demand for water is greatest.

Simla Hill States.—A collection of twenty-three Native States surrounding the sanitarium of Simla; bounded on the east by the high wall of the Himálayas; on the north-west by the mountains of Spiti and Kúlu belonging to the District of Kángra, and lower down by the Sutlej, separating them from the State of Sukét and Kángra proper; on the south-west by the plains of Ambála; on the north-east by the Dehrá Dún and the Native State of Garhwál. They extend between the parallels of lat. $30^{\circ} 20'$ and $32^{\circ} 5'$ N., and long. $76^{\circ} 30'$ and $79^{\circ} 1'$ E. They are controlled by the Superintendent of Hill States in subordination to the Commissioner of Ambála. The table on the opposite page gives a few of the leading statistics regarding them.

The mountains of the Simla States form a continuous series of ranges ascending from the low hills which bound the plains of Ambála to the great central chain of the Eastern Himálayas. This central chain terminates a few miles south of the Sutlej in the most northern of the States, that of Bashahr (Bassáhir). The same State is broken on its northern frontier by spurs from the snowy hills which separate it from Spiti, and on the east by similar spurs from the range by which it is shut off from Chinese Tartary. Starting from the termination of the Central Himálayas, a transverse range—the last to the south of the Sutlej—runs south-west throughout the length of the Simla States, forming the watershed between the Sutlej and the Jumna—in other words, between the Indus and the Ganges. A few miles north-east of Simla, it divides into two main branches, one following the line of the Sutlej in a north-west direction, and the other continuing south-east, until, at a few miles north of Subáthu, it meets at right angles the mountains of the Outer or Sub-Himálayan system, which have a direction parallel to the Central Himálayas, *i.e.* from north-east to north-west. It is upon this branch that the sanitarium of Simla lies.

South and east of Simla, the hills lying between the Sutlej and the Tons, the principal feeder of the Jumna, centre in the great Chor mountain, 11,982 feet high, itself the termination of a minor chain that branches off southwards from the main Simla range.

[Continued on page 500.]

Continued from page 498.]

The mountain system of these States (excluding Bashahr (Bassáhir) may be thus mapped out roughly into three portions:—(1) The Chor mountain, and spurs radiating from it, occupying the south-east corner; (2) the Simla range, extending from the central Himálayas to the neighbourhood of Sabáthu; (3) the mountains of the Sub-Himálayan series, running from north-east to north-west, and forming the boundary of the Ambála plains.

The last-mentioned group may be sub-divided into the Sub-Himálayas proper, and an outer range, corresponding to the Siwálik hills of Hoshiárpur on the one side, and of the Gangetic Doáb on the other. The Sub-Himálayan and the Siwálik ranges form parallel lines, having between them an open space of varying width. In Náhan this open space is known as the Khiárda Dún, a broad and well-cultivated valley. The corresponding Dún in Nálágarh is still more open, and is also richly cultivated.

The wilder parts of Bashahr (Bassáhir) beyond the Sutlej are thus described by Sir H. Davies:—

‘Immediately to the south of Spiti and Láhul is the district of Kunáwár, which forms the largest sub-division of the Bashahr principality, and consists of a series of rocky and precipitous ravines, descending rapidly to the bed of the Sutlej. The district is about 70 miles long by 40 and 20 broad at its northern and southern extremities respectively. In middle Kunáwár the cultivated spots have an average elevation of 7000 feet. The climate is genial, being beyond the influence of the periodical rains of India; and the winters are comparatively mild. Upper Kunáwár more resembles the Alpine region of Tibet. Grain and fuel are produced abundantly; the poppy also flourishes. The Kunáwáris are probably of Indian race, though in manners and religion they partially assimilate to the Tibetans. The people of the north are active traders, proceeding to Leh for *charas*, and to Gardokh for shawl-wool, giving in exchange money, clothes, and spices. The mountain paths are scarcely practicable for laden mules, and merchandise is carried chiefly on the backs of sheep and goats.’

The principal rivers by which the drainage of these hills is effected are the Sutlej, the Pabar, the Giri or Giri Gangá, the Gambhar, and the Sarsa.

The Sutlej enters Bashahr State from Chinese territory by a pass between two peaks, the northern of which is 22,183 feet above sea-level, and flows south-east through Bashahr, receiving the drainage from the Central Himálayas on the one side and the Spiti hills on the other, till it reaches the border of Kúlu, a few miles above the town of Rámpur. From this point it forms the western boundary of the Simla States, until, shortly before reaching the border of Kángra proper, it turns southwards,

and passes through the State of Biláspur, which it divides into two nearly equal portions. It is crossed by bridges at Wangtu, and at Latu below Kotgarh. In Biláspur small boats are employed on the river, and where inflated skins are used to effect a passage. The river is not fordable at any point. Its principal feeders in Bashahr are the Baw, from the south, and the Spiti from the north.

The Pabar, which is one of the principal feeders of the Tons and therefore of the Jumna, rises in the State of Bashahr, having feeders on the southern slopes both of the Central Himalayas and the transverse Simla range. It flows southwards, and passing into Garhwál, there joins the Tons.

The Giri, or Giri Gangá, rises in the hills north of the Chor, and collecting the drainage of the whole tract between that mountain and the Simla range, flows south-west until, meeting the line of the Outer Himalayas, it turns sharply to the south-east, and passing through the whole length of the State of Náhan, empties itself into the Jumna about 10 miles below the junction of that river with the Tons. Its principal feeder is the Ashmi or Assan river, which rises near Wáhisu in the Simla range, and, after receiving a considerable contribution from the eastern face of the hill upon which Simla station stands, joins the Giri just at the point where that river turns south-east.

The Gambhír rises in the Dagshai hill, and running north-east past Subáthu, receives the Blini and several other streams, which rise in the hills to the south of Simla station and still continuing its course north-east, empties itself into the Sutlej about 8 miles below the town of Biláspur.

The Sarsa collects the drainage of the Dún of Nálgarh.

Of these streams, the Pabar and Giri Gangá are of considerable volume. Of the rest, except the Sarsa all are perennial, receiving a small supply of water even in the winter months, and swelling to formidable torrents during the rainy season. The Pabar alone is fed from perennial snow.

Further information regarding the Simla Hill States will be found in the separate articles on each, in their alphabetical order.

Simráon—Ruined town in Champaran District, Bengal, situated partly in Nepál territory, the frontier line passing through the wall. The remains of the fort are in the form of a square walled enclosure with an outer wall 14 miles in circumference, and by an inner enclosure of 10. Inside are scattered the ruins of large buildings. The largest measures 333 yards along one side, and 210 along the other. The portions of the palaces and temples left standing disclose some fine carved basements, with a superstructure of bricks. They are all now in ruins, many, however, being much ruined. The main gate is situated to the north, and the palace in the centre of the enclosure.

both only exist as mounds, covered with trees and jungle. Tradition says that Simráon was founded by Nánaupá Deva in 1097 A.D. Six of his dynasty reigned with much splendour; but the last of the line, Hári Singh Deo, was driven out in 1322 by the Muhammadans.

Simrauta.—*Parganá* in Digbijaiganj *tahsíl*, Rái Bareli District, Oudh; bounded on the north by Haidargarh, on the east by Inhauna, on the south by Rái Bareli, and on the west by Kumhráwán and Hardoi. Area, 97·4 square miles, or 62,337 acres, of which 40·1 square miles, or 26,698 acres, are under cultivation. Population (1881) 52,480, namely, males 25,529, and females 26,951. Government land revenue, £6171, or at the rate of 3s. 11½d. per arable acre. Of the 73 villages comprising the *parganá*, 50 are held under *tálukdári*, 22 under *zamindári*, and 1 under *pattidári* tenure. Kanhpuria Rájputs are the principal landed proprietors, owning 35 of the *tálukdári* villages.

Sinawan.—*Tahsíl* in Muzaffargarh District, Punjab.—See SAN-AWAN.

Sinchal Pahár.—Long undulating mountain spur in Dárjiling District, Bengal, stretching gradually down to the Tista (Teesta), from the top of which, in lat. 26° 59' N., and long. 88° 20' 5" E., at a height of 8607 feet above the sea-level, Mount Everest is just visible. This hill is the loftiest mountain in the vicinity of Dárjiling station; its two peaks are locally known as the Bará and Chhotá Durbín. Their summits are covered with grass, and their sides are clothed with forest trees, bamboos, ferns, and scrub jungle. There were formerly barracks for a European regiment on the hill, but they have been abandoned for some years in favour of the lower site at Jallapahár.

Sinchulá.—Hill range in Jalpáigurí District, Bengal; forming the boundary between British territory and Bhután. Its average elevation is from 4000 to a little over 6000 feet, the highest peak, Renigango (lat. 26° 47' 30" N., long. 89° 37' 15" E.), being 6222 feet above sea-level. The hills run generally in long even ridges, thickly wooded from base to summit; but at places the summits bristle up into bare crags from 200 to 300 feet. From Chhotá Sinchulá (5695 feet high) a magnificent view is obtained over the whole of the Baxá Dwár. In the distance are seen large green patches of cultivation in the midst of wide tracts of brown grass and reed jungle, the cultivated spots being dotted with homesteads; in the foreground, near the hills, are dense *sál* and other tree forests, the whole being intersected by numerous rivers and streams. The Sinchulá range can nearly everywhere be ascended by men and by beasts of burden, but not by wheeled vehicles of any description.

Sind (*Scinde*).—A Province of British India, forming a Commissionership under the Governor of Bombay; lying between 23° and 28° 40' N. lat., and between 66° 50' and 71° E. long. The Province of

Sind forms the extreme north western portion of the Bombay Presidency, consisting of the lower valley and the delta of the Indus. It is bounded on the north by Baluchistan, the Punjab, and Bahawalpur State; on the east by the Native States of Jaisalmer and Jodhpur in Rájputána; on the south by the Rann of Cutch (Kachchh) and the Arabian Sea; and on the west by the territories of the Khén of Khelát. The Province of Sind consists of two classes of territory—(1) the five British Districts within the Province, and (2) the Native State of Khairpur. The aggregate area of the five British Districts was returned in 1881 at 48,014 square miles, or 38.55 per cent. of the area of the British territory of the Bombay Presidency, the total population at 2,413,823, or only 14.67 per cent. of the population of the Bombay Presidency. The Native State of Khairpur has an area of 6109 square miles, and a population (1881) of 129,153. Including Khairpur State, the Province of Sind contains an area of 54,123 square miles, and population (1881) of 2,542,976 souls. The administrative head quarters are at the city of KARACHI (Kurrachee), but the ancient capital of HAJIDARABAD still ranks among the populous towns of the Province. The following table exhibits the area, population, etc., of Sind according to the Census of 1881—

AREA, POPULATION, ETC., OF SIND

UNDER BRITISH ADMINISTRATION

DISTRICTS.	Area in Square Miles.	Number of Towns and Villages.	Number of Houses.	POPULATION.			Density of Population per square mile.
				Total Population.	Males.	Females.	
Karachi,	24,115	723	87,009	478,668	235,658	242,900	31.2
Haidarabad, . . .	9,020	1105	100,483	754,624	400,243	354,381	81.3
Shikarpur, . . .	10,001	1373	130,702	852,656	451,033	401,623	29.2
Thar and Parkar, .	12,729	73	36,412	203,344	112,470	90,874	11.1
Upper Sind Frontier, .	2,139	143	21,523	124,181	70,176	54,005	15.0
Total	48,014	3117	433,654	2,413,823	1,319,279	1,094,544	14.67

NATIVE STATE.

Khairpur,	6,109		20,000	122,153	70,770	51,383	21.1
GRAND TOTAL, . .	54,123		453,654	2,542,976	1,389,049	1,153,927	14.67

The following account of Sind, and the articles on places within that Province, are mainly condensed from Mr. A. W. Hughes' excellent and elaborate *Gazetteer of the Province of Sind* (London, 1876, second edition).

Physical Aspects.—Almost every portion of the great alluvial tract of Sind has at some time or other formed a channel for the river Indus itself, or one of its many branches. The main central stream of North-Western India, after collecting into its bed the waters of the five Punjab rivers, has deposited near its debouchure into the Arabian Sea a vast mass of deltaic matter, through which it flows by several shifting channels to join the sea on the southern border of the Province. In every direction, traces of ancient river beds may be discovered crossing the country like elevated dikes; for the level of the land, as in all other deltaic regions, is highest at the river bank. The Indus brings down from the turbid hill torrents a greater quantity of detritus than can be carried forward by its diminished velocity in the plain, and hence a constant accumulation of silt takes place along its various beds, raising their level above that of the surrounding country, and incidentally affording an easy opportunity of irrigation by side channels drawn from the central river.

The only elevations deserving the name of mountains occur in the Kirthar range, which separate Sind from Balúchistán, and attain in places a height of more than 7000 feet above sea-level. They first touch the Sind frontier about the 28th parallel of north latitude, and form the British boundary for 120 miles. Thenceforward they sink considerably in altitude, forming the lesser chain of the Pab hills, which after a length of 90 miles in a southerly direction terminate on the sea-coast in the promontory of Cape Monze. Their average elevation does not rise above 2000 feet. Among the valleys and ravines of the Pab range flows the river Hab, the only permanent stream in Sind, except the Indus and its tributaries. The wild and rocky tract of KOHISTAN, in the western portion of Karachí District, forms almost the only remaining exception to the general flatness of the Province. Another offshoot of the Kirthar chain, however, known as the Lakki range, extends in a barren mass eastward into the Sehván Sub-division, and presents evident marks of volcanic origin in its frequent hot springs and sulphurous exhalations. A few insignificant limestone ranges intersect the Indus valley, on one of which, known as the Ganjo hills, with an elevation of only 100 feet, stands the Talpur capital of HAIDARABAD. A second small chain, running in a north-westerly direction from the neighbourhood of Jaisalmer, attains towards the Indus a height of 150 feet, and forms the rocks on which are perched the towns of ROHRI and Sukkur, as well as the island fortress of BUKKUR (Bakhar).

SIND

The plain country comprises a mixed tract of dry desert and alluvial soil. The finest and most productive region lies in the neighbourhood of Shikarpur and Larkhina, where a long narrow island extends for 100 miles from north to south, enclosed on one side by the river Indus and on the other by the Western Nari. Another great alluvial tract with an average width of 70 or 80 miles stretches eastward from the Indus to the Eastern Nari. The Indus appears at one time to have spread its fertilizing waters through the wide waste at present known as the Eastern Desert, in the District of Thar and Parkar. A few of the ancient towns still stud the trackless expanse and dry water-courses intersect it in every part. Small abundant rain-bearing winds, shifting under the influence of each prevailing wind, large tracts rendered sterile for want of irrigation also occur in many other parts of Sind. Among them the most noticeable is the Little Desert of Shikarpur, commencing 30 miles west of that town and stretching to the foot of the Bolan Pass and ending in the clay deposited by the Bolan, the Nari, and other mountain torrents. The Thar Desert and its monotony renders it tame and uninteresting. A few can be seen dreary to a stranger approaching the desert in the lowland districts, entirely devoid of trees and shrubs. Even in the hills of Parkar, where fine rocky scenery abounds, the humidity is so great that the wanting, owing to the volcanic nature of the rocks. In the Parkar District, in the eastern portion of the Thar Desert, the Sub-division of Rohri the rocky hills are so numerous that they but sandhills, many of which however even rise to the height of their bold outline, and are sometimes even forested. The ranges of sandhills succeed one another like waves. Lakes are rare, the largest being the Makhrak Lake in the Sub-division, formed by an expansion of the Western Nari. During the inundation season it measures 20 miles in length and covers an area of about 180 square miles. At the same season it is 10 miles (dirdhs) of the Eastern Nari from prettily like the lakes of the great beauty they are seldom visited as the water is so shallow and dangerous places in which to encamp.

The alluvial strip which borders either bank of the river for a distance of 12 miles, though superior to every other tract in the soil and productiveness, can hardly be called a fertile one. Even here, however, extensive tracts of Achar and other low-lying places skirt the reaches of the river for miles. In the town of Srinagar, the Lakhi range of hills rises up at a steep angle toward the river in a perpendicular face of rock and forest. One of the finest views in the Province is those which embrace the town of Sakur and Rohri, and the island fortress of Bakhar with its

castellated walls, lying in the river between them. All three crown the range of limestone hills through which the Indus has here cut its way, and the minarets and houses, especially in Rohri, overhang the stream from a towering height above. A little to the south of Bukkur, again, lies the green island of Sádih Bela with its sacred shrine, while groves of date-palm and acacia stud the banks of the Indus on either side.

The soil of Sind consists of a plastic clay, strongly impregnated with salt. When covered with the floods (*lits*) of the Indus, either by artificial irrigation or through spontaneous change of channel, it quickly assumes the appearance of a rich lowland; and it changes its aspect as quickly to that of an arid desert when the water is once more diverted elsewhere. The land is thus fertile enough in the immediate neighbourhood of the existing river branches to yield two or more crops in the year without manuring. Nevertheless, the soil contains a large admixture of saltpetre; and in Southern Sind, where sand greatly prevails, it is so impregnated with common salt as to produce it in abundance by evaporation, after simply pouring water through its surface.

The extent of forest land is small for a Province of so large an area, only about 625 square miles being covered with woodland, not including those in Khairpur State. The Forest Department has charge of about 90 separate forests, chiefly situated along the banks of the Indus, extending southward from Ghotki to the middle delta. They run in narrow strips, from a quarter of a mile to 2 miles in breadth, and about 3 miles in length. These strips of forest are currently reported to have been constructed as game preserves by the Mírs. Many of them suffer greatly at times from the encroachments of the stream. The floods of 1863 swept away 1000 acres of the Dhárejá forest in Shikárpur District, and a similar misfortune occurred to the forests of Sundarbelo and Sámtia in the two succeeding years.

The indigenous trees consist chiefly of *babúl* (*Acacia arabica*), *bahan* (*Populus euphratica*), *kandi* (*Prosopis spicigera*), and *lai* (*Tamarindus indica*). The *babúl*, the staple tree of Lower Sind, produces good timber for boat-building and fuel; while its seed-pods supply a food for fattening cattle, its bark is employed for tanning, and its leaves form a favourite fodder of camels and goats. The *bahan*, the commonest tree of Upper Sind, yields a light soft wood for building purposes, from which also are manufactured the celebrated lacquered boxes of Hála and Khánót. The *táli* (*Dalbergia Sissoo*) grows to some extent in Upper Sind, though it cannot be considered as indigenous to the Province. The delta of the Indus contains no forests, but its shores and inlets abound with low thickets of mangrove trees, whose timber makes a good fuel. The Forest Department has lately intro-

duced several valuable exotics, including the tamarsk, the water-chestnut and the tallow tree. The revenue from this source has largely increased during the last two decades. In 1883-84, the amount realized by the sale of timber of all descriptions, including firewood, was £28,092. The date palm (*Phoenix sylvestris*) ripens its fruit in Sind, while the country also produces excellent apples, being to some extent intermediate in its flora between Hindustán and Khorásán. One third of the indigenous vegetation is Arabian or Egyptian.

The native fauna includes the tiger, found occasionally in the jungles of Upper Sind, the hyæna, the *gorkhar* or wild ass, the wolf, fox, wild hog, antelope, hog-deer, and ibex in the western hills, as well as the vulture and several falcons. The flamingo, pelican, stork, crane, and Egyptian ibis frequent the shores of the delta. Bustard, rock grouse, quail, and partridge occur among the game-birds, while flocks of wild geese, *kulang*, ducks, teal, and curlew cover the lakes and *dardis* during the cold season. Venomous snakes abound, and yearly cause a large number of deaths. The river fisheries of the Indus and its offshoots not only supply the Province with fresh fish, but afford a considerable export trade in dried *pila*, the *kisti* of Bengal. Among domestic animals, the camel of the one humped variety ranks first as a beast of burden, immense numbers being bred in the salt marshes of the Indus. Great herds of buffaloes graze on the swampy tracts of the delta, and *ghí*, made from their milk, forms an important item of export trade. Sheep and goats abound in Upper Sind, on the borders of the *Pat* in Shikárpur District, and in *Thar* and *Párlar*. The horses, though small, are active, hardy, and capable of enduring great fatigue. The Bálúchís of Upper Sind pay much attention to the breeding of mares. The Government have introduced English stallions, and horse-breeding is carried on for the purpose of furnishing a superior class of mounts for the cavalry, as well as improving the breed of horses in the country. The bullocks are small in size, and chiefly used for draught or for turning irrigation wheels.

The extreme south-eastern border of Sind is formed by the *Rann of Cutch* (*Kacchhu*), an immense salt water waste, with an area of about 9000 square miles. It bounds the District of *Thar* and *Párlar* to a distance of nearly 40 miles. Every part of it is devoid of herbage, and a large portion is annually converted into a salt lake from June to November, owing to the influx of the sea at *Lakhpur Bander* on the Kori mouth of the Indus, as well as at other places in *Cutch* (*Kacchhu*) and *Káthiáwar*. During the remaining six months of the year, after the evaporation of the water, the surface becomes covered with salt, while herds of antelopes and wild asses roam over the desert expanse. According to local tradition, a well tilled plain, irrigated by a branch of the Indus, once covered this portion of the *Rann*, but before the late

of man or an earthquake diverted the waters, and the tract has ever since remained a waste of salt. The upper part of the Kori mouth still bears the name of the Purána or ancient stream; and there is little doubt that the Indus once took a more easterly course than at present, and so rendered some portion of the Rann a fertile lowland.

The whole sea-coast of Sind, except the part between Karáchi (Kurrachee) and Cape Monze where the Pab hills approach the shore, is low and flat, and submerged at spring-tides. It consists, in fact, of a series of mud-banks deposited by the Indus, or in a few places of sandhills blown from seaward. The sea near the shore is very shallow, owing to the quantity of mud brought down by the river. A bank extends along the coast from Karáchi to Cutch, about 2 miles from the land, and 3 miles in width, generally dry at low water. This circumstance renders the approach to the shore extremely dangerous for large vessels.

History.—Sind owes its name as well as its existence to the river Indus or Sindhu, a Sanskrit term signifying water; though Muhammadan scholars prefer to derive the word from an eponymic patriarch Sind, the brother of Hind, and son of Nuh or Noah, whose descendants ruled over the country for many generations. Previous to the Arab invasion in 711 A.D., a Hindu dynasty appears to have reigned at Aror, near the present town of Rohri; and their capital, on the bank of the Indus, possessed many fine buildings, with extensive pleasure-gardens. The dominions of the native dynasty stretched, according to local tradition, from Kashmír and Kanauj to Surat and to Omán, besides including the Afghán territories of Kandahár and the Suláimán hills. The names of five kings belonging to this earliest line have been preserved to us, and their reigns are said to have extended over an aggregate of 137 years.

A Bráhma chamberlain to the last of them, by name Chachh, established himself on the throne after his master's death, and left the kingdom to two of his family in succession. But during the reign of his son Dahír, a few peaceful Muhammadan merchants, as the Arab version of the conquest asserts, who had been sent into Sind by the Khálifa Abdúl Málík to purchase female slaves and other articles of lawful commerce, were attacked by robbers, and either made prisoners or killed on the spot. One or two of the injured merchants alone escaped to make their complaints to the Khálifa; and the latter readily embraced so excellent an opportunity of spreading the faith of Islám into the delta of the Indus. He died before the army collected for the purpose could invade Sind; but his son despatched Muhammad Kásim Sakifi to carry out the conquest about 711 A.D.

Muhammad Kásim set out from Shiráz with a large force, and first captured the seaport of Debal, identified by some with MANORA, and by others with TATTA. Thence he marched upon Nerankot, the

modern Haidarabad, and after its capitulation he next took the strong fortress of Sehwan. Returning to Nerankot, the Musalman leader proceeded to cross the Indus, whose main channel then flowed east of the city, and successfully engaged the army of Rajá Dahir. The native prince was slain at the fort of Ráwar, while his family were carried away prisoners by the conqueror. In 713 Muhammad Kásim arrived at the capital, Aror, which was taken, and then advanced upon MULTAN (in the present Punjab Province) which submitted with an immense treasure. The end of the first great Musalman conqueror of India remains uncertain, but it seems probable that he was tortured to death with the sanction of Khálifa Sulaiman. Sind remained thenceforward, with scarcely a break in the hands of the Muhammadans.

On the extinction of the Ummayyide dynasty of Khálifas (750 A.D.) and the accession of the Abássides, the Indus delta passed to the new rulers, and the power of the Musalmáns began to attract the attention of the native princes on the northern frontier of Hindustán. But the hold of the Khálifas upon this distant Province grew slowly weaker and became virtually extinct in 871 A.D. Two native kingdoms raised themselves at Multán and Mánshura. The former comprised the upper valley of the united Indus as far as Aror, the latter extended from that town to the sea, and nearly coincided with the modern Province of Sind. The country was then well cultivated and Aror the capital, surrounded by a double wall is said to have almost equalled Multán in size, and to have possessed a considerable commerce. The Arab princes apparently derived but a very small revenue from Sind and left the administration wholly in the hands of natives. Arab soldiers held lands on military tenure, and liberal grants provided for the sacred buildings and institutions of Islám. Commerce was carried on by caravans with Khorásan and Zabulistán and by sea with China, Ceylon, and Malabar. The Arabs also permitted the native Sindians the free exercise of their own religion to a considerable extent.

When Mahmud of Ghazni invaded India in 1019 Sind was ruled by a Governor who nominally represented the Khálifa Kádir Billáh Abul Abbas Ahmad. After the capture of Multán and Lohi Mahmud sent his Wazir, Abdúr Razá, to conquer Sind which the Wazir accomplished in 1026. But six years later, Ibn Súmar, Governor of Multán laid the foundation of the Sumra dynasty in Sind, at first apparently as a titular vassal of the Ghaznavide monarchy. In 1051, however if not before, the Sumra kings made themselves completely independent, and extended their possessions as far as Nararpur, 26 miles south-west of Haldí. Under Kháfif, who made Tatta his capital, the dynasty attained its greatest power, and restrained with success the wild tribes of the western frontier. From the death of Kháfif however the Sumra dynasty lost its prestige, and in the reign of Urrah Mehl (1351) the Samra tribe, a

body of non-Musalmán immigrants from Cutch (Kachchh), conspired against and killed the Musalmán king, and placed Jám Unar, one of themselves, upon the throne of Sind.

The Samas were either Buddhists or Hindus, and had their capital city at Samanagar on the Indus, identified with the modern town of Schwán; but they resided chiefly at Tatta or at Samui, under the Makli Hills, 3 miles north-west of the former town. They were undoubtedly Rájputs of the Jadava stock, and they became Muhammadans not earlier than 1391 A.D. Jám Unar, first of the line, reigned three and a half years, but does not seem to have held all Sind under his sway, as the Hákims kept Bukkur and its neighbourhood on behalf of the king of the Turks. Junah, the second king, captured Bukkur, and the Hákims retreated to Uchh. Under his successor, the forces of the King of Delhi retook Bukkur, and carried the Jám and his family as prisoners to Delhi. In 1372, Firoz Tughlak invaded Sind, and compelled the ruling prince to tender a nominal allegiance. The Sama line consisted in all of 15 kings, the last of whom was supplanted by the Arghuns.

The Arghún dynasty traced its origin to Changiz Khán, and commenced its rule in Sind in 1521. The first prince of the line, Sháh Beg Arghun, marching down from Kandahár, defeated the Sama army in 1520, and sacked Tatta, the capital of Jám Firoz Sama. By a subsequent agreement, the Jám retained all Sind between Sukkur and Tatta, while the Sháh took the region north of Lakhi. But the Samas soon after repudiated this agreement; and a battle fought at Talti, near Schwán, resulted in their utter defeat and the secure establishment of the Arghun power. Sháh Beg afterwards captured the fort of Bukkur, and rebuilt the fortifications with bricks taken from the ancient stronghold of Aror. Just before his death in 1522, he made preparations to attack Gujarát, but did not live to accomplish his purpose. Sháh Beg was not only a bold soldier, but also a learned Musalmán theologian and commentator. His son and successor, Mírza Sháh Husain, finally drove Jám Firoz from Tatta to Cutch, and at length to Gujarát, where he died. Sháh Husain severely punished his subject tribes for internal wars, and sacked the towns of Múltán and Uchh, as well as the fort of Diláwar.

During Sháh Husain's reign, the Mughal Emperor Humáyún, being defeated by the Afghán, Sher Sháh, in 1540 A.D., fled to Sind, where he endeavoured unsuccessfully to take the fort of Bukkur. After a short stay in Jodhpur, Humáyún returned to Sind by way of Umarkot in 1542, and again attempted without success to conquer the country. Sháh Husain died childless in 1554, after a reign of thirty-four years, and with him ended the Arghun dynasty. A short-lived line, the Tarkhán, succeeded for a few years; but in 1592, the Mughal Emperor

Akbar, who was himself born at Umarkot during the flight of his father Humáyūn, defeated Mirza Jani Beg, ruler of Tatta, and united Sind for the first time with the Musalmán Empire of Delhi. The Province was incorporated under Akbar's organization in the Sulah of Multán.

During the flourishing period of the Mughal Empire, the general peace of the great monarchy extended to Sind, and but few historical events of importance occurred for the next century. In the interval, however, between the consolidation of the Empire by Akbar and the dismemberment which followed on the invasion of Nádir Sháh the Dáúdputras or sons of Dáúd Khan, rose to distinction. Weavers and warriors by profession, they led a wild and wandering life at Khinpur, Farás, and throughout the Sukkur country. After a long and sanguinary conflict with the Mahars, a race of Hindu origin, the Dáúdputras succeeded in establishing their supremacy over Upper Sind, and founded the town of Shikárpur. From the extinction of the native dynasties, Tatta had formed a scene of constant contention between neighbouring governors, till Jahángír put a stop to the strife by appointing removable lieutenants to administer the outlying Provinces of the Empire, and so checked the growth of a hereditary vicereignty in Sind.

Towards the end of the 17th century, however another race, closely allied to the Dáúdputras, rose to power in the lower Indus valley. The Kalhoris traced their descent historically to Muhammad of Kambríthá (1204 A.D.), and more mythically to Abbas, the uncle of the Prophet. About 1558, the family rose into notice through the sanctity of one Adam Sháh, the chief of a large sect of mendicants in Chánduka. The Governor of Multán attacked the religious leader, dispersed his followers, and put to death Adam Sháh himself. The Fakirs descended from the family long lived a life of warfare against the Mughal lieutenants, until at length in 1658, under Názir Muhammad Kalhora they began successfully to oppose the imperial troops, and to organize themselves into a regular government. At length, about 1701, Yar Muhammad Kalhora, assisted by the Sírís or Talpur tribe seized upon Sít Míqat, where he fixed his court, and obtained from the Emperor Aurangzeb a grant of the Deryát, together with a regular tale (Khuda Yár Khán) under the imperial system. By the year 1711, Yar Muhammad had further overrun the Kandíro and Lákhána tracts, as well as the country around Sukkur.

On the death of Yar Muhammad Kalhora in 1719 his son Nur Muhammad succeeded to his territories, and converted the Sírí Sub-division from the Dáúdputras. Schwáin and its dependences also fell under his rule, and his territory extended from the Multán border to Tatta. The fort of Sukkur, however, did not come into the possession of the Kalhoris till 1736. With this exception, Nur Muhammad's

authority stretched from the desert to the Balúchí Mountains. During his reign, the Talpur tribe of Balúchís, the last native rulers of Sind, first came into notice in the person of Mír Bahráṁ, an able officer of the Kalhora kings. When Nádir Sháh, the Persian conqueror, swooped upon Delhi in February 1739, and broke down the decaying Mughal organization, all the Provinces west of the Indus were detached from the Empire and incorporated with the Persian dominions. Tatta and Shikárpur formed part of the territory thus ceded to Nádir Sháh.

Shortly after his return to Kábul, Nádir set out upon a second expedition against Sind and the Punjab, in order to repress his troublesome vassal, Núr Muhammad. Two years earlier, the Kalhora prince had persuaded Sádik Allí, Subahdár of Tatta, to make over that Province in return for a sum of 3 *lákhs*; and this transaction apparently aroused the anger of his new suzerain. On Nádir's approach, Núr Muhammad at first fled to Umarnót, but afterwards surrendered with the loss of Shikárpur and Sibi, which the Sháh made over to the Dáúdputras and Afgháns. An annual tribute of 20 *lákhs*, with the honorary compensations of a high-sounding title (Sháh Kuli Khán), was imposed upon the Kalhora prince.

On Nádir Sháh's death, Sind became tributary in 1748 to Ahmad Sháh Duráni of Kandahár, who conferred on Núr Muhammad the new title of Sháh Nawáz Khán. In 1754, the tribute being in arrears, Ahmad Sháh advanced against Sind, and Núr Muhammad fled to Jaisalmer, where he died. His son, Muhammad Murád Yáb Khán, managed to appease the ruler of Kandahár, and obtained a confirmation of his rank and power. He founded the town of Murádábád. In 1757, his subjects rose against his oppressive government and dethroned him, placing his brother, Ghulám Sháh, upon the throne. The new prince, after two years of internal dissension, made his own position secure; and in 1762 he invaded Cutch (Kachchh), fighting the sanguinary battle of Jhana. Next year he resumed operations against Cutch, and took the seaports of Basta and Lakhpat on the Indus. In 1768 he founded the city of Haidarábád on the ancient site of Nerankot, and made it his capital till his death in 1772. During the early part of his reign, in 1758, the East India Company established a factory at Tatta. Sarfaráz Khán, his son and successor, discouraged the Company's operations, and the factory was eventually withdrawn in 1775. Soon afterwards, the Balúchís deposed the chief, and two years of anarchy followed.

In 1777, Ghulám Nabi Khán, a brother of Ghulám Sháh, succeeded in obtaining the throne. During his reign, Mír Bijar, a Talpur chief, rose in rebellion; and in the battle between them the Kalhora prince lost his life. Abdúl Nabi Khán, his brother, succeeded to the throne,

and put all his relatives to death as a precautionary measure. He then made a compromise with Mir Bijar, retaining the sovereignty for himself, but appointing the Talpur chief as his minister. In 1781, an army from Kandahar invaded Sind, where the tribute remained always in a chronic state of arrears, but Mir Bijar defeated it near Shikarpur. Thereupon Abdul Nabi Khan assassinated his too successful general. Abdullah Khan Talpur, son of the murdered man, at once seized upon the government, and the last of the Kalhoras fled to Khelat. Thence he made many unsuccessful efforts to regain his kingdom, and at last re-established himself for a while by the aid of Kandahar. But on his putting to death Abdullah Khan, Mir Fatch Ali, a kinsman of the murdered Talpur, once more expelled him. The Kalhora king made a final effort to recover his throne, but being defeated by Mir Fatch Ali he fled to Jodhpur, where his descendants still hold distinguished rank. With him ended the dynasty of the Kalhoras.

In 1783, Mir Fatch Ali Khan, first of the Talpur line established himself as Rais of Sind. He obtained a *farmān* from Shah Zamin of Kandahar for the government of Sind by the Talpurs. The history of Sind under its new dynasty—generally spoken of as the Talpur Mirs—is rendered very complicated by the numerous branches into which the ruling house split up. Fatch Ali Khan's nephew Mir Sohrab Khan settled with his adherents at Rohri, while his son Mir Tharo Khan removed to Shikharbandar, and each of them occupied the adjacent country as an independent ruler, throwing off all allegiance to the head of their house at Haidarabad.

The Talpurs thus fell into three distinct branches: the Haidarabad or Shikharbandpur family, ruling in Central Sind; the Mirs of the Manikani house, descendants of Mir Tharo ruling at Mirpur; and the Sohrabani line, derived from Mir Sohrab, ruling at Khairpur. Further to increase the complication, Fatch Ali, head of the Haidarabad Mirs, associated with himself in the government his three younger brothers: Ghulam Ali, Karim Ali, and Murid Ali. He then turned his attention to the recovery of Karachi and Umarho. The former, alienated to the Governor of Khelat, he recovered in 1792. The latter held by the Rājā of Jodhpur, the Mirs regained in 1813. In 1801 Mir Fatch Ali died, leaving one son, Sobhdar, and bequeathing his power to his three brothers. Of these, Ghulam Ali died in 1811 and left a son, Mir Muhammad, but the two surviving brothers retained the chief power in Haidarabad. Karim Ali died without issue in 1828, and Murid Ali left two sons, Mir Muhammad and Mir Ali. In 1840, the government of Haidarabad was carried on by these two Mirs together with their cousins Sobhdar and Mir Ali. Mir Muhammad died in 1841, leaving two sons, Mir Ali and Mir Haidar. The Talpur Mirs adorned Haidarabad and its suburbs till 1843.

many handsome buildings, of which their own tombs are the most remarkable.

The first connection of the British with Sind took place as early as 1758, in the matter of the abandoned factory at Tatta. In 1799, a commercial mission was sent to Sind, to conduct business between our Government and the Talpur Mírs, but it ended unsatisfactorily. The agent resided from time to time at Tatta, Sháhbandar, or Karáchi, and endured numerous indignities, until at length he received a peremptory order from the Mírs to quit their territory. The East India Company took no notice of this insult. In 1809, an arrangement was effected between the Mírs and our authorities, mainly for the purpose of excluding Frenchmen from settling in Sind.

In 1825, the Sindí tribe of Khosas made incursions into Cutch, and a military demonstration became necessary as a preventive measure. In 1830, Lieutenant (afterwards Sir Alexander) Burnes, after many delays and threats on the part of the Mírs, was permitted to follow up the course of the Indus, taking with him presents from the King of England to Ranjít Singh at Lahore. The river was then entirely unexplored, and the obvious object of the mission was the collection of information for political purposes. Two years later, Colonel Pottinger concluded a treaty with the Mírs for the advancement of commerce, by which traders and merchants were permitted to use the roads and rivers of Sind, though no Englishman might settle in the country. The Khairpur Mírs ratified this treaty, after their kinsmen at Haidarábád. In 1835, Colonel Pottinger obtained leave to survey the sea-coast of Sind and the delta of the Indus; yet trade did not enter the river, and the Mírs clearly mistrusted the intentions of their powerful neighbours.

In 1838, the first Afghán war necessitated the despatch of British troops to join the main army by way of the Indus, in spite of a clause in the treaty expressly forbidding the employment of the river as a military highway. Lord Auckland considered that so great an emergency overrode the text of the agreement, and declared that those chiefs who showed themselves unwilling to assist the British in such a crisis would be deprived of their possessions. In December of that year, a large force under Sir John Keane landed in Sind, but found itself unable to proceed, owing to the obstacles thrown in its way by the Mírs in supplying stores and carriage. After a threat to march upon Haidarábád, Sir John Keane at length succeeded in continuing his course. Owing to this hostile demeanour, a reserve force was despatched from Bombay in 1839, to take up its station in Sind. The Balúchí garrison at Manora, near Karáchi, endeavoured to prevent it from landing, and the British accordingly found it necessary to occupy that fort.

A treaty was afterwards, in 1839, concluded with the Haidarábád

Mirs, by which they agreed to pay 23 *lakh*s to Siáh Shaja, in compensation of all arrears of tribute due to the Afgháns, to admit the establishment in Sind of a British force not exceeding 5000 men, the expenses being defrayed in part by the Mirs themselves; and finally, to abolish all tolls upon trading boats on the Indus. The Khairpur Mirs concluded a similar treaty, except as regards the subsidy. The English then took possession of the fort of Bukkur, under the terms of the engagement. By careful conciliatory measures, the British representatives secured the tranquillity of the country, so that the steam flotilla navigated the river unimpeded. Nur Muhammad, senior Mir, died in 1841, and the Talpur Government passed to his two sons, conjointly with their uncle, Nasir Khán.

In 1842 Sir Charles Napier arrived in Sind, with sole authority over all the territory on the Lower Indus. New conditions were proposed to the Mirs, owing to delay in payment of the tribute, these terms including the cession of Karachi, Latta, Sukkur, Bukkur, and Rohri. After some delay and a slight military demonstration, the treaty was signed in February 1843. But the Baluchis composing the Mirs' army did not acquiesce in this surrender of independence, and shortly afterwards they attacked the Residency, which stood near the Indus, a few miles from Haidrábád. Major Outram and his small suite, after defending the building for a short time, and themselves compelled to retreat to a steamer then lying in the river. He soon after joined Sir C. Napier's force. On the 17th of February, Napier found the Mir's army, 22,000 strong, posted on the Indus river, near Miffanfi (Mifni). He gave them battle with only 2500 men of all arms, and 12 pieces of artillery, and gained a complete and glorious victory. The Baluch loss amounted to about 5000 men, which that of the British did not exceed 257, of whom 19 were officers. Shortly after, the chief Mirs of Haidrábád and Khairpur surrendered as prisoners of war, and the fort of Haidrábád was captured together with the Mirs' treasure, computed at about £1,000,000 sterling. In March, Napier received reinforcements from Sukkur, and went in search of the enemy, with 5000 men. He found the Baluch army, 20,000 strong, under Sher Muhammad of Mirpur in a strong position near Dibo. After a desperate resistance, the Syrians fled in disorder, their leader, Sher Muhammad, returning to the desert. Soon afterwards, our troops occupied Mirpur, Khas, and Umarkot. Sind was declared a conquered country, and annexed to the British dominions.

The Talpur family thus ceased to be a ruling power, after a sovereignty of fifty-three years. The Mirs were retained successively at Bombay, Poona, and Calcutta; but in 1854, Lord Dalhousie ordered them to return to Sind and take up their residence at Haidrábád. Under the Talpurs, the government of Sind consisted of a ruler

military feudalism. The Mírs themselves had little education or refinement, and lived in primitive Balúchí simplicity, their extravagant propensities being shown in their fondness for horses, arms, and field sports. Their sole aim was to hoard up wealth, oppose all improvements, and enjoy themselves after their own fashion.

Immediately after the annexation, Sir C. Napier was appointed the first British Governor; while a pension of 3½ *lákhs*, together with lands in *jadgir*, was distributed amongst the deposed Mírs. The judicial and revenue systems underwent a speedy remodelling; and the Province was divided into extensive Collectorates. Since the British annexation, the chief events in Sind have consisted of commercial improvements, including especially the immense harbour works at KARÁCHÍ, which have rendered the modern capital one of the most important seaports of Western India. Under the Commissionership of Sir Bartle Frere (1851-59), the Province took most important steps in the direction of mercantile progress; and at a later date, the construction of the Indus Valley portion of the Sind, Punjab, and Delhi Railway, from Karáchí to join the Punjab line at Múltán, has already contributed greatly to the prosperity of the country.

Population.—Sind is a very sparsely populated Province even at the present day. No statistics are available as to the number of inhabitants under its native rulers, though a probable conjecture sets it down in the early part of this century at not more than 1,000,000 persons, or only about 16 to the square mile. A Census taken in 1856, exclusive of the territory of Mír Ali Murád Khán, or Khairpur State, returned the total population at 1,772,367 persons. An accurate enumeration undertaken in 1872 gave the total, again excluding Khairpur territory, at 2,203,177; thus showing a gain of 430,810 persons, or 26 per cent., in the fifteen years. The Census of 1881 disclosed a total population of the British Districts of 2,413,823, showing a further increase of 210,646, or 9·56 per cent., in the nine years between 1872 and 1881.

The main feature of this increase, which is found in every District of the Province, seems to be the influx of foreigners, chiefly from the adjacent territories of Balúchistán and the Punjab. In Karáchí, as in the city of Bombay and other large seaports, the indigenous population is in the minority. A good deal of the increase in the more rural parts of the Province has been attributed to the general development of the people, under the influence of prosperous harvests and improved means of transport to market. A part of the increase, however, is only apparent, and is due to more correct enumeration, especially in the case of females. The rate of increase in the towns has been generally higher than in the surrounding country. Karáchí owes its prosperity to the development of its sea trade, especially since the opening of direct railway communication with Upper India and the western frontier.

Shikārpur has also profited in the same manner, and the trading centre of Sukkur has doubled its population since 1872.

The results of the Census of 1881 may be summarized as follows—Area of British Districts, 48 014 square miles. Population 2,413 833 (males 1,316 830, and females 1,096 993), number of towns 12, and of villages 3405, number of occupied houses 433 584 and of unoccupied 149,701. From these the following averages are deduced—Persons per square mile, 50·3; towns and villages per square mile, 0·07, houses per square mile, 12·0; persons per house 5·5. The population, which is extremely scattered in all parts of the Province, gathers thickest in Shikārpur, 85·2 per square mile, and Haidarabad 83·3 per square mile. In the Frontier District of Upper Sind, the average falls to 58. The extensive District of Karachi, though it contains the capital town and largest commercial centre, has but 33·9 persons to the square mile; in Khairpur State, the average is only 21·1, and in the wide but desert expanse of the Thar and Larkar District, it does not exceed 15·9.

Classified according to sex, the native population in 1881 amounted to—males 1,314 391, and females 1,096 026. The European element was represented by 3127 persons, namely, males 2279 and females 848. Eurasians numbered 279, namely, males 160 and females 119. Classified according to sex and age, of the entire population exclusive of Khairpur State, there were returned—under 15 years, boys 546 007, and girls 441,574, total children, 987 579 or 40·9 per cent. 15 years and upwards, males 770 825, and females 654 419, total adults 1,426,244, or 59·1 per cent.

Religion and Caste—Classified by religion, the Muhammadans numbered 1,887,204, or 78·5 per cent. of the total population, Hindus, 307 070, or 12·6 per cent., Sikhs, 126 976, or 5·3 per cent., non-Hindus, 171 86 040, or 3·5 per cent., Christians, 6082; Jains, 1191; Parsis, 1063; Jews, 153; Brahmos, 26, and Buddhists, 9. The Muhammadans, who form the bulk of the inhabitants, fall naturally into two classes—the native Sindis, and the naturalized tribes, such as Savaris, Afghans, Baluchis, Africans, and Khwājas. The Muhammadan population by race, as distinguished from descendants of converts, consisted of Sindis, 1,273 761, Baluchis, 409 012, Savaris, 37 734, Afghans, 32 888, Pathans, 14 729, and 'others', 119 000. According to sect, the Muhammadans were returned—Sunnis, 1 555,645, Shāhis, 28 603, Wahābis, 174, and 'others' 280.

The Sindis represent the original Hindu population, converted to Islam under the Ummayyid Khalīfas. They are taller and fairer than the natives of Bengal, of dark complexion and frizzly hair. Their detractors represent them as idle, indolent, and dissipated, addicted to drunkenness, and personally dirty, which is not the case.

tion to truthfulness has given them a bad name amongst neighbouring tribes. On the other hand, they are quiet and inoffensive, kindly, faithful, and of unimpeachable honesty. In religion they are Sunnis. The Sindis are sub-divided into about 300 clans or tribes, but the caste system does not exist among them. The Sindí language belongs to the pure Neo-Sanskritic group, and contains far less of alien admixture than any of the cognate tongues. It stands closer to the old Prákrit than does either Maráthí, Hindí, or Bengálí; and it has preserved an immense number of grammatical forms which have dropped out of the other vernaculars. Three dialects of Sindí are distinguished in Upper and Lower Sind and in the Thar, respectively. The literature of the language consists mainly of translations from the Arabic, chiefly theological, and a few rude national ballads.

Among the races of foreign origin, the Sayyids were patronized by the Kalhora princes, who granted them several considerable estates; but the Talpurs proved less liberal. The Afgháns came originally from Khorásán, and now reside in the neighbourhood of Haidarábád and in Northern Sind. They far surpass the Sindis in personal appearance, strength, and courage. The Balúchís, wild mountaineers from the barren hills to the westward, settled in Sind under the Talpur dynasty, and received large *jágírs* in return for military services. They are fairer, more powerful, and hardier than the Sindis; they have genuine though peculiar ideas of honour; and they are brave soldiers, with a large share of national pride. On the other hand, they are grossly illiterate, rough in manners, drunken and debauched, violent and revengeful, and wholly addicted to coarse amusements. In religion they belong to the Sunní sect, though the Talpur Mírs, on their arrival in Sind, adopted the Shiá persuasion. About 80 clans are settled in the plains. The Africans represent the slaves of Sind, brought over by way of Maskat from Zanzibar or Abyssinia. Emancipated at the British annexation, they still marry, as a rule, within their own race, and remain inmates of their former masters' houses. A small body of Memons gather around Haidarábád, Sehván, and Karáchí. They are doubtless Hindus by origin, who became Musalmáns and emigrated to Sind during the Kalhora rule. They engage in trade, agriculture, and breeding camels. Many of them possess great learning, and they have done more than any other class to introduce religious knowledge into the Province. The Khwájas, a numerous body in Karáchí, are heterodox Musalmáns, carrying the Shiá doctrines to an extreme.

The Hindus occupy in Sind a position analogous to that of the Musalmáns in Hindustan. Few of them, apparently, belong to native families which have survived the long Muhammadan domination; they have generally immigrated from the Punjab in recent times, and retain their distinctive names, features, and religion. The Bráhmans comprise

two classes, which do not intermarry, and they are mainly confined to the large towns. One class, called *awils*, formed the principal clerks and writers in the time of the Mirs, and rose to the position of Government. They imitate the Muhammadans in their dress and manner of wearing the hair, and are in all a most intelligent class of the community. The lower castes are essentially similar to their brethren in the Punjab. The Sikhs reside in considerable numbers at Haidarabad, Schwân, and other towns. The Census of 1881 subdivided the Hindus by caste and social distinctions into—Prâhmarîs, 13,531, Râjputs, 10,534, Lohânîs, 211,926 and others, 69,088.

Among the Christians of the Province, 3198 were Roman Catholics, 2198 Protestants, and 686 of other Christian creed. Adopting another principle of division, there were 3127 Europeans, 2676 native Christians, and 279 Eurasians.

As regards occupation, the Census of 1881 distributed the male population into six main groups—(1) Professional class, including civil and military officials of every kind, 19,242, (2) domestic servants, inn and lodging house keepers, 18,926, (3) commercial class, including bankers, merchants, carriers, etc., 31,239, (4) agricultural and pastoral class, including gardeners, 476,573, (5) industrial class, including all manufacturers and artisans, 147,225, and (6) indolent and non-productive class, comprising labourers, male children, and persons of unspecified occupation, 623,625.

Of the 3417 towns and villages of Sind, 985 contain less than two hundred inhabitants, 848 between two and five hundred, 978 between five hundred and one thousand, 431 between one and two thousand, 97 between two and three thousand, 48 between three and five thousand, 22 between five and ten thousand, 3 between ten and fifteen thousand, 4 between twenty and fifty thousand, and 1 above fifty thousand.

KARACHI, the capital city, had a total population in 1881 of 73,560 persons, but its commercial importance is far greater than this total would seem to imply. SHIKARPUR, the great depot of trade between with the Holân Pass and Khorâsân, had 42,496. HAINARAT, the Talpur capital, 48,153. The other chief towns which are mentioned include—AROR, the capital of Sind under the Mîr's, 11,111, LAR, MAHARAJ, a mass of extensive ruins of very great antiquity, 10,000, Shâhdâdpur, the fortified island of PAKISTAN, in the Rîvâr, the port on the principal mouth of the Indus (2141 persons), KHARAT, the capital of the State of the same name, KHARAT, the capital of the Indus Valley Railway opposite Haidarabad (8222), LARHANA, a considerable manufacturing town (13,188), JODHPUR (10,224), SHIKARPUR (4524), the deserted port of SHAHRANAK, SHIKARPUR, the principal port of the Indus, and point of departure for the railway to the Holân Pass (27,389), TATTI, the old city, situated on the left bank of the Indus, 10,000.

(8830); JACOBABAD, the chief military station of the Frontier District (11,352); KAMBAR (6133); GARHI YASIN (5541); and MATARI (5054).

Agriculture.—The total extent of cultivated land in Sind in 1881–82 amounted to no more than 2,121,072 acres, by far the greater portion of the Province being absolutely barren. There are two principal harvests—the *rabi*, sown in August, September, or October, and reaped in February, March, or April; and the *kharif*, sown during the floods of the Indus, in May, June, July, or August, and reaped in October, November, or December. The *rabi* consists of wheat, barley, gram, vetches, oil-seeds, indigo, hemp, and vegetables. The *kharif* includes the millets known as *bajra* (*Pennisetum typhoideum*) and *joar* (*Sorghum vulgare*), the two chief food-grains in Sind, rice, oil-seeds, pulses, and cotton. The area under each staple in 1881–82 was as follows:—*Joar*, 493,694 acres; *bajra*, 474,786 acres; rice, 518,210 acres; oil-seeds, 122,464 acres; wheat, 225,946 acres; cotton, 70,178 acres; barley, 10,630 acres; indigo, 5325 acres; tobacco, 9586 acres; and sugar-cane, 2689 acres; pulses, 90,066 acres; gram, 22,039 acres; miscellaneous products, such as vegetables, fruits, etc., 75,459 acres. The distribution into harvests was as follows:—*Kharif*, 1,652,261 acres; *rabi*, 381,080 acres; intermediate or mixed, 87,731 acres.

The fruits common to the country include dates, plantains, mangoes, limes, oranges, pomegranates, citrons, figs, grapes, tamarinds, mulberries, and melons. The apples of Sind are famous for their fine quality. The British have introduced apricots, peaches, and nectarines, with excellent results. The methods of cultivation still differ little, if at all, from the primitive type. Rotation of crops is unknown, and the implements belong to the coarsest patterns. Two bullocks generally draw the clumsy native plough; while a heavy log of wood, with a man perched on either end, and drawn by four bullocks, does duty for a harrow.

The dry character of the soil, and the almost complete absence of rain, render irrigation a matter of prime importance to the cultivator. Though situated on the very verge of either monsoon, the Province derives no benefit from their rainfall; for the north-western monsoon, which deluges the hills of Balúchistán, extends no farther eastward than Karáchi; while the south-western monsoon terminates at Lakhpat Bandar on the boundary of Cutch (Kachchh), as regularly as though it intentionally avoided the frontiers of Sind. Sometimes, indeed, for two or three years in succession, no rain falls in the Province. Under these circumstances, the Indus almost becomes to Sind what the Nile is to Egypt. Numerous irrigation canals, drawn from the main river or its tributaries, intersect the country in every direction. These canals are carried away from the raised bed of the stream in an oblique direction, so as to secure the greatest possible fall per mile. None of them have their heads where the bank is permanent, and none are deep enough to

draw off water except during inundation. The river must consequently rise several feet before the canals will fill. Many of the channels are old natural beds of the side branches, now deserted, and all have the appearance rather of rivers than of artificial cuts.

The canal system is very imperfect, owing to the want of permanent head works, and the constant accumulation of silt. Cultivation is accordingly exposed to many risks, except in those lands where irrigation is always carried on by means of water wheels, but as this method is expensive, the poorer cultivators prefer the inferior and precarious tillage of lands which can be directly flooded from the canals, while a small deficiency of water often entirely cuts off the whole crop. From the capricious nature of the water supply, cultivation accordingly becomes a species of lottery, the cultivator being rich one season and a bankrupt the next. Too little or too much water, an early or a late supply, may destroy his only chance of a harvest. Owing to the frequent failures, agriculture is, on the whole, a poorly paid occupation, yet the peasantry prefer the gambling risk to steady and well paid labour.

This precarious and uncertain cultivation renders the Sind peasant an improvident and thriftless body. They are almost always in debt to the Hindu money lenders, who often exact as much as ten per cent on their advances. The population is almost wholly engaged in agriculture, yet the Province does not usually produce much more than a sufficient quantity of food grains for its own consumption and considerable imports take place in years of scarcity.

The land tenures of Sind belong to extremely simple types. The landowners may be divided into three classes—large proprietors, a numerically small but very influential body, the holders of smaller estates, of a few hundred acres, answering to the middle-class gentry, and the peasant proprietors, a large body, paying revenue directly to Government, or to the revenue holding Government rights. The British authorities have upheld and fostered the rights of the smaller owners against the encroachments of the *zamindars*; thus encouraging the spirit of independence amongst the cultivating classes.

The total agricultural population of the Province of Sind in 1881 was returned at 496,134, giving an average of 18·2 acres of cultivated land to each. The total agricultural population dependent on the soil amounted to 1,340,239 or 55·52 per cent. of the population of the Province. The total amount of Government revenue, including local rates and cesses on land, £662,022 or 27 acres of 2s. 6½d. per cultivated acre.

Commerce and Communications—The trade of Sind centres entirely upon the great seaport of Karachi, a city of 110,000 inhabitants and now the chief port of entry and exit for the Province. The value of the imports into Karachi in 1881-82 was estimated at £1,770,000.

while those into the whole Province, excluding the capital, were only £32,505. In the same year, the exports from Karáchi amounted to £3,959,333, and from the remainder of Sind to £85,314. The staple articles of export are raw cotton, wool, and grain of various kinds.

Karáchi has long formed the chief outlet for the cotton crops of Sind and the Punjab. The Province at one time actually imported the material necessary for its own petty domestic manufactures from Cutch (Kachchh) and Gujarát, to the amount of several thousand *maunds* annually. About 1840, however, extensive cotton plantations sprang up in Sind itself. In 1861, exports first began; and in 1866 they had reached the total of 28,128,900 lbs. A large portion of this amount, however, came from the Punjab. The home yield at present averages from 18,000 to 20,000 bales annually; though it is calculated that the Province still contains 3,000,000 acres of uncultivated land capable of growing the plant. The remainder consists of Punjab cotton, from the Districts of Múltán, Lahore, and Amritsar; but it bears in European markets the name of 'Sind,' from its place of shipment. Since 1870, a large trade in raw cotton has sprung up with China. The total export of raw cotton in 1882 amounted to 27,802,384 lbs.

The wool of Sind forms a staple of almost equal importance; though the larger portion of the quantity exported comes, not from the Province itself, but from Ferozpur District in the Punjab, and from Afghánistán and Balúchistán. The supply from the latter countries is brought into the market in a dirty condition. The value of wool exported from Karáchi in 1873-74 was £634,874; and in 1881-82, £739,673.

Quite recently a very important and increasing trade in wheat with Europe has sprung up. The supply comes almost entirely from the Punjab. The following table shows the exports of wheat from Karáchi for the twelve years ending 1883-84:—

Year.	Quantity.	Value.	Year.	Quantity.	Value.
	Cwts.	£		Cwts.	£
1872-73, . . .	168,966	75,394	1878-79, . . .	22,333	12,858
1873-74, . . .	797,639	387,314	1879-80, . . .	274,764	153,462
1874-75, . . .	141,872	61,578	1880-81, . . .	169,465	86,757
1875-76, . . .	306,063	129,469	1881-82, . . .	1,852,334	948,243
1876-77, . . .	455,240	195,416	1882-83, . . .	2,732,275	1,281,238
1877-78, . . .	607,470	332,109	1883-84, . . .	4,372,832	1,952,647

NOTE.—In 188c, through railway communication was completed between Karáchi and the Punjab.

Extensive beds of brine salt occur on the Sirgander Creek, an eastern arm of the Indus, said to be capable of supplying the consumption of the whole world for a century. The deposit is remarkably pure, and consists of large crystals. Excise restrictions long prevented it from competing with other Indian salts, but these have now been removed.

The great harbour works of KARACHI are mentioned under that article. Communications are carried on by means of the Indus, by numerous excellent roads by the Sind Larkana and Delhi Railway, and by the Sind Pishin Railway. The river, the great source of wealth to the Province, is under the charge of a special Government department, the Indus Conservancy, which has removed obstructions to navigation as soon as it was possible. The Sind Larkana and Delhi Railway runs from Karachi to Delhi, a distance of 1160 miles, its main object being to facilitate the transmission of goods from Karachi to Northern Sind and the Punjab, thereby thus saving the long detour by sea and river between Karachi and the mouth of the Indus Delta. The Indus at Sukkur has not yet been bridged, but a railway bridge is now (1886) in course of construction. The stone work of the bridge has been finished and its trial completed, only awaiting the arrival of the iron work for the bridge piers from Blackburn & Co. to Rohm. At present, from Rohm on the railway to Sukkur the railway proceeds into Bhirwahpur, crosses the Indus by a Turkish system at Multan. From the Punjab to the Sind by the Delhi and Quetta, about 152 miles have been made by the railway, and only 40 miles of this are in the Province of Sind. The railway, which in 1864, connects Karachi with Lahore, is the first line of communication between the Turkish Government telegraph with the Indian telegraph, and with Western Europe. Another line runs from Karachi to the Mekran coast and thence by submarine cable to Bushire in Persia, connecting with the Russian system, as well as with the submarine telegraph line to England.

Administration—Sind forms a Province subordinate to the Government of Bombay. Its administration is vested in those of KARACHI, SHIKARPUK and HANUWATI, and in the two Districts of THAR and PARKAR and the British Settlements, all under a Deputy Commissioner besides the Native Agents. The total imperial revenue of the Province in 1881-82 was £509,311, of which £482,497 was derived from land revenue, £2553 from a canal maintenance rate levied on the cultivators, and from miscellaneous items of irrigation revenue. The local revenue were—forests, £40,131, excise, £91,051, stamp duty, £2965, registration, £2965, stamps, £38,416, postal, £44,000, telegraph, £12,592, licence-tax, £14,546, customs, £53,417, and

£2555; and *ghí*-tax levied only in Thar and Párkar District, £2236. The local revenue in the same year amounted to £131,521, arising mainly from public works and municipal funds. The land-tax ordinarily forms two-thirds of the net revenue of Sind; but remissions are constantly necessitated by droughts, floods, or bursting of embankments. In spite of these drawbacks, however, the revenue has steadily increased under British rule. The cost of clearing canals forms one of the most important items of public expenditure.

The total police force of the Province consisted in the year 1881 of 4180 officers and men; but the area includes so large an extent of desert, that any general statement of numbers per square mile would only mislead. In Haidarábád District, where population is thickest, there is 1 policeman to every 12 square miles and to every 1019 inhabitants; in Karáchi District, including the capital, there is 1 policeman to every 9 square miles and to every 326 of the population; while in the desert District of Thar and Párkar there is only 1 policeman to every 22 square miles and to every 357 inhabitants. Number of civil judges, 33; and of stipendiary magistrates, 104.

Education has made rapid and satisfactory progress in Sind since the British annexation. In 1859-60, the Province contained only 20 Government schools. The total number of Government schools in 1873-74 amounted to 213, of which 26 were for girls. The number of pupils was 12,728, of whom 8531 were Hindus and only 4139 Muhammadans. In 1883-84, the schools under the Education Department had increased to 340, with 23,273 pupils. The number of indigenous schools at either date cannot be accurately ascertained. The Musalmán population show but little interest in education, and specially neglect that of their daughters. Haidarábád and Sukkur each possess a normal school, and the former town has also an engineering school. Among private institutions, the European and Indo-European schools at Karáchi, and the missionary schools in that town and Haidarábád, teach up to the matriculation standard of the Bombay University. The Census of 1881 returned 27,413 males and 2201 females as under instruction, besides 76,983 males and 2849 females able to read and write but not under instruction. There are four printing presses at Karáchi, and two at Shikárpur.

Medical Aspects.—Owing to its prevalent aridity, and the absence of the monsoons, Sind ranks amongst the hottest and most variable climates in India. The average temperature of the summer months is 95° F., and that of the winter months 60°. But the thermometer frequently rises in summer to 110° and occasionally to 120°; while in winter it falls at night a few degrees below freezing-point, and ranges even in the day-time from 40° to 80°. No other part of India has so long a continuance of excessively hot weather, owing to

the deficiency of rain. The climate on the sea-coast, however, is much more equable in temperature than in Upper Sind, and Karachi, the great centre of European population, enjoys a strong sea breeze, which blows day and night from April to October. In Northern Sind the extremes of temperature are strongly marked. The thermometer at Shikarpur often sinks below freezing point in winter, and ice forms as late as February, yet in summer, for weeks together, the readings at midnight do not fall below 100° F. This great and prolonged heat, coupled with the exhalations arising from the stagnant pools left after the annual inundation, produces a fatal fever and ague. The natives suffer severely from its effects, and British troops have often experienced a terrible mortality. The other prevailing diseases include small pox and cholera. The latter complaint has often appeared in epidemic form, and wrought great mischief in the country districts, but at Karachi, its ravages have lately been averted by the excellent sanitary precautions taken by the British authorities. Five civil surgeons are stationed respectively at Karachi, Haidarabad, Sukkur, Shikarpur and Jacobabad, and an apothecary at Kotri. Numerous charitable dispensaries have been established in all the chief towns. Total number of patients treated in 1883-84 in the several hospitals and dispensaries, 19,422 of whom 5372 were in-door patients. Vaccination has made satisfactory progress, no opposition being raised except amongst the Hindu population. In 1873-74, the Government vaccinators operated upon 105,457 persons.

Sindewahi (Sindhar)—Town in Brahmapur Taluk (Chinda District, Central Provinces, situated in lat 20° 17' N. and long 79° 42' E. 16 miles north of Muli. Population (1881) 4569 mostly Hindus, number 3941, Muhammadans, 56 Jains, 15 and non-Hindus, 557. A fine tank 3 miles north-east of the town irrigates a wide extent of rice and sugar-cane fields. Sindewahi manufactures cotton cloth and bangles, which are exported, and possesses some trade in raw cotton, grain, and sugar. Government school, police bungalow.

Sindgi.—North-eastern Sub-division of Bijapur District, Madras Presidency. Area, 812 square miles. Population (1881) 72,680, namely, males 36,466, and females 36,214, occupying 14,745 houses in 141 villages. Hindus, 63,027, Muhammadans, 9259 and others, 334. Except some villages on the Bhima river, the east of Sindgi is a rough rocky plain, with frequent, and, in some cases, abrupt, hills. It is scantily cultivated, treeless, and monotonous. The portion of the Sub-division on the banks of the Bhima to the north and east is a black soil plain, separated by long, low, step-like ridges of trap. These are mostly formed from the wearing of the trap and laterite, with patches of grey and dark red and sometimes sand. The plain is well cultivated along the river banks, dotted with rich villages. In the south the part watered by the Don river is the best cultivated portion of the Sub-

division. The supply of water is scanty. Of the total area of 812 square miles, 48 square miles are occupied by alienated villages. The remainder contains 389,687 acres of Government and 78,787 acres of alienated cultivable land; 16,415 acres of uncultivable land; 44 acres of forests; and 3356 acres of village sites, roads, and rivers. In 1881-82, 275,625 acres were under actual cultivation; cereals and millets occupied 206,378 acres; pulses, 8503 acres; oil-seeds, 18,779 acres; fibres (cotton), 40,208 acres; and miscellaneous crops, 1757 acres. In 1883 the Sub-division contained 2 criminal courts; police circles (*thānds*), 7; regular police, 46 men; village watch (*chaukidars*), 502. Land revenue (1882), £18,823.

Sindgi.—Chief village of Sindgi Sub-division, Bijapur District, Bombay Presidency; situated 35 miles north east of Bijapur town. Population (1881) 3154. In December 1824, a band of insurgents led by a Bráhmaṇ, Devakar Dikshit, marched on Sindgi, captured the fort, and plundered the town. In 1866 the fort was dismantled. Dispensary.

Sindhiapura.—Petty State of Rewa Kántha, Bombay Presidency. Area, 4 square miles. The chief is named Chauhán Jitabáwa. Estimated revenue, £200; of which £5, 14s. is paid as tribute to the Gáekwár of Baroda. Owing to the insanity of the chief, the estate has been under direct British management since 1870.

Sindhorá.—Village in Benares *tahsil*, Benares District, North-Western Provinces; situated in lat. $25^{\circ} 32' 13''$ N., long. $82^{\circ} 58' 28''$ E., 16 miles north-north-west from Benares city. Population (1881) 1985, principally Bráhmans, Kandu Baniyás, and Chamárs. Large mart for grain and cloth; small manufacture of sugar.

Sindí.—Town in Wardhá *tahsil*, Wardhá District, Central Provinces; situated in lat. $20^{\circ} 48'$ N., and long. $78^{\circ} 56'$ E., 20 miles east of Wardhá town; and a station on the Great Indian Peninsula Railway. Population (1881) 4644, chiefly weavers and cultivators. Hindus number 3970; Muhammadans, 502; Jains, 148; and non-Hindu aborigines, 24. Manufactures—coarse cotton cloth, oil, bangles, and shoes. A market is held every Thursday and Friday. Sindí has a school, a dispensary, and a storage yard for cotton near the railway station.

Sindkher (*Sindkhed*).—Chief town of Sindkher *parganá*, Buldáná District, Berar. Lat. $19^{\circ} 57'$ N., long. $76^{\circ} 10'$ E. Population (1881) 2695. According to one tradition, the town was founded and named about 1000 years ago by a king Sinduráur; according to another, it takes its name from Sidha Khetak, 'village of saints,' an unbroken line of whom are said to have lived here since the foundation of the place. The *parganá* of Sindkher was granted in *jágír* to the Kází of the town about 1450 A.D.; who afterwards gave it over voluntarily to the Jáduns,

the head and founder of whom was Lakhji a Kájput from Kurmah in North Hindustan. Since then, Sindkher has been regarded as the chief seat of this family, who subsequently rose to much fame and power. The *ji, fir* of the *pargana* was held by the Jaduns for about 100 years, but was then restored to the *kazi* of the *day* by Murshid Ali Khan a nobleman who came to Sindkher on a commission from the Delhi Government. The half finished fort still stands north west of Sindkher, it is about 150 yards square. The temple of Nalkatheswar to the south west is supposed to be the oldest structure built by Hemar Panth, it bears an inscription which is however, nearly effaced, being several feet under water in the tank near the temple. Several palaces such as the Mahábhágh, Mahákál, the Dismukhi's residence, and three or four large wells built by the Jaduns attest the magnificence and prosperity of the town in their time. In one of the frequent transfers from the Nizám to the Marathás, Sindkher fell to Sindhira who held it for nearly sixty years. It was restored to the Nizám in 1803. Báji Ráo Peshwa encamped at Sindkher for some days in 1818, when the British troops were on his track. In 1804 General Wellesley (Wellington) wrote 'Sindkher is a nest of thieves, the situation of this country is shocking the people are starving in hundreds and there is no Government to afford the slightest relief.' The decline of the town was hastened by marauders whose names—Mohan Singh Budhni Shah and Gházi Khán—are yet remembered with terror. Of the once extensive irrigated gardens of Sindkher, only a few fruit trees survive.

Sindkhera.—Town in Virdel Sub-division Khándesh District, Bombay Presidency, situated in lat $21^{\circ} 17' 30''$ N and lon $74^{\circ} 50' 1''$ E 14 miles north of Dhulá. Population (1881) 4,993. Head-quarters of Virdel Sub-division. Municipal income in 1883-84, £141. incidence of taxation per head of population 5½d. Post office.

Sindurjana.—Town in Amraoti District Berar.—See *SINDURJANA*.

Sindwa.—Village and fort in Central India situated in lat $21^{\circ} 40' 5''$ and long $75^{\circ} 20' 1''$ E (Thornton), on the route from Mhow to Bombay, 90 miles south west of the former town and 274 north-east of the latter. It lies 9 miles north of the Sindwa Ghat a somewhat steep but much frequented mountain pass leading from the highlands of the Satpura range to the valley of the Narmada in Khándesh. On the south side, Sindwa is a strong square fort with a front of about 265 yards most of it built of fine cut stone and mortar. It had nine round towers one at each angle, as well as one in the centre of each curtain. Four gateways were protected by strong mud outworks. A dry ditch of no great size runs along the north-east and south faces. The town inside the walls has a mud fort in its centre. The grand entrance on the south consists of a very strong gateway flanked by two large round

towers, with a commanding terrace and curtain running between. Wide ramparts surround the fort, with several guns of different sizes. One or two large reservoirs, well provided with water. Ceded to the British Government by Holkar under the treaty of Mandeswar (1818); but restored to him upon the condition of his building a bridge over the Gohi river.

Singa.—Mountain pass in Bashahr State, Punjab; leading across the Himálayan range, which bounds Kunáwár to the south. Lat. $31^{\circ} 15'$ N., long. $78^{\circ} 29'$ E. Stated by Thornton to be open from May till the middle of August, but impracticable at other times from the depth of the snow. Elevation above sea-level, between 16,000 and 17,000 feet.

Singálilá.—Hill range in Dárjiling District, Bengal. An immense spur, 60 miles long, stretching south from Kánchanjangá to the plains of India, and separating Sikkim from East Nepál. Lat. $27^{\circ} 1'$ to $27^{\circ} 14'$ N., and long. 88° to $88^{\circ} 2'$ E. The waters from its west flank flow into the Támbár, and those from the east into the Great Ranjít, a feeder of the Tísta. The highest peaks of the Singálilá range are—PHALALUM, 12,042; SUBARGUM, 10,430; and TANGLU, 10,084 feet.

Singampunári.—Village in Tirupatúr *táluk*, Sivagangá *zamíndári*, Madura District, Madras Presidency. Population (1881) 5769, namely, Hindus, 5638; Muhammadans, 114; and Christians, 17.

Singánallúr.—Village in Coimbatore *táluk*, Coimbatore District, Madras Presidency, and a station on the south-western line of the Madras Railway; situated in lat. $12^{\circ} 9'$ N., and long. $77^{\circ} 16' 40''$ E. Population (1881) 7793, occupying 1632 houses. Hindus number 7743; Muhammadans, 15; and Christians, 35. The town and fort were destroyed by the Maráthás. The town has recovered under British rule, and is now a busy place.

Singanmat.—Principal peak in the Sankara range, Santál Parganás District, Bengal. Well known as a landmark to all the country round. As recently as 1867 a human sacrifice was made on the summit of this hill as a propitiatory offering by the Mál Paháriás of Sankara village.

Singapur (*Singapuram*).—Town in Jaipur (Jeypore) State, Vizagapatam District, Madras Presidency; situated in lat. $19^{\circ} 3' 19''$ N., and long. $82^{\circ} 43' 16''$ E., 21 miles west of Bissem Katak on the Banjara route to Nágpur. Population (1881) 999, chiefly Uriyás, dwelling in 229 houses.

Singárapet (*Singaricotta*, *Tingrecotta*).—Pass connecting the Districts of Salem and South Arcot, Madras Presidency.—*See* CHENGAMA.

Singaurgarh.—Hill fort in Damoh District, Central Provinces; situated in lat. $23^{\circ} 32' 30''$ N., and long. $79^{\circ} 47'$ E., 26 miles north-west of Jabalpur city, on a high hill commanding the narrow Sangrámpur valley. Founded by Rájá Bel, a Chandela Rájput, it was enlarged by Rájá Dalpat Sá, of Garha-Mandlā, who made it the seat of Government

about 1540. It was the scene of the defeat of Rānī Durgāvatī by Aṣaf Khān, an officer of Akbar, and the fort sustained a siege of nine months in the days of Aurangzeb. The remains of the outer circumvallation are very extensive. Of the inner fort on a high central hill, only a tower and some ruined reservoirs remain. Two smaller towers also stand on neighbouring hills.

Singhāna—Town in the Shaikhāvātī district of Jaipur State, Rājputāna, situated in lat $28^{\circ} 5' N$, and long $75^{\circ} 44' E$, 95 miles south west of Delhi, and 80 north of Jaipur city. Population (1881) 5259, namely, Hindus, 3117, Muhammadans, 2123, and 'others,' 19. Elphinstone describes it as a handsome town built of stone, on the skirts of a hill of purplish rock, about 600 feet high. A copper mine in a rocky hill, 3 miles south west of the town, contains ore of a poor quality, yielding from 2 to 7 per cent of metal. There are two ores, a sulphate and a sulphuret. This mine having become less productive than formerly, has been closed since 1872. The miners used to pay to the Rājā a duty on the produce. Post-office.

Singhbhum (*Sinha-bhumi*, 'Lion Land')—British District in the Lieutenant Governorship of Bengal, lying between $21^{\circ} 59'$ and $22^{\circ} 53' N$ lat, and between $85^{\circ} 2'$ and $86^{\circ} 56' E$ long. Area, 3753 square miles. Population (1881) 453,775 souls. The District forms the south eastern portion of the Chutī Nāgpur Division. It is bounded on the north by the Districts of Lohārdagā and Mānbhum on the east by Midnapur, on the south by the Tributary States of Orissa, and on the west by Lohārdagā and the Tributary States of Chutī Nāgpur. The boundaries follow for the most part the crests of the hill ranges which wall in the District on every side, but owing to the fact that few of the ranges have distinctive names, it is impossible to define the boundary line more precisely. A portion of the northern boundary, 15 miles in length, is marked by the Subarnarekhā river, which fills a gap between two hill ridges, and a still smaller part of the southern boundary coincides with the same river, which here separates Singhbhum from the Orissa State of Morbhanj. Farther west, again, the Baitarnī river, rising in Keunjhar, forms 8 miles of the boundary between that State and Singhbhum District. Singhbhum District is made up of the Government estate of the Kolhān or Ho-desam ('country of the Hos'), the Fiscal Division of Dhalbhum, and the political estates of Parahāt, Sāraikālā, and Kharsāwan. The administrative head-quarters are at CHANDASA.

Physical Aspects—The central portion of Singhbhum consists of a long undulating tract of country, running east and west, and enclosed by great hill ranges. The depressions which lie between the successive ridges are terraced for rice cultivation on the system followed in the Districts of HAZARIBAGH and LOHARDAGĀ, and the scenery in this central strip,

extending from the Subarnarekhá river on the east to the Angárbari range to the west of Cháibásá, which is the most fertile part, is like that of Chutiá Nágpur Proper. It is fairly clear from forest, and varies in elevation above sea-level from 400 feet near the Subarnarekhá on the east, to 750 feet around the station of Cháibásá. To the south of this is an elevated plateau embracing 700 square miles of country, where the general level rises to upwards of 1300 feet, and meets the hills of Keunjhar State in Orissa. The west of the District, bordering on Chutiá Nágpur, is a mountainous tract of vast extent, sparsely inhabited by the wildest of Kol tribes, and considered by Colonel Dalton to be the region from which that race first descended into the plains of Singhbhúm.

The éxtreme south-west corner, bordering on Gángpur State, is a still grander mass of mountains, rising to a height of 3500 feet, and known as 'Saranda of the seven hundred hills.' The population here is very scattered; and the whole of Saranda contains but a few poor hamlets nestling in deep valleys, and belonging for the most part to one of the least reclaimed tribes of Kols. From the Layadá Hill range on the north-west of Singhbhúm, many rocky spurs strike out into the District, of which the more prominent attain an elevation of 2900 feet.

Among other ranges and peaks, the following may be mentioned:—The Chaitanpur range, in the estate of Kharsáwán, reaches an elevation of 2529 feet. The Kápargádi range, a conspicuous ridge, rises abruptly from the plain; its highest peak is 1398 feet above the sea, and from that point the range runs south-east till it culminates in Tuilígarh Hill (2492 feet). Thence the ridge gradually widens out, till it forms the northern limit of the Meghásani range in the Orissa State of Morbhanj. On the south-west of the District, a series of hills without any general name rise to a height of 3500 feet, and entirely occupy the tract referred to above as 'Saranda of the seven hundred hills.' A conspicuous spur of this mass of hills stretches out towards Cháibásá, and culminates in the peak of Angárbari, 2137 feet high.

The Singhbhúm hills present in appearance a broken outline of sharp-backed ridges and conical peaks. For the most part they are covered with thick forest, except on the borders of the central fertile plateau, where many of the lower slopes have been cleared for the purpose of cultivation.

The principal rivers of the District are the SUBARNAREKHA (chief affluents, the Karkai and Sanjai), which drains the eastern portion of the District bordering on Midnapur; and the KOEL, with its affluents the North and South KARO and the KOINA, which receives the drainage of the western part of the District, and of the mountainous region of Saranda. The beds of all the rivers are rocky, and

barriers to navigation exist in many parts of their course. The banks are steep and covered with jungle, and no system of river bank cultivation is known in the District.

There are no canals or lakes in Singhbhum, and the only form of artificial irrigation is the construction of embanked reservoirs across the upper ends of the natural depressions in which rice is grown. Water is thus stored, and is let out upon the crop by channels cut through or round the embankment.

Minerals—Iron in a nodular form is obtained in most of the hills ranges. The nodules are small, of a dull red colour, and show a glossy surface if subjected to friction. Ore also occurs in the form of a black earth, which is rich in metal, and is usually found in stratified masses, which have to be dug out and broken in pieces before smelting. The furnaces used are built of mud in a cylindrical form, and are about three feet high. They are charged from the top with alternate layers of ore and charcoal, and, after smelting, the iron is taken out from the bottom of the furnace. The blast is obtained from two cup-shaped bellows, which are worked alternately with the feet. Good iron is found in minute quantities in the sands of the rivers in the form of spangol. Copper was formerly obtained from the foot of a range of hills in Dhalbhum, old workings, ascribed to the Jains, are found, extending over many miles, and the operations appear to have been thoroughly exhaustive. Subsequent attempts made to work the mines by European methods have proved unremunerative. Nodular limestone (*limestone* or *glutin*) occurs all over the District, but not in sufficient quantities to be useful for road making. Slate and coloured earths are found to the south west of Cháibásá. Soapstone occurs in several places, and is manufactured into cups and platters.

Forests, Jungle Products, etc—About two-thirds of Singhbhum District are covered with primeval forest, the principal trees being *Shorea robusta*, *dsan* (*Terminalia tomentosa*), *gam-jar* (*Gmelina arborea*), *lusam* (*Schleichera trijuga*), *tan* (*Cedrela Toona*), *pal-jar* (*Pterocarpus Marsupium*), *sissu* (*Dalbergia Sissoo*), *kes* (*Albizia melanoxylon*), and *simun* (*Eugenia jambolana*). Of these, the *tan* is the most valuable, for the hardness of its timber and the size of the beams which the larger specimens yield. The *pal-jar* is a light, soft wood, but, unless well varnished, gives out a very disagreeable odour when wetted. No teak is met with, and no rattan. Jungle products of various kinds abound, but, owing to the isolated position of the District, they command only a nominal value, and yield no revenue. The chief articles of jungle produce are lac, beeswax, *chit*, or the bark of certain creepers twisted into rope, *Asi* grass, which is used for making mats, and a variety of leaves and roots, which are used for food.

The forests give shelter to tigers, leopards, bears, &c., and are the

kinds of deer; and small herds of elephants occasionally wander across the boundary from the Meghāsani Hills in Morbhanj. Wild ducks, pigeons, geese, snipe, partridge, and quail are found in the low-lying lands. The pangolin or scaly ant-eater is one of the curiosities of the District. Snakes of all kinds abound.

History.—The following section of this article is condensed from Colonel Dalton's valuable *Ethnology of Bengal*, the portions used being quoted in full in Hunter's *Statistical Account of Bengal*, vol. xvii. pp. 107–114. The Singhbhum Rājput chiefs have been known to the officers of the British Government since 1803, in which year the Marquis of Wellesley, Governor-General, caused friendly communications to be addressed to the ancestor of the present Rājā of Sāraikalā (whose territory adjoined the Jungle Mahāls, then under the East India Company), regarding the assistance which he promised to render in the prosecution of the war against Rāghuji Bhonsla of Nāgpur. There does not appear to have been any intercourse between British officials and the people of the Kolhān previous to the year 1819. Of the interior of their country, for years after the acquisition of the surrounding Districts, nothing whatever was known. The Hos or Larka Kols would allow no strangers to settle in, or even pass through, the Kolhān; and pilgrims to Jagannāth had to make a circuit of several days' journey to avoid it. In 1819, the Assistant Political Agent was directed to proceed to Parāhāt, to negotiate a settlement with its chief; but he did not succeed in penetrating so far into their country, owing to the fears entertained by the people of the savage character of the aboriginal Kols. The Political Officer writes—'The Rājā and the *samindārs* of Singhbhum, who are in attendance on me, have so formidable an opinion of the power and ferocity of these savages, that, notwithstanding the considerable force under my command, they are evidently much alarmed, and have made a formal protest against the dangers of the march.'

In 1820, the Rājā of Parāhāt acknowledged himself a feudatory of the British Government, and agreed to pay a small tribute. At this time, the Rājā and *samindārs* of Singhbhum were pressing on the Political Agent, Major Roughsedge, their claims to supremacy in the Kolhān, asserting that the Kols were their subjects in rebellion, and urging on Government to force them to return to their allegiance. The Kols denied that they were subject to the chiefs. Until they quarrelled they regarded them, they said, as friends and allies, not as rulers; and if they had at any time been their subjects, they had achieved their liberty in various hard-fought fields, and were entitled to their independence. The chiefs admitted that for more than fifty years they had been unable to exercise any control over them; and Major Roughsedge refers to three formidable but abortive attempts made (the

last in 1800) to subjugate them. After these attacks on their independence, it appears that the Larkas retaliated on all the bordering villages, committing great ravages and depopulating entire villages.

In 1820, Major Roughsedge entered their country with a force of artillery, cavalry, and infantry, with the avowed object of compelling the Kols to submit to the Rájás who claimed their allegiance. He did his best to conciliate them, and was at first in hopes that he had succeeded. He was allowed to advance unmolested into the heart of the territory, but while encamped at Chálása on the Kor river near the present station of the same name an attack was made with a sight of the camp by a body of Larkas who killed one man and wounded several others with their battle axes. They then moved away towards the hills, but their retreat was cut off by Lieutenant Macland who in several encounters dispersed them with great loss. The whole of the northern *prís* or communities entered into engagements to pay tribute to the Rájá of Singhbhūm. But in leaving the country Major Roughsedge had to encounter the still fiercer Kols of the southern *prís* and after fighting every inch of his way out of Singhbhum he left them unsubdued. Immediately afterwards, a war broke out between the Larkas who had submitted and those who had not, and a body of 100 Hindustani Irregulars sent to the assistance of the former were driven out by the latter.

In 1821, a large force was employed to reduce the Larkas and after a month's hostilities, the leaders encouraged by a promise made to them, rendered, and entered into agreements to pay tribute. The Rájá had agreed that 'if they were oppressed by any of the chiefs, they would resort to arms, but would complain to the chief commanding the troops on the frontier, or to some other competent authority. After a year or two of peace, however they again became restless and gradually extended the circle of their depredations. The assistance rendered by the Rájá's Kols in the rebellion of 1831 was too great for the Government to escape serious notice. Sir Thomas Munson, who was then Agent to the Government of the North Western Provinces and Non Regulation Province of the South Western Provinces, recognised the necessity of a thorough subjugation of the Kols. He proposed an occupation of Singhbhum by an expedition and suggested that, when the people were brought under control, they should be placed under the direct management of a British officer stationed at Chálása in the heart of the country. These views were adopted, a force under Colonel Richards entered Singhbhum in 1836, and by the end of the February following the whole of the head men had submitted and entered into engagements to pay

bear true allegiance to the British Government. From this time until 1857 there was no disturbance, and the District seemed to have settled down into quietness and prosperity. In that year, the Paráhát Rájá, after wavering for a little between loyalty and rebellion, chose the latter, and a considerable section of the Kols supported him. A tedious and difficult campaign ensued, the rebels taking refuge in the mountain fastnesses whenever they were driven from the plains. Eventually, however, they surrendered (in 1859), and the capture of the Rájá put an end to the disturbances.

Since that year the Kols have given no trouble. Under the judicious management of a succession of officers, whose names will always be household words in the Kolhán, these savages have been gradually tamed, softened, and civilised, rather than subjugated. Up to a few years ago, they steadily opposed the opening of roads through their territory, removing from the villages to the hills (their usual custom when dissatisfied and excited) till the obnoxious posts set up to mark the alignment were taken down, and the project abandoned. Now their country is in all directions traversed by good roads, made by themselves under the superintendence of their officers. New sources of industrial wealth have been opened out, new crops requiring more careful cultivation introduced, new wants created and supplied; even a desire for education has been engendered and fostered, and already well-educated Kols are to be found among the clerks of the Chái-básá courts. The ameliorating influences of Christianity have also made themselves felt, in a striking manner, among the Kols. The work has gone on with increasing vigour of late years, and the number of converts is now much larger than the returns of 1881 (quoted below) indicate.

Population.—The first attempt at an enumeration of the people of Singhbhúm was made in 1867, when a Census was undertaken of the Government estate of the Kolhán. From the results of this, an estimate was made for the total population of the District, as then constituted, which amounted, according to the calculations, to 355,906 souls. The regular Census of 1872, on an area corresponding to the present District, returned the population at 318,180. The last enumeration in 1881 disclosed a population of 453,775, showing an apparent increase of 135,595, or 42·61 per cent., in nine years—an increase, however, mainly due to defective enumeration in 1872.

The results of the Census of 1881 may be summarized as follows:—Area of District, 3753 square miles, with 1 town and 3000 villages; number of houses, 86,306, namely, occupied 85,843, and unoccupied 463. Total population, 453,775, namely, males 226,681, and females 227,094. Average density of the population, 121 persons per square mile; villages per square mile, 0·80; persons per village, 151; houses

per square mile, 23, inmates per house, 5.29. Classified according to sex and age, the population consisted of—Under 15 years of age, boys 100,404, and girls 95,695, total children 196,099, or 43.2 per cent of the population 15 years and upwards males 126,277 and females 131,399, total adults 257,676 or 56.8 per cent.

Religion—Classified according to religion the population in 1881 consisted of—Hindus, 447,810 or 98.68 per cent of the total Muhammadans, 2329, Christians 2988 and others, 648 consisting entirely of non Hindu Santals.

Among aboriginal tribes the most numerous are the Kols, of whom there were 187,723 in 1881 all returned as Hindus by religion. The name Kol, as popularly used includes not only Hos and Mundas, but also the Dravidian Uraons while its scientific use embraces the cognate Kolarian tribes of Mundas, Hos or Larka Kols, Khums and Kharwars. The two last tribes are returned separately in the Census Report of 1881, the former numbering 40,000 and the latter 3900, thus making a total Kol population of 131,615 or 51 per cent of the whole District. The bulk of the Kol enumerated are the Hos, otherwise called Larka or light Kols, who are the characteristic aboriginal race of Singbhum.

A detailed account of this tribe taken from Colonel Dalton's *Sketch of Bengal*, will be found in *The Statistical Atlas of Bengal* vol. vii pp. 39-59 and in a more abbreviated form under the article Kols, *ibid.*, vol. viii pp. 253-260. The Kols appear to have no tradition of origin or migration that throw much light on their history. As has been said in the preceding section they isolated themselves for many years, and even at the present day the exclusiveness of the old Hos is remarkable. They will not allow aliens to hold lands in their villages, and, indeed if it were left to them no strangers would be permitted to settle in the Kolhan. Physically the Kols are the finest of all the Kolarian tribes. The men average 5 feet 6 inches in height, the women 5 feet 3 inches, and the women are noticeable for their fine erect carriage and intelligence. They do not encumber themselves with much clothing, and even wealthy men move about all but naked as if they were in the tropics, in purple and fine linen. The Hos are far from being idle, and are great sportsmen. They are a just and brave people, and their festivals are all connected with that spirit. They have a great reverence for the dead, and their peculiar funeral and other ceremonies are well described by Colonel Dalton. The Hos are never rude, a love, or at least the practice of, cleanliness and respect, rendering them keenly sensible of the advantages of civilization, and since they have come under our rule, they have been

picious, less revengeful, less bloodthirsty, less contumacious,' than they were. They are still, however, easily excited to rash action.

Of the other aboriginal tribes in Singhbhúm, Santáls number 52,602, of whom all but 648 are returned as Hindus. Bhuiyás number 8141; Gonds, 1628; and 'others,' 10,513. Total aborigines, 304,499, or 67·1 per cent. of the District population. It is singular that, although the Singhbhúm aborigines are the wildest and most backward of all the Districts of the Chutiá Nágpur Division, the whole of the aboriginal population, with the exception of 648 Santáls, should be returned as Hindus by religion.

Among recognised Hindus, the higher castes are numerically very weak. Bráhmans number only 2886; Rájputs, 1949; Káyasths, 993; Khandaits, 391; and Baniyás, 2259. Among the lower or Súdra castes are included the following:—Goálá, the most numerous caste in the District, 38,672; Tántí, 20,839; Kúrmí, 9122; Lohár, 7728; Kumbhár, 6882; Telí, 3394; Dhobí, 2626; Sunri, 2611; Málí, 2342; Nápit, 2321; Dom, 2171; Harí, 1355; Sadgop, 1239; and Baurí, 1055. Caste-rejecting Hindus number 3491, including 2868 Vaishnavs.

The Muhammadans only number 2329, or 0·5 per cent. of the District population. None of the reforming sects of Islám are represented in Singhbhúm; and the existing Musalmán community makes no converts, except among Hindus who have been expelled from their caste. Nearly the whole of the native Christians are converts from the aboriginal races. Three missions are at work in the District—the Society for the Propagation of the Gospel, the Lutheran Evangelical Mission, and a Roman Catholic Mission.

Urban and Rural Population.—The population is entirely rural, and the only place with upwards of five thousand inhabitants is CHAIBASA, which in 1881 contained a population of 6006. Of the 3000 villages, no less than 2276 contained less than two hundred inhabitants; 611 had between two hundred and five hundred; 106 between five hundred and a thousand; and 7 between one thousand and two thousand inhabitants. In the wilder jungles to the south and east of the Kolhán proper, there still exist, in the shape of tanks and architectural remains, traces of a people more civilised than the Kols of the present day. The most interesting of these are—Benu Ságar, a fine tank surrounded by the ruins of what must have been a large town; Kiching, with its temples still resorted to by pilgrims; and two very curious artificial pools of water, called the Surmí and Durmí. The sepulchral and monumental stones which are characteristic of the Mundas and Hos occur in large numbers throughout the District.

The Material Condition of the People.—The wonderful progress in the material condition of the people that has taken place of late years may

be vividly illustrated by two quotations from Government Reports. In reporting on Singhbhum District in 1854, Sir Henry Ricketts referred in the following terms to Captain Haughton's proposal that the *fan* or customary price paid for a wife should be abolished, as being a serious check to the increase of population — 'For some reasons it certainly would be good were the custom abolished, but so long as the Kols continue to be what the Kols are now, any plan which has the effect of preventing an increase of their numbers is not without advantage. I cannot consider it desirable that there should be more Kols, though I would omit no endeavour to improve the condition, both moral and physical, of those who unfortunately hold some of the furthest *parçai* of Singhbhum.' In 1873, Captain Garbett described the Kol villages as 'perfect pictures of comfort and prettiness' adding that 'the brisk attendance and business done at markets, the increasing use of brass instead of earthen utensils, the more common wearing by the women of a better description of *sari*, and a dozen other indications in themselves perhaps slight, but important in the aggregate, all attest the growing progressive prosperity of the people. This improvement has been accompanied by a marked increase in the numbers of the people. In the hills and backwoods, types of the more primitive Ho may still be found, but in a few more years if these wild foresters remain in their present condition, they will be altogether repudiated by their refined brethren round Cháibásí. The Hindu inhabitants of Singhbhum, chiefly Mathurbásis, Goálás and Kurmís, are good cultivators and some have risen to be substantial farmers. They are particularly enterprising in reclaiming waste land and founding new villages. Certainty of tenure, freedom from agrarian disputes and low rates of rent all over the District are the chief causes which have effected this change in the material condition of the people aided by the extension of roads in all directions, the development of fresh sources of industrial wealth—such as the trade in *tasar* silk—the cultivation of new crops and the gradual spread of education.

Agriculture—The system of rice cultivation is similar to that described in the article on HAZARIBAGH, though it is not so fully developed here as in that District and LOHARDAGA. Land is classified on the same principle, and the crops are the same, but except in villages occupied by the Hindu caste of Kurmís, the general style of cultivation is primitive, and the land undergoes scarcely any systematic preparation for the crop. Of late years, however, the Kols have made a considerable advance in the methods of tillage, and now get three crops in the year when formerly they had but one. The chief crops of the District besides rice, are wheat, Indian corn, peas, gram, mustard, sugar-cane, cotton, and tobacco. The area under different crops has been estimated as follows—Rice, 503,233 acres, cotton, 23,637 acres, Indian corn,

63,029 acres; oil-seeds, 40,665 acres; wheat, 1271 acres; pulses, 3813 acres. As, however, great uncertainty attaches to all the agricultural statistics of the Chutiá Nágpur Division, these figures must be looked upon as approximate only. Wages in Singhbhúm have not risen of late years in proportion to the increase in the price of ordinary food staples. Labour is abundant, and families are, as usual in the case of a considerable aboriginal population, large. Unskilled labourers (male) receive from 2½d. to 3d. a day, and females 1½d. The rate for women is the same as it was in former times, but men used to receive only 1½d. Bricklayers and carpenters now earn 6d. per diem; formerly their wages were 3½d. The average price of the best cleaned rice is about 2s. 9d. per cwt., and of coarse rice 2s. 3½d. The price of the best unhusked rice is about 1s. 1d., and of Indian corn 1s. 8½d. per cwt. These prices represent a rise of from 25 to 50 per cent. on the rates which ruled twenty years ago.

The prevailing land tenures vary in different parts of the District. In the Kolhán there is now only one kind of tenure,—under which rent is paid direct to Government by each individual cultivator, whose right of occupation is hereditary, but liable to enhancement of rent at the expiration of the current settlement. Dhalbhúm bears a fixed assessment of £426, 14s. It was originally one of the Jungle Maháls, and was transferred to Singhbhúm from Mánbhúm in 1846. The proprietor of the *parganá* calls himself Rájá, but he is officially styled *zamíndár*. The Kolhán pays an assessment of £4606 a year; the Paráhát estate, £1760; and Baudgáon, £67. Among the intermediate tenures between the *zamíndár* and the cultivators may be mentioned—*khoroposh* or maintenance grants (74 in number) to younger members of the *zamíndár's* family; *ghátwáli* tenures for some kinds of police service, the precise nature of which cannot now be ascertained; and *sad chakrán* holdings (51), service tenures entirely dependent on the pleasure of the *zamíndár*. The other prevalent intermediate tenures are—*Brahmottar*, 93; *debottar*, 85; and *pradhání* or farming leases for (839) limited or (74) unlimited periods. The actual cultivating tenures in Dhalbhúm are known by the generic term *prajáli* (from *prajā*, a peasant), and are of two kinds, *khínt katti* and *thiká*. The *khínt katti* cultivators are supposed to be descendants of the persons who originally reclaimed the land from jungle, and formed the village; all of them have permanent rights of occupancy, and some have the further privilege of holding at a fixed rate of rent. Cultivators holding under the *thiká* tenure are persons who came into the village after the first reclaimers. Their holdings are not transferable, and they have no share in the common rights of the village. *Chakrán* or service holdings are very numerous, and the chiefs consequently derive a proportionally small income from their large estates.

Natural Calamities—The District is subject to partial scarcities, caused by deficiency in the local rainfall. In years of drought, the cultivators resort to artificial reservoirs, wells, and tanks for water to irrigate their fields. The famine of 1866 was felt throughout the District, but only severely in Dhalbhum, where the chief food of the people is rice. The highest price reached for ordinary rice in Singhbhum in that year (in August) was £1, 2s a cwt. The District mainly depends on the winter rice, and if the yield of that crop were to be less than one half, and if the price of ordinary rice were to rise as high as from 7s to 9s a cwt, these symptoms should be considered as a warning of approaching famine.

Commerce and Trade, etc—The trade of Singhbhum is carried on mainly by means of permanent markets, the chief of which are held at Chaibasa, Kharsawan, Saraikala, and Baharagurha. The principal exports are grain, pulses, oil seeds, stick lac, iron, and *tasar* silk cocoons, the chief imports—salt, cotton yarn, English piece goods, tobacco, and brass utensils. The value of the silk export was estimated in 1871 to amount to £10,000, and it is said that the total value of the exports largely exceeds that of the imports. The chief manufactures of Singhbhum are coarse cotton cloth, brass and earthenware cooking utensils, and soapstone platters. There are a few weavers of *tasar* silk cloth in Saraikala. Copper is found in Saraikala and Dhalbhum, and an English Company was started in 1857 to work the mine. The enterprise was conducted on too expensive a scale, and failed in 1859, a second Company, formed in 1862, was not more fortunate, and was dissolved in 1864, without having even paid rent for the two years over which its operations extended. The total length of roads in Singhbhum in 1883 was 536 miles.

Administration—In 1837, the revenue of the District, which was then smaller in area than at present, amounted to £527, almost entirely derived from land, and the current expenditure to £1011, or nearly double the revenue. In 1846, the *pargana* of Dhalbhum, assessed in perpetuity at £426, was added to the District, and in 1850–51, the total revenue was returned at £1219, and the civil expenditure at £1928. Thus within a period of thirteen years between 1837 and 1850–51, the revenue more than doubled owing partly to the extension of cultivation in the Kolhan, and the other partly from Dhalbhum. It failed, however, to cover the expenses of civil administration, which had increased by 58 per cent. in the same period. In 1870–71, the net revenue had risen to £1,000 and the total expenditure to £1,063. In 1883–84 the revenue was £10,084, and the cost of civil administration £1,000. The land-tax forms by far the largest item in the revenue of the District. In 1837 it amounted to £523, derived from the

Kolhán. In 1846, the land revenue was £1133; and the *samináir* of Dhalbhúm was the only registered proprietor, and Dhalbhúm and the Kolhán were the only two estates on the District rent-roll. In 1883-84, the land revenue was £6096, the number of estates being four, namely, the Kolhán, Dhalbhúm, Paráhát, and Baudgáon.

In 1883, the regular police force numbered 161 men of all ranks, maintained at a total cost of £3277. There was also a rural police or village watch of 546 men, maintained by contributions from the villagers, and costing £956. The total machinery, therefore, for the protection of person and property in the District consisted of 607 officers and men, showing (according to the Census returns of area and population) 1 man to every 6·2 square miles of the area and to every 747 of the population. The estimated total cost was £4233, giving an average of £1. 2s. 6½d. per square mile of area and 2¼d. per head of the population. Suicide is a characteristic crime of the District, chiefly among the Kols, who are an extremely sensitive race. The average daily number of prisoners in the Cháibásá jail in 1883 was 63.

The progress of education in Singhbhúm has, owing to its secluded position, been very slow, but of late years there has been a great improvement. The number of Government and aided schools in 1870-71 was 9, with 684 pupils. By 1882-83 the number of schools had increased to 170, and the pupils to about 8500. The Census Report of 1881 returned 4540 boys and 107 girls as under instruction, besides 4655 males and 132 females able to read and write but not under instruction.

There are no administrative Sub-divisions in Singhbhúm, nor are there any *parganás* properly so called. The real internal divisional units of the District are the estates already referred to. The *pír*, or group of villages, is the administrative unit of the old village organization of the Hos and Mundas; but the fiscal character which it bears in the Kolhán is solely of British institution, and does not form part of the indigenous system. It is both smaller and more symmetrical than the *parganá* of the Regulation Districts.

Medical Aspects.—The climate of Singhbhúm is, as might be supposed from its inland position, dry. The civil station of Cháibásá is healthy, but the jungle-clad hill tracts are so malarious that they cannot be visited with safety before the month of November. December and January are the coldest months, and at this season the thermometer sometimes falls as low as 50° F. The weather in the hot season is extremely trying, the thermometer frequently marking 106° F. in the shade. The average annual rainfall is returned at 57 inches. The prevailing endemic diseases are intermittent and remittent fevers of the ordinary type. Epidemics of small-pox and cholera have occasionally occurred; the severest recent outbreak of cholera was that which immediately followed the famine of 1866. There is a charitable

dispensary at Cháibásá. [For further information regarding Singhbhum, see *The Statistical Account of Bengal*, by W W Hunter, vol xvii pp 1-146 (London, Trubner & Co, 1877), also Mr (the late Sir Henry) Rickett's *Report on Singhbhum District* (1854), the *Bengal Census Report* for 1881, and the several annual Administration and Departmental Reports of the Bengal Government]

Singheswarthán—Village in Bhágalpur District, Bengal, situated in lat. $25^{\circ} 58' 48''$ N, and long $86^{\circ} 50' 31''$ E, 4 miles north of Madah purá. Well known in Behar for being the scene of the largest elephant fair north of the Ganges, this is held in January, and attended by traders from Purnáh, Monghyr, Tirhut, and the neighbouring parts of Nepál. Native shoes, English cloth, horses, long Nepálese knives or *kukris* form the other principal articles of commerce. Temple belonging to the Pándes.

Singhpur—Town in Narsinghpur *tahsil*, Narsinghpur District, Central Provinces. Population (1881) 3130, namely, Hindus, 2612, Muhammadans, 343, Kabirpanthis, 40, and non Hindu aboriginal tribes, 135.

Singhpur (or *Souasthan Sinhpur*)—Petty State in the Mehwas tract of Khándesh District, Bombay. Population (1881) 646. A small tract of plain country covered by thick forest, which, besides timber, yields *mahuá* flowers, wax, and honey. The soil is good, but, except near villages, is little cultivated. The chief is a Bhíl.

Singimárá.—Village in the south west of Goalpára District, Assam, near the left bank of the Brahmaputra, about 42 miles west of Tura station in the Gáro Hills, with which it is connected by road. An important weekly market is held in the village, which is largely resorted to by the Gáros.

Singimárá—Principal river of Kuch Behar State, Bengal. Entering the State under the name of the Jál dhaká, at its extreme north west corner, near Moranger hát in Khati, it flows in a south-eastern direction by the villages of Giladangá, Panigrám, Dhaibangá, Khaterbarí, and Mátábhángá. In the middle of its course it is called the Mansháhi, and lower down, the Singimárá. It has several cross communications with the Dharíá or Torshá, and finally joins that river on the southern border of the State, near the trading villages of Durgápur and Gitá dahá. It has several large tributaries, among which may be mentioned the Mujná, Satangá, Duduyá, Dolang, and Dálkhodá. The capital of Kuch Behar was formerly situated on the banks of the Singimárá, near Gostinimárá (at Kamatápur), where the ruins of temples and fortresses still attest the bygone greatness of former days. The river is navigable all the year round by boats of 100 *maunds* burden as far as the Sub-divisional station of Mátábhángá, and even a little beyond, and in the rainy season is largely used for navigation.

Singlá.—River in the extreme south-east of Sylhet District, Assam, flowing north from the Lushái Hills into the Kusiára branch of the Surmá river. It has given its name to an elephant *mahál* or hunting-ground, and also to a forest reserve.

Singpho Hills.—Tract of country bordering the extreme eastern frontier of Assam, occupied by the Singphos, a wild tribe who are said to be an offshoot of the Ka-khyens of Burma. In their own language, the word 'Singpho' means man. In ethnical characteristics, language, and religion, the Singphos differ markedly from the Khamtís and other neighbouring races of Shan origin. They are said to have first settled in their present home towards the close of the 18th century, when the power of the Ahom kings was falling into decay. Their permanent villages were placed on the Tengápání river east of Sadiyá, and on the Buri Dihing river in the tract called Námrúp. They took advantage of the disturbed state of Upper Assam, caused by the rebellion of the Moámáriás, to ravage the whole valley of the Brahmaputra, and carry off numbers of the Assamese into slavery. At the present time, there is a mongrel race well known in Upper Assam under the name of Doanniyás, sprung from the intercourse between the Singphos and their female slaves. When the British took possession of the Province, these raids were suppressed. Captain Neufville, the commandant at Sadiyá, is said to have released 5000 Assamese captives after a single expedition. The Singphos have now entirely abandoned their old habits of lawlessness. They live by agriculture, and have considerable skill in the smelting of iron and in the weaving of cotton into coloured plaid checks. According to the Census Report of 1872, they only numbered 257 souls in the settled portion of Lakhimpur District. In 1881, the Census returned the Singphos at 1774, still confined to Lakhimpur District.

Singrauli.—Tract of land in Mírzápur District, North-Western Provinces; consisting of a depressed alluvial basin, below the level of the surrounding country, and composed in parts of a rich black loam, merging at other places into a hard and unproductive clay.

Singraur.—Village in Soráon *tahsíl*, Allahábád District, North-Western Provinces; situated in lat. $25^{\circ} 35' 3''$ N., and long. $81^{\circ} 41' 10''$ E., 18 miles north-west of Allahábád city. Population (1881) 1723. Singraur is said to have been a large place in former days, but the Ganges first undermined its southern face, and swept away a large portion of the town, leaving a precipitous cliff some 90 feet in height. Since then the river has deserted the town, and only a small branch now passes under Singraur, in the wide channel where the whole stream of the Ganges once passed along. Singraur was the scene of the last act in the rebellion of Khán Zamán and his brother Bahádur against Akbar. A ruined mound known as the Surya Bhita, a mile north of

the town, marks the site of an ancient Sun temple. Station of the Grand Trigonometrical Survey.

Sinhachalam (*Sinha*, 'a lion')—Temple in Viragapatam District, Madras Presidency, situated in lat. $17^{\circ} 46' N$, and long $83^{\circ} 11' 8'' E$, on a hill (800 feet above sea level) 6 miles north west of Viragapatam town. The shrine, which is most picturesquely situated in a wooded glen, containing springs and beautiful cascades, is dedicated to the Lion incarnation of Vishnu, and is held in great veneration. It is believed to have been built by the Gajapati kings of Orissa about 600 years ago, and among other handsome blackstone carvings, it bears an inscription dated 1526, recording the visit of the hero Krishna Kájá. About 200 years ago, it was endowed by the Pusapátis. It is now in the charge of the Mahárájá of Vizianagaram, who has a house and beautiful rose garden here, the latter laid out by his ancestor Sitárái Ráo. The Mahárájá has also built and endowed a *choultry* (native inn) for pilgrims.

Sinhgarh (*Sinhgad*, 'Lion's fort')—Hill fort in the Haveli Sub-division of Poona (Puná) District, Bombay Presidency, lat. $18^{\circ} 21' 51'' N$, and long $73^{\circ} 47' 51'' E$. Situated about 12 miles south west of Poona city, on one of the highest points of the Sinhgarh Bhuleswara range, 4322 feet above sea level, and about 2300 feet above the plain.

On the north and south, Sinhgarh is a huge rugged mountain with a very steep ascent of nearly half a mile. From the slopes rises a great wall of black rock more than 40 feet high, crowned by nearly ruined fortifications. The fort is approached by pathways, and by two gates. The north-east or Poona gate is at the end of a winding ascent up a steep rocky spur, the Kalyán or Konkán gate to the south west stands at the end of a less difficult ascent, guarded by three gateways, all strongly fortified and each commanding the other. The outer fortifications, which consist of a strong stone wall flanked with towers, enclose a nearly triangular space about two miles round. The north face of the fort is naturally strong, the south face, which was stormed by the English in 1818, is the weakest. The triangular plateau within the walls is resorted to as a health resort by the European residents of Poona in April and May, and has several bungalows.

The fort was known as Kondhána until in 1647 Sivaji changed its name to Sinhgarh. In 1340, the Delhi Emperor, Muhammad Tughlak blockaded the fort. In 1486 it fell to the founder of the Alwar nagar dynasty on his capture of Shivner. In 1637, Kondhána was given up to Bijápúr. In 1647, Sivaji acquired the fort by means of a large bribe to its Muhammadan commander, and changed its name to Sinhgarh. In 1662, on the approach of a Muhammadan Shaista Khán, Sivaji fled from Supa to Sinhgarh, and from thence he made his celebrated surprise on Shaista Khán's residence in the

In 1665, a Mughal force blockaded Sinhgarh, and Sivají submitted. In 1670, it was retaken by Tánájí Málusra; this capture forms one of the most daring exploits in Maráthá history. Between 1701 and 1703, Aurangzeb besieged Sinhgarh. After three and a half months' siege the fort was bought from the commandant, and its name changed to Bakshindábaksh, or 'God's gift.' In 1706, as soon as the Mughal troops marched from Poona to Bijápur, Shankrají Náráyan Sachiv, chief manager of the country round, retook Sinhgarh and other forts. Sinhgarh remained with the Maráthás till the war of 1818, when it was carried by storm by General Pritzler.

Sinjhauri Sháhzádpur.—Town in Faizábád (Fyzábád) District, Oudh; situated in lat. $26^{\circ} 24' N.$, and long. $82^{\circ} 35' E.$, on a picturesque spot on the high bank of the Tons, opposite Akbarpur, 36 miles from Faizábád town, on the road to Jaunpur. Founded by Sujhawal, a Bhar chief, and called after him Sujhawalgarh, which has since been altered to Sinjhauri. A certain Sayyid Táji settled here, and dug a tank; a tomb on an island within this tank bears an inscription dated 1365 A.D., one of the oldest in Oudh. A family of Rájput bankers formerly flourished here. Population (1881) 4522, of whom 1252 were Sunnis, 88 Shiás, and 3182 Hindus. Four mosques; 4 Hindu temples; 916 houses, of which 24 are of masonry.

Sinnar.—Sub-division of Násik District, Bombay Presidency. Area, 519 square miles. Population (1881) 66,081, namely, males 33,359, and females 32,722, occupying 10,189 houses in 1 town and 98 villages. Hindus number 61,394; Muhammadans, 1978; and 'others,' 2709. Sinnar, the southmost Sub-division of Násik, is a rather bare table-land, bounded on the south by a high range of hills which run into Ahmadnagar District. The Sub-division contains soil of almost every variety. The water-supply, especially in the east and in the hilly parts to the south, is scanty. The climate is healthy. In 1880-81, 6277 holdings or *khátás* were recorded, with an average area of 37 acres and an average assessment of £2, 16s. In the same year, 187,797 acres were under actual cultivation, of which 2473 acres were twice cropped. Cereals and millets occupied 164,090 acres; pulses, 14,179 acres; oil-seeds, 8088 acres; fibres, 225 acres; and miscellaneous crops, 3688 acres. In 1883 the Sub-division contained 1 civil and 2 criminal courts; police circle (*tháná*), 1; regular police, 45 men; village watch (*chaukidárs*), 124. Land revenue, £15,073.

Sinnar.—Town and municipality in Násik District, Bombay Presidency, and head-quarters of Sinnar Sub-division; situated in lat. $19^{\circ} 50' 25'' N.$, and long. $74^{\circ} 2' 30'' E.$, on the Násik and Poona road, 17 miles south-east of the former town. It is a municipal town, with a population (1881) of 7960 persons, almost entirely engaged in agriculture. Hindus number 7288; Muhammadans, 525; Jains, 75; Christians, 11;

and 'others,' 61. Municipal revenue in 1883-84, £184, incidence of taxation per head of population, 5½d. Sub-judge's court, post-office, dispensary, and two vernacular schools. Weekly market on Sundays. A large portion of the land around the town is irrigated, and produces rich crops of sugar cane, plantains, betel leaves, and rice. Except 173 looms chiefly for weaving robes or *saris*, and a few silk weavers, Sinnar has no trade or manufacture. Sinnar is said to have been founded by a Gauli Rāja, whose son, Rāo Govind, built the handsome temple outside the town, at a cost of 2 *lāks* of rupees (say £20,000). The town was at one time the head-quarters of the local government under the Mughal Emperors.

Siobāra (or *Shubara*) — Petty Bhil State in Khāndesh District, Bombay Presidency — See DANG STATES.

Siobāra — Poor but populous town in Bijnaur (Bijnor) District, North Western Provinces, situated in lat 29° 12' N, and long 78° 38' E, on the Morādābād and Haridwār road, 28 miles south-east of Bijnaur town. Population (1881), 9014, namely, Muhammadans, 6119, Hindus, 2825, and Jains, 70. Station on the recently opened northern extension of the Oudh and Rohilkhand Railway.

Siprā (*Sipri*) — River of Central India, rising in Malwā, on the north side of the Vindhyan range 11 miles east of the small town of Pipalda, in lat 22° 37' N, and long 76° 12' E. 'It has,' writes Thornton, 'a winding course, generally north westerly, through a fertile country. About 40 miles from its source it receives on its left side the small river Kaund, and, passing subsequently by the towns of Ujjain and Mehidpur, falls into the Chumbal on its right bank in lat 23° 54' N, and long 75° 29' E, after a total course of 120 miles. During the rains, the Siprā swells and overflows many places on its banks. In 1821, it rose to such a height as to wash away part of the town of Mehidpur.'

Sira — *Taluk* in Tumkur District, Mysore State, having been transferred from Chitaldrug District in 1868. Area, 590 square miles, of which 132 are cultivated. Population (1881) 49,889, namely, males 25,543, and females 24,346. Hindus number 47,760. Muhammadans 2119, and Christians, 10. Land revenue (1881-82) exclusive of water rates, £8587, or 25.10d. per cultivated acre. The coconuts are of a specially fine quality. In 1883 the *taluk* contained 1 criminal court, with 4 police circles (*thanas*), regular police, 56 men, village watch (*chaukidars*), 182.

Sira — Town in Tumkur District, Mysore State, situated in lat 13° 44' 43" N, and long 76° 57' 16" E, 33 miles north north west of Tumkur town, and 73 miles north west from Bangalore, head-quarters of the Sira *taluk*. Population (1881) 3154, dwelling in 669 houses. Hindus number 2292, and Muhammadans 862.

Formerly the capital of a Muhammadan Province. Its foundation is attributed to Rangappá Náyak, of Ratnágirí; but before the fort was completed, it was captured, in 1638, by Randullá Khán, general of the Bijápur King. Shortly afterwards, Sira was included in the *jágír* granted to the Maráthá Sháhjí, the father of Sivají the Great. In 1687, on the conquest of the Bijápur kingdom by the Mughal Emperor Aurangzeb, Sira was made the capital of a new Province south of the Tungabhadra, which nominally included the greater part of the modern State of Mysore. The two best known Nawábs or Governors were Kásim Khán and Diláwar Khán. Under the latter ruler, the town attained its highest prosperity. The number of houses is said to have been 50,000. An elegant palace, erected by Diláwar Khán, now in ruins, furnished the model for the palaces of Bangalore and Seringapatam. In 1757, Sira was taken by the Maráthás, but recovered for the Musalmáns by Haidar Ali in 1761. During the great struggle for power in the Karnátik, Sira suffered severely. On one occasion, Tipú transported 12,000 families to form the population of his new town of Ganjáma. The finest buildings now standing are the Jamá Masjíd of hewn stone, and the fort also of stone, with a regular moat and glacis.

A large proportion of the inhabitants are Kurubars by caste, who manufacture *kamblis* or coarse blankets to the total value of about £500 in the year. The price of each blanket varies from 1s. to £1, 4s. Common sealing-wax is also made, but the weaving of chintz is now an extinct industry.

Siraguppa (*Siruguppa*).—Town in Bellary *táluk*, Bellary District, Madras Presidency. A badly built, unhealthy town, situated on the south bank of the Tungabhadra river, in lat. $15^{\circ} 38' 50''$ N., and long $76^{\circ} 56' 30''$ E. Population (1881) 5013, occupying 1181 houses. Hindus number 3327, and Muhammadans 1686.

Sirájganj (*Serajgunge*).—Sub-division of Pábná District, Bengal, lying between $24^{\circ} 0' 45''$ and $24^{\circ} 45'$ N. lat., and between $89^{\circ} 17'$ and $89^{\circ} 53'$ E. long. Area, 946 square miles; villages, 2095; houses, 97,543. Population (1881) 699,764, namely, males 346,880, and females 352,884. Hindus numbered 178,831; Muhammadans, 520,671; Christians, 38; and Jains, 224. Average number of persons per square mile, 740; villages per square mile, 2.21; houses per square mile, 105; persons per village, 334; inmates per house, 7.17. This Sub-division consists of the four police circles of Shahzádpur, Ulápára, Sirájganj, and Raiganj. In 1883 it contained 3 magisterial and 3 civil courts, a police force of 128 men, and a village watch of 2200 men.

Sirájganj.—Town in Pábná District, Bengal, and the most important river mart in the Province; situated near the Jamuná or main

SIR. IJGANY

SIRIJGANJ

stream of the Brahmaputra, in lat. $24^{\circ} 26' 58''$ N. and long. $87^{\circ} 47' 5''$ E. Population (1872) 18,873, (1881) 21,037, namely, 11,213, and females 9824. Muhammadans number 12,255, Hindus 8574; and 'others,' 178. Municipal income (1876-77), £573 (1883-84), £1265, of which £921 was derived from taxes on the incidence of taxation, 10^d per head. The town consists of 12 streets and is traversed by the Pabna and Chandikona roads. It is only a market, there are 4 *chits* or landing places for boats on the Dhānbandi river (which flows through Sirajganj). Khatun, Khatunbāri, and the Jute Company *chit* in Machampur.

The following description of Sirajganj and its river trade is condensed from the *Report on the River Trade of Berar for 1871* by the late having been originally supplied by Mr. Anon, who was for several years Magistrate of the Sirajganj subdivision.

The town is said to take its name from a local zamindar of the 17th century. It then stood upon the bank of the Jamuna. In 1845 an excessive flood of the river washed the entire town away. The traders thereupon retreated some 5 miles backward to the new bank, and when the river, in a fresh caprice, returned to its old bed they determined to remain where they were safe from the floods. The town at a long distance from their old place thus was built on the left bank of the Jamuna, and between the houses and the river a high wall was flowing the waste of sand between the houses and the river. The branch stream that passes through the town is the *chit* of the Jamunā, wherever this may happen to be the case. It is a narrow stream, away acres of land and alters its navigable channel every year, business is entirely conducted on the *chit* of the Jamunā, it is that Sirajganj has been described in the *Annals of Bengal* as 'a town without houses'—namely, a town without houses on the river's brink, nor a tree to afford shelter. The boats are anchored in mid stream, fleets of small craft are moored at the natural bends of the river, while the men have to be carried up and fro in light *dinghies*, to conduct their trade. The boats of the light head-dresses of the Mirwans afford a place for the goods of the Bengalis and the rich consumers of the country. Europeans. On the shore, crowds of coolies are engaged in 'bricks' of jute, packing them into *dhows* for export to Calcutta and all those engaged have to traverse the *chit* of 5 miles of sand that intervenes between the town and the river. In 1877 there were six European firms engaged in the trade at Sirajganj; and also an agency of the Bank of Bengal.

imports specie every year to the amount of about £500,000, to liquidate the favourable balance of exchange. The principal native merchants are Márwáris, locally known as Káyas, who are immigrants from Rájputána, and mostly profess the Jain religion. Their head-quarters in Bengal are in Murshidábád District, but their operations extend as far as the eastern corner of Assam. Like their brethren in the Deccan, they are a clannish race, who undertake considerable speculations in reliance upon the good faith of their numerous and distant correspondents. They are described as honest, frugal, and diligent, but quite uneducated. The Bengálí traders chiefly belong to the caste of Sháhás. They are very intelligent, but lack enterprise and confidence in one another.

The business of Sirájganj is mainly that of a changing station. The agricultural produce of all the country round is brought in in small boats, either by the cultivators themselves or by petty dealers, and here transferred to the wholesale merchants, for shipment to Calcutta in steamers or large cargo boats. In return, piece-goods, salt, hardware, and all sorts of miscellaneous articles are received from Calcutta for distribution. In 1876-77, the aggregate value of the registered trade of Sirájganj, including both exports and imports, amounted to more than $3\frac{1}{4}$ millions sterling; but in this total a great deal is counted twice over. The following are the principal items, in one table or the other:—Jute, £606,000; European piece-goods, £264,000; salt, £263,000; oil-seeds, £171,000; oil, £97,000; rice and other grain, £83,000; sugar, £83,000; tobacco, £74,000; gunny-bags, £69,000. The larger half of this trade is conducted direct with Calcutta, to which the exports in 1876-77 were valued at £831,000. Next in importance comes the trade of the surrounding country, and then the supply of rice and general stores to the coolies on the Assam tea-gardens. The relative amount of business done with the neighbouring Districts is shown by the following figures:—Imports from Rangpur, 830,000 *maunds* of jute, 62,000 *maunds* of tobacco, and 28,000 *maunds* of oil-seeds; exports to Rangpur, 167,000 *maunds* of salt and £18,000 of piece-goods; imports from Maimansingh, 294,000 *maunds* of jute and 140,000 *maunds* of mustard seed; exports to Maimansingh, 71,000 *maunds* of salt and £43,000 of piece-goods: imports from Kuch Behar, 160,000 *maunds* of jute and 28,000 *maunds* of tobacco; exports to Kuch Behar, 35,000 *maunds* of salt: imports from Jalpáiguri, 44,000 *maunds* of jute and 40,000 *maunds* of tobacco; imports from Bogra, 209,000 *maunds* of jute; imports from Goálpára in Assam, 98,000 *maunds* of jute and 166,000 *maunds* of mustard seed. Owing to the discontinuance of the registration of the total traffic of Sirájganj in the beginning of 1878, later figures than those given above are not available. Certain statistics with

regard to the trade with Calcutta are shown in the following graphs.

The export jute trade is conducted entirely with Calcutta, and fluctuates according to the demand in that market. The largest exports were reached in 1872-73, when the local estimate made by the Board of the traders was 3,500,000 *maunds*. In 1876-77 the local estimate was 2,021,168 *maunds*, valued at £606,000. In 1877-78 it was 2,156,372 *maunds*, and in 1885-86, 2,621,629 *maunds* being the largest figure for any year in the history of Bengal. There are three means of communication with Calcutta, which is separated from one another—by country boat, by steamer and by rail. The two latter now carry together upwards of two-thirds of the total. The proportion carried by them has increased by upwards of a third since 1877. In 1876-77, 993,654 *maunds* were by land, 1,022,488 by rail, and 450,842 by steamer. In 1885-86, 1,022,488 *maunds* were despatched to Calcutta by boat, 76,740 by rail, and 1,022,488 *maunds* by steamer. The time taken by the boat is only two days, as compared with eight or nine days by steamer, and somewhat less than thirty days by rail. Freight by the boat is very low, but the railway and the steamers always maintain the same rate with one another. The freight by boat ranges from 10 to 15 *annas* per 1000 *maunds*, averaging about 12 *annas* per 1000 *maunds*. By rail and steamer rates from 7½ to 10 *annas* per 1000 *maunds*, about 10½. But, as is usual in India, these rates are not uniform, and several reductions require to be made in certain months, which can be instituted. The boats ship by a local market, and it has become customary to load a 1000 *maund* boat with 1000 *maunds* or an excess of 10 per cent. The railway uses a standard of 80 lbs, and the steamers one of 58 lbs. As a local market, the allowance (inclusive of insurance at the rate of 1 per cent on the cargoes, and the difference of discount between the bank and the market and three days), it has been estimated that the cost of sending 1000 *maunds* of jute from Sirajganj to Calcutta is £37, 11s. 6d by boat, as compared with £45 by rail. This is a great advantage in cheapness, the rail is not used by the local traders, who would not be trusted by the market, and they do not themselves bear the risk of shipwreck and loss of cargo. The persons in a rising market, when the price is high, do not send to Calcutta before a fall.

The Sirajganj Jute Company, which commenced operations in 1877, has a large steam factory in the suburbs of Calcutta, employing a permanent to over 3500 men, women, and children. It has a large number of the numerous mills on the Hooghly, and it is the only one having to import its coal, which can only be obtained from the

the rainy season ; but besides supplying the local demand, it annually exports large numbers of gunny-bags to Calcutta. They are carried by rail at favourable rates, though the coal always comes up by boat. In 1876-77, the export of gunny-bags was 3,161,500 in number, valued at £69,550. In 1877-78 the number was 2,950,625 ; while by 1885-86 it had increased to 6,061,240. In 1876-77, the import of coal for the use of the mill was 112,600 *maunds*, valued at £5630. In 1885-86, coal was imported to Sirájganj to the extent of 153,393 *maunds*.

The other principal articles of trade with Calcutta in 1885-86 were returned as follows:—Exports from Sirájganj : husked rice, 38,639 *maunds* ; other food-grains, 13,633 *maunds* ; oil-seeds, 365,837 *maunds* ; drugs, 32,430 *maunds* ; and tobacco, 29,250 *maunds*. Imports from Calcutta : piece-goods, value £273,427 ; salt, 469,787 *maunds* ; and metals, chiefly manufactured, 16,069 *maunds*.

The municipal committee have twice taken a boat census of Sirájganj. On 31st August 1873, the number of boats found was 1436, laden with 162,000 *maunds* of goods, of which nearly three-fifths was jute. On 4th September 1874, 1185 boats were counted, with cargoes aggregating 195,000 *maunds*. Sirájganj was also a registration station, at which 49,644 boats were counted in the year 1876-77, passing up or down stream. The registration of traffic was abolished in the beginning of 1878, and later statistics than those given above, except as regards the trade with Calcutta, are not available.

Sirakot.—Ruined fort and temple in Kumáun District, North-Western Provinces ; situated in 29° 49' N. lat., and 80° 17' E. long., 9 miles north-west of the confluence of the Gori and Eastern Káli rivers. Elevation above sea-level, 6924 feet. Crowns a rocky ridge, with two of its sides scarped to a sheer depth of 2000 feet, and having its front terminated by a chasm 700 feet in depth. The narrow path from Almorá to Nepál winds round one of its flanks. The temple stands upon a conical rock, rising nearly perpendicularly from the ridge covered by the crumbling fortifications. During the Gúrkha invasion in the early part of the century, the garrison was cut off from their water-supply, upon which they surrendered, and the fort has ever since remained in a ruinous condition.

Siráli.—Village in Makrai Native State, Hoshangábád District, Central Provinces. Population (1881) 2025, namely, Hindus, 1753 ; Muhammadans, 271 ; and 'others,' 1.

Siralkoppa.—Town and municipality in Shimoga District, Mysore State. Lat. 14° 20' 50" N., long. 75° 19' 53" E. Population (1881) 1954. Important mercantile centre, where the jaggery prepared from sugar-cane in the surrounding country is collected for despatch to the neighbouring Districts of Bombay and Madras. Piece-goods and

blankets are received in exchange. Government drivers. A weekly fair held on Sundays is attended by 1700 persons. Murabai census in 1882, £102, or 1s. old per head of population.

Siran (Sirin)—River in Hazara District, Punjab, a tributary of the Indus. Rises at the head of the Bhoranman, and in $34^{\circ} 46'$ N, long. $73^{\circ} 19'$ E, drains the Pikhli valley and the greater part of Tanawal, and falls into the Indus at latitude $34^{\circ} 54'$ N, long. $72^{\circ} 44'$ E, after a length of about 50 miles. It is a river of scenery in different parts of its course from the wild mountain gorges of the upper glens to the broad expanse of irrigated fields in the Pikhli vale and the low but rugged hills of Tanawal. Abounds in fish, especially the mahdair. The Pikhli women call the Siran their 'female slave' as it irrigates the fields, grows the rice, husks their rice, and cleans their cotton. Numerous rapids on the bank. Nowhere navigable. fordable almost everywhere except during floods.

Sirasgāon.—Town in Illichpur District, Bihar. Lat. $25^{\circ} 22'$ N, long. $77^{\circ} 45'$ E. Population (1881) 2405. Hindu 1800, 4455 Muhammadans, 871 and Jains 62. The town is the seat of a taluk of £1481, being the richest community in the District. It has a Marāthi and Urdu schools, small weekly market.

Sirāthu.—North western taluk of North Western Provinces, contiguous with Katta paraganas. It is a rich and highly cultivated alluvial tract and the lower part of it with an upland tract fairly irrigated by wells and with a fair average quality. The Sasur Khaderi *rahi* runs through the taluk from west to south-east, and it is also intersected by the Grand Trunk Road.

The area of the taluk, according to the latest estimate (1881), was 236 square miles. Of this 230 square miles were available for Government revenue, of which 140 square miles were available for 42 square miles cultivable but not under tillage and 88 square miles uncultivable waste. Government land revenue £26,400. Local rates and cesses levied on the land £24,000. Income by cultivators, £33,097. Population (1881) 125,000. Hindus 61,728, and females 61,658. Hindus number 104,400. Muslims 18,935; and Christians. Of the 252 villages in the taluk, 100 contain less than five hundred inhabitants, 60 between five hundred and a thousand; 26 between one and five thousand and 10,000 and above a thousand. In 1884 the subdivision contained 100 villages, 3 police circles (*khaddis*), with a regular police force of 274 and a village watch or rural force of 274 *chak* *dar*.

Sirāthu.—Village in Allahabad District, North Western Provinces, and head-quarters of Sirāthu taluk, situated on the right bank of the

81° 22' E., 38 miles west-north-west of Allahábád city. Population (1881) 1711. Besides the usual Sub-divisional courts and offices, the town contains a post-office and police station. It is also a station on the East Indian Railway.

Sirdhána.—Town in Meerut (Merath) District, North-Western Provinces.—See SARDHANA.

Sirgújá.—Native State in Chutiá Nágpur, Bengal.—See SARGUJA.

Sirhind (*Sarhind*).—Tract in the Lieutenant-Governorship of the Punjab; consisting of the north-eastern portion of the plain which intervenes between the Jumna and the Sutlej rivers. It includes the British Districts of AMBALA (Umballa), LUDHIANA, and FIROZPUR, together with the Native States of PATIALA, JIND, and NABHA, each of which see separately. Sirhind has now no existence as an administrative division of territory; but in the historical sense, it includes all that portion of the cis-Sutlej tract which lies between the Simla Hills on the north-east, the Jumna Valley Districts (Karnál and Rohtak) on the east, Hariána (Sirsa and Hissár) on the south, and the Sutlej on the north-west; or more roughly speaking, it embraces the level plain between the Himálayas and the desert of Bikaner, the Sutlej and the Jumna. This tract comprises the whole watershed of the now deserted stream which once formed the great SARASWATI (Sarsuti) river; and the newly opened Sirhind Canal will doubtless once more spread fertility over its somewhat desolate expanse. (For further particulars, see CIS-SUTLEJ STATES.)

Sirhind Canal.—An important irrigation work, in Ambála (Umballa) and Ludhiána Districts, and Patialá, Nábha, and Jind States, Punjab. The canal draws its supply from the Sutlej near Rupar, and runs through Ludhiána and Firozpur Districts. Other branches traverse Patialá, Nábha, and Jind, terminating in Sirsa and Karnál Districts. Water was admitted into the main canal in July 1882, but the branch system has not yet (1885) been completed, although the works are being pushed forward with great energy. Up to the close of the official year 1883–84, the total Government expenditure on capital account was £5,033,284. This is exclusive of a large sum contributed by the Native States which will be benefited by the canal.

Sirmur (*Sarmor*).—One of the sub-Himálayan or Hill States under the Government of the Punjab, frequently called NAHAN, from the name of the chief town. Sirmur is bounded on the north by the Hill States of Balsan and Jabbal; on the east by the British District of the Dehra Dún, from which it is separated by the rivers Tons and Jumna; on the south-west by Ambála (Umballa) District, and some detached portions of the Native State of Kalsia; and on the north-west by the Native States of Patialá and Keunthál. It lies between lat. 30° 24'

SIRMUR.

Physical Aspects—Except a very small tract along the south western extremity, where a few straggles of the Saranwati (Saraswati) are in the

[illegible]

also been opened. Iron-ore is abundant, and the Rájá established a foundry some years ago, and has made every endeavour to develop the natural resources of the State. Owing, however, to the difficulties of carriage from the mines, the enterprise has not hitherto proved a financial success. The extensive slate strata are in some places quarried to supply roofing. There is also a mine of mica.

So dense are the forests that the sportsman finds difficulty in making his way through them in search of wild elephants, tigers, leopards, bears, and hyænas, with which they abound. Wild pea-fowl are in many places very numerous, being unmolested in consequence of the superstitious regard of the natives.

History.—Sirmur, which means ‘a crowned head,’ was the place of residence of the Rájás who ruled over the State before the present dynasty entered the country. It is said that the last Rájá of the ancient line was swept away by a flood; and that Agar Sain Ráwal, of the ruling family of Jaisalmer, from whom the present chief is descended, being at that time in the neighbourhood on a pilgrimage to the Ganges, took possession of the vacant throne. This occurred in 1095 A.D. The descendants of Agar Sain Ráwal have retained the chiefship ever since. In 1803 the country was brought into subjection by the Gúrkhas, who in turn were expelled in 1815 by the British under Sir David Ochterlony. The Rájput Rájá was reinstated in his ancient possessions, with the exception of the fort and *parganá* of Kutáha or Gurhi, given to the Musalmán *sardár* of that place for good service against the enemy; the Khiárda Dún, which was subsequently, in 1833, restored; a tract of hill country to the north of the river Giri made over to the Rájá of Keunthál; and the *parganá*s of Jaunsar and Bawar in the Dehra Dún, annexed to the British dominions.

The present Rájá, Shamsheer Prakásh, K.C.S.I., was born about 1843. He receives a salute of 11 guns, and maintains a small force of 55 cavalry, 300 infantry, with 10 field guns, and 20 artillerymen. The police force numbers 125 men. The relations of the chief with the British Government are defined in a *sanad*, dated 21st September 1815, under which he is required to consult the Superintendent of the Hill States in all matters connected with the management of the State, and to furnish a contingent to the British forces when called on. Sentences of death require the confirmation of the Superintendent and the Commissioner of Ambála (Umballa), but all other punishments are awarded by the Rájá on his own authority. The Rájá, who pays no tribute, enjoys an estimated revenue of £21,000.

Population, etc.—No Census had ever been taken of the Punjab States prior to 1881, but in that year a regular enumeration of the people was conducted, on the same lines as in the British Districts. The following is a summary of the results as regards Sirmur State:

SIRMUR

— Area, 1077 square miles, number of villages 2068, and town houses, 26,872, of which 21,562 were occupied and 5310 unoccupied. Number of families, 23,181. Total population, 112,371, male 63,305, and females 49,066, average density of population, 104 persons per square mile. Hindus numbered 107,634, or 95·8 per cent., Muhammadans, 4240, or 3·7 per cent., Sikhs, 468, Christians 21, and Jains, 8.

The principal products are opium and several kinds of grain. Ginger is largely cultivated, and the State is famous for its fine breed of sheep. The houses are generally three storeys high, built of stone, boarded with timber, of which there is great abundance as fine forests of fir, oak, rhododendron, horse-chestnut, and other trees overspread the mountains. The roofs are generally of slate, but sometimes of shingle. The family inhabits the upper storey, which is surrounded by an enclosed balcony projecting 6 or 8 feet beyond the wall. The villages usually situated on the slopes or tops of hills, have a picturesque effect in the landscape. The natives of the plains towards the north of a race allied to the Hindus of the Mongolian stock. Goitre is very prevalent amongst all classes. The dress of the middle classes consists of a simple tunic or frock reaching down to the knees, trousers, and a scarf usually worn across the shoulders, but when the sun is hot, thrown over the head, the lower orders content themselves with a blanket girt round the waist, the higher ranks dress after the fashion of Hindustan, and wear the Sikh turban. The religion prevailing in Sirmur is mainly Hinduism, to which is added the superstitious adoration and dread of innumerable local divinities, with which the imagination of the people is imbued. The people are divided into castes as in the plains, and Brahmans abound. The most important tribe in the hills is named Kanet, members of which number 37,817, or 33·6 per cent. of the total population of the State. Kanets are Hindus, and probably of true Kanet descent. They are popularly supposed to be degenerate Khatris, who have fallen from their high estate in consequence of a custom which prevails amongst them of purchasing their wives allowing the marriage of widows. The language is a dialect of

Local Aspects—The climate of Sirmur varies with the elevation—that of the Chor, where the surface of the ground is under snow for a greater part of the year, to the stifling malaria of the low lying Dún. In shape, the Khurda Dún resembles a deep narrow shut in by high walls on every side, except towards the east, opens to the Jumna, it has a deep alluvial swampy soil, with rank vegetation, and its climate consequently is peculiarly

hot and oppressive for about two months after the rain and the air is charged with noxious vapours. The great Dún is mere desert or jungle, untrodden by man, except by cutters, or by the collectors of gum catechu, which is very abundant by the Mimosa. Cultivation is, however, steady and with the clearance of the jungle, the climate will approach that of the neighbouring Dehra Dún.

END OF VOLUME XII.

hot and oppressive for about two months after the rains have ceased, and the air is charged with noxious vapours. The greater part of the Dún is mere desert or jungle, untrodden by man, except by a few woodcutters, or by the collectors of gum catechu, which is yielded in great abundance by the *Mimosa*. Cultivation is, however, steadily spreading; and with the clearance of the jungle, the climate will approximate to that of the neighbouring Dehra Dún.

END OF VOLUME XII.

